

---

## **Focused Feasibility Study for Surface Soil at the Main Pits and Pushout Area, J-Field Toxic Burning Pits Area, Aberdeen Proving Ground, Maryland**

---

**Environmental Assessment Division  
Argonne National Laboratory**



Operated by The University of Chicago,  
under Contract W-31-109-Eng-38, for the

**United States Department of Energy**

## *Argonne National Laboratory*

Argonne National Laboratory, with facilities in the states of Illinois and Idaho, is owned by the United States Government, and operated by the University of Chicago under the provisions of a contract with the Department of Energy.

This technical memo is a product of Argonne's Environmental Assessment Division (EAD). For information on the division's scientific and engineering activities, contact:

Director, Environmental Assessment Division  
Argonne National Laboratory  
Argonne, Illinois 60439-4815  
Telephone (708) 252-3107

Presented in this technical memo are preliminary results of ongoing work or work that is more limited in scope and depth than that described in formal reports issued by the EAD.

Publishing support services were provided by Argonne's Information and Publishing Division (for more information, see IPD's home page: <http://www.ipd.anl.gov/>).

## *Disclaimer*

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

*Reproduced directly from the best available copy.*

*Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (423) 576-8401.*

*Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Road, Springfield, VA 22161.*

---

## **Focused Feasibility Study for Surface Soil at the Main Pits and Pushout Area, J-Field Toxic Burning Pits Area, Aberdeen Proving Ground, Maryland**

---


by

T. Patton, P. Benioff, C. Biang, J. Butler, W. Davies, R. Haffenden, J. Hayse, I. Hlohowskyj, L. Martino, L. Poch, E. Portante, J. Quinn, C.-Y. Yuen, Y.-Y. Wang, and G. Williams

Environmental Assessment Division,  
Argonne National Laboratory, 9700 South Cass Avenue, Argonne, Illinois 60439

June 1996

Work sponsored by U.S. Army Aberdeen Proving Ground, Directorate of Safety, Health, and Environment



This report is printed on recycled paper.

## CONTENTS

FOREWORD .....	xvii
NOTATION .....	xviii
SUMMARY .....	S-1
S.1 Introduction .....	S-1
S.2 Focused Feasibility Study Approach .....	S-2
S.3 Interim Remedial Action Objectives .....	S-2
S.3.1 Objectives and Scope .....	S-2
S.3.2 Preliminary Remediation Goals .....	S-3
S.4 Potentially Applicable Technologies .....	S-4
S.5 Description of Alternatives .....	S-4
S.5.1 Alternative 1: No Action .....	S-7
S.5.2 Alternative 2: Limited Removal and Disposal, and In-Situ Containment ....	S-7
S.5.3 Alternative 3: Removal and Short-Term Storage .....	S-7
S.5.4 Alternative 4: Removal, On-Site Treatment, and Limited Disposal .....	S-8
S.5.5 Alternative 5: Removal, Off-Site Treatment, and Disposal .....	S-8
S.6 Identification of Final Alternatives .....	S-8
S.7 Evaluation Summary and Comparative Analysis .....	S-9
S.8 References for Summary .....	S-15
1 INTRODUCTION .....	1-1
1.1 Background .....	1-1
1.2 Purpose of this Report .....	1-1
1.3 Organization of this Report .....	1-3
2 SITE BACKGROUND .....	2-1
2.1 Site History .....	2-1
2.2 Site Description .....	2-2
2.2.1 Topography .....	2-2
2.2.2 Soil .....	2-3
2.2.3 Surface Water .....	2-3
2.2.4 Geology and Hydrogeology .....	2-3
2.2.5 Climate .....	2-8
2.2.6 Ecology .....	2-9
2.2.7 Land Use .....	2-12
2.3 Nature and Extent of Contamination .....	2-13
2.3.1 Soil .....	2-13

## CONTENTS (Cont.)

2.3.2	Groundwater .....	2-19
2.3.3	Sediment .....	2-20
2.3.4	Surface Water .....	2-20
2.4	Contamination Sources and Release Mechanisms .....	2-20
2.5	Potential Exposure Pathways .....	2-21
2.5.1	Human Exposure .....	2-21
2.5.2	Ecological Exposure .....	2-23
2.6	Contaminants of Concern .....	2-23
2.6.1	Human Health Contaminants of Concern .....	2-23
2.6.2	Contaminants of Ecological Concern .....	2-27
2.7	Concurrent Studies .....	2-29
2.7.1	Remedial Investigation .....	2-29
2.7.2	Human Health Risk Assessment .....	2-30
2.7.3	Ecological Risk Assessment .....	2-30
2.7.4	Sitewide Feasibility Study .....	2-33
3	INTERIM REMEDIAL ACTION OBJECTIVES .....	3-1
3.1	Objectives and Scope .....	3-1
3.2	Compliance with Regulatory Requirements .....	3-3
3.3	Interim Preliminary Remediation Goals .....	3-7
4	IDENTIFICATION AND SCREENING OF TECHNOLOGIES .....	4-1
4.1	Criteria for Identifying and Screening Technologies .....	4-1
4.2	Technology Identification and Screening .....	4-2
4.2.1	Institutional Controls .....	4-2
4.2.2	In-Situ Containment .....	4-4
4.2.3	Removal .....	4-5
4.2.4	Treatment .....	4-6
4.2.5	Short-Term Storage .....	4-15
4.2.6	Disposal .....	4-15
4.3	Potentially Applicable Technologies .....	4-17
5	DEVELOPMENT AND SCREENING OF PRELIMINARY ALTERNATIVES .....	5-1
5.1	Criteria for Developing Alternatives .....	5-1
5.2	Identification of Preliminary Alternatives .....	5-2

## CONTENTS (Cont.)

5.2.1	Alternative 1: No Action .....	5-3
5.2.2	Alternative 2: Limited Removal and Disposal, and In-Situ Containment .....	5-3
5.2.3	Alternative 3: Removal and Short-Term Storage .....	5-3
5.2.4	Alternative 4: Removal, On-Site Treatment, and Limited Disposal .....	5-4
5.2.5	Alternative 5: Removal, Off-Site Treatment, and Disposal .....	5-4
5.3	Criteria for Screening Alternatives .....	5-5
5.4	Screening of Preliminary Alternatives .....	5-5
5.4.1	Alternative 1: No Action .....	5-5
5.4.2	Alternative 2: Limited Removal and Disposal, and In-Situ Containment .....	5-6
5.4.3	Alternative 3: Removal and Short-Term Storage .....	5-7
5.4.4	Alternative 4: Removal, On-Site Treatment, and Limited Disposal .....	5-8
5.4.5	Alternative 5: Removal, Off-Site Treatment, and Disposal .....	5-10
5.5	Screening Summary and Identification of Final Alternatives .....	5-11
6	DESCRIPTION OF FINAL ALTERNATIVES .....	6-1
6.1	Alternative 1: No Action .....	6-1
6.2	Alternative 2: Limited Removal and Disposal, and In-Situ Containment .....	6-2
6.2.1	Limited Removal .....	6-2
6.2.2	Disposal .....	6-4
6.2.3	In-Situ Containment .....	6-5
6.2.4	Shoreline Stabilization .....	6-5
6.3	Alternative 3: Removal and Short-Term Storage .....	6-6
6.3.1	Removal .....	6-6
6.3.2	Storage Facility Construction .....	6-8
6.3.3	Shoreline Stabilization .....	6-8
6.4	Alternative 4: Removal, On-Site Treatment, and Limited Disposal .....	6-9
6.4.1	Removal .....	6-9
6.4.2	On-Site Treatment .....	6-10
6.4.3	Limited Disposal .....	6-12
6.5	Alternative 5: Removal, Off-Site Treatment, and Disposal .....	6-13
6.5.1	Removal .....	6-13
6.5.2	Off-Site Treatment and Disposal .....	6-13

## CONTENTS (Cont.)

7	DETAILED EVALUATION OF ALTERNATIVES .....	7-1
7.1	Alternative 1: No Action .....	7-2
7.1.1	Overall Protection of Human Health and the Environment .....	7-2
7.1.2	Compliance with ARARs .....	7-3
7.1.3	Long-Term Effectiveness and Permanence .....	7-3
7.1.4	Reduction of Toxicity, Mobility, or Volume .....	7-4
7.1.5	Short-Term Effectiveness .....	7-4
7.1.6	Implementability .....	7-4
7.1.7	Cost .....	7-5
7.2	Alternative 2: Limited Removal and Disposal, and In-Situ Containment .....	7-5
7.2.1	Overall Protection of Human Health and the Environment .....	7-5
7.2.2	Compliance with ARARs .....	7-5
7.2.3	Long-Term Effectiveness and Permanence .....	7-6
7.2.4	Reduction of Toxicity, Mobility, or Volume .....	7-7
7.2.5	Short-Term Effectiveness .....	7-7
7.2.6	Implementability .....	7-9
7.2.7	Cost .....	7-10
7.3	Alternative 3: Removal and Short-Term Storage .....	7-13
7.3.1	Overall Protection of Human Health and the Environment .....	7-13
7.3.2	Compliance with ARARs .....	7-13
7.3.3	Long-Term Effectiveness and Permanence .....	7-14
7.3.4	Reduction of Toxicity, Mobility, or Volume .....	7-15
7.3.5	Short-Term Effectiveness .....	7-15
7.3.6	Implementability .....	7-17
7.3.7	Cost .....	7-18
7.4	Alternative 4: Removal, On-Site Treatment, and Limited Disposal .....	7-21
7.4.1	Overall Protection of Human Health and the Environment .....	7-21
7.4.2	Compliance with ARARs .....	7-21
7.4.3	Long-Term Effectiveness and Permanence .....	7-22
7.4.4	Reduction of Toxicity, Mobility, or Volume .....	7-23
7.4.5	Short-Term Effectiveness .....	7-23
7.4.6	Implementability .....	7-25
7.4.7	Cost .....	7-26
7.5	Alternative 5: Removal, Off-Site Treatment, and Disposal .....	7-28
7.5.1	Overall Protection of Human Health and the Environment .....	7-28
7.5.2	Compliance with ARARs .....	7-28
7.5.3	Long-Term Effectiveness and Permanence .....	7-29
7.5.4	Reduction of Toxicity, Mobility, or Volume .....	7-30

## CONTENTS (Cont.)

7.5.5	Short-Term Effectiveness .....	7-30
7.5.6	Implementability .....	7-32
7.5.7	Cost .....	7-32
7.6	Monitoring and Mitigative Measures .....	7-34
8	COMPARATIVE ANALYSIS OF ALTERNATIVES .....	8-1
8.1	Threshold Criteria .....	8-1
8.1.1	Overall Protection of Human Health and the Environment .....	8-1
8.1.2	Compliance with ARARs .....	8-6
8.2	Primary Balancing Criteria .....	8-7
8.2.1	Long-Term Effectiveness and Permanence .....	8-7
8.2.2	Reduction of Toxicity, Mobility, or Volume .....	8-8
8.2.3	Short-Term Effectiveness .....	8-8
8.2.4	Implementability .....	8-9
8.2.5	Cost .....	8-9
8.3	Modifying Criteria .....	8-11
8.4	Summary .....	8-11
9	REFERENCES .....	9-1
10	LIST OF PREPARERS .....	10-1
APPENDIX A:	Vadose Zone Model of Metal Transport for the Toxic Burning Pits Area of J-Field .....	A-1
APPENDIX B:	Applicable or Relevant and Appropriate Requirements .....	B-1
APPENDIX C:	Sampling Data for the Toxic Burning Pits Area January 1993 – June 1995 .....	C-1
APPENDIX D:	Characterization of the Toxic Burning Pits Area .....	D-1
APPENDIX E:	Ecological Risk Assessment Modeling Methods .....	E-1
APPENDIX F:	Determining Interim Remedial Action Costs .....	F-1
APPENDIX G:	English/Metric — Metric/English Equivalents .....	G-1

## TABLES

S.1	Estimated Areas and Volumes of Contaminated Surface Soil at the Main Pits and Pushout Area . . . . .	S-4
S.2	Risk-Based Interim Preliminary Remediation Goals for Surface Soil at the TBP Area . . . . .	S-6
S.3	Comparative Analysis of Alternatives . . . . .	S-11
2.1	Bird Species of Special Federal and State Concern Reported at APG . . . . .	2-11
2.2	Mean and Maximum Background Soil Concentrations of Metals Reported for Off-Site Areas Surrounding APG . . . . .	2-15
2.3	Potential Human Exposure Pathways at the TBP Area under Current Land-Use Conditions . . . . .	2-22
2.4	Ecological Receptors for the TBP Area . . . . .	2-24
2.5	Identification of Human Health–Based Contaminants of Concern for Soil in the TBP Area . . . . .	2-25
2.6	Contaminants of Ecological Concern for TBP Area Soils . . . . .	2-29
2.7	Identification of Preliminary Ecological Contaminants of Concern for the TBP Area . . . . .	2-35
3.1	Estimated Areas and Volumes of Contaminated Surface Soil at the Main Pits and Pushout Area . . . . .	3-1
3.2	Human Health–Based Interim Preliminary Remediation Goals for Surface Soil at the TBP Area . . . . .	3-7
3.3	Ecological Effects Quotient Risk Estimates of Soil Contaminant Concentrations for Selected Ecological Receptors at the TBP Area . . . . .	3-9
3.4	Estimated Surface Soil Contaminant Concentrations Necessary to Achieve a No-Effects Level for Selected Ecological Receptors that Use the TBP Area . . . . .	3-10

## TABLES (Cont.)

3.5	Ecological Risk-Based Interim Preliminary Remediation Goals for Soils at the TBP Area .....	3-13
3.6	Risk-Based Interim Preliminary Remediation Goals for Surface Soil at the TBP Area .....	3-14
4.1	Summary of Screening Analysis for Institutional Controls .....	4-3
4.2	Summary of Screening Analysis for In-Situ Containment .....	4-5
4.3	Summary of Screening Analysis for Removal .....	4-6
4.4	Summary of Screening Analysis for In-Situ Treatment Technologies .....	4-7
4.5	Summary of Screening Analysis for Ex-Situ Treatment Technologies .....	4-10
4.6	Summary of Screening Analysis for Biological Treatment .....	4-14
4.7	Summary of Screening Analysis for Short-Term Storage .....	4-16
4.8	Summary of Screening Analysis for Disposal .....	4-17
4.9	Summary of Potentially Applicable Technologies .....	4-18
5.1	Screening Results for Preliminary Alternatives .....	5-12
7.1	Cost Estimate for Alternative 2 .....	7-11
7.2	Cost Estimate for Alternative 3 .....	7-19
7.3	Cost Estimate for Alternative 4 .....	7-27
7.4	Cost Estimate for Alternative 5 .....	7-33
7.5	Major Monitoring and Mitigative Measures for Action Alternatives .....	7-35
8.1	Comparative Analysis of Alternatives .....	8-2

## TABLES (Cont.)

8.2	Comparative Costs for Cleanup Activities under Alternatives 2, 3, 4, and 5 .....	8-10
A.1	$K_d$ Values and Results .....	A-6
A.2	Inorganic Materials of Concern $K_d$ Values .....	A-10
B.1	State Regulations and To-Be-Considered Requirements for J-Field .....	B-3
B.2	Federal Regulations and To-Be-Considered Requirements for J-Field — Potential Contaminant-Specific Requirements .....	B-11
B.3	Federal Regulations and To-Be-Considered Requirements for J-Field — Potential Location-Specific Requirements .....	B-13
B.4	Federal Regulations and To-Be-Considered Requirements for J-Field — Potential Action-Specific Requirements .....	B-15
C.1	Index to Data Tables for the J-Field TBP Area .....	C-4
C.2a	Volatile Organics Analyses for Surface Water, April 1993 .....	C-6
C.2b	Volatile Organics Analyses for Surface Water, September 1993 .....	C-8
C.2c	Volatile Organics Analyses for Surface Water, February 1994 .....	C-10
C.2d	Volatile Organics Analyses for Surface Water, May 1994 .....	C-13
C.3a	Semivolatile Organics Analyses for Surface Water, April 1993 .....	C-14
C.3b	Semivolatile Organics Analyses for Surface Water, September 1993 .....	C-17
C.3c	Semivolatile Organics Analyses for Surface Water, May 1994 .....	C-19
C.4a	Inorganic Analyses for Surface Water, September 1993 .....	C-21
C.4b	Inorganic Analyses for Surface Water, May 1994 .....	C-23

## TABLES (Cont.)

C.5a	Pesticide and Polychlorinated Biphenyl Analyses for Surface Water, April 1993 .....	C-24
C.5b	Pesticide and PCB Analyses for Surface Water, September 1993 .....	C-26
C.5c	Pesticide and PCB Analyses for Surface Water, May 1994 .....	C-28
C.6a	General Chemistry Analyses for Surface Water, May 1994 .....	C-29
C.6b	Explosive Compounds Analyses for Surface Water, May 1994 .....	C-30
C.6c	Chemical Warfare Agent Degradation Products and Organosulfur Compounds Analyses for Surface Water, April 1993 .....	C-31
C.7a	Volatile Organics Analyses for Sediment Borings, April 1994 .....	C-32
C.7b	Volatile Organics Analyses for Sediment Borings, June 1995 .....	C-38
C.8a	Semivolatile Organics Analyses for Sediment Borings, April 1994 .....	C-40
C.8b	Semivolatile Organics Analyses for Sediment Borings, June 1995 .....	C-53
C.9a	Inorganic Analyses for Sediment Borings, April 1994 .....	C-55
C.9b	Inorganic Analyses for Sediment Borings, June 1995 .....	C-60
C.10	Pesticide and PCB Analyses for Sediment, June 1995 .....	C-62
C.11	Explosive Compounds Analyses for Sediment, June 1995 .....	C-63
C.12	CWA Degradation Products and Organosulfur Compounds Analyses for Sediment, June 1995 .....	C-64
C.13a	Volatile Organics Analyses for Soil Borings, January 1993 .....	C-65
C.13b	Volatile Organics Analyses for Soil Borings, January 1994 .....	C-71
C.13c	Volatile Organics Analyses for Soil Borings, May 1994 .....	C-77

## TABLES (Cont.)

C.13d	Volatile Organics Analyses for Soil Borings, May 1995 .....	C-91
C.14a	Semivolatile Organics Analyses for Soil Borings, January 1993 .....	C-102
C.14b	Semivolatile Organics Analyses for Soil Borings, January 1994 .....	C-116
C.14c	Semivolatile Organics Analyses for Soil Borings, May 1994 .....	C-126
C.14d	Semivolatile Organics Analyses for Soil Borings, May 1995 .....	C-142
C.15a	Inorganic Analysis for Soil Borings, January 1993 .....	C-160
C.15b	Inorganic Analyses for Soil Borings, January 1994 .....	C-165
C.15c	Inorganic Analyses for Soil Borings, 1994-1995 .....	C-169
C.15d	Inorganic Analysis for Soil Borings, May 1995 .....	C-176
C.16a	Pesticide and PCB Analyses for Soil Borings, January 1993 .....	C-188
C.16b	Pesticide and PCB Analyses for Soil Borings, May 1995 .....	C-193
C.17	On-Site Analytical Suite Results for Soil Borings, December 1993–May 1994 .....	C-195
C.18	Explosive Compounds Analyses for Soil Samples, May 1995 .....	C-198
C.19	CWA Degradation Products and Organosulfur Compound Analyses for Soil, May 1995 .....	C-200
C.20	Dioxin and Total Petroleum Hydrocarbons Analyses for Soil Samples, May 1995 .....	C-202
C.21a	Volatile Organics Analyses for Groundwater, May 1994 .....	C-203
C.21b	Volatile Organics Analyses for Groundwater in Piezometer Located in Marsh, September 1994 .....	C-208
C.22	Semivolatile Organics Analyses for Groundwater, May 1994 .....	C-211

## TABLES (Cont.)

C.23	Inorganic Analyses for Groundwater, May 1994 .....	C-215
C.24	General Chemistry Analyses for Groundwater, May 1994 .....	C-220
C.25	Pesticide and PCB Analyses for Groundwater in the Surficial Aquifer, May 1994 .....	C-223
C.26	Explosive Compounds Analyses for Groundwater in the Surficial Aquifer, June 1994 .....	C-224
C.27	Radiochemistry Analyses for Groundwater, June 1994 .....	C-225
D.1	Summary of On-Site Analytical Methods and Corresponding Analytes .....	D-8
D.2	Modified On-Site Analytical Suite .....	D-9
D.3	Results of the Field-Portable X-Ray Fluorescence Analysis at the TBP Area .....	D-12
D.4	Analytical Results for Selected Metals in Soil .....	D-19
D.5	Toxicity Characteristic Leaching Procedure Results for Selected Metals in Soil .....	D-22
D.6	Analytical Results for Selected Volatile Organic Compounds in Southern Main Pit Soil .....	D-25
D.7	Analytical Results for Selected Metals in Southern Main Pit Soil .....	D-27
D.8	Analytical Results for Polychlorinated Biphenyls and Total Petroleum Hydrocarbons in Southern Main Pit Soil .....	D-28
D.9	Analytical Results for Selected Metals in Surface Water Samples Collected in May 1994 .....	D-34
D.10	Summary of Volatile Organics Analyses for Surface Water .....	D-35
D.11	Contract Laboratory Program Analytical Suite .....	D-37

## TABLES (Cont.)

D.12	Analytical Results for Selected Volatile Organic Compounds in Groundwater, 1994 .....	D-38
D.13	Construction Data and Summary of Volatile Organic Compounds Detected in J-Field Marsh Piezometers in 1994 .....	D-40
D.14	Analytical Results for Selected Inorganics in Groundwater, 1994 .....	D-42
E.1	Exposure Routes Evaluated for Ecological Receptors at the TBP Area .....	E-5
E.2	Exposure Point Concentrations of Contaminants of Ecological Concern for the TBP Area .....	E-7
E.3	Species-Specific Exposure Factors Used to Model the Applied Daily Dose for Ecological Receptors that Use the TBP Area .....	E-9
E.4	Soil-to-Plant Transfer Factors Used to Model the Applied Daily Dose for Ecological Receptors that Use the TBP Area .....	E-12
E.5	Species-Specific NOAEL Benchmark Values Used to Estimate the Environmental Effects Quotient .....	E-18
G.1	English/Metric Equivalents .....	G-3
G.2	Metric/English Equivalents .....	G-3

## FIGURES

S.1(a)	Contaminated Surface Soil, 0-6 in., to Be Addressed by the Proposed Action at the TBP Area .....	S-5
S.1(b)	Contaminated Surface Soil, 6-24 in., to Be Addressed by the Proposed Action at the TBP Area .....	S-5
1.1	Location of J-Field in the Edgewood Area at APG .....	1-2

## FIGURES (Cont.)

1.2	Locations of Principal Site Features at J-Field .....	1-3
2.1	Locations of Main Features and Monitoring Wells at the TBP Area .....	2-2
2.2	Generalized Hydrogeologic Cross Section and Direction of Groundwater Flow at J-Field TBP Area .....	2-4
2.3	Estimated Contaminated Area at Depth Interval 0-6 in. with Heavy Metal Concentration Levels above Mean Background .....	2-17
2.4	Estimated Contaminated Area at Depth Interval 6-24 in. with Heavy Metal Concentration Levels above Mean Background .....	2-17
2.5	Estimated Contaminated Area at Depth Interval 0-6 in. with Heavy Metal Concentration Levels above Maximum Background .....	2-18
2.6	Estimated Contaminated Area at Depth Interval 6-24 in. with Heavy Metal Concentration Levels above Maximum Background .....	2-18
2.7	Estimated Contaminated Area at Depth Interval 2-4 ft with Heavy Metal Concentration Levels above Mean Background .....	2-19
3.1	Contaminated Surface Soil, 0-6 in., to Be Addressed by the Proposed Action at the TBP Area .....	3-2
3.2	Contaminated Surface Soil, 6-24 in., to Be Addressed by the Proposed Action at the TBP Area .....	3-2
6.1	Location of In-Situ Containment Area and Shoreline Stabilization, Alternative 2 .....	6-2
6.2	Location of Fenced Work Zone and Proposed Storage Facility, Alternative 3 .....	6-9
6.3	Location of Fenced Work Zone and Proposed Treatment Facility and Staging Area, Alternative 4 .....	6-11
6.4	Process Flowchart for the Soil Washing/Leaching Facility .....	6-12

## FIGURES (Cont.)

A.1	Concentration Profiles for Lead Using a $K_d$ Value of 150 mL/g for a 50-Year Period .....	A-7
A.2	Concentration Profiles for Cadmium Using a $K_d$ Value of 15 mL/g .....	A-8
A.3	Concentration Profiles for Zinc Using a $K_d$ Value of 5.0 mL/g .....	A-9
D.1	Location of Passive and Active Soil-Gas Measurements at the TBP Area: 1993-1994 .....	D-5
D.2	Locations of Active Soil-Gas Sampling at the TBP Area .....	D-6
D.3	Locations of In-Situ X-Ray Fluorescence Measurements at the TBP Area .....	D-11
D.4	Locations of Surface Soil Samples Collected at the TBP Area since 1993 .....	D-16
D.5	Locations of Soil Borings at the TBP Area .....	D-23
D.6	Distribution of Polychlorinated Biphenyls at the TBP Area .....	D-29
D.7	Locations of Surface Water and Sediment Samples and Sediment Borings near the TBP Area .....	D-31
D.8	Potential Contamination Sources at the TBP Area .....	D-36

## FOREWORD

Argonne National Laboratory acknowledges Mr. Larry Thebeau and Mr. Prakash Ramaswamy of ICF Kaiser Engineers, Inc., for the development of Alternative 2 (Limited Removal and Disposal, and In-Situ Containment) for this focused feasibility study. Mr. Thebeau and Mr. Ramaswamy prepared Sections 4.2.2, 5.2.2, 6.2, 7.2.7, and F.1.

## NOTATION

The following is a list of acronyms, initialisms, chemical abbreviations, and units of measure used in this document.

### ACRONYMS AND INITIALISMS

ADD	applied daily dose
AE	assimilation efficiency
ANL	Argonne National Laboratory
AOC	area of concern
APG	Aberdeen Proving Ground
ARAR	applicable or relevant and appropriate requirement
ART	Alternative Remedial Technologies, Inc.
ASTM	American Society for Testing and Materials
AWQC	ambient water quality criteria
BRA	baseline risk assessment
CAMU	Corrective Action Management Unit
CCMAS	Construction Cost Management Analysis System
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act (as amended)
CFR	Code of Federal Regulations
CLP	Contract Laboratory Program
CMS	corrective measures study
COC	contaminant of concern
COEC	contaminant of ecological concern
COMAR	Code of Maryland Regulations
CRC	Chemical Rubber Company
CRQL	contract-required quantitation limit
CSTA	Combat Systems Test Activity
CWA	chemical warfare agent
DANC	decontaminating agent, noncorrosive
DNAPL	dense, nonaqueous-phase liquid
DOE	U.S. Department of Energy
DOT	U.S. Department of Transportation
DRE	destruction/removal efficiency
DSHE	Directorate of Safety, Health, and Environment (U.S. Army)
DW	dry weight

EEQ	environmental effects quotient
EMD	Environmental Management Division (U.S. Army)
EO	Executive Order
EP	extraction procedure
EPA	U.S. Environmental Protection Agency
ERA	ecological risk assessment
ERT	Emergency Response Team
FEMA	Federal Emergency Management Agency
FFS	focused feasibility study
FR	Federal Register
FS	feasibility study
GPR	ground-penetrating radar
HAZMAT	hazardous materials
HE	high explosives
HFA	Human Factors Applications, Inc.
HW	hazardous waste
IRA	interim remedial action
IRD	interim remedial design
LDR	land disposal restriction
LEL	lower explosive limit
MCL	maximum contaminant level
MCR	maximum credible release
MDNR	Maryland Department of Natural Resources
MSL	mean sea level
NCP	National Oil and Hazardous Substances Pollution Contingency Plan
NOAA	National Oceanic and Atmospheric Administration
NOAEL	no observed adverse effects level
NPDES	National Pollutant Discharge Elimination System
NPL	National Priorities List
NR	National Resources
O&M	operation and maintenance
O&P	overhead and profit
OB/OD	open burning/open detonation
ODC	other direct cost
OSAS	on-site analytical suite

OSHA	Occupational Safety and Health Administration
OSWER	Office of Solid Waste and Emergency Response
PL	Public Law
PRG	preliminary remediation goal
QC	quality control
RACER	Remedial Action Cost Engineering and Requirements System
RCRA	Resource Conservation and Recovery Act
RFI	RCRA facility investigation
RI	remedial investigation
RME	reasonable maximum exposure
ROD	Record of Decision
SARA	Superfund Amendments and Reauthorization Act of 1986
SPTF	soil-to-plant transfer factor
SVE	soil-vapor extraction
SWMU	solid waste management unit
TAL	target analyte list
TBC	to-be-considered requirement
TBP	Toxic Burning Pits
TCL	target compound list
TCLP	toxicity characteristic leaching procedure
TDS	total dissolved solids
TSCA	Toxic Substances Control Act
TSD	treatment, storage, and disposal
UCL	upper confidence limit
USATHAMA	U.S. Army Toxic and Hazardous Materials Agency
USC	United States Code
USGS	U.S. Geological Survey
UV	ultraviolet
UXO	unexploded ordnance
WPP	white phosphorus burning pits
XRF	X-ray fluorescence

## CHEMICAL ABBREVIATIONS

BHC	benzene hexachloride
BTEX	benzene, toluene, ethylbenzene, and xylenes
CAH	chlorinated aliphatic hydrocarbon
DCE	dichloroethylene
11DCE	1,1-dichloroethylene
12DCE	1,2-dichloroethylene
DDD	4,4'-dichlorodiphenyldichloroethane
DDE	4,4'-dichlorodiphenyldichloroethylene
DDT	4,4'-dichlorodiphenyltrichloroethane
DNAPL	dense nonaqueous-phase liquid
EDTA	ethylenediamine tetraacetic acid
GA	ethyl N,N-dimethyl phosphoramidocyanidate (tabun)
GB	isopropyl methylphosphonofluoridate (sarin)
GD	pinacolyl methylphosphonofluoridate (soman)
HD	sulfur mustard
LNAPL	light nonaqueous-phase liquid
PAH	polyaromatic hydrocarbon
PCB	polychlorinated biphenyl
PEH	petroleum hydrocarbon
PETN	pentaerythritol tetranitrate
RDX	hexahydro-1,3,5-trinitro-1,3,4-triazine
SVOC	semivolatile organic compound
111TCE	1,1,1-trichloroethane
112TCE	1,1,2-trichloroethane
TCLEA	1,1,2,2-tetrachloroethane
TCLEE	tetrachloroethylene
TNT	trinitrotoluene
TPH	total petroleum hydrocarbon
TRCLE	trichloroethylene
VOC	volatile organic compound
VX	methylphosphonothioic acid

## UNITS OF MEASURE

cm	centimeter(s)	L	liter(s)
°F	degree(s) Fahrenheit	m <sup>3</sup>	cubic meter(s)
ft	foot (feet)	mg	milligram(s)
ft <sup>2</sup>	square foot (feet)	mi	mile(s)
gal	gallon(s)	mm	millimeter(s)
gpm	gallon(s) per minute	ng	nanogram(s)
h	hour(s)	µg	microgram(s)
in.	inch(es)	ppm	part(s) per million
kg	kilogram(s)	s	second(s)
km	kilometer(s)	V	volt(s)
kW	kilowatt(s)	yd <sup>3</sup>	cubic yard(s)

**FOCUSED FEASIBILITY STUDY FOR SURFACE SOIL AT THE MAIN  
PITS AND PUSHOUT AREA, J-FIELD TOXIC BURNING PITS  
AREA, ABERDEEN PROVING GROUND, MARYLAND**

**SUMMARY**

**S.1 INTRODUCTION**

The Environmental Management Division of Aberdeen Proving Ground (APG), Maryland, is conducting a remedial investigation and feasibility study of the J-Field area at APG pursuant to the Comprehensive Environmental Response, Compensation, and Liability Act, as amended (CERCLA). J-Field is located within the Edgewood Area of APG in Harford County, Maryland. Since World War II, activities in the Edgewood Area have included the development, manufacture, testing, and destruction of chemical agents and munitions. These materials were destroyed at J-Field by open burning/open detonation. Portions of J-Field continue to be used for the detonation and disposal of unexploded ordnance (UXO) by open burning/open detonation under authority of the Resource Conservation and Recovery Act.

J-Field is almost flat and is covered by open fields, woods, and nontidal marshes. It encompasses about 460 acres at the southern end of Gunpowder Neck Peninsula. The peninsula is surrounded by tidal estuaries on three sides — Gunpowder River to the west and Chesapeake Bay to the south and east.

The Toxic Burning Pits (TBP) area, one of the designated areas of concern at J-Field, is located on about 9 acres in the southern portion of J-Field. This area was used to dispose of bulk chemical wastes, drummed chemical wastes, high explosives, various chemical agents, and chlorinated solvents. The TBP location contains several potential source areas of contamination, including five burning pits, a pushout area, a storage area, a disposal area, and a demolition area.

Results from the remedial investigation (Yuen et al. 1996) indicate that the principal contaminant sources at the TBP area are surface and subsurface soils associated with the two main pits and the pushout area. Surface soil is the environmental medium of greatest concern; soil contaminants include heavy metals and organic compounds. These contaminants may be released by surface runoff, precipitation infiltration, and gaseous emission of volatile organic compounds. Contaminant transport from these sources has resulted in contamination of sediments and surface water in the marsh-pond ecosystem that borders the pushout area and the southern boundary of the site. Surface water and sediments are contaminated primarily with heavy metals; some organic compounds have also been detected.

This report presents the focused feasibility study (FFS) for the TBP area at J-Field. The purpose of this study is to develop and evaluate potential remedial action alternatives to address surface soil contamination at three source areas within the J-Field TBP area: the northern main pit, the southern main pit, and the pushout area. Other source areas and contaminated media at the TBP area are outside the scope of this interim remedial action and will be addressed as part of the long-term remediation for J-Field.

## **S.2 FOCUSED FEASIBILITY STUDY APPROACH**

The initial task of the FFS was to develop remedial action objectives and define the scope of the proposed action given the information available from the remedial investigation, human health and ecological risk assessments, and earlier investigations. Interim preliminary remediation goals (PRGs) were developed for each contaminant of concern (COC) on the basis of risk to human and ecological receptors and probable future land use. The objectives and scope (Section S.3) guided the subsequent tasks of identifying and screening remedial action technologies (Section S.4), assembling and screening preliminary remedial action alternatives (Sections S.5 and S.6), conducting treatability studies, and evaluating the final remedial action alternatives. The last step in the evaluation process was a comparative analysis of alternatives (Section S.7).

## **S.3 INTERIM REMEDIAL ACTION OBJECTIVES**

### **S.3.1 Objectives and Scope**

The overall objectives of the proposed interim remedial action at the TBP area of J-Field are to:

- Reduce exposure of human and environmental receptors to surface contamination in three source areas: the northern main pit, the southern main pit, and the pushout area;
- Minimize the potential for contaminant migration via sediment transport from these areas;
- Minimize the potential for contaminant migration via downward leaching through these areas; and
- Support long-term site remediation.

Three source areas of contamination at the TBP area are the subject of this FFS: the northern main pit, the southern main pit, and the pushout area. Two additional pits in the pushout area have been filled in and are partially covered by soil pushed out from the main pits. Preliminary results of human health and ecological risk assessments (ICF Kaiser Engineers 1995a; Hlohowskyj et al. 1996) indicate that contaminated surface soil in these areas should be addressed to protect human health and the environment. An interim remedial action could be implemented that would achieve the objectives stated above.

Preliminary area and volume estimates for these areas are presented in Table S.1. Figure S.1 shows the areas with metal concentrations that exceed the mean regional background as reported by ICF Kaiser Engineers (1995b). The figure also includes areas with levels of contaminants that exceed the interim PRGs reported in Table S.2. The interim PRGs developed for surface soils at the TBP area (Section S.5) were used to determine which source areas should be cleaned up as part of the interim action and which could be appropriately left in their current condition until further action is taken at the site as part of the long-term remediation for J-Field.

### **S.3.2 Preliminary Remediation Goals**

For the TBP area, human health-based interim PRGs for soil were developed by using the risk-based soil concentrations derived by the U.S. Environmental Protection Agency (EPA) Region III. EPA Region III derives the risk-based values by following the Superfund risk assessment guidelines (EPA 1989a,b) and standard default assumptions (EPA 1991a); the values are based on carcinogenic and noncarcinogenic effects of ingesting “industrial” soil (as opposed to residential soil).

Two approaches were employed to develop ecological risk-based interim PRGs for the TBP area: (1) use of the contaminant uptake models developed for the ecological risk assessment to back-calculate acceptable surface soil concentrations and (2) use of the human health-based interim PRGs for COCs for which uptake modeling was not performed. In this latter approach, risk reduction for ecological resources is considered to be directly correlated with the reduction of contaminant concentrations or with removal of contaminated media. Thus, reducing surface soil contaminant concentrations to the levels of the human health risk-based interim soil PRGs would also reduce risk for ecological resources. In both approaches, each derived interim soil PRG was screened against the regional background soil concentration of that contaminant, and the greater of the two values was selected as the interim PRG.

Table S.2 integrates the ecological and human health risk-based PRGs and presents an overall list of preliminary interim soil PRGs for the TBP area. The identified interim soil PRG for each COC is the lower of the human health and ecological risk-based interim PRGs. These interim PRGs are initial guidelines and are not intended to set final cleanup levels or to establish that cleanup to meet these goals is warranted (EPA 1991b, 1994).

**TABLE S.1 Estimated Areas and Volumes of Contaminated Surface Soil at the Main Pits and Pushout Area**

Contaminated Surface Soil Interval <sup>a</sup>	Contaminants of Concern	Area (ft <sup>2</sup> )	Volume (yd <sup>3</sup> )
0-6 in.	Metals, organics	218,300	4,043
6-24 in.	Metals, organics	208,600	11,590


<sup>a</sup> See Figure S.1 for location of excavation area.

## S.4 POTENTIALLY APPLICABLE TECHNOLOGIES


Remedial technology types and process options that are potentially applicable to addressing contaminated soil at the TBP area were identified and screened on the basis of effectiveness, implementability, and cost and for applicability to specific site conditions in accordance with EPA guidance (1988). The current understanding of contaminants and conditions at the site suggested that the general response actions that could be implemented to achieve the project objectives (Section S.3) are institutional controls, in-situ containment, removal, treatment, short-term storage, and disposal. Specific application of these technologies to site conditions was evaluated to determine which would be most appropriate for interim remedial action at the TBP area. The technology types retained through the screening process include institutional controls (access restriction, ownership and use or deed restriction, and monitoring); in-situ containment (surface control diversions, vertical barriers, and caps); removal (excavation, and clearing and grubbing); ex-situ treatment (stabilization/fixation, soil washing, soil leaching, incineration, and thermal desorption); short-term storage (on-site open and closed structures); and disposal (off-site land-based facility). These technologies were combined to develop preliminary interim remedial action alternatives for the TBP area.

## S.5 DESCRIPTION OF ALTERNATIVES

Preliminary alternatives for remediating surface soil at the TBP area were developed and screened in accordance with CERCLA, EPA guidance (1988), and the National Oil and Hazardous Substances Pollution Contingency Plan (EPA 1990). Five preliminary alternatives were developed and screened on the basis of implementability, effectiveness, and cost. These alternatives are described briefly in the following subsections.



**FIGURE S.1(a) Contaminated Surface Soil, 0-6 in., to Be Addressed by the Proposed Action at the TBP Area**



**FIGURE S.1(b) Contaminated Surface Soil, 6-24 in., to Be Addressed by the Proposed Action at the TBP Area**

**TABLE S.2 Risk-Based Interim Preliminary Remediation Goals (PRGs) for Surface Soil at the TBP Area**

Contaminant	Interim PRG (mg/kg)
Volatile and semivolatile organic compounds	
Trichloroethene	1.3 <sup>a</sup>
2-Methylnaphthalene	NA <sup>b</sup>
Explosive	
Nitroglycerin	NA
Inorganic materials	
Aluminum	7,940 <sup>c</sup>
Antimony	3.7 <sup>a</sup>
Arsenic	3.8 <sup>d</sup>
Barium	64.4 <sup>a</sup>
Beryllium	1.3 <sup>d</sup>
Cadmium	0.34 <sup>c</sup>
Chromium	16.7 <sup>c</sup>
Cobalt	25.0 <sup>a</sup>
Copper	100 <sup>a</sup>
Cyanide	1.0 <sup>a</sup>
Lead	58.7/400 <sup>e</sup>
Mercury	0.04 <sup>c</sup>
Selenium	0.20 <sup>c</sup>
Silver	2.0 <sup>a</sup>
Zinc	37.0 <sup>c</sup>

<sup>a</sup> Interim PRG is ecological risk-based (see Table 3.5).

<sup>b</sup> NA = No interim PRG developed. Insufficient data to develop ecological risk-based interim PRG, and no EPA Region III human health-based PRG has been developed (see Table 3.2).

<sup>c</sup> Ecological risk-based PRG value is below mean background concentration; interim PRG is mean background concentration.

<sup>d</sup> Interim PRG is human health-based (see Table 3.2).

<sup>e</sup> The ecological risk-based PRG is 58.7 mg/kg (see Table 3.5). EPA currently recommends a soil cleanup value of 400 mg/kg for residential land use (see Table 3.2). The cleanup goal for lead has been as high as 1,000 mg/kg at other APG sites (Wrobel 1995).

### **S.5.1 Alternative 1: No Action**

Alternative 1 is included to provide a baseline for comparison with the other action alternatives. Under this alternative, the site would continue to operate under restricted access. Current conditions of the contaminated surface soil would continue. The baseline condition of the J-Field TBP area would include only minor maintenance activities, such as mowing and monitoring.

### **S.5.2 Alternative 2: Limited Removal and Disposal, and In-Situ Containment**

Under Alternative 2, contaminated surface soil in the two main pits and pushout area would be contained in place with a protective soil cover. Limited excavation and disposal would be implemented to address contaminated soil in the main pits (specifically arsenic and polychlorinated biphenyls [PCBs]).

The “risk-reduction cover” would involve placing a geotextile fabric over the vegetation-cleared surface (about 5 acres) and covering it with a layer of soil sufficient to raise the site topography above the 100-year floodplain. The soil layer would be stabilized with a vegetative cover. Runoff from the area would be diverted by surface grading controls. Erosion of contaminated soil from the portion of the pushout area in contact with the marsh would be mitigated by installing a vertical barrier. Because the soil layer would be emplaced incrementally in 2-ft layers, UXO screening most likely would not be required for this component. A UXO survey would be required for the limited excavation component, especially if conventional equipment were used. The area of excavation would be limited, so hand removal methods could be used (if the density of metal contacts present is high). The limited disposal component under Alternative 2 would involve shipping about 400 yd<sup>3</sup> of soil to a permitted off-site facility for treatment (stabilization and possibly incineration) and disposal.

Stabilization of the shoreline to the south of the TBP area would also be implemented as part of this alternative. Installation of a boulder riprap berm would reduce the potential for long-term erosion along the shoreline.

### **S.5.3 Alternative 3: Removal and Short-Term Storage**

Under Alternative 3, contaminated surface soil in the two main pits and pushout area that exceeds soil cleanup criteria would be removed and transported to an on-site, short-term storage facility, where it would be stored until final remediation is addressed at J-Field.

Soil would be excavated to a depth of 2 ft from the source areas with standard earthmoving equipment, such as front-end loaders, scrapers, and backhoes. The excavation area would be

surveyed for UXO in the upper 2 to 4 ft. Approximately 16,000 yd<sup>3</sup> of soil would be removed. The short-term storage facility would be constructed adjacent to the Prototype Building to minimize the distance the material would have to be transferred. The short-term facility would be a modular building consisting of fabric walls. The base of the structure would require the construction of a bermed and drained concrete or asphalt pad equipped with a leachate collection system. An air infiltration system might also be required.

#### **S.5.4 Alternative 4: Removal, On-Site Treatment, and Limited Disposal**

Under Alternative 4, contaminated soil in the two main pits and pushout area that exceeds soil cleanup criteria would be removed and treated by soil washing/leaching to reduce the volume of waste for off-site disposal.

The removal component of Alternative 4 would be similar to that of Alternative 3; however, the excavated soil would be transported to an on-site soil washing/leaching treatment facility, which would be constructed adjacent to the Prototype Building. For the conceptual design, it was estimated that 16,000 yd<sup>3</sup> of soil would be treated. After removal and treatment, the cleaned material would either remain on-site to be used as fill (pending a treatability variance or CERCLA waiver) or be shipped to an off-site solid waste disposal facility, in accordance with the State of Maryland's preference. Limited disposal under Alternative 4 would involve shipping recovered lead, scrap metal, and other (nonhazardous) refuse, as necessary, to an off-site facility (smelter and/or municipal landfill). A portion of the soil from the southern main pit, contaminated with PCBs, would also be sent off-site for treatment and disposal.

#### **S.5.5 Alternative 5: Removal, Off-Site Treatment, and Disposal**

Under Alternative 5, contaminated soil in the two main pits and pushout area that exceeds soil cleanup criteria would be removed and transported to an off-site treatment and disposal facility.

The removal component of Alternative 5 would be similar to that of Alternative 3; however, the excavated soil would be temporarily staged on-site following excavation, then transported to an off-site treatment and disposal facility.

### **S.6 IDENTIFICATION OF FINAL ALTERNATIVES**

On the basis of the screening analysis for preliminary alternatives, all five of the preliminary alternatives were retained for detailed analysis. Although the no-action alternative (Alternative 1) would not be protective of human health and the environment in the long term, it was

retained through this screening to provide a basis for comparison with the remaining action alternatives during the subsequent detailed analysis. Alternatives 2 and 3 were retained because they offer low-cost options for reducing risk; however, Alternative 3 it is not considered effective in the long term and would thus require an additional action at a future date. Alternatives 4 and 5 were retained because they offer permanent solutions to surface soil contamination; however, these alternatives are fairly costly.

## **S.7 EVALUATION SUMMARY AND COMPARATIVE ANALYSIS**

Table S.3 provides the comparative analysis of the five remedial action alternatives. The analysis is summarized as follows.

All of the final remedial action alternatives for the TBP area, except for the no-action alternative (Alternative 1), satisfy the threshold criteria for protecting human health and the environment and complying with regulatory requirements, with waivers as appropriate. Overall protectiveness would be comparable for Alternatives 2, 4, and 5. Alternative 3 is protective in the short term but would require an additional component (e.g., off-site treatment and disposal) to be as protective as Alternatives 4 and 5.

Only Alternatives 2, 4, and 5 are expected to provide a permanent solution that would ensure protection for a very long time; however, long-term effectiveness under Alternative 2 could be affected by the potential for flooding. It is possible that the soil washing/leaching treatment under Alternative 4 would be more protective than Alternative 5 if, at some future date, the stabilized/solidified waste were to be exposed to the environment and the contaminants leached. However, appropriate design and good engineering practices would minimize the likelihood of such an occurrence.

Each action alternative would reduce contaminant mobility. Under Alternative 2, waste toxicity and volume would be only somewhat reduced. Under Alternative 3, waste volume would not be affected. Under Alternative 4, waste volume would decrease. Waste volume would increase under Alternative 5 because of the addition of cement and fly ash to stabilize the waste. Treatment methods under Alternatives 2, 4, and 5 would reduce contaminant toxicity; under Alternative 4, metals would be recovered and recycled.

The short-term effectiveness of Alternatives 2 through 5 would be comparable. The overall risk to the general public would be higher for Alternative 5 because it involves off-site transport of a large volume of contaminated soil. Environmental impacts at the TBP area from excavation and construction activities would be common for all action alternatives, and comparable impacts would be expected. Mitigative measures would be used to minimize potential short-term impacts.

Emplacement of the “risk-reduction cover” under Alternative 2 would be straightforward, as would construction of the storage facility under Alternative 3. Implementing Alternative 4 would also be fairly straightforward, although additional studies would be required to refine the soil washing/leaching treatment system design and cost estimates. The chemical stabilization/solidification treatment that would be performed off-site under Alternative 5 is fairly well established and would not require further development before implementation.

Alternative 2 has the lowest overall estimated cost (\$1.8 million) of the action alternatives; however, this estimate only includes projected costs for the next 30 years and is not directly comparable to Alternatives 3, 4, and 5 (for excavation to 2 ft). Alternative 5 is considered more cost-effective than Alternative 4 for site cleanup. The estimated total cost of Alternative 5 is \$10.5 million (for excavation to 2 ft), and it would provide a similar level of overall effectiveness as Alternative 4, which would cost an estimated \$13.1 million.

TABLE S.3 Comparative Analysis of Alternatives

Alternative 1: No Action	Alternative 2: Limited Removal and Disposal, and In-Situ Containment	Alternative 3: Removal and Short-Term Storage	Alternative 4: Removal, On-Site Treatment, and Limited Disposal	Alternative 5: Removal, Off-Site Treatment, and Disposal
<b><i>Overall Protection of Human Health and the Environment</i></b>				
Would not ensure protection of human health and the environment in the long term. Source areas would not be removed or treated, and exposures could increase over time.	Engineering and mitigative measures would be employed during the remedial action period so that no significant adverse impacts would occur to the general public or environment. Worker exposures would be similarly controlled to levels within health-protective limits. Long-term exposures would be minimized by removing "hot spots" (arsenic and PCBs) from the main pits and by covering remaining contaminated soil with a protective soil cover.	Generally similar to Alternative 2. Long-term exposures would be minimized by removing and storing contaminated soil from the main pits and pushout area for about 5 years. At the end of that time, an additional component (e.g., off-site treatment and disposal) would be needed to ensure long-term protection.	Generally similar to Alternatives 2 and 3. Long-term exposures would be minimized by removing and treating contaminated soil from the main pits and pushout area.	Generally similar to Alternatives 2, 3, and 4. Treatment and disposal of a large volume of contaminated soil would be conducted off-site; therefore, the overall risk of exposure to the general public would be higher than that for Alternatives 2, 3, and 4.
<b><i>Compliance with ARARs</i></b>				
Would not meet all ARARs, including the corrective action requirements of RCRA and TSCA. In addition, would not satisfy the CERCLA-mandated preference for remedies that reduce contaminant toxicity, mobility, or volume through treatment.	Would meet all pertinent ARARs (with waivers as appropriate), including those that address protection of endangered species and habitats, floodplains, and wetlands. Implementing Alternative 2 might require preparation of a sediment and erosion control plan.	Same as Alternative 2. The on-site storage facility would be operated to ensure compliance with RCRA.	Same as Alternatives 2 and 3. The on-site treatment facility would be operated to ensure compliance with RCRA.	Same as Alternatives 2, 3, and 4, with additional disposal requirements that would be met, including RCRA hazardous waste generator.

TABLE S.3 (Cont.)

Alternative 1: No Action	Alternative 2: Limited Removal and Disposal, and In-Situ Containment	Alternative 3: Removal and Short-Term Storage	Alternative 4: Removal, On-Site Treatment, and Limited Disposal	Alternative 5: Removal, Off-Site Treatment, and Disposal
<b>Long-Term Effectiveness and Permanence</b>				
Current exposures and impacts would continue and could increase over time because of continued contaminant migration. Existing institutional controls would continue to limit access to site workers and other authorized personnel, thereby reducing risk to the general public.	More protective than Alternatives 1 and 3 because contaminated soil would be partially removed; the remaining soil then would be covered to reduce exposure of human and environmental receptors to surface contamination. Soil cleanup criteria would be applied to the removal of soils and to the delineation of the area to be covered.	More protective than Alternative 1 because contaminated soil would be removed and stored in an enclosed facility to provide an interim solution for risk posed by contaminated surface soil. Soil cleanup criteria would be applied as appropriate to the removal of soils, so the action would reduce contaminant concentrations remaining in soil to the most protective levels practicable.	More protective than Alternatives 1 and 3 because contaminated surface soil would be removed and treated (soil washing/leaching) to provide a permanent solution for risk posed by contaminated surface soil. Soil cleanup criteria would be applied as appropriate to the removal of soils, so the action would reduce contaminant concentrations remaining in soil to the most protective levels practicable.	Similar to Alternative 4, except that exposure of stabilized/solidified waste to the environment could result in contaminants leaching from the waste over time.
<b>Reduction of Toxicity, Mobility, or Volume</b>				
Toxicity, mobility, and volume of contaminated soil would not change.	The in-situ containment component would significantly reduce contaminant mobility. Contaminant volume would be somewhat reduced by the limited removal and disposal component. Contaminant toxicity would not be reduced.	Short-term storage of soil in an on-site facility would significantly reduce contaminant mobility. An estimated 16,000 yd <sup>3</sup> (27,200 tons) of soil would be stored on-site for about 5 years. Contaminant toxicity and volume would not be reduced.	Chemical treatment of soil by soil washing/leaching would significantly reduce contaminant mobility and volume. An estimated 16,000 yd <sup>3</sup> (27,200 tons) of soil would be treated on-site by soil washing/leaching. This process could reduce original soil volume by about 94%; the remaining 6% could then be sent off-site for disposal. Toxicity of PCBs would be reduced. Lead toxicity would not be reduced; however, the metal would be removed and recycled.	Chemical treatment of soil with the stabilization/solidification technology would significantly reduce contaminant mobility. An estimated 16,000 yd <sup>3</sup> (27,200 tons) of soil would be treated off-site by chemical stabilization/solidification. This process could increase the original soil volume and weight by as much as 30% and 60%, respectively. This would result in a total treated volume of about 20,800 yd <sup>3</sup> and total weight of about 35,360 tons to be placed in a landfill. Contaminant toxicity would not be reduced.

TABLE S.3 (Cont.)

Alternative 1: No Action	Alternative 2: Limited Removal and Disposal, and In-Situ Containment	Alternative 3: Removal and Short-Term Storage	Alternative 4: Removal, On-Site Treatment, and Limited Disposal	Alternative 5: Removal, Off-Site Treatment, and Disposal
<i>Short-Term Effectiveness</i>	<p>Exposures would be lower than for Alternatives 3, 4, and 5, which involve large-scale excavation. Mitigative measures would still be required in the short term because of particulate and VOC emissions associated with removal and transportation activities. No adverse impacts to the general public are expected from contaminant releases during implementation of this alternative. Soil, vegetation, and wildlife disturbances would be significant during soil excavation activities. An estimated 5 acres would be affected. Most impacts to biota would be temporary. Surface water impacts associated with the construction of a berm along the pushout-marsh boundary would be minimal (and localized). Surface water input would be reduced, but reduction in erosion and transport of soils into the marsh would be a benefit to the marsh ecosystem. Mitigative measures would be implemented to minimize impacts to air quality and those associated with noise levels.</p>	<p>Exposures could be higher than Alternatives 1 and 2 in the short term because of particulate and VOC emissions associated with removal, transportation, and storage activities. Mitigative measures would be implemented to minimize potential human health and environmental impacts. Risks to a site worker would increase compared to Alternative 1; however, worker health and safety precautions would be used to control exposures. No adverse impacts to the general public are expected from contaminant releases during implementation of this alternative. Soil, vegetation, and wildlife disturbances would be significant during soil excavation activities. An estimated 5 acres would be affected. Most impacts to biota would be temporary. Activities are not expected to affect threatened or endangered species. Mitigative measures would be employed to minimize impacts to surface water resources (including the adjacent marsh), air quality, and those associated with noise levels.</p>	Similar to Alternative 3.	<p>Similar to Alternatives 3 and 4, except that overall risk to the general public would be higher because this alternative would involve the off-site transport of a large volume of contaminated soil. Additional mitigative measures would be implemented to reduce related impacts.</p>

TABLE S.3 (Cont.)

Alternative 1: No Action	Alternative 2: Limited Removal and Disposal, and In-Situ Containment	Alternative 3: Removal and Short-Term Storage	Alternative 4: Removal, On-Site Treatment, and Limited Disposal	Alternative 5: Removal, Off-Site Treatment, and Disposal
<b>Implementability</b>				
Minimum site operations (monitoring and maintenance) would continue with the use of readily available resources.	Fairly straightforward to implement. Resources are readily available for UXO screening, soil removal, in-situ containment, and shoreline stabilization.	Fairly straightforward to implement. Resources are readily available for UXO screening, soil removal, and on-site storage. Short-term storage facilities are available as kits and can be customized to meet project specifications.	Similar to Alternative 3. Soil washing/leaching has been used at several hazardous waste sites and probably would not require further development before it could be implemented at the TBP area. Further bench-scale testing would be required to refine and optimize the design of the treatment system.	Similar to Alternatives 3 and 4. Chemical stabilization/solidification is an established technology and would not require further development before it could be implemented.
<b>Cost</b>				
The total cost would be the lowest in the short term (about \$3 million over a 10-year period), but the comparative level of effectiveness would be low. In addition, the cost could be potentially higher than the action alternatives over the long term because conditions could worsen over time, necessitating an expensive expanded response in the future.	The total cost would be about \$1.8 million, the lowest of all the action alternatives. This cost, however, reflects only O&M costs for the next 30 years. Because contaminated soil would remain in place, O&M costs would likely extend indefinitely into the future. Repairs associated with the catastrophic effects of a 100-year flood (should such occur) are not reflected in this estimate.	The total cost would be about \$5.0 million (for 16,000 yd <sup>3</sup> of soil), the second lowest of all the action alternatives. This cost, however, does not include the cost of an additional component (off-site treatment and disposal) that would be needed to ensure long-term protectiveness and permanence. Therefore, while this alternative would achieve project objectives of reducing exposures and minimizing contaminant migration at a low cost, it is considered the least cost-effective because additional components would be required when the 5-year storage period ended.	The total cost would be about \$13.0 million (for 16,000 yd <sup>3</sup> of soil), which is the highest of the action alternatives. The soil washing/leaching component would account for 86% of the total direct cost of this alternative.	The total cost would be about \$10.5 million (for 16,000 yd <sup>3</sup> of soil), which is lower than Alternative 4 for the same overall level of effectiveness. Off-site treatment and disposal would account for 85% of the total direct cost of this alternative.

## S.8 REFERENCES FOR SUMMARY

Hlohowskyj, I., et al., 1996, *Remedial Investigation Report for J-Field, Aberdeen Proving Ground, Maryland, Volume 2: Ecological Risk Assessment*, draft prepared by Argonne National Laboratory, Argonne, Ill., for U.S. Army, Aberdeen Proving Ground, Md., Directorate of Safety, Health, and Environment.

ICF Kaiser Engineers, 1995a, *J-Field Toxic Burn Pits Baseline Human Health Risk Assessment*, draft prepared for U.S. Army Environmental Center, Aberdeen Proving Ground, Md., Aug.

ICF Kaiser Engineers, 1995b, *Reference Sampling and Analysis Program at the U.S. Army Aberdeen Proving Ground, Soil, Sediment, and Surface Water Reference Data Report*, prepared for U.S. Army Environmental Center, Aberdeen Proving Ground, Md., July.

U.S. Environmental Protection Agency, 1988, *Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA*, Interim Final, EPA/540/G-89/004 (OSWER Directive 9355.3-01), Office of Emergency and Remedial Response, Washington, D.C., Oct.

U.S. Environmental Protection Agency, 1989a, *Risk Assessment Guidance for Superfund*, Vol. I, *Human Health Evaluation Manual*, Part A, EPA/540/1-89/002, Office of Emergency and Remedial Response, Washington, D.C., Dec.

U.S. Environmental Protection Agency, 1989b, *Risk Assessment Guidance for Superfund*, Vol. II, *Environmental Evaluation Manual*, EPA/540/1-89/001, Office of Emergency and Remedial Response, Washington, D.C., March.

U.S. Environmental Protection Agency, 1990, "National Oil and Hazardous Substances Pollution Contingency Plan; Final Rule (40 CFR Part 300)," *Federal Register*, 55(35):6154-6176, Feb. 21.

U.S. Environmental Protection Agency, 1991a, *Human Health Evaluation Manual, Supplemental Guidance: Standard Default Exposure Factors*, OSWER Directive 9285.6-03, Office of Emergency and Remedial Response, Washington, D.C., March 25.

U.S. Environmental Protection Agency, 1991b, *Risk Assessment Guidance for Superfund*, Vol. 1, *Human Health Evaluation Manual*, Part B, *Development of Risk-Based Preliminary Remediation Goals*, EPA/540/R-92/003, Office of Emergency and Remedial Response, Washington, D.C., Dec.

U.S. Environmental Protection Agency, 1994, *Revised Interim Soil Lead Guidance for CERCLA Sites and RCRA Corrective Action Sites*, OSWER Directive 9355.4-12, Office of Emergency and Remedial Response, Washington, D.C., Aug.

Wrobel, J., 1995, personal communication from Wrobel (Directorate of Safety, Health, and Environment, U.S. Army Aberdeen Proving Ground, Md.) to L. Martino (Argonne National Laboratory, Argonne, Ill.), July 15.

Yuen, R., et al., 1996, *Remedial Investigation Report for J-Field, Aberdeen Proving Ground, Maryland, Volume 1: Remedial Investigation Results*, draft prepared by Argonne National Laboratory, Argonne, Ill., for U.S. Army, Aberdeen Proving Ground, Md., Directorate of Safety, Health, and Environment.

## 1 INTRODUCTION

### 1.1 BACKGROUND


The Environmental Management Division (EMD) of Aberdeen Proving Ground (APG), Maryland, is conducting a remedial investigation and feasibility study (RI/FS) of the J-Field area at APG pursuant to the Comprehensive Environmental Response, Compensation, and Liability Act, as amended (CERCLA). J-Field is located within the Edgewood Area of APG in Harford County, Maryland (Figure 1.1). Since World War II, activities in the Edgewood Area have included the development, manufacture, testing, and destruction of chemical agents and munitions. These materials were destroyed at J-Field by open burning/open detonation (OB/OD). Portions of J-Field continue to be used for the detonation and disposal of unexploded ordnance (UXO) by OB/OD under authority of the Resource Conservation and Recovery Act (RCRA).

J-Field is almost flat and is covered by open fields, woods, and nontidal marshes. It encompasses about 460 acres at the southern end of the Gunpowder Neck Peninsula (Figure 1.1). The peninsula is surrounded by tidal estuaries on three sides — Gunpowder River to the west and Chesapeake Bay to the south and east.

The Toxic Burning Pits (TBP) area, one of the designated areas of concern (AOCs) at J-Field, is located on about 9 acres in the southern portion of J-Field (Figure 1.2). This area was used to dispose of bulk chemical wastes, drummed chemical wastes, high explosives, various chemical agents, and chlorinated solvents. The TBP location contains several potential source areas of contamination, including five burning pits (two main pits and the methylphosphonothioic acid [VX], mustard, and liquid smoke pits), a pushout area, a storage area, a disposal area, and a demolition area.

### 1.2 PURPOSE OF THIS REPORT

The purpose of this focused feasibility study (FFS) is to develop and evaluate potential remedial action alternatives to address surface soil contamination at three source areas within the J-Field TBP area: the northern main pit, the southern main pit, and the pushout area. The FFS report documents this process; its purpose is to provide sufficient information to support an informed decision regarding an appropriate interim remedial action for these areas.



**FIGURE 1.1** Location of J-Field in the Edgewood Area at APG




FIGURE 1.2 Locations of Principal Site Features at J-Field

### 1.3 ORGANIZATION OF THIS REPORT

Section 1 of this report presents background information and summarizes the purpose of the proposed action within the context of the RI/FS process. Section 2 describes the site history and environmental setting. The environmental setting includes site topography, soil, surface water, geology and hydrogeology, groundwater, climate, ecology, and land use. Also provided are an overview of available information about the nature and extent of contamination at the TBP area and a discussion of exposure pathways. Contaminants of concern (COCs) are also identified in Section 2.

Section 3 describes the overall objectives of the interim remedial action. Other site aspects discussed include applicable or relevant and appropriate requirements (ARARs), to-be-considered requirements (TBCs), and the development of interim preliminary remediation goals (PRGs). In

Section 4, potentially applicable technologies are screened on the basis of effectiveness, implementability and cost, and site-specific conditions. Section 5 describes and screens the preliminary interim remedial action alternatives.

Section 6 provides a detailed description of the final interim remedial action alternatives. These alternatives are evaluated in Section 7 against nine general criteria: overall protection of human health and the environment; compliance with ARARS; long-term effectiveness and performance; reduction of contaminant toxicity, mobility, and volume through treatment; short-term effectiveness; implementability; and cost. The discussion of state and community acceptance has been deferred and will be addressed in the Responsiveness Summary prepared for the Record of Decision (ROD) for the site. Section 8 presents a comparative analysis.

All references cited in this report are listed in Section 9, and a list of preparers is given in Section 10. Appendix A evaluates potential metal transport via leaching through the unsaturated zone at the TBP area. Appendix B provides tables summarizing preliminary identification of ARARs and TBCs for J-Field. Appendix C consists of data summary tables for the TBP area. Appendix D describes the RI characterization activities and sampling results at the TBP area. Appendix E explains the uptake model and approach used to develop ecological-based interim PRGs. The methodology and assumptions used to determine the costs of the interim remedial action alternatives are presented in Appendix F. Appendix G gives conversion factors between metric and English units of measure.

## 2 SITE BACKGROUND


### 2.1 SITE HISTORY

Disposal operations at the TBP area began in the 1940s and continued until about 1980. The pits were used most extensively between the late 1940s and 1960s. Items disposed of included bulk chemical wastes, drummed chemical wastes, high explosives (HE) (by OB/OD), nerve agents, incapacitating agents (also known as riot-control agents), chlorinated solvents, and blister agents (Nemeth 1989).

Information from interviews, sampling, geophysical surveys, and analysis of historical aerial photographs indicates that five disposal pits were used at the TBP area (Figure 2.1). The two existing (or main) burning pits, each covering an area of about 4,500 ft<sup>2</sup>, were most actively used for the disposal of various chemical agents and explosives. These pits are referred to as the northern and southern main pits in this report and are the only visible open pits in this area. Two other burning pits (the VX and mustard pits, Figure 2.1) are buried. The liquid smoke disposal pit, a small pit measuring 4 × 6 ft, has also been reported (Nemeth 1989); however, its specific location is not clear. In the HE demolition ground, near the southern edge of the site (Figure 2.1), HE munitions were disposed of by detonation (Nemeth 1989). The TBP storage area, a fenced area near the southwestern end of the mustard pit, was used for storage, as evidenced by historical aerial photographs taken in the 1960s (U.S. Army 1965). A scrap metal mound has been observed in the field near the southwestern portion of the site, adjacent to the marsh. This area (the TBP southwestern suspect burning area, Figure 2.1) was probably active in the 1950s and 1960s, as indicated by historical aerial photographs, and may have been used for burning and/or demolition. A small square pit, measuring about 3.5 × 4.25 ft, lies between the southwestern suspect burning area and monitoring well P9. This feature is believed to be the liquid smoke disposal pit.

Procedures for open burning in the TBP area involved placing 3-4 ft of wood dunnage in a pit, placing the materials to be burned on top of the dunnage, adding fuel oil, and igniting it. Scrap metal items were removed and reburned in the same manner. Large metal items were recovered and disposed of as scrap. The depths of the pits were maintained by pushing burned soil and ash out toward the adjacent marsh. The areas where this material now resides are referred to collectively as the "pushout" area (Figure 2.1). The pushout area associated with the four burning pits occupies about 100,000 ft<sup>2</sup> and extends more than 100 ft into the marsh (Sonntag 1991). Currently, the pushout area shows obvious signs of disturbance, including an uneven surface, areas of bare ground, and disposal debris (e.g., rebar, sheet metal, and rusted pipes).

An agent known as DANC (decontaminating agent, noncorrosive) was commonly used to decontaminate scrap metal contaminated with mustard, Lewisite, and VX (Nemeth 1989). DANC



**FIGURE 2.1** Locations of Main Features and Monitoring Wells at the TBP Area

is an organic N-chloroamide compound in solution with 1,1,2,2-tetrachloroethane (TCLEA); it typically contains 90-95% (by weight) TCLEA.

## 2.2 SITE DESCRIPTION

### 2.2.1 Topography

J-Field is nearly flat, with a maximum relief of about 10 ft. The elevation in the TBP area ranges from about 14 ft above mean sea level (MSL) near the main pits to bay level at the shore. The adjacent marsh and freshwater pond are at an elevation of about 5 ft above MSL during wet periods.

### 2.2.2 Soil

The APG was not mapped in the most recent Harford County soil survey (Smith and Matthews 1975). However, a previous survey by Perkins and Winant (1927) includes the APG. Their map indicates that the surface of J-Field comprises fairly equal areas of Elkton silt loam, Sassafras loam, and tidal marshes, with minor areas of Sassafras silt loam. Smith and Matthews (1975) describe the Elkton soil as slowly permeable and poorly drained. The Sassafras soils are moderately permeable and well drained. The tidal marsh soil is sandy to clayey, with peat or muck.

### 2.2.3 Surface Water

Surface water features at J-Field include freshwater marshes, a marsh pond, and two unnamed streams that discharge into the Bush River (Figure 1.1). The freshwater marsh and pond along the southern shore near the TBP area are separated from Chesapeake Bay by sandy beaches. Because the beach acts as a dam, this marsh typically has water levels about 2 ft above high tide (Hughes 1993a). The large pond in this marsh has a maximum depth of about 5 ft. Other large marshes are present along J-Field's eastern and western shores. Water levels in these marshes are tidal influenced (Hughes 1993b). The streams along the eastern coast of J-Field are also affected by tides. Discharge is minimal except during heavy rainfalls (Hughes 1993a). The TBP area is located within the 100-year floodplain (Federal Emergency Management Agency [FEMA] 1986).

A tidal measuring station, located on Pooles Island (about 1 mi southeast of J-Field), shows that the difference between the mean high tide and the mean low tide is about 1.2 ft (National Oceanic and Atmospheric Administration [NOAA] 1993). The average level of the surrounding estuaries at Pooles Island is about 0.9 ft above MSL (Hughes 1993c). Vroblesky et al. (1989) determined an average bay level of 1.5 ft above MSL at an APG site north of J-Field. Hughes (1993b) suggested that the bay level measured by Vroblesky et al. was higher because the tide station for the study was located on an inland creek and not in the bay or estuary.

The depth of water in the Gunpowder River and Chesapeake Bay proper within 0.5 mi of J-Field's shores is generally shallower than 12 ft below mean lower low water (NOAA 1993).<sup>1</sup>

### 2.2.4 Geology and Hydrogeology

The stratigraphy at J-Field consists of Pleistocene sediments of the Talbot Formation underlain by Cretaceous sediments of the Patapsco Formation (Potomac Group). The Pleistocene deposits are divided into three main units: a surficial, unconfined aquifer of interbedded sand, clay,


---

<sup>1</sup> "Mean lower low water" refers to the mean of the lower of the two daily low tides.

and silt; a confining unit of sandy and silty clay; and a confined sand and gravel aquifer (Hughes 1993a). On the basis of current knowledge of contaminant distribution, groundwater studies have focused on the surficial aquifer. The generalized stratigraphy in the TBP area is shown in Figure 2.2.

The deeper Talbot deposits fill a paleochannel eroded into the Patapsco sediments. Pleistocene paleochannels are common in the region (Kerhin et al. 1988), and similar features have been identified at other APG study areas (Lorah and Clark 1992; Vroblesky et al. 1989; Oliveros and Vroblesky 1989). Hughes (1991, 1992, 1993a) performed a marine seismic survey around the J-Field peninsula to determine the offshore extent of the geologic units. The seismic data suggest that the confining unit and the confined aquifer pinch out against the sides of a southwest-trending paleochannel. The width of this feature is approximately 1 mi.

Several monitoring wells were installed in the TBP area during the field investigations conducted at J-Field (Figure 2.1). One TH-series well (TH4) was installed near the TBP area by the U.S. Army Toxic and Hazardous Materials Agency (USATHAMA) during a 1977 environmental survey. Five additional wells (P1-4, 9) were installed by Princeton Aqua Science (1984). These wells



**FIGURE 2.2** Generalized Hydrogeologic Cross Section and Direction of Groundwater Flow at J-Field TBP Area (Source: Modified from Hughes 1993a)

are all screened in the surficial aquifer to a maximum depth of 20 ft; they do not penetrate the confining unit.

The U.S. Geological Survey (USGS) installed five monitoring well nests (JF4-JF8), each consisting of three wells, in each of the three main Pleistocene units (Hughes 1993a). The well screens range in length from 3 to 5 ft. Hughes estimated hydraulic conductivities for these units based on slug tests performed in these and other J-Field monitoring wells.

In 1993, well JF173 was installed southeast of the main pits to monitor for dense, nonaqueous-phase liquids (DNAPLs) at the base of the surficial aquifer. The well is screened over a 5-ft interval, ranging from a depth of 26 to 31 ft (Patton 1994). Well JF183 was installed for use as a pumping well for the pumping test conducted in 1994; it is screened across the entire depth of the surficial aquifer.

In early 1996, wells JF201 and JF203 were installed adjacent to well TH4. Well JF203 is shallow, installed to replace the sediment-filled TH4. Well JF201 was installed to a depth of 165 ft to assess the confined aquifer.

#### **2.2.4.1 Surficial Aquifer**

The surficial aquifer is composed of medium- to fine-grained sand with interbedded clay (Hughes 1993a). The sand is generally red to gray in color; the clay is dark to light gray. The sandy facies are commonly silty or clayey. Hughes suggests that these sediments were deposited in an estuarine or marginal marine system during a period of higher sea level. A 10-ft vertical exposure of this unit can be viewed along the coast west of the TBP area. Here the stratigraphy is mainly reddish silt with fine sand. A 1-ft clay layer is also present. The depositional units appear to be continuous along the 50-ft length of the 10-ft-high cliff.

The total thickness of the surficial aquifer in the TBP area ranges from 30 to 40 ft. The USGS data suggest a basal contact elevation of 25-31 ft below MSL. Clay or silt units with thicknesses of up to 8 ft have been logged within this unit.

The hydraulic conductivity of the surficial aquifer has been estimated in several ways. Hughes (1993a) measured it to be in the range of  $1.0 \times 10^{-4}$  to  $3.7 \times 10^{-4}$  cm/s (0.29 to 1.04 ft/day), with a median of  $2.4 \times 10^{-4}$  cm/s (0.69 ft/day). These values are typical of silty sand or silt (Freeze and Cherry 1979). Because of the problems inherent in slug testing of wells, the results often underestimate the horizontal conductivity (Bradbury and Muldoon 1990; Hughes 1993b). During calibration of a draft modeling study, a value of  $2.8 \times 10^{-3}$  cm/s (8 ft/day) was assigned to this unit (Hughes 1993b). A pump test at well JF183, installed in 1994, indicated a hydraulic conductivity

of  $1.9 \times 10^{-3}$  cm/s (5.3 ft/day) (Quinn 1995). This value is consistent with a silty to clean sand (Freeze and Cherry 1979).

Despite the available data, the permeability of the surficial aquifer at the TBP area and throughout most of J-Field is uncertain. Because of the arrangement of interbedded facies, the permeability of the surficial aquifer varies over several orders of magnitude laterally and vertically. Any measurement of permeability is highly spatially dependent because of location-specific stratigraphy and well construction factors, including the depth interval of the well screen.

The flow rate produced by the pump test well was low. A yield of 2 gpm could not be sustained during a step drawdown test. The constant-rate pump test was completed with a flow rate of 1 gpm.

Continuous-head recordings available from the USGS for the 1993 water year indicate that the head in the surficial aquifer in the TBP area is more than 6 ft above MSL during a wet springtime and approximately 1 ft below MSL during August and September, when high evapotranspiration rates prevail.

The surficial aquifer receives most of its recharge by infiltration of precipitation; however, during dry periods, water levels in wells may be slightly lower than bay level (Hughes 1993a). A flow reversal may take place during these periods, with flow from the tidal estuaries providing recharge to the aquifer.

Under Maryland Code of Regulations 26.08.02.09, the surficial aquifer at J-Field is classified as a Type II(b) aquifer (Lemaster 1995). A Type II(b) aquifer has a transmissivity between 1,000 and 10,000 gal/day/ft, a permeability greater than 100 gal/day/ft<sup>2</sup>, and natural water with a total dissolved solids concentration of between 500 and 1,500 mg/L.

#### **2.2.4.2 Confining Unit**

The confining unit contains silty and sandy clay with shell fragments and varying amounts of organic matter. The clay is dark gray or olive gray in color. Hughes (1993a) interprets the sediment to be an estuarine deposit.

The basal contact elevation of the confining unit in the TBP area ranges from 64 ft to deeper than 145 ft below MSL (according to logs for well JF201). The thickness of this unit in the TBP area ranges from 35 ft in the northwestern portion of the area to greater than 125 ft in the southeastern portion. The thickness apparently depends on the depth of paleochannel erosion into the Potomac Group.

Slug tests performed by Hughes (1993a) on three wells in this unit yielded hydraulic conductivity values of less than  $3 \times 10^{-6}$  to  $7.0 \times 10^{-5}$  cm/s (0.01-0.20 ft/day), with a median value of  $1.8 \times 10^{-5}$  cm/s (0.05 ft/day). These values fall into the typical range of fine-grained materials (Freeze and Cherry 1979). Hughes (1993c) suggests that the slug test generally provides an estimate of horizontal conductivity, so the vertical conductivity may be much less. A value of  $1.8 \times 10^{-6}$  cm/s ( $5 \times 10^{-3}$  ft/day) used by Hughes (1993b) is comparable to that of Vroblesky et al. (1989), who modeled a nearby clay-filled estuarine paleochannel with a vertical hydraulic conductivity of  $6.8 \times 10^{-8}$  cm/s ( $2 \times 10^{-4}$  ft/day).

#### 2.2.4.3 Confined Aquifer

The confined aquifer consists of gravelly sand with some clay and clayey sand. The confined aquifer is a fluvial deposit that blankets the bottom of a paleochannel identified by marine seismic and exploratory borings.

The thickness of the confined aquifer cannot be determined with USGS cluster well data because the confined aquifer monitoring wells do not fully penetrate the aquifer. Data from a deep USGS exploratory boring located near cluster JF8 (Figure 2.1) indicate that the base of the confined aquifer near the pits is about 120 ft below MSL (Hughes 1993a).

Slug tests were performed in four J-Field wells screened in the confined aquifer (Hughes 1993a). Hydraulic conductivity values determined for two wells completed in permeable portions of the aquifer were  $3.9 \times 10^{-2}$  and  $3.2 \times 10^{-1}$  cm/s (110 and 930 ft/day), with a median of  $1.3 \times 10^{-1}$  cm/s (390 ft/day). Hydraulic conductivity values determined for two other wells screened in fine-grained zones were  $1.1 \times 10^{-3}$  and  $1.8 \times 10^{-2}$  cm/s (3.2 and 52 ft/day), with a median of  $3.9 \times 10^{-3}$  cm/s (11 ft/day).

#### 2.2.4.4 Cretaceous Sediments

The Cretaceous Patapsco Formation sediments beneath J-Field are alluvial deposits of interbedded fine-grained sand and massive clay (Hughes 1993a). The Cretaceous clays are differentiated from Pleistocene clays by color in the USGS stratigraphic logs. Rather than the dark and olive gray of the confining unit, the Patapsco clays vary among reddish brown, light gray, white, light red, and olive yellow. The top of the Cretaceous sediments dips from 105 ft below MSL in the western portion of J-Field to 157 ft in the east (Hughes 1993a). Interpretation of gamma logs of the exploratory boreholes suggests that the sands range from 2 to 30 ft thick and that the clays range from 5 to 45 ft thick. Stratigraphic cross sections suggest that the various lenses are highly discontinuous laterally (Hughes 1993a). The Cretaceous deposits are underlain by metamorphic rock at a depth of about 800 ft.

### **2.2.4.5 General Groundwater Flow**

Field measurements of heads at J-Field indicate that groundwater flow is generally from topographically high areas to topographically low areas, such as marshes and estuary discharge areas (Hughes 1993a). In the TBP area, the water table has a local high in the area between the main pits and the Prototype Building. No pumping stresses are imposed on the Talbot aquifers at or in the vicinity of J-Field. The nearest pumping wells are 4 mi away, across the Gunpowder River (Hughes 1993a).

A comparison of the heads of wells screened in the three Pleistocene units indicates a downward gradient, suggesting leakage from the surficial aquifer into the confining unit and confined aquifer (Hughes 1993a). However, in wetlands and estuaries, flow is assumed to be vertically upward as groundwater flows from the deeper units to the discharge areas. The vertical head gradient within the surficial aquifer currently cannot be determined because only one well is screened in the surficial aquifer at each USGS well nest.

Hughes (1993a) describes the head distribution pattern in the confining unit and the confined aquifer as generally similar to that of the surficial aquifer. A low lateral head gradient was observed, so lateral flow is minimal. Discharge is believed to occur through the confining unit into the estuaries. During dry periods, flow reversals occur as the heads in the surficial aquifer fall slightly below those in the confined aquifer.

The tide in the bay influences water levels in some wells screened in the surficial aquifer at J-Field. The degree of influence depends on the distance from the shore and the presence of fine-grained confining or semiconfining units within the surficial aquifer. Continuous-head data are available from USGS for two wells (JF63 and JF43) in the TBP area. Stratigraphic logs for these wells indicate that they are screened in and overlain by fine sand (Hughes 1993a). The heads do not demonstrate the two highs and lows per day expected for tidally influenced wells. These data suggest that the distance from the shore to the TBP area is sufficient to negate tidal influence.

Hughes (1993a) did not observe tidal effects in wells screened in the confining unit. The confined aquifer, however, exhibited a strong tidal influence in continuous water-level data from six confined-aquifer monitoring wells. The heads fluctuate over a range of about 0.75 ft. Over a two-day period, the water levels in the wells show a high degree of similarity independent of distance from the shoreline. The head changes are therefore attributed to tidal loading on the confined aquifer.

### **2.2.5 Climate**

The Harford County area has a continental-type climate with significant temperature contrasts between winter and summer (Smith and Matthews 1975). The average daily high and low

are 65°F and 42°F, respectively. The average annual temperature is about 54°F. The average annual precipitation of 45 in./year is distributed fairly uniformly throughout the year.

## **2.2.6 Ecology**

Ecological surveys were conducted at J-Field as part of the overall site ecological risk assessment (ERA), and the results of these surveys are presented in the draft ERA report (Hlohowskyj et al. 1996). The following subsections (2.2.6.1 through 2.2.6.4) summarize the ecological setting of the TBP area on the basis of the results presented in that report.

### **2.2.6.1 Terrestrial Habitats**

Terrestrial habitats at the TBP area include grassland and forested plant communities and represent less than 0.02% of the available terrestrial habitat at J-Field. The area immediately surrounding the main pits comprises disturbed habitats consisting exclusively of mowed and unmowed grassland with patches of bare ground. The areas of bare ground are located mainly in the pushout area, where a variety of disposal debris, such as rebar, sheet metal, and rusted pipes, is present. The grassland is bordered to the south, east, and north by marsh habitat, with a narrow band of upland forest occurring between the marsh and grassland habitat along the southern and southeastern boundary of the area. Dominant woody species in the forested habitats include black gum, sycamore, sweetgum, red and white oaks, and black tupelo.

### **2.2.6.2 Freshwater Habitats and Wetlands**

The freshwater marsh southeast of the main pits and largely surrounding the pushout area is the major nontidal freshwater habitat in the southern portion of the Edgewood Peninsula. No other freshwater habitats are present at the main pits and pushout area. A large freshwater pond occurs near the center of the marsh. The pond is classified as an intertidal estuarine permanently flooded wetland (Hlohowskyj et al. 1996). The areal extent of the pond varies seasonally with changes in the water table and precipitation periods, averaging about 2.5 acres. No permanent surface water connections exist between the pond and Chesapeake Bay, although occasional connection is possible during very high tides and during extremely heavy rains. The marsh is classified as an intertidal estuarine wetland irregularly flooded by tides (Hlohowskyj et al. 1996). Common reed, the dominant plant species (Van Lonkhuyzen 1994), forms floating mats in some parts of the marsh. Palustrine forested and scrub/shrub seasonally flooded wetlands are also present along portions of the perimeter of the marsh, particularly along the southern and northern boundaries of the TBP area.

### 2.2.6.3 Fish and Wildlife

More than 40 mammal, 22 reptile, and 15 amphibian species have been reported from the APG (USATHAMA 1993), and many of these species may occur at J-Field and use portions of the TBP main pits and pushout area.

Small mammals that have been collected from the TBP area include the white-footed mouse, meadow vole, and short-tailed shrew. Red fox and feral house cats have been observed at the TBP area, while bats have been observed flying over the site (Hlohowskyj et al. 1996). Although white-tailed deer, raccoon, muskrat, gray squirrel, and eastern chipmunk may occasionally forage at the site, the main pits and pushout area provide little or no habitat for these species.

The main pits and pushout area may provide seasonal or year-round habitat for a variety of reptile and amphibian species, primarily the American toad, northern spring peeper, spotted salamander, eastern box turtle, and a number of snake and lizard species; however, use of the main pits and pushout area by these species is most likely limited. In contrast, the marsh and pond represent good habitat for a variety of reptiles and amphibians, including bullfrog, leopard frog, eastern painted turtle, and common snapping turtle. The surrounding wooded areas also provide habitat for a variety of species.

Although more than 40 species of fish have been reported to occur in the APG area, most of these species are found in Chesapeake Bay and the Gunpowder and Bush Rivers. Fish collected from the marsh pond adjacent to the pushout areas include the bluespotted sunfish, banded killifish, spottail shiner, and golden shiner (Hlohowskyj et al. 1996).

The APG site is located along the Atlantic Flyway, a major migration corridor used by birds in spring and autumn. Because of the presence of the flyway and the diversity of habitat types in the vicinity, more than 140 species of birds have been reported from the APG (USATHAMA 1993), and many may use J-Field as foraging or nesting habitat. Qualitative auditory and visual surveys of birds were conducted in all seasons at the TBP area, and more than 110 species were reported from the site (Hlohowskyj et al. 1996). Birds reported for the area included mourning doves, American robins, eastern bluebirds, eastern kingbirds, and a variety of sparrows. Hawks that are known to nest in the J-Field area and may use the TBP area include the American kestrel and red-tailed hawk. Although osprey are known to nest at J-Field, it is unlikely that the osprey would feed on any of the fish species collected to date from the pond, primarily because of the small size of the fish.

A large variety of waterfowl occurs in the areas surrounding J-Field. The State of Maryland has designated Pooles Island, located about 1.5 km (1 mi) south of the Edgewood Peninsula and the TBP area, as a "Colonial Waterbird Nesting Site" (McKegg 1992). In addition, the open water areas north of the J-Field site have been identified by the state as a "Historic Waterfowl Staging and Concentration Area" (McKegg 1992). Waterfowl and shorebirds that have been reported from the

area and observed in the vicinity of the TBP area include mallard, tundra swan, wood duck, and great blue heron (Hlohowskyj et al. 1996). The small size of the pond, however, probably limits its use by large numbers of shorebirds or waterfowl.

#### 2.2.6.4 Threatened and Endangered Species

No mammals, amphibians, or reptiles identified on the State of Maryland's rare, threatened, and endangered list have been reported for the J-Field area (Maryland Department of Natural Resources [MDNR] 1992). The bobcat, classified as in need of conservation by Maryland (MDNR 1992), has been reported for the general vicinity of APG (USATHAMA 1993) but not for the J-Field site. The eastern harvest mouse, listed by Maryland as endangered, historically has been reported for the area, but is now considered extirpated from the state (MDNR 1992). A number of bird species reported from the APG are state-listed species (MDNR 1992), including the barn owl (watchlist), sora (highly rare), dark-eyed junco (rare), and northern harrier (rare), and the grassland habitats at the pushout area and adjacent marsh provide suitable habitat for these species. The dark-eyed junco and the northern harrier were observed at the TBP area during the avian surveys conducted at the site. Table 2.1 identifies state and federally listed bird species that have been reported for APG.

**TABLE 2.1 Bird Species of Special Federal and State Concern Reported at APG**

Common Name	Scientific Name	State Status <sup>a</sup>	Federal Status
Bald eagle	<i>Haliaeetus leucocephalus</i>	Endangered	Threatened
Common barn owl	<i>Tyto alba</i>	Watchlist	Not listed
Common moorhen	<i>Gallinula chloropus</i>	Needs conservation	Not listed
Dark-eyed junco	<i>Junco hyemalis</i>	Rare	Not listed
Golden-crowned kinglet	<i>Regulus satrapa</i>	Rare	Not listed
Loggerhead shrike	<i>Lanius ludovicianus</i>	Endangered	C2 <sup>b</sup>
Northern harrier	<i>Circus cyaneus</i>	Rare	Not listed
Peregrine falcon	<i>Falco peregrinus</i>	Endangered	Endangered
Sharp-shinned hawk	<i>Aegolius acadicus</i>	Highly rare	Not listed
Sora	<i>Porzana carolina</i>	Highly rare	Not listed
Yellow-bellied sapsucker	<i>Sphyrapicus varius</i>	Historical	Not listed
Yellow-rumped warbler	<i>Dendroica coronata</i>	Uncertain	Not listed

<sup>a</sup> Source: MDNR (1992).

<sup>b</sup> C2 = Federal candidate for listing as a threatened or endangered species.

Several federally listed species are known to occur at the APG and may forage in suitable habitats near the TBP area (MDNR 1992; Wolflin 1992; USATHAMA 1993) (Table 2.1). The peregrine falcon is federally listed as endangered. No suitable habitat for the peregrine falcon occurs at the Edgewood Peninsula or the J-Field site; however, this species may be an occasional visitor to the area, especially during migration. The loggerhead shrike is a federal category 2 species that has been reported for APG and may forage in the TBP area. A federal category 2 species is a candidate for listing as either threatened or endangered. Neither the peregrine falcon nor the loggerhead shrike were observed at the TBP area during the avian surveys at the site.

APG supports the most significant concentration of bald eagles (federally listed as threatened) on the northern Chesapeake Bay (Wolflin 1992). A bald eagle nest site is located approximately 1.5 km (1 mi) north of the J-Field site. Occupation by the bald eagle is light to moderate on Pooles Island and the shoreline areas of the Edgewood Peninsula (Wolflin 1992). The bald eagle may forage on waterfowl at the marsh and pond adjacent to the pushout area but is unlikely to use the immediate TBP area because of the absence of suitable habitat and because of human activities at the site and surrounding areas.

### 2.2.7 Land Use

The lower portion of the Edgewood Peninsula is generally dedicated to a military test range, with no resident population and only a limited number of site workers; however, the range fields offer restricted, seasonal accessibility to a limited number of hunters. Upland game hunting and bow hunting of deer and woodchuck are allowed along the northern border of (but not within) J-Field and farther north on the peninsula. Blinds for hunting deer with guns are scattered throughout the peninsula, including several locations in the northern portion of J-Field. However, the J-Field blinds are no longer available to hunters; hunting and trapping are no longer allowed within the J-Field boundary (Wrobel 1994). Seasonal hunting of migratory waterfowl is permitted along the entire shoreline of J-Field.

Although most of the AOCs are no longer used for OB/OD, a portion of the Robins Point Demolition Ground is currently active and is operating under interim status under RCRA. An open burning pan located 50 m west of the Prototype Building and an open detonation area at the White Phosphorus Pits area are also being used for emergency disposal operations.

Recent remedial activities at O-Field have required rerouting Robins Point Road through N-, D-, and I-Fields; the firing range; and H-Field; thus making J-Field less accessible. These changes in the main access route to J-Field will most likely preclude any future development of the J-Field site in the near term. In the long term, disturbances due to testing at H- and I-Fields make development of the J-Field site unlikely.

## 2.3 NATURE AND EXTENT OF CONTAMINATION

The following subsections summarize what is currently known about the nature and extent of contamination at the TBP area. Because the focus of this report is to address contaminated surface soil in the main pits and pushout area, the discussion of soil is most detailed. Site characterization data collected from 1993 to 1995 are presented in Appendix C. Appendix D, which is based on the draft RI report (Yuen et al. 1996), provides more details (including locations of samples) on the results of the RI at the TBP area.

### 2.3.1 Soil

As part of the J-Field RI, soil samples have been collected from the TBP area and analyzed for various constituents. This discussion is divided into sections for the northern main pit, the southern main pit, and the pushout area east of the main pits to describe the contaminants found at each area. Two additional pits, the VX pit and the mustard pit, occur within the pushout area. These pits have been filled in and are partially covered by soil pushed out from the main pits. A brief discussion of these pits is included in Section 2.3.1.3.

#### 2.3.1.1 Northern Main Pit

Soil borings ranging in depth from 4 to 12 ft were drilled in six locations (JBP2-W, JBP2-C, JBP2-E, TBNPBOR1, TBNPBOR2, and TBNPBOR3; see Figure D.5) within the northern main pit as part of the RI. Samples taken from the borings indicate that contamination in the pit is not homogeneous. In general, contamination is higher in the western portion of the pit than in the eastern portion. The highest levels of volatile organic compound (VOC) contamination occur in sample TBNPBOR3 at the depth interval between 4 and 10 ft. Contaminants include acetone (up to 6,000 µg/kg at 8-10 ft), tetrachloroethylene (TCLEE) (up to 750 µg/kg at 6-8 ft), chlorobenzene (up to 23,000 µg/kg at 4-6 ft), ethyl benzene (up to 6,600 µg/kg at 6-8 ft), toluene (up to 4,200 µg/kg at 6-8 ft), and total xylenes (up to 46,000 µg/kg at 6-8 ft). Other VOCs, present at lower concentrations, include 1,1-dichloroethylene (11DCE), 12DCE, chloroform, TCLEA, and trichloroethylene (TRCLE). Semivolatile organic compounds (SVOCs) were also highest in sample TBNPBOR3 and include bis(2-ethylhexyl) phthalate (up to 1,900 µg/kg at 6-8 ft), 2-methylnaphthalene (up to 2,100 µg/kg at 6-8 ft), and naphthalene (up to 1,800 µg/kg at 6-8 ft).

Metal contamination in soil underlying the northern main pit reflects a similar pattern as exhibited by the VOCs: contamination is highest in the western and central portions of the pit. The highest levels of heavy metal contamination occur in the upper 4 ft of soil. Metals include arsenic (up to 2,290 mg/kg), cadmium (up to 77 mg/kg), chromium (up to 240 mg/kg), copper (up to 7,120 mg/kg), lead (up to 4,790 mg/kg), and zinc (up to 17,800 mg/kg). In general, concentrations

of these metals decrease with depth, although elevated concentrations of metals were detected at depths of up to 12 ft. Toxicity characteristic leaching procedure (TCLP) analyses indicate high leachate levels of arsenic (155-216 µg/L), lead (1,620-26,500 µg/L), and cadmium (16.4-187 µg/L). The soil is therefore considered hazardous (i.e., characteristically toxic) with respect to lead and cadmium.

Low levels of PCBs (<10 mg/kg at 0-2 ft) and dioxin/furan compounds (< 5 µg/kg at 4-6 ft) were also detected in the western portion of the northern main pit. One sample (TBNPBOR3) had a total petroleum hydrocarbon (TPH) concentration of 19,000 mg/kg at 4-6 ft.

### **2.3.1.2 Southern Main Pit**

Soil borings ranging in depth from 4 to 10 ft were drilled in five locations (JBP1-W, JBP1-E, JHDP-C, TBSPBOR1, and TBSPBOR2; see Figure D.5) within the southern main pit as part of the RI. In general, the highest levels of VOC contamination are in the eastern portion of the pit. Although no VOC contamination was present at the surface, VOC concentrations were found to generally increase with depth. The highest concentrations of VOCs, found in the eastern portion of the pit, include 12DCE (8,400 µg/kg at 10 ft), trans-12DCE (3,220 µg/kg at 6 ft), 1,1,2-trichloroethane (112TCE) (8,540 µg/kg at 6 ft), TCLEA (3,270,000 µg/kg at 6 ft), TCLEE (25,700 µg/kg at 6 ft), TRCLE (263,000 µg/kg at 6 ft), and vinyl chloride (302 µg/kg at 6 ft). SVOCs were highest in the upper 2 ft; these include N-nitrosodiphenylamine (up to 950 µg/kg), hexachloroethane (up to 580 µg/kg), and pyrene (up to 580 µg/kg).

In general, heavy metals contamination is lower in the southern main pit than in the northern main pit; the highest levels occur in the upper 4 ft of soil. Metals include arsenic (up to 28.2 mg/kg), cadmium (up to 7 mg/kg), copper (up to 366 mg/kg), lead (up to 831 mg/kg), and zinc (up to 1,240 mg/kg). In general, metal concentrations decreased with depth in the southern main pit.

PCBs (e.g., Aroclor 1254) were found in the upper 4 ft in the eastern portion of the southern main pit (in sample JBP1-E, collected by Weston, Inc., in 1993). Sampling indicates a fairly localized area of PCB contamination in the surface soil.

### **2.3.1.3 Pushout Area East of Main Pits**

Surface soil samples collected by Weston, Inc., in 1992 indicate that VOC contamination is present in the upper 1 ft of the pushout area soil; these include acetone (up to 1,460 µg/kg), TCLEA (up to 13,200 µg/kg), and TRCLE (up to 26,000 µg/kg). SVOCs were also detected: hexachloroethane (up to 498 µg/kg), phenanthrene (up to 311 µg/kg), and pyrene (up to 215 µg/kg). Figure D.4 shows the locations of all samples collected within the pushout area.

Sampling in the pushout area also indicates that concentrations of heavy metals in the upper 4 ft exceed background concentrations (Table 2.2). The eastern portion of the pushout area exhibits the highest concentrations, although elevated concentrations were found throughout. In the upper 2 ft, metals include arsenic (up to 41 mg/kg), copper (up to 4,320 mg/kg), and lead (up to 94,000 mg/kg). TCLP analyses indicate that pushout area soil is hazardous with respect to lead. The vertical extent of metal contamination in soil is related to the thickness of the pushout material and increases toward the marsh. In general, metal concentrations decrease with depth.

Low levels of PCBs (Aroclor 1248, up to 3 mg/kg in sample JBPMA) were found in the upper 1 ft (Figure D.6). Low levels of pesticides were also found in the upper 1 ft (4,4'-dichlorodiphenyltrichloroethane [DDT], up to 177 µg/kg in sample JBPMA). No explosives were detected in the surface soil samples.

Within the pushout area are two buried pits: the VX pit and the mustard pit (Figure 2.1). These pits were delineated during the RI by aerial photographic analysis (Yuen et al. 1996) and geophysical surveys (Daudt et al. 1994; Davies et al. 1995). Four surface soil samples (OT16A,

**TABLE 2.2 Mean and Maximum  
Background Soil Concentrations of Metals  
Reported for Off-Site Areas  
Surrounding APG**

Metal	Concentration in Soil (mg/kg)	
	Mean	Maximum
Aluminum	7,940	17,300
Antimony	3.14	<9.8
Arsenic	2.57	5.29
Barium	43.6	125
Beryllium	0.44	1.42
Calcium	534	1,980
Chromium	16.8	68.9
Copper	8.72	27.5
Iron	12,300	23,500
Lead	21.6	117
Magnesium	1,010	3,920
Manganese	276	1,140
Mercury	0.04	<0.14
Nickel	8.37	24.1
Potassium	384	1,700
Selenium	0.21	0.497
Zinc	37	242

Source: ICF Kaiser Engineers (1995a).

OT16B, OT19A, and OT19B; see Figure D.4) were collected from two locations near the VX pit. Five borings (VXBOR1-VXBOR5; see Figure D.5), ranging in depth from 4 to 16 ft, were drilled into the VX pit as part of the RI. The nature of contamination at the VX pit was only partially characterized due to the potential presence of UXO (especially in the area of VXBOR3 and VXBOR4). On the basis of available data, the bottom of the VX pit is inferred to be about 4-6 ft below the ground surface.


Soil samples from the VX pit indicate that contamination is highest at the disposal center within the pit (near borings VXBOR3 and VXBOR4). In this area, surface soil is contaminated with moderate to high levels of heavy metals (including copper, up to 343 mg/kg; lead, up to 262 mg/kg; and zinc, up to 1,629 mg/kg), low levels of chlorinated ethenes and ethanes, petroleum-related compounds (including benzene, up to 42 µg/kg; ethyl benzene, up to 2,900 µg/kg; and xylenes, up to 2,300 µg/kg), low levels of dioxins and furans, low levels of pesticides, 1,4-dithiane (a chemical warfare agent [CWA] degradation product), and phthalates. The vertical extent of contamination is estimated to be deeper than 6 ft. Near the disposal center, in areas near the western end of the pit, metal contamination is limited to the upper 2 ft, while organic contamination is minimal. The TPH content is high at depth.

Five surface soil samples (CLP6 [0-6 in.], CLP6 [6-24 in.], CLP7 [0-6 in.], CLP7 [6-24 in.], and CLP7 [24-48 in.]; see Figure D.4) were collected at two locations near the mustard pit. Three borings (HBOR1-HBOR3; see Figure D.5), ranging in depth from 10 to 16 ft, were drilled near the mustard pit (because of the potential presence of UXO, no borings were taken from within the pit). The bottom of the mustard pit is estimated to be about 4-6 ft below the ground surface.


Soil samples from the mustard pit indicate that heavy metals (including arsenic, up to 16 mg/kg; copper, up to 204 mg/kg; lead, up to 4,960 mg/kg; and zinc, up to 896 mg/kg) are present, especially in the upper 2 ft. Contamination decreases with depth and was not detected below 6 ft in the three borings. Very low levels of petroleum-related compounds and phthalates were detected in the upper 2 ft. Low levels of chlorinated ethanes and ethenes were detected in surface and subsurface soil. Low levels of CWA degradation products (diisopropylmethyl phosphonate and 1,4-dithiane) were also detected in samples taken at a depth of 6 ft.

#### 2.3.1.4 Summary


Figures 2.3 and 2.4 illustrate the extent of metal contamination at two depth intervals (0-6 in. and 6-24 in., respectively), which exceeds the mean background values given in Table 2.2. The figures take into account the concentrations of several metals, including aluminum, arsenic, barium, cadmium, chromium, copper, lead, mercury, and zinc. The extent of contamination at these depth intervals is reduced when compared to maximum background values (Figures 2.5 and 2.6). Figure 2.7 shows an estimated area at 2-4 ft, which was inferred from limited soil sampling in the




**FIGURE 2.3 Estimated Contaminated Area at Depth Interval 0-6 in. with Heavy Metal Concentration Levels above Mean Background**




**FIGURE 2.4 Estimated Contaminated Area at Depth Interval 6-24 in. with Heavy Metal Concentration Levels above Mean Background**



**FIGURE 2.5 Estimated Contaminated Area at Depth Interval 0-6 in. with Heavy Metal Concentration Levels above Maximum Background**



**FIGURE 2.6 Estimated Contaminated Area at Depth Interval 6-24 in. with Heavy Metal Concentration Levels above Maximum Background**



**FIGURE 2.7 Estimated Contaminated Area at Depth Interval 2-4 ft with Heavy Metal Concentration Levels above Mean Background**

interval of 2-4 ft. This estimate also considered the contamination present in the overlying soil and the likelihood for contaminant mobility. At the interval of 2-4 ft, VOC contamination is also present (and may also be present in low concentrations in the interval of 0-2 ft).

### 2.3.2 Groundwater

Groundwater in the surficial aquifer in the TBP area is contaminated primarily with VOCs, particularly TCLEA (up to 260,000 µg/L in well JF83), 112TCE (up to 2,000 µg/L in well JF83), 12DCE (up to 37,000 µg/L in piezometer JFPM1A), TRCLE (up to 41,000 µg/L in well JF83), TCLEE (up to 3,400 µg/L in well P-3), and vinyl chloride (up to 3,200 µg/L in piezometer JFPM1A). Wells JF73 and JF83 and piezometer JFPM1A are located downgradient and about 200 to 400 ft from the two main pits.

### 2.3.3 Sediment

Sediment samples were collected from the marsh as part of the RI (Yuen et al. 1996; see Figure D.7). Marsh sediments adjacent to the pushout area show significantly high levels of heavy metals in the upper 2 ft of the sediment column, including arsenic (up to 14 mg/kg), lead (up to 1,780 mg/kg), copper (up to 515 mg/kg), and zinc (up to 3,410 mg/kg). These contaminants correlate well with those found in the pushout area, suggesting that erosion via surface runoff is the mechanism of transport for these contaminants. Low levels of organic contaminants were also detected, including 4,4'-dichlorodiphenyldichloroethane (DDD) (up to 22 µg/kg), 4,4'-dichlorodiphenyldichloroethylene (DDE) (up to 16 µg/kg), 12DCE (45 µg/kg), TRCLE (up to 29 µg/kg), and vinyl chloride (up to 18 µg/kg). In one surface sediment sample (TPSED1), 2,4-dinitrotoluene was found at a concentration of 2,110 µg/kg. A variety of polycyclic aromatic hydrocarbons (PAHs), including fluorene (410 µg/kg), chrysene (1,200 µg/kg), pyrene (up to 1,800 µg/kg), anthracene (up to 280 µg/kg), and the benzo- series (up to 2,300 µg/kg), were found at a depth of 2-4 ft in sample SEDBOR7-1 (Figure D.7).

### 2.3.4 Surface Water

Surface water samples from the adjacent marsh were also collected as part of the RI (Figure D.7). The samples were analyzed for organic compounds (VOCs, SVOCs, pesticides, and polychlorinated biphenyls [PCBs]) and inorganic materials (metals and cyanide). Several VOCs have been detected in the surface water, suggesting that contamination is migrating from the pit (source) areas via groundwater to the marsh. The organic contaminants detected include 12DCE (up to 1,700 µg/L), TRCLE (up to 3,615 µg/L), 112TCE (up to 138 µg/L), and TCLEA (up to 4,348 µg/L). SVOCs, pesticides, and PCBs were not detected. Lead (up to 1,590 µg/L), copper (up to 525 µg/L), and zinc (up to 4,040 µg/L) were also detected in several samples. The elevated concentrations of metals indicate that contamination has migrated to the marsh, most likely by surface runoff from the TBP and pushout areas.

## 2.4 CONTAMINATION SOURCES AND RELEASE MECHANISMS

Potential contamination sources identified in the RI include the two main pits, the mustard and VX pits, and their associated pushout areas; and a storage area, a disposal area, and an HE demolition area (Yuen et al. 1996; Figure 2.1). As described in the RI, surface and subsurface soil samples collected at the storage area did not indicate the presence of contamination. Soils from the HE demolition area showed concentrations of some metals above mean background levels but below maximum background levels (Table 2.2). The sources of contamination at the TBP area are the two main pits, the pushout area, the two buried pits within the pushout area (VX and mustard pits), and

the disposal area. The disposal area has not yet been fully characterized and is therefore not included in this FFS.

Release of contaminants from their primary source is most likely through lateral dispersion, surface runoff, leaching, and vertical infiltration. The lateral dispersion was enhanced by the pushout operations after each disposal/decontamination activity. Surface runoff is an important release mechanism for contaminants in the surface soil, especially in the pushout area. Leaching and infiltration are also important release mechanisms because fuel, liquid wastes (e.g., chlorinate solvents), and decontaminating agents (e.g., bleach and DANC) were used in the pits. These contaminants have been detected in groundwater downgradient of the site. A modeling study to evaluate the transport of metals through the vadose zone at the TBP area is presented in Appendix A.

## **2.5 POTENTIAL EXPOSURE PATHWAYS**

### **2.5.1 Human Exposure**

Even under current conditions of restricted site access, a number of potential human exposure pathways have been identified at the J-Field study area (ICF Kaiser Engineers 1994b). These pathways, summarized in Table 2.3, include the exposure routes of dermal contact, ingestion of soil and water, and inhalation of vapors and particulate matter. The most likely human receptors include site workers, trespassers, or persons fishing along the J-Field shoreline. Because J-Field is situated in a restricted area with a wide range of physical security measures (including patrols by military police), the likelihood of trespassing at J-Field is considered low. However, the trespasser scenario is being retained in this study to comply with U.S. Environmental Protection Agency (EPA) guidance (1991a) requiring consideration of trespassers in the baseline risk assessment (BRA). Hunters are no longer considered likely human receptors because hunting at J-Field has been banned (Wrobel 1994).

Preliminary investigations indicate that the potential for most human exposure pathways at J-Field ranges from no (or negligible) potential for significant exposure to low potential (ICF Kaiser Engineers 1994b). Incidental soil ingestion and/or dermal contact with soil by on-site individuals may have a low to moderate potential for significant exposure because of the elevated chemical concentrations detected in surface soil in the vicinity of the TBP area. In addition, incidental ingestion and/or dermal contact with contaminated surface water or sediments has an unknown potential for significant exposure because of the limited data currently available. Infrequent contact with these media (surface soil, sediments, and surface water) and the use of protective clothing by on-site workers during remediation activities would be expected to prevent significant exposures.

**TABLE 2.3 Potential Human Exposure Pathways at the TBP Area under Current Land-Use Conditions**

Medium	Chemical Release Source	Exposure Pathway/Receptor <sup>a</sup>
Soil (surface, subsurface)	Previous dumping and disposal activities	Incidental ingestion and/or dermal contact with surface soil by personnel working at site, persons fishing, and trespassers
	Aerial deposition from past explosions and fires	
Groundwater	Leaching of chemicals from contaminated soil and buried wastes	Although groundwater is contaminated, no exposure pathway exists because there is currently no human uses of groundwater at this site or in downgradient areas
Surface water/ sediments	Groundwater discharge to Gunpowder River, Bush River, or Chesapeake Bay	Incidental ingestion and/or dermal contact by site workers, persons fishing, and trespassers
	Surficial runoff of chemicals from disposal areas	
Food chain (fish/shellfish)	Uptake from food sources that have bioaccumulated chemicals	Ingestion of contaminated fish and shellfish caught by local fishermen from the Gunpowder River, Bush River, or Chesapeake Bay near J-Field
	Uptake of chemicals from exposure to contaminated media	
Air (vapor-phase, particulate matter)	Volatilization from subsurface wastes or soil	Inhalation of contaminated dust and vapors by site workers, persons fishing along the J-Field shoreline, and trespassers
	Volatilization of chemicals from groundwater that has discharged to surface water	
	Wind erosion of contaminated surface soil from disposal areas and spills	
	Dispersion and deposition of dust from destruction of explosive materials at Robins Point Demolition Ground	

<sup>a</sup> Hunters are no longer considered likely human receptors because hunting at J-Field has been banned (Wrobel 1994).

Source: Adapted from ICF Kaiser Engineers (1994b).

For the purpose of an interim remedial action, it is assumed that the most likely human exposure pathway is incidental ingestion of contaminated surface soil by site workers at the TBP area.

### **2.5.2 Ecological Exposure**

Of the 35 species of aquatic and terrestrial biota identified as ecological receptors for the J-Field site (Hlohowskyj et al. 1995), 17 are appropriate for evaluation of ecological exposure and risk at the TBP area (Table 2.4). Exposure routes identified and evaluated in the J-Field ERA include exposure to and uptake from soil, surface water, and sediment.

For this FFS, contaminated surface soils represent the ecological media of concern at the TBP area and may affect 11 of the 17 receptors identified for this area (Table 2.4). The principal exposure pathways to the ecological receptors at the site are the incidental ingestion of contaminated soil by terrestrial biota, root uptake of contaminants by vegetation, and food-chain transfer of contaminants to higher trophic levels. This latter pathway represents the major contaminant route to the birds of prey that may use the site. For example, soil contaminants may be taken up by vegetation, which in turn is consumed by mice, which constitute a large portion of the diet of the red-tailed hawk.

## **2.6 CONTAMINANTS OF CONCERN**

### **2.6.1 Human Health Contaminants of Concern**

COCs for soil were selected for the TBP area according to U.S. Environmental Protection Agency (EPA) Region III guidance for Superfund sites (EPA 1993a, 1995). Maximum chemical concentrations detected during the ongoing RI and earlier investigations of the TBP area were screened against EPA risk-based concentrations. EPA Region III guidance includes a database, updated semiannually, of approximately 600 contaminants in air, drinking water, fish tissue, and soil (EPA 1995). Risk-based concentrations for each contaminant were derived for the above exposure pathways corresponding to a hazard quotient of 1, or a lifetime cancer risk of  $10^{-6}$ , by using protective default exposure scenarios and the best available toxicity information (EPA 1993a).

Table 2.5 includes the maximum levels of all surface soil contaminants detected at least once in the TBP area. The maximum concentrations for surface soil (defined as 0-2 ft in depth) were screened against EPA's risk-based concentrations. Chemicals with maximum concentrations exceeding the risk-based concentrations were identified as COCs for surface-soil-related pathways

TABLE 2.4 Ecological Receptors for the TBP Area

Receptor	Habitat Type	Occurrence at the TBP Area	Exposure Point Media
Grasses ( <i>Andropogon</i> spp.)	Upland	Pushout area, main pits area	Soil
Maple ( <i>Acer</i> spp.)	Upland	Southern portion of area	Soil
Common reed	Wetlands	Marsh	Sediment
Phytoplankton and zooplankton	Quiet surface waters	Pond, marsh	Surface water
Golden shiner	Quiet surface waters	Pond, marsh, and marsh edges	Surface water
Leopard frog	Quiet surface waters	Marsh and pond margins	Surface water
Great blue heron	Surface waters and wetlands	Marsh and pond margins	Surface water
American kestrel	Semi-open grasslands	Pushout area, main pits area	Soil and surface water
Red-tailed hawk	Wetlands, grasslands, and forests	Entire area	Soil and surface water
American robin	Wetlands, grasslands, and forests	Entire area	Soil and surface water
Tree swallow	Grasslands with wooded edges or nearby woodlots	Entire area	Soil and surface water
Mallard duck	Wetlands with nearby grasslands	Pond, marsh, and pushout area	Soil, surface water, and sediment
White-tailed deer	Old fields, grasslands, and forests	Entire area	Soil and surface water
Muskrat	Surface waters and wetlands	Marsh, pond	Surface water and sediment
White-footed mouse	All upland habitats	Entire area	Soil and surface water
Eastern cottontail	Upland habitats and marsh edges	Entire area	Soil and surface water
Red fox	Wetlands, grasslands, and forests	Entire area	Soil and surface water

**TABLE 2.5 Identification of Human Health-Based Contaminants of Concern for Soil (0-2 ft) in the TBP Area**

Chemical	Maximum Concentration <sup>a</sup> (mg/kg)	Risk-Based Concentration <sup>b</sup> (mg/kg)	Contaminant of Concern
Volatile organic compounds			
Acetone	0.02	200,000	No
Benzene	0.1	200	No
2-Butanone	0.037	1,000,000	No
Carbon disulfide	0.038	200,000	No
Chlorobenzene	0.1	41,000	No
Chloroform	0.05	940	No
11DCE	0.10	9.5	No
trans-12DCE	0.17	18,000	No
Methylene chloride	0.10	760	No
TCLEA	2.5	29	No
TCLEE	1.0	110	No
Toluene	0.05	410,000	No
TRCLE	2.8	520	No
Xylenes	0.05	1,000,000	No
Semivolatile organic compounds			
Benzo(b)fluoranthene	1.25	7.8	No
Benzo(k)fluoranthene	1.25	78	No
Bis(2-chloroethyl)ether	1.25	5.2	No
Diethylphthalate	1.25	1,000,000	No
Fluorene	1.25	82,000	No
Hexachlorobenzene	3.1	3.6	No
Hexachloroethane	1.25	410	No
2-Methylnaphthalene	1.25	NA <sup>c</sup>	Yes
2-Methylphenol	1.25	100,000	No
4-Methylphenol	1.25	10,000	No
N-Nitrosodiphenylamine	0.95	1,200	No
Phenol	1.25	1,000,000	No
Pyrene	1.25	61,000	No
2,4,6-Trichloroaniline	7.9	170	No
Pesticide/PCB			
Aroclor 1248	0.57	0.74 <sup>d</sup>	No
Explosives			
Nitroglycerin	15.3	NA	Yes

TABLE 2.5 (Cont.)

Chemical	Maximum Concentration <sup>a</sup> (mg/kg)	Risk-Based Concentration <sup>b</sup> (mg/kg)	Contaminant of Concern
Inorganic materials			
Aluminum	22,600	1,000,000	No
Antimony	501	820	No
Arsenic	1,440	3.8	Yes
Barium	1,580	140,000	No
Beryllium	1.38	1.3	Yes
Cadmium	35.5	1,000	No
Calcium	36,000	— <sup>c</sup>	No
Chromium	878	10,000	No
Cobalt	108	120,000	No
Copper	4,320	82,000	No
Cyanide	120	41,000	No
Iron	154,000	610,000	No
Lead	94,200	400 <sup>f</sup>	Yes
Magnesium	3,880	— <sup>c</sup>	No
Manganese	633	10,000	No
Mercury	3.6	610	No
Molybdenum	6.9	10,000	No
Nickel	84.5	41,000	No
Potassium	1,460	— <sup>c</sup>	No
Selenium	7.12	10,000	No
Silver	41.9	10,000	No
Sodium	521	— <sup>c</sup>	No
Thallium	19.3	160 <sup>g</sup>	No
Vanadium	32.7	14,000	No
Zinc	17,800	610,000	No

<sup>a</sup> Maximum detected concentrations for surface soil samples (0-2 ft in depth). These values are taken from currently available data, excluding non-Contract Laboratory Program data collected by Weston.

<sup>b</sup> From EPA (1995), for "industrial" soil.

<sup>c</sup> NA = not available.

<sup>d</sup> Risk-based concentrations for PCB isomers are based on Aroclor mixtures.

<sup>e</sup> Risk-based concentrations for these compounds are not available due to low toxicity.

<sup>f</sup> EPA currently recommends a soil lead cleanup value of 400 mg/kg for residential land use but site-specific pharmacokinetic modeling for nonresidential (adult) screening, when necessary (EPA 1994).

<sup>g</sup> A risk-based concentration was not available for the class of thallium compounds, so the value for thallium sulfate was used instead.

of human exposure. In addition, except for several inorganic materials commonly found in soil (noted on Table 2.5), chemicals without a risk-based concentration were also included as COCs.

Although this approach is intended for use in BRAs (EPA 1993a), it is a conservative screening methodology that should be appropriate for identifying human health COCs for interim remedial action at the TBP area. The risk-based concentrations were derived by using conservative default exposure scenarios (EPA 1991a) and the most recent reference doses and carcinogenic potency slopes. Consequently, the risk-based concentrations “represent relatively protective environmental conditions at which EPA would typically not take action” (EPA 1993a). EPA Region III’s risk-based screening approach was also used to select COCs at J-Field for determining soil concentrations that would be protective of human health, especially for site remediation workers (ICF Kaiser Engineers 1994a).

In addition, the COC screening methodology assumes a scenario of surface exposures to site personnel and remediation workers (i.e., the use of maximum surface soil concentrations and ingestion of industrial soils). This approach is not intended to take into account potential contaminant leaching to the groundwater. In that case, soil screening levels for groundwater use (recently developed by EPA) would be used to screen for COCs. Because the available soil screening levels for transfers from soil to groundwater are often orders of magnitude lower, there would be additional COCs to evaluate if the groundwater pathway were considered (e.g., VOCs). Similarly, human health-based interim PRGs would be correspondingly lower. However, the surface exposure scenario developed in this report is appropriate for a removal action, supplemented by a BRA and sitewide FS that considers potential contaminant leaching to groundwater.

## **2.6.2 Contaminants of Ecological Concern**

The contaminants of ecological concern (COECs) in soils were identified for the TBP area by using data collected as part of the RI for J-Field (Yuen et al. 1996). These contaminants were identified by comparing measured soil concentrations with a number of chemical-specific factors, including background concentrations and screening benchmark values. The detection frequency, capacity to bioaccumulate or bioconcentrate, and importance as a micro- or macronutrient were also considered in the selection process. The procedure for selecting the COECs follows the general approach recommended by EPA in the Human Health Evaluation Manual (EPA 1989a) and EPA Region III guidance for identifying COCs (EPA 1993a) and is consistent with the screening approach used for the TBP area human health risk assessment (see Section 2.6.1 and ICF Kaiser Engineers 1995b).

Contaminant characterization data for soil were first evaluated with respect to analytical methods, detection limits, quality control (QC) samples, and blanks. Details regarding this portion

of the screening process are presented in the J-Field ERA report (Hlohowskyj et al. 1996). The following steps were then performed, in order, by using the remaining soil data for the TBP area:

- The detection frequency of each contaminant was evaluated, and all contaminants with detection frequencies of 0% were eliminated from further consideration in the ERA.
- Contaminant concentrations were compared to reported background concentrations (ICF Kaiser Engineers 1995a). The one-tailed nonparametric Mann-Whitney test (Zar 1984) was employed to test for similarity between background and site concentrations, and contaminants were retained for further screening if they were found to significantly ( $p < 0.05$ ) exceed background concentrations. However, if the sample size for a contaminant from a particular site and medium was less than or equal to 3, a statistical comparison was not possible. In these instances, the maximum reported concentration was compared directly to the maximum reported background concentration, and a contaminant was retained for further screening if the reported maximum concentration exceeded the maximum background level.
- Chemical contaminants were compared to screening values. These values represent media concentrations considered to be protective of biota. Contaminants present at maximum concentrations exceeding screening concentrations were retained as the final COECs.
- Chemicals that were present at maximum concentrations within background levels but greater than the screening values were retained as final COECs.

Background concentrations used in the screening process are those identified for the region (ICF Kaiser Engineers 1995a). Soil screening values were obtained from a number of sources, including the EPA Region III screening levels, Opresko et al. (1994), Will and Suter (1994), NOAA/HAZMAT (undated), and the open scientific literature. Although soil benchmarks considered protective of human health are available (e.g., EPA 1993a), these were not used in the screening process.

The contaminants identified as the final COECs and carried through the remainder of the ERA were those with maximum concentrations that exceeded background and/or screening level concentrations. The screening process also considered essential plant and animal nutrients and bioconcentration and bioaccumulation potential. The final list of COECs for the TBP area soils is presented in Table 2.6.

**TABLE 2.6 Contaminants of Ecological Concern for TBP Area Soils**

Acetone	Cobalt	Nickel
Aluminum	Copper	Nitroglycerin
Antimony	Cyanide	N-Nitrosodiphenylamine
Aroclor 1248	1,1-Dichloroethene	Phenol
Arsenic	Diethyl phthalate	Potassium
Barium	Fluorene	Selenium
Benzene	Hexachlorobenzene	Silver
Benzo(b)fluoranthene	Hexachloroethane	1,1,2,2-Tetrachloroethane
Benzo(k)fluoranthene	Iron	2,4,6-Trichloroaniline
Beryllium	Lead	Trichloroethene
Bis(2-chloroethyl)ether	Magnesium	Vanadium
2-Butanone	Mercury	m & p Xylene
Cadmium	2-Methylnaphthalene	Zinc
Carbon disulfide	2-Methylphenol	
Chromium	4-Methylphenol	

## 2.7 CONCURRENT STUDIES

### 2.7.1 Remedial Investigation

The suspected contamination sources at the TBP area include the two main pits, the VX and the mustard pits, and their associated pushout areas; and a storage area, a disposal area, and an HE demolition ground. The specific location of the liquid smoke disposal pit is uncertain. Because the two main pits are visible at the surface today, their extent is easy to determine. Examination of historical aerial photographs indicates that their extent has not changed significantly over time. The remaining pits (VX, mustard, and liquid smoke) have been buried. The approximate locations of the VX and mustard pits have been identified with the aid of historical aerial photographs. The results of ground-penetrating radar (GPR) surveys conducted in the area of the VX pit correlate well with the location identified in the aerial photographs. Additional geophysical surveys and soil sampling will be conducted to verify the locations of all other pits and associated unloading zones, which are considered potential groundwater contamination sources.

Characterization of the TBP area is continuing so that long-term remedial alternatives may be developed for the entire site during the FS. The nature and extent of soil contamination in the remaining pits, the storage area, the disposal area, and demolition area are currently under investigation as part of the RI.

### **2.7.2 Human Health Risk Assessment**

Human health risk assessments were recently conducted for J-Field (ICF Kaiser Engineers 1995a, 1996). The J-Field risk assessment focuses on potential exposure to chemical contaminants at hazardous waste disposal areas within J-Field, except for soil, surface water, and sediment at the TBP area, which were evaluated in a separate report (ICF Kaiser Engineers 1995a). Draft reports of these assessments have been released for public comment. The objective of the risk assessment is to determine the potential for and extent of human health risks resulting from contaminants at J-Field. Human exposures to chemical contaminants detected at J-Field or migrating from the waste disposal sites were evaluated specifically for the following environmental media: groundwater, soil, air, surface water, and sediment.

The approach for conducting the human health risk assessment at J-Field is outlined by ICF Kaiser Engineers (1994b). The preliminary list of potential receptors and human exposure pathways (which is based on a review of the site background and history) was reevaluated. Because the scope of the human health risk assessment is broad, additional field and laboratory data from the RI were needed to fully characterize the potential for human health risks. The data generated during the RI at J-Field were analyzed statistically to determine the significance of chemical concentration data. After the collection and statistical analysis of data, the BRA was performed to estimate human health impacts resulting from past activities at J-Field. Human health risks for each complete pathway were evaluated according to EPA guidance for BRAs (EPA 1989a,b). A similar approach was used for the TBP area baseline human health risk assessment (ICF Kaiser Engineers 1995a), which evaluated soil, surface water, and sediment data.

As stated in EPA guidance, risk-based remediation goals are initial guidelines that need to be reviewed and possibly modified upon completion of the BRA or when additional information is available (EPA 1991b). To reduce uncertainties and support the development of final remediation goals, the review should include exposure assumptions, future land use, and media and contaminants of potential concern.

### **2.7.3 Ecological Risk Assessment**

An ERA (Hlohowskyj et al. 1996) was recently completed for the TBP area. This risk assessment included the following:

- Evaluations of species abundance and community composition that used quantitative and qualitative surveys of wetland and upland vegetation and terrestrial and aquatic invertebrate and vertebrate biota;

- Quantitative evaluations of physiological parameters of soil invertebrates, such as enzyme activity and respiration rates;
- Quantitative evaluations of processes mediated by soil invertebrates, such as litter decomposition and nitrogen mineralization; and
- Toxicity tests of site soils, sediments, and surface waters on a variety of invertebrates, vertebrates, and plants.

Surveys of the aquatic invertebrate community at the TBP area marsh and pond showed a diverse community representing a wide variety of taxa. Except in the site nearest the pushout area, the benthic fauna in the pond and marsh represented communities expected to occur in such habitats. The fish community was dominated by two species, one of which was present in very large numbers. No fish collected exhibited any external evidence (lesions, ulcers, fin rot, exophthalmus) of contaminant effects or other environmental stressors.

The vertebrate surveys showed a very diverse bird community inhabiting or using the site; more than 100 species were identified. No individuals exhibited any obvious external abnormalities. Four amphibian species and four native mammal species (white-footed mouse, meadow vole, short-tailed shrew, and red fox) were collected or observed, and none of the specimens exhibited any external abnormalities (lesions or tumors).

The survey results showed reduced invertebrate abundance in the disturbed soils of the area. Total macroinvertebrate numbers, bacterial and fungal biomass, and nematode numbers were significantly lower, particularly at the pushout area, than those measured at on-site and off-site reference areas. The trophic structure of the nematode community at the pushout area was also different from that observed at the reference area.

The activity of several bacterial and fungal nutrient-acquiring enzymes in the pushout area was significantly lower than that at the reference site. Enzyme activity was significantly and negatively correlated with the total metal content of the soil. Substrate-induced respiration and soil nitrogen dynamics were also lower in the pushout area than in the reference location.

Toxicity testing of aquatic media showed no acute toxicity of surface water from the pond or marsh, but chronic toxicity was indicated for surface water from the marsh. This toxicity was restricted to surface water collected from the marsh immediately next to the pushout area; it was manifested as growth inhibition of the floating vascular plant *Lemna* and reduced survival and growth in larval fish. No chronic toxicity was detected for surface water from the pond. Toxicity testing of sediments indicated bacterial (Microtox) inhibition, and some tests showed an increase in mortality of the amphipod *Hyaella*. The sediments exhibiting toxic effects were all collected from along the boundary between the pushout area and the marsh. No toxicity was detected in sediments

collected from the pond. The distribution of the measured surface water and sediment toxicity suggests that the toxicity of these media is a result of contaminated surface soil and precipitation running off from the pushout area to the marsh. Testing of groundwater from the surficial aquifer at the TBP area showed both acute and chronic toxicity to a variety of test organisms, including zooplankton, vascular plants, amphibians, and larval fish.

Soils from the TBP area had lethal and sublethal effects on earthworms and vegetation. Soils from the southern main pit and the pushout area resulted in nearly 100% mortality in earthworms, and significant weight loss in worms was detected in soil mixtures containing more than 25% of site soil. Toxicity testing evaluating seedling emergence, growth, and survival in lettuce showed seedling emergence rate  $\leq 2.5\%$  for soils from the pushout area and southern main pit and seedling emergence rate  $< 75\%$  from other areas of the TBP area.

Risk estimation based on uptake modeling (Appendix E) indicates that the soil contamination at the TBP poses a substantial risk to several receptors. Aluminum, antimony, arsenic, cadmium, chromium, cyanide, lead, mercury, selenium, and zinc were each found to pose an extreme risk (environmental effects quotient [EEQ]  $> 100$ ) for at least one modeled ecological receptor. However, the exposure point concentrations used to model the uptake of particular contaminants were frequently based on the maximum detected concentrations for the site. In actuality, the concentrations to which receptors would likely be exposed at the site range from levels much lower than the exposure point concentrations (e.g., minimum detected values) to the maximum detected concentration. Thus, the results present a conservative view of risks likely to be incurred from contamination at the site (i.e., more likely to detect risks).

Extreme and moderate risks from soil contamination are indicated to terrestrial vegetation from 7 soil contaminants, and moderately high to extreme risk is indicated to a variety of terrestrial receptors for 13 COECs. Extreme risks were identified for 8 COECs (7 metals and cyanide) and 3 receptor species, while moderate to high risks were identified for 11 COECs (10 metals and cyanide). Low risks were identified for only two COECs, chromium and trichloroethene. The large number of receptors for which high or extreme risks were identified, together with the results of the effects assessment, supports the risk characterization that soil from the TBP area poses a high risk to ecological resources.

The EEQ and weight-of-evidence approaches for risk estimation indicate that the TBP area poses a high risk for adverse ecological impacts. This risk is associated primarily with contaminated soils in the pushout area and pits and is related primarily to heavy-metal concentrations rather than PCBs, pesticides, VOCs, or SVOCs. The contaminated soils of the pushout area are also the probable primary source of the contamination and high risk identified in surface water and sediment along the marsh-pushout area boundary (Hlohowskyj et al. 1996). The lack of suitable benchmark values for several of the receptor species precluded the calculation of EEQ risk values for a number

of the organic COECs. However, the absence of these risk estimates does not affect the conclusion that the TBP area soils pose a high risk for adverse ecological impacts.

The high risk identified for the TBP area may be significant at a local scale for most terrestrial wildlife that use the site. Adverse impacts were identified for several ecological variables and across multiple taxa and trophic levels. These impacts should largely be restricted to biota that occur within the TBP area boundaries and not extend to other areas of J-Field or APG. However, potential impacts on wide-ranging biota may affect wildlife populations that are not restricted to the J-Field boundary. The use of the site by migratory waterfowl and avian predators, such as the red-tailed hawk and American kestrel, is of particular concern. Consequently, the TBP area poses risks that would be ecologically significant, given the potential importance of the surrounding marsh to waterfowl and the implications that impacts on raptor populations could have on control of prey populations in the J-Field area.

#### **2.7.4 Sitewide Feasibility Study**

A sitewide FS is being conducted for J-Field. The purpose of the FS is to gather sufficient information to develop and evaluate alternative remedial actions to address contamination at J-Field AOCs, including the TBP area groundwater.



### 3 INTERIM REMEDIAL ACTION OBJECTIVES

#### 3.1 OBJECTIVES AND SCOPE

The overall objectives of the proposed interim remedial action at the TBP area of J-Field are to:

- Reduce exposure of human and environmental receptors to surface contamination in three source areas: the two main pits and pushout area,
- Minimize the potential for contaminant migration via sediment transport from these areas,
- Minimize the potential for contaminant migration via downward leaching through these areas, and
- Support long-term site remediation.


The source areas of contamination at the TBP area are described in Section 2.4. Three of these source areas are the subject of this FFS: the northern main pit, the southern main pit, and the pushout area (Figure 2.1). Preliminary results of human health and ecological risk assessments (Section 2.7) indicate that contaminated surface soil in these areas should be addressed to protect human health and the environment. An interim remedial action could be implemented that would achieve the objectives stated above.

Technologies that could be applied to address contaminated surface soil in the main pits and pushout area are discussed in Section 4. Figures 3.1 and 3.2 show the areas of surface soil contamination to be addressed by the proposed action. Preliminary area and volume estimates for these areas are presented in Table 3.1. Volumes apply only to the excavation scenarios proposed under Alternatives 3, 4, and 5. Area of contamination applies to all the action alternatives, including


**TABLE 3.1 Estimated Areas and Volumes of Contaminated Surface Soil at the Main Pits and Pushout Area**

Contaminated Surface Soil Interval <sup>a</sup>	Contaminants of Concern	Area (ft <sup>2</sup> )	Volume (yd <sup>3</sup> )
0 to 6 in.	Metals, organics	218,300	4,043
6 to 24 in.	Metals, organics	208,600	11,590

<sup>a</sup> See Figure 3.1 for location of excavation area.



**FIGURE 3.1 Contaminated Surface Soil, 0-6 in., to Be Addressed by the Proposed Action at the TBP Area**



**FIGURE 3.2 Contaminated Surface Soil, 6-24 in., to Be Addressed by the Proposed Action at the TBP Area**

the covering of soil as proposed in Alternative 2 and the excavation scenarios proposed under Alternatives 3, 4, and 5. The areas depicted in Figures 3.1 and 3.2 represent the areas with metal concentrations exceeding the mean regional background as reported by ICF Kaiser Engineers (1995a). The methodology used to derive this estimate is presented in Section 2.3. The areas depicted in the figures also cover the areas with levels of contaminants exceeding the interim PRGs reported in Table 3.5. The interim PRGs developed for surface soils at the TBP area (Section 3.3) were used to determine which source areas at the TBP area should be addressed as part of the interim action and which could be appropriately left in their current condition until further action is taken at the site as part of the long-term remediation for J-Field. Other source areas and contaminated media (groundwater, surface water, sediment, and subsurface soils) at the TBP area are outside the scope of this interim remedial action and will be addressed as part of the long-term remediation for J-Field (Section 2.7.4).

### 3.2 COMPLIANCE WITH REGULATORY REQUIREMENTS

In accordance with Section 121 of CERCLA and the National Oil and Hazardous Substances Pollution Contingency Plan (NCP), the proposed action would be implemented in accordance with ARARs. Identification of ARARs is site-specific and is defined as follows:

- Applicable requirements are cleanup standards, standards of control, and other substantive environmental protection requirements, criteria, or limitations promulgated under federal or state environmental or facility siting laws that specifically address a hazardous substance, pollutant, contaminant, remedial action, location, or other circumstance at a CERCLA site. Only those state standards that are identified by a state in a timely manner and that are more stringent than federal requirements may be applicable.
- Relevant and appropriate requirements are cleanup standards, standards of control, and other substantive environmental protection requirements, criteria, or limitations promulgated under federal or state environmental or facility siting laws that, while not “applicable” to a hazardous substance, pollutant, contaminant, remedial action, location, or other circumstances at a CERCLA site, address problems or situations sufficiently similar to those encountered at the CERCLA site that their use is well suited to the particular site. Only those state standards that are identified by a state in a timely manner and that are more stringent than federal requirements may be relevant and appropriate.

As described in EPA guidance, ARARs can be divided into three categories: contaminant-specific, location-specific, and action-specific. Contaminant-specific ARARs address certain chemical species or classes of contaminants and relate to the allowable limits of contaminant

concentrations in various environmental media (soil, groundwater, surface water, air). Location-specific ARARs are based on the specific setting and nature of the site, such as location in a floodplain and proximity to wetlands. Action-specific ARARs relate to specific response actions (i.e., excavation or soil washing/leaching) that are proposed for implementation at the site.

In addition to ARARs, the NCP provides for the use of other advisories, criteria, or guidance TBCs. These are advisories, criteria, and standards that are issued by the federal or state regulatory body but not legally binding because they have not been properly promulgated. The identification of TBCs is not mandatory; however, they are to be used as appropriate to complement the ARARs.

Potential ARARs for the proposed action at the TBP area are identified on the basis of the nature of contamination, the site location, and the proposed activities (including both federal and State of Maryland requirements). A comprehensive list of potential ARARs is presented in Appendix B.

The NCP acknowledges the EPA's policy of responding by distinct operable unit at a site rather than waiting to take one consolidated response action (EPA 1990a). Therefore, this interim action has a limited scope, and requirements are ARARs only when they pertain to the issues to be addressed and the specific activities to be conducted under the interim action. For instance, this interim action addresses only the excavation and removal of contaminated soils and does not concern groundwater remediation, which is within the scope of a concurrent RI/FS. The interim action would also contribute to improving migration of contaminants to surface waters but does not address surface water remediation. Therefore, Appendix B does not address ARARs outside the scope of soil excavation, treatment, and disposal.

Appendix B identifies federal and state location-specific requirements for permitting and approvals for activities taking place in wetlands and floodplains (e.g., the movement of soils, grading, and fill discharge). Location-specific requirements also address impacts on wildlife and cultural, historic, or archeological sites.

Federal standards and guidelines are available for only a few of the soil contaminants of concern at the J-Field TBP area: metals (e.g., lead), dioxin, and PCBs. These soil contaminants are governed by RCRA and the Toxic Substances Control Act (TSCA), respectively. The management and disposal of soils contaminated with lead or arsenic are governed by the Maryland RCRA program. No Maryland State PCB standards or guidelines are established; therefore, federal standards for management and disposal of PCB-contaminated soils would be contaminant-specific ARARs.

Under RCRA regulations, any waste that fails the TCLP is a characteristic hazardous waste. The soil in the TBP area was analyzed and found to be characteristically hazardous for lead and

arsenic (i.e., the TCLP extract exceeded 5 mg/L). Because the operations at the TBP ceased before 1979, if the soil is left in place and no current actions are taken that constitute treatment, storage, or disposal as defined by RCRA, RCRA land disposal restriction (LDR) regulations would not be applicable to the TBP. However, if lead- or arsenic-contaminated characteristic hazardous waste is to be excavated and land-disposed, it must meet the RCRA LDR regulations and, thereunder, must be treated to meet an extraction procedure (EP) or TCLP concentration of less than 5 mg/L prior to disposal. Therefore, Maryland's EPA-authorized RCRA program regulations and standards will govern any activities concerning excavated contaminated soils, including any storage, treatment, or disposal activities.

The EPA recognized early on that RCRA constituent-contaminated soil is different than hazardous wastes generated in a process (as-generated wastes) and that treatment of soil should also be different. Therefore, the treatment standards for soil were delayed until May 8, 1992. An additional 1-year extension was granted and has since expired. Therefore, hazardous waste soil is now subject to the same treatment standards as as-generated wastes.

In the proposed Phase II LDR rule, the EPA included provisions to establish constituent-specific treatment standards for soils contaminated with hazardous wastes. However, after receiving a number of comments, the EPA issued a subsequent Federal Register Notice (58 FR 59,976, November 12, 1993) that announced its intention to not include soil LDRs in the Phase II LDR final rule. In the preamble of the Phase II LDR final rule, the EPA reiterated its position that "treatment standards for as-generated wastes are generally inappropriate or unachievable for soils contaminated with hazardous wastes" (59 FR 47,980, September 19, 1994). Now the EPA has issued its proposed Hazardous Waste Identification Rule — Media (61 FR 18,779, April 29, 1996).

This proposed rule would establish modified LDR treatment requirements and modified permitting procedures for higher-risk contaminated media that remain subject to hazardous waste regulations and give the EPA and any state authorized to implement the Hazardous Waste Identification Rule — Media the authority to remove certain lower-risk contaminated media from regulations as a hazardous waste, including minimum technological requirements. Once adopted, this rule would govern the storage, treatment, and disposal of hazardous waste-contaminated soils at remediation sites overseen by either the EPA or an authorized state. As proposed, this rule would also supersede the Corrective Action Management Unit (CAMU) regulations. Therefore, adoption of this rule would affect the management of any hazardous waste soils excavated after the rule's effective date.

However, until a new regulation is finalized, Maryland RCRA regulations, including LDRs, will apply to any hazardous waste soils excavated for storage, treatment, or disposal. Upon excavation, any soils that are hazardous wastes by definition (i.e., either characteristic waste due to lead contamination) must be stored pursuant to RCRA storage regulations and treated and disposed of pursuant to RCRA LDR regulations. Under the Phase II Universal Treatment Standards, hazardous

constituents other than those that cause wastes to exhibit a characteristic are “underlying hazardous constituents.” These underlying hazardous constituents may also have to be treated to specified maximum concentrations prior to land disposal. Underlying hazardous constituents are defined as any constituent listed in 40 Code of Federal Regulations (CFR) 268.48, except zinc, that can reasonably be expected to be present at the point of generation of the hazardous waste at a concentration above the constituent-specific Universal Treatment Standard [40 CFR 268.2(i)]. Therefore, if any constituent listed in 40 CFR 268.48 is expected to be present in the waste soil in excess of the listed treatment standard concentration, it must also be treated before land disposal can take place.

In light of the uncertainty surrounding the treatment of hazardous waste soils, the EPA has presumed that a treatability variance will be used to comply with LDRs for the disposal of contaminated soil. EPA has published several guides for soils subject to treatability variances, including alternative treatment standards (EPA 1990b). The contaminated soil will need to be treated to meet either the concentration range or the percent reduction range for each hazardous constituent listed. A threshold concentration is used to determine which alternative standard to apply. The concentration range would be applied if the waste sample constituent concentration exceeded the threshold, and the percent reduction range would be applied if the threshold were not exceeded.

If an alternative cannot meet the identified ARARs, it may be assessed to determine whether the alternative meets the grounds for invoking a CERCLA waiver provision. The waiver provisions allow an alternative to not attain all ARARs where the alternative is an interim measure that will become part of a total remedial action that will attain ARARs [40 CFR 3000.430(f)(1)(ii)(C)].

TSCA regulations set forth standards for PCB-contaminated soils once they are excavated and there is a need to manage, store, treat, and dispose of them. TSCA also addresses cleanup standards and guidelines for contaminated soil left in place. Under TSCA regulations, materials contaminated with PCBs in concentrations exceeding 50 ppm (mg/kg) must be stored in specially designed facilities, and disposal must be either by incineration or in a chemical waste landfill at an EPA-approved facility. Under EPA’s PCB spill cleanup policy (40 CFR Part 761 [Subpart G]) for spills of materials contaminated with greater than 50 ppm PCBs in restricted-access areas, soil within the spill area must be excavated and backfilled with soil containing PCBs in concentrations less than 25 ppm.

The PCB spill cleanup policy (40 CFR 761.120) applies only to spills taking place after the effective date of the regulation and is not a mandatory standard; therefore, the policy is not an ARAR but a TBC. However, according to EPA guidance, the policy sets forth the standards and guidelines that are used by EPA to determine PRGs for CERCLA sites (EPA 1990a). No state standards or guidelines exist for PCB-contaminated soils.

PCBs have been found to contaminate soils at the TBP area in concentrations exceeding 50 ppm; therefore, TSCA regulations for the management, storage, treatment, and disposal of PCBs will govern interim actions concerning such PCB-contaminated soil, and the PCB spill cleanup policy will be an important TBC in determining the cleanup standard.

### 3.3 INTERIM PRELIMINARY REMEDIATION GOALS

The development of risk-based PRGs early in the RI/FS process can aid in identifying appropriate remedial action alternatives at a site. The site-specific information required to develop risk-based PRGs usually consists of (1) the COCs, (2) the concentrations of the COCs by medium, (3) the human and ecological receptors, and (4) the probable future land use. For the TBP area, human health-based interim PRGs for soil were developed by using the EPA Region III derived risk-based soil concentrations (Table 3.2). EPA Region III derives the risk-based values following

**TABLE 3.2 Human Health-Based Interim Preliminary Remediation Goals (PRGs) for Surface Soil at the TBP Area**

Contaminant	Interim PRG (mg/kg)
Semivolatile organic compound	
2-Methylnaphthalene	NA <sup>a</sup>
Explosive	
Nitroglycerin	NA
Inorganic materials	
Arsenic	3.8 <sup>b</sup>
Beryllium	1.3
Lead	400 <sup>c</sup>

<sup>a</sup> NA = Not available.

<sup>b</sup> Human health-based interim PRG for arsenic is based on the EPA Region III risk-based concentration for arsenic as a carcinogen. The noncarcinogenic concentration for arsenic is 610 mg/kg.

<sup>c</sup> EPA (1994) currently recommends a soil lead cleanup value of 400 mg/kg for residential land use but site-specific pharmacokinetic modeling for nonresidential adult screening, when necessary.

the Superfund risk assessment guidelines (EPA 1989a) and standard default assumptions (EPA 1991a); the values are based on carcinogenic and noncarcinogenic effects of ingestion of “industrial” soil (as opposed to residential soil). The interim PRGs for the TBP area are initial guidelines and are not intended to set final cleanup levels or establish that cleanup to meet these goals is warranted (EPA 1991b, 1994).

EPA has not developed risk-based soil concentrations for ecological resources similar to the human health-based PRGs. Two approaches were employed to develop ecological risk-based interim PRGs for the TBP area: (1) use of the contaminant uptake models developed for the ERA to back-calculate acceptable surface soil concentrations and (2) use of the human health-based interim PRGs for COCs for which uptake modeling was not performed. In this latter approach, risk reduction for ecological resources is considered to be directly correlated with the reduction of contaminant concentrations or with removal of contaminated media. Thus, reducing surface soil contaminant concentrations to the levels of the human health risk-based interim soil PRGs would also reduce risk for ecological resources. In both approaches, each derived interim soil PRG was screened against the regional background soil concentration of that contaminant, and the greater of the two values was selected as the interim PRG.

In the ERA for J-Field (Hlohowskyj et al. 1996), uptake modeling was used to estimate a daily uptake or dose (the applied daily dose [ADD]) for each COEC. Potential risk to an ecological receptor was estimated by comparing the modeled ADD value with a benchmark value representing a safe daily uptake. The ratio of the ADD to the benchmark value is termed the environmental effects quotient (EEQ) and is analogous to the hazard quotient used for estimating human health risks. For a particular contaminant, a potential risk is indicated for all values of the EEQ exceeding 1.00. Details regarding the uptake models and estimation of the EEQ are presented in Appendix E. It was possible to develop EEQ risk estimates only for those contaminants for which suitable benchmark values were available.

For the TBP area, the J-Field ERA modeled contaminant uptake and developed EEQ risk estimates for terrestrial vegetation and 11 vertebrate receptor species. Risk estimates exceeding values of 1.00 were identified for aluminum, antimony, arsenic, barium, cadmium, chromium, cobalt, copper, cyanide, lead, mercury, selenium, silver, zinc, and trichloroethene for terrestrial vegetation and six of the modeled terrestrial receptors (Table 3.3). To derive the ecological risk-based interim PRG values, the uptake models were used to identify contaminant surface soil concentrations that would limit the EEQ risk values for each receptor species to less than 1.00, and the lowest estimated soil concentration among all the receptors was selected as the interim PRG value. The species-specific interim surface soil PRGs derived for the TBP area are shown in Table 3.4.

**TABLE 3.3 Ecological Effects Quotient Risk Estimates of Soil Contaminant Concentrations for Selected Ecological Receptors at the TBP Area<sup>a,b</sup>**

Contaminant	Ecological Effects Quotient						
	Vegetation	White-Footed Mouse	Eastern Cottontail	White-Tailed Deer	American Robin	American Kestrel	Red-Tailed Hawk
Aluminum	NA <sup>c</sup>	97.1	263	12.7	2.02	0.01	0.13
Antimony	100	50.7	138	5.98	NA	NA	NA
Arsenic	144	113	352	16.6	2.59	0.06	0.67
Barium	1.60	4.50	24.2	1.01	9.90	0.03	0.23
Cadmium	3.60	24.8	110	3.88	5.94	0.02	0.13
Chromium	251	1.21	3.61	0.15	7.30	0.03	0.35
Cobalt	4.30	NA	NA	NA	NA	NA	NA
Copper	43.2	3.79	19.1	0.80	9.40	0.03	0.22
Cyanide	NA	46.3	125	5.24	NA	NA	NA
Lead	942	103	507	21.3	1,527	5.20	40.4
Mercury	NA	16.2	117	5.53	68.2	0.20	1.19
Selenium	7.10	51.0	139	5.99	12.1	0.06	0.33
Silver	21.0	NA	NA	NA	NA	NA	NA
Trichloroethene	NA	1.37	3.46	1.02	NA	NA	NA
Zinc	1,780	3.94	22.8	0.96	981	3.29	20.1

<sup>a</sup> EEQ values exceeding 1.00 indicate potential risk to an ecological receptor. Values between 1.0 and 10 indicate low potential risk, values between 10 and 50 indicate moderate potential risk, values between 50 and 100 indicate high potential risk, and values exceeding 100 are indicative of extreme potential risk to ecological receptors.

<sup>b</sup> EEQ values are shown only for those contaminants of ecological concern for which the EEQ values exceeded 1.00 for at least one receptor.

<sup>c</sup> NA = A suitable benchmark value for this contaminant is not available for this receptor, and it is not possible to calculate an EEQ value at this time.

**TABLE 3.4 Estimated Surface Soil Contaminant Concentrations Necessary to Achieve a No-Effects Level (100% Risk Reduction) for Selected Ecological Receptors that Use the TBP Area<sup>a</sup>**

Surface Soil Contaminant Concentration (mg/kg)							
Contaminant	Vegetation	White-Footed Mouse	Eastern Cottontail	White-Tailed Deer	American Robin	American Kestrel	Red-Tailed Hawk
Aluminum	NR <sup>b</sup>	NP <sup>c</sup>	NP	NP	11,084	NR	NR
Antimony	5.00	9.55	3.36	80.1	NA <sup>d</sup>	NA	NA
Arsenic	10.0	12.3	9.7	82.3	556	NR	NR
Barium	1,000	349.4	64.4	1,557	159	NR	NR
Cadmium	10.0	1.4	0.316	9.1	6.0	NR	NR
Chromium	3.50	727	242	NR	120	NR	NR
Cobalt	25.0	NA	NA	NA	NA	NA	NA
Copper	100	1,137	224	NR	459	NR	NR
Cyanide	NA	2.59	0.96	22.9	NA	NA	NA
Lead	100	900	181	4,358	58.7	18,083	2,323
Mercury	NA	0.221	0.029	0.637	0.052	NR	3.0
Selenium	1.00	NR	NR	1.18	NR	NR	NR
Silver	2.00	NA	NA	NA	NA	NA	NA
Trichloroethene	NA	1.3	NP	1.9	NA	NA	NA
Zinc	10.0	4,516	776	NR	16.7	5,393	878

<sup>a</sup> For each contaminant and receptor, the soil concentration identified will give a modeled applied daily dose to the ecological receptor that limits the ecological effects quotient (EEQ) to less than 1.00, resulting in a potential 100% reduction in risk.

<sup>b</sup> NR = Current levels of soil contamination pose no risk to the receptor as determined by the modeled uptake and a resultant EEQ value less than 1.00.

<sup>c</sup> NP = Because of contaminant uptake from exposure routes from media other than soil, a 100% risk reduction is not possible from remediation of soil alone.

<sup>d</sup> NA = Suitable benchmarks for this contaminant are not available for this receptor, and it is not possible to calculate an EEQ value or an interim PRG at this time.

The ecological risk-based PRGs should be used with care. Because of the assumptions and uncertainties associated with the uptake models used to predict ADD values, the PRG values for some receptors may be greatly overprotective. The uptake models use a COEC exposure point concentration that is either the maximum concentration reported from the TBP area or the 95% upper confidence limit (UCL) of all the reported concentrations. For most of the contaminants, the maximum reported concentration was used as the exposure point concentration for the uptake modeling. The use of either value as the exposure point concentration is consistent with EPA Region III guidance (Davis 1994) and results in a very conservative modeled daily contaminant uptake. For the uptake modeling, the exposure point concentration is assumed to be homogeneously distributed across the entire site, and the resultant EEQ risk estimate represents the potential risk to ecological receptors from a uniform, sitewide contaminant concentration. In reality, the actual occurrence and distribution of the exposure point concentration (maximum or 95% UCL) is restricted to specific locations within the TBP area, such as the pits and trenches, and concentrations at most locations within the TBP area are much lower than the exposure point concentrations. Thus, the EEQ risk estimates are likely greatly overestimated, and the ecological risk-based PRGs are likely greatly overprotective for most if not all the contaminants and receptors.

Modeling contaminant uptake also requires exposure factor information on species-specific ecological and physiological parameters, such as body weight, ingestion rate, and diet. In contrast to the exposure factor data available for human health risk assessments, species-specific exposure factors for ecological receptors are largely unavailable. The exposure factors used to estimate contaminant uptake, and the benchmark values used to calculate the EEQs, were either (1) species-specific but not population specific, (2) not species-specific but from related taxa, or (3) developed with empirically derived allometric equations. Each of these sources adds to the uncertainty of the ADD and EEQ risk estimates and the interim PRGs.

Additional uncertainty with the uptake modeling that may affect the PRG values is related to the assumptions regarding contaminant transfer between trophic levels and contaminant assimilation. The ADD, EEQ, and PRG values were all derived assuming 100% contaminant transfer and assimilation; however, for most biota, it is unlikely that contaminant transfer or assimilation is 100% efficient. So, this assumption likely overestimates the true degree of contaminant uptake by the modeled receptors and, thus, the ADD and EEQ; therefore, the PRG values are probably overprotective.

The final uncertainty associated with the contaminant models that may result in overly protective PRGs is the nature of the benchmark values used for estimating the EEQ risk values. The benchmark values used were reported in the literature to produce no observable adverse effects in the exposed species. However, benchmark values specific to the species of concern at the TBP area were not available for all the COECs, and benchmark values were extrapolated between species as necessary. In some cases, uncertainty factors (Davis 1994) were used to minimize uncertainty

associated with benchmark extrapolations between species of the same class and between species of different classes (Appendix E).

For each COEC, the lowest PRG among those developed for all the receptors was chosen as the interim ecological risk-based PRG (Table 3.5). For some COECs, the interim PRG soil concentrations are less than the reported regional background concentrations, and attaining the PRGs for some COECs would require remediation to below background levels. For those COECs with interim PRGs below background levels, the background concentrations were selected as the ecological risk-based interim soil PRGs. However, remediation to background levels would produce risk reductions in excess of 97% for all the COECs except aluminum (Table 3.5). Regional background aluminum concentrations are indicated to pose a high risk to ecological resources. However, remediation to background levels of this COEC would result in a 64% reduction in the current risk level identified for the TBP area.

For those contaminants with insufficient available data to model an ADD, calculate an EEQ risk estimate, and derive an ecological risk-based interim soil PRG, the human health-based interim soil PRGs were used as the default ecological risk-based interim PRGs.

Table 3.6 integrates the ecological and human health risk-based PRGs and presents an overall list of preliminary interim soil PRGs for the TBP area. The identified interim soil PRG for each COC is the lower of the human health and ecological risk-based interim PRGs presented in Tables 3.2 and 3.5, respectively. These interim soil PRGs are initial guidelines and are not intended to set final cleanup levels or establish that cleanup to meet these goals is warranted (EPA 1991b, 1994). Rather, they provide a basis for the initial evaluation of remedial alternatives and for the development of remedial boundaries at the TBP area.

TABLE 3.5 Ecological Risk-Based Interim Preliminary Remediation Goals (PRGs) for Soils at the TBP Area

Contaminant	Ecological Risk-Based Interim PRG (mg/kg) for 100% Risk Reduction <sup>a</sup>	Current EEQ Risk Level <sup>b</sup>	Mean Background Soil Concentration (mg/kg)	Background EEQ Risk Level	Current Risk Reduction by Using Background-Based PRG (%)
Aluminum	NP <sup>c</sup>	263	7,940	99.4	64.1
Antimony	3.7	137	3.14 <sup>d</sup>	0.08	> 100 <sup>e</sup>
Arsenic	9.7	352	2.57	0.71	> 100
Barium	64.4	24.2	43.6	0.68	> 100
Cadmium	0.32	110	0.34	1.07	99.0
Chromium	3.5	251	16.7	4.79	98.1
Cobalt	25.0	4.3	7.25	0.29	> 100
Copper	100	43.2	8.72	0.09	> 100
Cyanide	1.0	125	NA <sup>f</sup>	0.67	> 100
Lead	58.7	1,527	21.6	0.40	> 100
Mercury	0.03	117	0.04	1.67	98.6
Selenium	0.05	139	0.20	4.12	97.0
Silver	2.0	21	0.31 <sup>d</sup>	0.16	> 100
Trichloroethene	1.3	3.46	NA	NA	NA
Zinc	10.0	1,780	37.0	3.70	99.8

<sup>a</sup> Predicted contaminant soil concentration necessary to limit the ecological effects quotient (EEQ) to less than 1.00, resulting in a potential 100% risk reduction.

<sup>b</sup> Predicted EEQ risk values estimated by using current contaminant levels detected in soils at the TBP area.

<sup>c</sup> Greatest risk was identified for the eastern cottontail (Table 3.3). Because of the contaminant uptake via ingestion of drinking water, a 100% risk reduction is not possible for this species from soil remediation alone. Remediation to background levels will result in a 64% risk reduction for this species. Similarly, 100% risk reduction from soil remediation is not possible for the white-tailed deer or the white-footed mouse. Remediation to background aluminum concentrations would result in a 100% risk reduction for the American robin but risk reductions of only 56% and 64% for the white-tailed deer and white-footed mouse, respectively.

<sup>d</sup> Reported background concentrations were all below detection limits; mean background concentrations were estimated by using one-half the reported method detection limits (ICF Kaiser Engineers 1995a).

<sup>e</sup> Risk reduction is greater than 100% when the background EEQ value is less than 1.00, while risk reduction equals 100% when the EEQ equals 1.00.

<sup>f</sup> NA = Benchmark value is not available, so estimation of EEQ is not possible at this time.

**TABLE 3.6 Risk-Based Interim Preliminary Remediation Goals (PRGs) for Surface Soil at the TBP Area**

Contaminant	Interim PRG (mg/kg)
Volatile and semivolatile organic compounds	
Trichloroethene	1.3 <sup>a</sup>
2-Methylnaphthalene	NA <sup>b</sup>
Explosive	
Nitroglycerin	NA
Inorganic materials	
Aluminum	7,940 <sup>c</sup>
Antimony	3.7 <sup>a</sup>
Arsenic	3.8 <sup>d</sup>
Barium	64.4 <sup>a</sup>
Beryllium	1.3 <sup>d</sup>
Cadmium	0.34 <sup>c</sup>
Chromium	16.7 <sup>c</sup>
Cobalt	25.0 <sup>a</sup>
Copper	100 <sup>a</sup>
Cyanide	1.0 <sup>a</sup>
Lead	58.7/400 <sup>e</sup>
Mercury	0.04 <sup>c</sup>
Selenium	0.20 <sup>c</sup>
Silver	2.0 <sup>a</sup>
Zinc	37.0 <sup>c</sup>

<sup>a</sup> Interim PRG is ecological risk-based (see Table 3.5).

<sup>b</sup> NA = No interim PRG developed. Insufficient data to develop ecological risk-based interim PRG, and no EPA Region III human health-based PRG has been developed (see Table 3.2).

<sup>c</sup> Ecological risk-based PRG value is below mean background concentration; interim PRG is mean background concentration.

<sup>d</sup> Interim PRG is human health-based (see Table 3.2).

<sup>e</sup> The ecological risk-based PRG is 58.7 mg/kg (see Table 3.5). EPA currently recommends a soil cleanup value of 400 mg/kg for residential land use (see Table 3.2). The cleanup goal for lead has been as high as 1,000 mg/kg at other APG sites (Wrobel 1995).

## 4 IDENTIFICATION AND SCREENING OF TECHNOLOGIES

Alternative interim remedial actions for the TBP area at J-Field were developed by identifying remedial technology types and process options that are potentially applicable to addressing contaminated soil. The technologies considered in selecting interim remedial action alternatives for contaminated soil in the TBP area include those identified in the NCP (EPA 1990a). These technology types and process options were screened for applicability to the site in accordance with EPA guidance (EPA 1988).

### 4.1 CRITERIA FOR IDENTIFYING AND SCREENING TECHNOLOGIES

The criteria for identifying potentially applicable technology types and process options are provided in EPA guidance (EPA 1988) and the NCP (EPA 1990a). Technologies identified in this section were screened on the basis of site-specific conditions and the current understanding of the TBP area at J-Field. Section 121 of the Superfund Amendments and Reauthorization Act of 1986 (SARA) identifies a strong statutory preference for remedial actions that are highly reliable and provide long-term protection. The primary requirements for a selected remedy are that it protects human health and the environment and meets the objectives of the proposed action in a cost-effective manner. Additional selection criteria include the following:

- In preferred remedies, the principal element is treatment to permanently or significantly reduce the toxicity, mobility, or volume of hazardous substances, pollutants, or contaminants.
- Where practical treatment technologies are available, off-site transport and disposal without treatment is the least preferred alternative.
- Permanent solutions and alternative treatment technologies or resource recovery technologies should be addressed and used to the maximum extent practicable.

These criteria have been considered in identifying and screening technologies to determine the appropriate components of remedial action alternatives for the TBP area.

The remedial action objectives for the TBP area are described in Section 3. The current understanding of contaminants and conditions at the site suggests the general response actions that could be implemented to achieve these objectives are institutional controls, in-situ containment, removal, treatment, short-term storage, and disposal. Specific application of these technologies to site conditions was evaluated to determine which would be most appropriate for interim remedial

action at the TBP area. These technologies were screened on the basis of effectiveness, implementability, and cost, as defined by the following factors:

- Effectiveness — in terms of protecting human health and the environment in both the short term and the long term;
- Implementability — in terms of technical and administrative feasibility and resource availability; and
- Cost — in a comparative manner (i.e., low, moderate, or high) for technologies of similar performance and/or implementability.

These screening criteria were applied only to the technologies and general response actions being evaluated; combinations of technologies to address site-specific contamination problems were evaluated after the technologies were assembled into alternatives. This evaluation is presented in Section 5.

The no-action response was also included in this evaluation to provide a baseline for comparison; it is evaluated as an alternative in Sections 5 and 7. The technology types and process options identified for the other response actions were screened for applicability to address contaminated soils at the TBP area. Potentially applicable technologies are discussed in Section 4.3, and the results of the screening process are presented in Table 4.9.

## **4.2 TECHNOLOGY IDENTIFICATION AND SCREENING**

### **4.2.1 Institutional Controls**

Institutional controls are measures that preclude or minimize public exposure by limiting access to or use of contaminated areas. Institutional controls include measures to restrict access, such as security guards or fencing, ownership and use or deed restrictions, and monitoring. Institutional controls do not reduce contaminant toxicity, mobility, or volume, but they can reduce the potential for exposure to contaminated material.

Access to the Edgewood down range area (including J-Field) is controlled by security guards and is limited to authorized personnel. Vehicular access to J-Field is controlled by a locked gate. These measures mitigate potential public exposure to contamination. However, these measures are not as effective at mitigating exposure of wildlife to contamination on-site. Fencing around the TBP area would not control exposures to wildlife, especially small and burrowing mammals and birds.

The U.S. Army has custody of the site and is expected to maintain this custody and accountability into the future. This measure controls public exposures to on-site contamination by restricting access and use.

An extensive environmental monitoring program is currently in place as part of the RI. Additional monitoring will be employed during future response actions. This measure can support the mitigation of potential exposures to humans and wildlife by providing data on the nature and extent of contamination and the effectiveness of primary control measures such as containment or removal. Future monitoring activities for the TBP area and other J-Field AOCs will be discussed in the FS report.

The screening analysis for institutional controls is summarized in Table 4.1. On the basis of effectiveness, implementability, and cost, all institutional controls currently in place have been retained. Fencing of the TBP area is not recommended. The most significant control at the site is land ownership. As long as the U.S. Army maintains custody of the APG site, the potential for significant public exposure will remain low because land use can be controlled and access to

**TABLE 4.1 Summary of Screening Analysis for Institutional Controls**

Institutional Control Measure	Effectiveness	Implementability	Cost
Access restriction	Entry to the Edgewood down range area (which includes J-Field) is controlled by security guards. Vehicular access to the site is controlled by a locked fence. These measures are effective at mitigating potential public exposure to on-site contamination; however, they are less effective at mitigating potential exposures to wildlife. Fencing around the TBP area would not control exposures to wildlife and is not recommended.	Fences, guards, and other such measures are easy to implement, and resources are readily available.	Low
Ownership and use or deed restrictions	The U.S. Army has custody of APG and is expected to maintain this custody and accountability into the future.	Ownership and use or deed restrictions are easy to implement, and resources are readily available.	Low
Monitoring	An extensive monitoring program is currently in place as part of the RI. Additional monitoring will be employed during future response actions and will support mitigation of potential exposures to humans and wildlife.	Monitoring is easy to implement, and resources are readily available.	Moderate

contaminated areas can be restricted. Additional control measures would be needed to reduce the potential for significant exposure of wildlife.

#### **4.2.2 In-Situ Containment**

In-situ containment involves technologies that confine contamination to its current locations in the soil. These technologies reduce contaminant mobility and the associated potential for exposure, but they do not reduce contaminant toxicity or volume. In-situ containment technologies that address contamination in surface soils include surface controls/diversions, vertical barriers, and caps/covers.

Surface controls/diversions are used to divert surface runoff around contaminated areas to minimize the potential for contaminant resuspension. Graded contours, swales, and berms can effectively control surface water runoff and can limit the mobility of contaminants. These measures alone, however, may not be effective for surface water bodies (e.g., marsh) that are hydrologically connected to the surficial aquifer system or other surface water bodies. Therefore, vertical barriers may also be needed. In addition, erosion of contaminated soil from the portion of the pushout area in contact with the marsh could be mitigated by installing a vertical barrier.

A contaminated area can be encapsulated by placing barriers on top (caps/covers). Capping (e.g., a RCRA-engineered cap) of soil could effectively reduce airborne emissions (e.g., VOCs), precipitation-enhanced percolation and leaching, and contaminant resuspension via surface water runoff. This method would limit exposures of humans and wildlife to contamination in the surface soils. A stabilized surface would be required prior to cap placement and would most likely necessitate some grading and excavation. Therefore, a UXO survey would also be required over the area to be capped. In-situ capping of the main pits and pushout areas could prove difficult to implement, and the effectiveness of the cap would be constrained by the shallow water table and its proximity to the marsh. In addition, because the J-Field site is a designated floodplain, measures would be required to minimize the potential for damage from flood water. These measures would include shoreline stabilization and building the cap to elevations above flood level.

An alternative to an engineered cap is a protective soil cover, referred to here as a “risk-reduction cover.” The risk-reduction cover also would be effective at minimizing contaminant mobility and limiting exposures at the surface. Under this option, a geotextile membrane would be laid over the contaminated area and covered with soil. This approach could be implemented with little or no UXO screening.

The screening analysis for in-situ containment is summarized in Table 4.2. On the basis of effectiveness, implementability, and cost, the in-situ containment technologies (surface controls/diversions, vertical barriers, and caps/covers) have been retained.

**TABLE 4.2 Summary of Screening Analysis for In-Situ Containment**

In-Situ Containment Measure	Effectiveness	Implementability	Cost
Surface controls/diversions	Could effectively reduce contaminant mobility at the site. Such measures alone, however, might not be effective for the marsh because of its hydrological connection to the surficial aquifer.	Could be implemented with conventional equipment and procedures, and resources are readily available.	Low
Vertical barriers	Could effectively reduce contaminant mobility at the site, especially in ground-water and in places where the pushout area is in contact with the marsh.	Could be implemented with conventional equipment and procedures, and resources are readily available.	Low to moderate
Caps/covers	Could effectively limit airborne emissions (e.g., VOCs), precipitation-enhanced percolation and leaching, and contaminant resuspension via surface water runoff. Because J-Field is designated as a flood-plain, measures would be required to minimize damage from flood waters.	Could be implemented with conventional equipment and procedures, and resources are readily available. UXO survey might be required.	Low to moderate

### 4.2.3 Removal

Removal of contaminated material can limit contaminant mobility and volume at the affected source area and can facilitate treatment and disposal that could reduce contaminant toxicity, mobility, and volume.

Excavation with conventional earth-moving equipment (e.g., bulldozers, backhoes, and front-end loaders) could effectively remove soil in the main pits and pushout area at the TBP area. The area of excavation would have to undergo a UXO survey, and the soil would have to be monitored for CWAs during excavation.

Soil also could be removed by hand if the density of metal contacts is high or if only limited excavation is required. Human Factors Applications, Inc. (HFA) surveys have shown that conventional earth-moving equipment could be used in areas with metal contact densities of 1 to 28 contacts per 100-ft<sup>2</sup> area.

Contaminated vegetation can also be removed by standard clearing and grubbing methods to reduce exposures and limit biotic transport.

The screening analysis for removal is summarized in Table 4.3. On the basis of this evaluation, these technologies have been retained as potentially applicable to address surface soil contamination in the TBP area.

#### 4.2.4 Treatment

##### 4.2.4.1 In-Situ Physical/Chemical Treatment Technologies

Several in-situ physical/chemical treatment technologies are available for treating soil contaminated with metals, SVOCs, and PCBs (VOCs are present only at depth and will not be addressed by the proposed interim remedial action). These technologies include soil flushing, stabilization/solidification, vitrification, and electrokinetic processing. The main advantage of in-situ treatment is that it allows soil to be treated without being excavated and transported, resulting in potentially significant cost savings. However, in-situ treatment generally requires longer time periods to be effective, and there is less certainty about the uniformity of treatment because of the variability in soil characteristics and because the efficacy of the process is more difficult to confirm (EPA 1994). For the TBP area, UXO screening and removal would have to precede in-situ treatment.

The screening analysis of potential in-situ treatment technologies is discussed in the following subsections and is summarized in Table 4.4.

**Soil Flushing.** Soil flushing is the extraction of contaminants from the soil with water or other suitable aqueous solutions. This method is applicable to coarse-grained soils contaminated with

**TABLE 4.3 Summary of Screening Analysis for Removal**

Removal Measure	Effectiveness	Implementability	Cost
Excavation	Could remove the source of contamination to limit contaminant mobility and volume and to reduce related exposures. It could also facilitate treatment and disposal.	Could be implemented with conventional equipment and procedures, and resources are readily available. UXO surveys and CWA screening would be required.	Moderate to high
Clearing and grubbing	Could effectively remove vegetation from source areas to reduce related exposures and limit biotic transport.	Could be implemented with conventional equipment and procedures, and resources are readily available.	Low

**TABLE 4.4 Summary of Screening Analysis for In-Situ Treatment Technologies**

Treatment Technology	Effectiveness	Implementability	Cost
Soil flushing	Applicable to soils contaminated with SVOCs and metals; would not address soils with PCB contamination. Effectiveness is limited by variability in permeability across the TBP area. The potential for mobilizing contaminants beyond the capture zone is also a concern.	Implementation limited by variable soil conditions and low-permeability soil that could impede percolation and contact with reagents. Presence of UXO may also be a constraint.	Moderate to high
Stabilization/solidification	Effective at limiting mobility of metals only; therefore, only applicable to soils in the pushout area. Contaminant mobility would be reduced, but contaminant toxicity would not. Volume of contaminated material would increase. Long-term effectiveness uncertain due to the unpredictable effects of weathering, groundwater infiltration, and physical disturbance (e.g., local detonations).	Implementation limited by scattered nature of contamination. Proximity to marsh and presence of UXO may also be constraints.	Moderate to high
In-situ vitrification	Applicable to soils contaminated with organics and metals. Toxicity and mobility of organics and metals would be reduced; volume would not.	Somewhat difficult to implement because of the innovative nature of this technology. Implementation limited by high organic content in soil. Presence of UXO may also be a constraint.	Moderate to high
Electrokinetic processing	Could reduce the area of contamination to be addressed by mobilizing metals and some organics with an electric current applied across the site. Studies indicate a period of 10 years may be required to concentrate contaminants. The potential for mobilizing contaminants beyond the capture zone is a concern. Would not be effective at mobilizing particulate lead from pushout area soils.	Somewhat difficult to implement because of the innovative nature of this technology. Presence of UXO may also be a constraint.	Moderate to high

SVOCs and metals. PCBs would not be removed by this process. Extraction fluids are passed through soil by using an injection or infiltration process, recovered, and recycled when possible. Recovered groundwater and fluids laden with desorbed contaminants may require treatment to meet appropriate discharge standards before release to wastewater treatment facilities or receiving streams. Treatment of the recovered fluids results in process sludges and residual solids, such as spent carbon and spent ion exchange resin, which must be appropriately treated before disposal. Air emissions of VOCs from recovered fluids would be collected and treated, as appropriate, to meet applicable regulatory standards.

The effectiveness of soil flushing is limited at sites, like the TBP area, with low-permeability soils. The permeability of soils in the TBP area varies laterally and vertically over several orders of magnitude because of the arrangement of interbedded facies, making any estimates of effectiveness difficult. In addition, the potential for immobilizing contaminants beyond the capture zone and introducing surfactants to the subsurface is of general concern. Soil flushing is considered a developing technology. For these reasons, soil flushing has been rejected from further consideration.

**Stabilization/Solidification.** In stabilization/solidification technologies, a fixing or stabilizing agent is mixed into the soil to create a product that is stable and resistant to leaching. In this process, additives are mixed directly into contaminated soil by conventional backhoes or equipment specifically designed for in-situ chemical injection and mixing. This technology effectively reduces the mobility of contaminants through both physical and chemical means. In-situ stabilization/solidification is considered most effective for immobilizing metals; therefore, it could only be applied in situ to fix contaminated soil at the pushout area. SVOC- and PCB-contaminated soil would have to be addressed by implementing an additional treatment technology.

The long-term effects of weathering (e.g., freeze-thaw cycles, acid precipitation, and wind erosion), groundwater infiltration, and physical disturbance (e.g., local detonations) could significantly affect the integrity of the stabilized mass, potentially reducing the long-term effectiveness of this technology. Contaminant mobility would be reduced, but contaminant toxicity would not. In addition, the volume of contaminated material would increase. For these reasons, stabilization/solidification has been rejected from further consideration.

**In-Situ Vitrification.** In-situ vitrification uses an electric current to melt soil or other earthen materials at extremely high temperatures (2,900 to 3,650°F) and thereby immobilize most inorganics (metals) and destroy organics (VOCs, SVOCs, and PCBs) by pyrolysis. To initiate the process, graphite electrodes are placed on the surface of the soil so that current can flow in the soil beyond the boiling temperature of water to the melting point of soil. The molten soil zone grows downward and outward. A vacuum-pressurized hood is placed over the vitrification zone to contain

and process any contaminants emanating from the soil during vitrification. The vitrification product is a chemically stable, leach-resistant glass and crystalline material similar to obsidian or basalt. Metals are incorporated within the vitrified product. Water vapor and organic pyrolysis combustion products are captured and drawn into an off-gas treatment system that removes particulates and other contaminants from the gas.

The in-situ application of this technology is considered innovative for waste treatment and has only been operated for test and demonstration purposes. For this reason, in-situ vitrification has been rejected from further consideration.

**Electrokinetic Processing.** Electrokinetic processing is an in-situ transport process that uses electric current to decontaminate soils contaminated with metals and some organics (polar species), such as phenol. The effectiveness of this technology is based on its ability to concentrate contaminants within a small area, thus reducing the area of contamination to be addressed. The application of electric current produces an acid in the anode compartment that sweeps across the soil, desorbing contaminants from the surface of soil particles and initiating electromigration of contaminants toward the respective electrodes. To initiate the process, anode and cathode series are inserted or laid on the ground, and a current is established across the electrodes. A conditioning fluid is introduced at the electrodes. A recent bench-scale study indicates that the time required to concentrate contamination in the TBP area could be as long as 10 years (Peters 1995). In addition, this process would not be effective at removing particulate lead, which makes up a significant proportion of contamination in the pushout area (U.S. Department of Energy [DOE] 1993/1994; EPA 1993b,d). For these reasons, electrokinetic processing has been rejected from further consideration.

#### 4.2.4.2 Ex-Situ Physical/Chemical Treatment Technologies

Several ex-situ physical/chemical treatment technologies are available for treating soil contaminated with metals, SVOCs, and PCBs. These technologies include stabilization/fixation, vitrification, soil washing, soil leaching, oxidation/reduction, dehalogenation, incineration, and thermal desorption. The main advantages of ex-situ treatment are that it generally requires shorter time periods than in-situ treatment and that it affords more certainty about the uniformity of treatment because of the ability to homogenize, screen, and continuously mix the soil. However, ex-situ treatment requires excavation of soils, leading to increased costs and engineering for equipment, the necessity of UXO surveying, possible permitting, and material handling (EPA 1994).

The screening analysis of potential ex-situ treatment technologies is discussed in the following subsections and summarized in Table 4.5.

**TABLE 4.5 Summary of Screening Analysis for Ex-Situ Treatment Technologies**

Treatment Technology	Effectiveness	Implementability	Cost
Stabilization/fixation	Effective at limiting mobility of metals and PCBs; applicable to soils from the pushout area and southern main pit. Contaminant mobility would be reduced, but contaminant toxicity would not. Final waste volume would increase.	Could be implemented with readily available equipment and materials.	Moderate
Vitrification	Effective at reducing toxicity of organics and metals. Volume would be reduced. Applicable to soils contaminated with organics and metals.	Could be implemented with readily available equipment and materials.	High
Soil washing	Effective at reducing toxicity, mobility, and volume of metals and SVOCs (and possibly PCBs); applicable to soils in the northern main pit and pushout area.	Could be implemented with readily available equipment and materials.	Low to moderate
Soil leaching	Effective at reducing toxicity, mobility, and volume of metals and SVOCs; applicable to soils in the northern main pit and pushout area.	Could be implemented with readily available equipment and materials.	Moderate
Reduction/oxidation	Effective at reducing contaminant toxicity, mobility, and volume; applicable to soils contaminated with metals only.	Could be implemented with readily available equipment and materials.	Moderate
Dehalogenation	Effective at reducing toxicity, mobility, and volume of PCBs and halogenated SVOCs; applicable only to soils in the main pits.	Could be implemented with readily available equipment and materials.	Moderate
Incineration	Effective at reducing contaminant volume; toxicity and mobility would not be reduced. Bottom ash would require further treatment by stabilization. May be required to treat PCB-contaminated soil (depending on concentrations).	Could be implemented with readily available equipment and materials.	Moderate to high
High-temperature thermal desorption	Effective at reducing toxicity, mobility, and volume of organics only; applicable to soils in the main pits.	Could be implemented with readily available equipment and materials.	Moderate

**Stabilization/Fixation.** In stabilization/fixation technologies, a fixing or stabilizing agent is mixed into the soil to create a product that is stable and resistant to leaching. This process involves mixing reagents with contaminated soil in a mixing vessel, such as a pug mill, to immobilize the contaminants and solidify the waste. This technology effectively reduces the mobility of contaminants through both physical and chemical means. Stabilization/fixation is considered effective for immobilizing metals and PCBs; therefore, it could only be applied to soils excavated from the pushout area and southern main pit. SVOC-contaminated soil may have to be addressed by implementing an additional treatment technology (e.g., if treatment codes are exceeded).

The predominant fixing agents currently in use are Portland cement, lime/fly ash, Portland cement/fly ash, and Portland cement/sodium silicate. Gypsum, bentonite, and zeolites could also be used, as could a number of proprietary agents. Chemical stabilization with cement and fly ash is an established practice for treating hazardous waste and has been retained as potentially applicable to address surface soil contamination in the TBP area.

**Ex-Situ Vitrification.** Ex-situ vitrification is designed to encapsulate inorganic contaminants rather than reduce inorganic contaminant concentration. This process involves electrically heating contaminated material to temperatures high enough to cause it to melt. Vitrification is applicable to a full range of contaminants. Inorganic contaminants are encapsulated in the vitrified mass; organic contaminants are destroyed because of the high temperatures achieved during processing. Organic off-gases and some volatile metal contaminants would have to be controlled and treated during process operation. The vitrified product is a chemically stable, leach-resistant glass or crystalline material similar to obsidian or basalt, ready for disposal. This technology is not considered cost-effective for the small volume of soils to be treated at the TBP area; on this basis, ex-situ vitrification has been rejected from further consideration.

**Soil Washing.** Soil washing is an aqueous-based process that reduces soil contamination through the use of particle size separation. This technology is applicable to soils contaminated with metals, SVOCs, and possibly PCBs. The effectiveness of soil washing is based on the finding that most organic and inorganic contaminants tend to bind, either chemically or physically, to the fine-grained fraction of the soil matrix (clay, silt, and organic soil particles). Washing processes that separate the fine particles (silt and clay) from the coarser material (sand and gravel) separate and concentrate the contaminants into a smaller volume of soil that can be further treated or disposed of.

Gravity separation is an effective method for removing high or low specific gravity particles, such as lead. Attrition scrubbing removes adherent contaminant films from coarser particles. The clean, larger fraction can be returned to the site for use as clean fill. The washing agent and soil fines are residuals from this process that would require further treatment (e.g., through soil

leaching). A bench-scale study has indicated that density separation is effective at removing metals from the sand fraction of TBP area pushout soils (Alternative Remedial Technologies, Inc. [ART] 1995). An additional study is needed to evaluate the efficacy of treating the fine-grained fraction through chemical extraction (soil leaching). On the basis of this preliminary study, it is estimated that a volume reduction of 94% may be achievable. For this reason, this technology type has been retained.

**Soil Leaching.** Soil leaching is a chemical process used to remove metals that remain in the fine sand, silt, and clay soil particles after the soil washing and separation process. Sand and fines are leached in separate parallel circuits with an acid solution. The effectiveness of soil leaching is achieved through dissolving smaller metallic particles and ionic metals remaining in the soil. A final step may include precipitation of metals from the leaching solution for recovery and recycling. Soil leaching is applicable to soils contaminated with metals and possibly SVOCs. PCB-contaminated soil would have to be addressed by implementing an additional treatment technology; however, these soils constitute a small fraction of the TBP area soils to be treated. On this basis, soil leaching has been retained.

**Reduction/Oxidation.** Reduction/oxidation (redox) reactions chemically convert contaminants to nonhazardous or less toxic compounds that are more stable, less mobile, and/or inert (EPA 1994). The oxidizing agents most commonly used for treatment are ozone, hydrogen peroxide, hypochlorites, chlorine, and chlorine dioxide. Chemical redox is applicable to soils contaminated with metals. SVOC- and PCB-contaminated soil would have to be addressed by implementing an additional treatment technology. This technology is not considered cost-effective for soils with high contaminant concentrations (because of the large amounts of oxidizing agent required); on this basis, chemical redox has been rejected from further consideration.

**Dehalogenation.** Dehalogenation is a decomposition process (e.g., base-catalyzed decomposition or glycolate) designed to remediate soils contaminated with chlorinated organic compounds (especially PCBs and halogenated SVOCs). During the dehalogenation process, contaminated soil is screened, processed with a crusher and pug mill, and mixed with sodium bicarbonate. The mixture is heated in a rotary reactor to decompose and partially volatilize the contaminants. The effectiveness of this technology is limited in soils with high clay and moisture content. In addition, it is only applicable to a small portion of the soils to be excavated at the TBP area. On this basis, dehalogenation has been rejected from further consideration.

**Incineration.** Waste material can be incinerated by rotary kiln, fluidized bed, slagging, and liquid injection incinerators. Rotary kiln and fluidized bed incineration are typically used to destroy

organic contaminants. Rotary kilns are refractory-lined, slightly inclined, rotating cylinders that function as a combustion chamber and operate at temperatures up to 1,800°F. Waste is introduced at the high end, and ash is collected from the bottom end. Flue gases pass through a secondary chamber and control equipment before exiting to the atmosphere. Fluidized-bed incinerators contain a bed of sized granular refractory material in a refractory-lined vessel. Waste is injected onto the bed and incinerated as air is forced up through the bed at a velocity sufficient to fluidize the burning material.

Incineration technologies do not reduce the toxicity or mobility of inorganic constituents; they do reduce the total waste volume but produce an ash residue. Heavy metals can produce a bottom ash that requires further treatment by stabilization, although volatile metals would leave the combustion unit with the flue gases and would require the installation of gas cleaning systems for removal. In addition, given the small volume of soil to be treated, this option would only be applied at an off-site facility. Waste transport would result in an increased risk of transportation accidents and related impacts, the magnitude of which would depend on the waste volume and type, mode of transportation, and facility location. Given the high costs associated with transportation and treatment, incineration is not considered cost-effective. However, this option has been retained because it may be required to treat PCB-contaminated soil (depending on concentrations, incineration may be the required treatment).

**High-Temperature Thermal Desorption.** High-temperature desorption involves heating wastes to temperatures of 600 to 1,000°F. It is applicable to soils contaminated with SVOCs and PCBs. In the treatment process, a carrier gas or vacuum system transports volatilized water and organics to the gas treatment system. Some volatile metals may also be removed. Contaminants are removed from the gas stream and disposed of. Bench-scale studies would be required to determine the effectiveness of organics removal. Thermal desorption is only applicable to a small portion of the soils to be excavated at the TBP area, but it is considered a cost-effective treatment for PCB-contaminated soil. On this basis, this option has been retained.

#### 4.2.4.3 Biological Treatment Technologies

Several biological technologies are available for treating contaminated soil. Biological treatment technologies use living organisms, such as bacteria or fungi, to detoxify or immobilize contaminants in waste. These technologies are applied primarily for converting organic contaminants into nontoxic products. Bioremediation has also been used to degrade inorganic contaminants, such as nitrates, and it can be used to detoxify or immobilize certain metals by changing their oxidation state. The SVOC- and PCB-contaminated soils in the main pits are candidates for bioremediation.

Biological treatment technologies can be implemented as either in-situ or ex-situ processes. The advantage of in-situ treatment is that it allows soil to be treated without being excavated and transported, resulting in a significant cost savings. However, in-situ treatment generally requires longer time periods, and there is less certainty about the uniformity of treatment because of the variability in soil characteristics and because the efficacy of the process is more difficult to confirm (EPA 1994). Ex-situ treatment generally requires shorter time periods; however, it requires excavation of soils, leading to increased costs and engineering for equipment, the necessity of UXO surveying, possible permitting, and material handling/worker exposure considerations (EPA 1994).

The screening analysis of potential biological treatment technologies is discussed in the following subsections and is summarized in Table 4.6.

**In-Situ Bioremediation.** In-situ bioremediation is a destructive technique aimed toward stimulating microorganisms in the soil to grow and use the contaminants as a food and energy source by creating a favorable environment for the microorganisms. Generally, this means providing some combination of oxygen, nutrients, and moisture and controlling the temperature and pH. Sometimes, microorganisms adapted for degradation of specific contaminants can be applied to enhance the process. This technology is applicable to soils contaminated with organics (e.g., PCBs); it is not applicable to soils contaminated with metals.

A recent treatability study has shown that sufficient numbers of microorganisms suitable for removal of the organic COCs are present; however, the low permeability of the soil would limit the effectiveness of in-situ bioremediation (Huang 1994).

Because in-situ bioremediation is only applicable to a small portion of the soils to be excavated at the TBP area, it has been rejected from further consideration.

**TABLE 4.6 Summary of Screening Analysis for Biological Treatment**

Biological Treatment Technology	Effectiveness	Implementability	Cost
In-situ bioremediation	Applicable to soils contaminated with organics; would not address metals contamination in the pushout area.	Implementation limited by low-permeability soil that could impede aeration of soils.	Moderate
Ex-situ bioremediation	Applicable to soils contaminated with organics; would not address metals contamination in the pushout area.	Can be implemented with conventional equipment and procedures.	Moderate

**Ex-Situ Bioremediation.** Ex-situ bioremediation technologies include slurry-phase and solid-phase processes applicable to soils contaminated with organics (e.g., PCBs). Slurry-phase methods, such as batch treatment in a reactor, might be effective because operating parameters could be closely controlled. Solid-phase methods, such as placing in piles, have the advantage of low setup costs. Metals would not be addressed through either treatment.

A recent treatability study reported that significant numbers of microorganisms, including methanotrophs and biphenyl degraders (that are appropriate for degrading organics), are present and that ex-situ bioremediation by using bulking agents might be effective. Another treatability study has indicated that significant numbers of heterotrophs suitable for degradation of chlorinated organics may also be present (Huang 1994).

Because ex-situ bioremediation is only applicable to a small portion of the soils to be excavated at the TBP area, it is not considered a cost-effective treatment. Therefore, ex-situ bioremediation has been rejected from further consideration.

#### **4.2.5 Short-Term Storage**

Short-term storage involves isolating contaminated material to protect human health and the environment until the material can be treated and/or permanently disposed of. This technology typically involves constructing an engineered facility to minimize the potential for contaminant migration. Short-term storage would not reduce contaminant toxicity or volume, but it could reduce contaminant mobility and potential exposures. Such facilities also could be developed to support cleanup activities. The storage facility could be an enclosed structure or an outdoor area with a gravel pad or other base and covers, such as tarpaulins. These options could be applied either on-site or at an off-site facility.

The screening analysis of short-term storage is summarized in Table 4.7. Use of an off-site facility would require that the material be transported off-site and that an appropriate facility be available. Waste transport would result in an increased risk of transportation accidents and related impacts, the magnitude of which would depend on the waste volume and type, mode of transportation, and facility location. No suitable off-site facility exists for short-term storage of site waste, and none is likely to become available in the near future. Therefore, only the on-site application has been retained.

#### **4.2.6 Disposal**

Disposal options for contaminated soil involve confinement for permanent disposition. The only disposal option considered for the waste resulting from site remediation at the TBP area is

**TABLE 4.7 Summary of Screening Analysis for Short-Term Storage**

Short-Term Storage Facility	Effectiveness	Implementability	Cost
Open and enclosed structures	Could effectively protect human health and the environment in the short term by reducing contaminant mobility and limiting exposures. The off-site application of this option has been rejected on the basis of potential increased risk to workers and the general public due to increased likelihood of exposures associated with waste transportation.	The on-site application could be easily implemented with readily available resources. Such facilities also could be developed to support cleanup activities. An appropriate storage facility is not currently available off-site, and it is unlikely that such a facility would become available in the near future.	Low to moderate

off-site land-based facilities. Material determined to be hazardous under RCRA could be shipped to a permitted facility; nonhazardous material could be shipped to a sanitary or demolition landfill. Related requirements are presented in Appendix B (Table B.4).

Under RCRA regulations (40 CFR Part 261), a solid waste is considered to be a regulated hazardous waste if it is not otherwise excluded from regulation as a hazardous waste and either exhibits any of the characteristics identified in Subpart C of this regulation (a “characteristic hazardous waste”) or is listed in Subpart D of the regulation (a “listed hazardous waste”). Waste determined to be hazardous as defined by RCRA must be disposed of according to the requirements of 40 CFR Parts 264 and 268 (see Appendix B). In addition, the LDRs promulgated by EPA in 40 CFR Part 268 preclude the disposal of certain contaminants without prior treatment. The LDRs would apply to any TBP area soils regulated under 40 CFR Part 268, and land disposal of such waste would require that appropriate treatment standards be met. The treatment standards are based on contaminant concentrations in the waste, the treatment technology used, or waste characteristics after treatment. Untreated soils from the TBP area pushout area may be categorized as hazardous waste code D008 under 40 CFR Part 261 (Subpart C) because of the high lead concentrations. These soils would require treatment by stabilization to satisfy LDRs prior to disposal. PCB-contaminated soils would also require treatment prior to disposal. If TBP area soils are found to be regulated under TSCA (e.g., if concentrations of PCBs exceed 50 ppm in unrestricted-access areas), these soils may require incineration prior to disposal. If PCB-contaminated soils are not regulated under TSCA (i.e., if concentrations are less than 50 ppm), they would undergo stabilization prior to disposal.

The implementability of land disposal at an off-site facility is affected by the availability of suitable sites for disposal of APG waste. Special pricing through an on-site contractor at APG could keep disposal costs down relative to off-site contractors, thereby making disposal a cost-effective option.

The screening analysis of the disposal option is summarized in Table 4.8. On the basis of this evaluation, the disposal option has been retained.

### 4.3 POTENTIALLY APPLICABLE TECHNOLOGIES

Potentially applicable technologies for remediation of the TBP area are summarized in Table 4.9. This summary is based on the screening analysis presented in Section 4.2. The technology types that have been retained through this analysis were used to develop preliminary interim remedial action alternatives for the TBP area. These alternatives are identified in Section 5.

**TABLE 4.8 Summary of Screening Analysis for Disposal**

Disposal Option	Effectiveness	Implementability	Cost
Off-site, land-based disposal	Provides protection of environment and reduces exposures. Treatment of contaminated soils would be required prior to disposal.	Subtitle C and D landfills are available in the eastern region of the United States (e.g., Virginia and Pennsylvania).	Moderate

TABLE 4.9 Summary of Potentially Applicable Technologies

General Response Action	Technology Type	Evaluation Result	Comments
No action	Not applicable	Retained	Would provide a baseline for comparison with action alternatives.
Institutional control	Access restriction	Retained	Could effectively limit entry to contaminated areas and could be used to support other response actions.
	Ownership and use or deed restrictions	Retained	Could minimize exposures to site contaminants by limiting use of contaminated areas and could be used to support other response actions.
	Monitoring	Retained	Could provide data useful for minimizing exposures and could be used to support other response actions.
In-situ containment	Surface control diversions	Retained	Could limit contaminant mobility by directing surface runoff from contaminated areas and could be used to support other response actions.
	Vertical barriers	Retained	Could limit contaminant mobility by impeding groundwater discharge to the marsh and by minimizing erosion of contaminated soil from the pushout area.
	Caps/covers	Retained	Could limit airborne emissions, precipitation-enhanced percolation and leaching, and contaminant resuspension via surface water runoff.
Removal	Excavation	Retained	Could effectively remove the source of contamination and could be readily implemented. UXO survey would be required.
	Clearing and grubbing	Retained	Could effectively remove vegetation from the site to support overall cleanup activities.

TABLE 4.9 (Cont.)

General Response Action	Technology Type	Evaluation Result	Comments
In-situ treatment	Soil flushing	Rejected	Difficult to implement because of limitations due to site conditions. Ineffective for removing PCBs.
	Stabilization/solidification	Rejected	Difficult to implement because of limitations due to site conditions. Ineffective for limiting mobility of PCBs.
	Vitrification	Rejected	Difficult to implement because of innovative nature of technology and site conditions.
	Electrokinetic separation	Rejected	Difficult to implement because of innovative nature of technology and site conditions. Ineffective at mobilizing particulate lead.
Ex-situ treatment	Stabilization/fixation	Retained	Could reduce contaminant mobility but increases volume. Would require an engineered treatment facility.
	Vitrification	Rejected	Could reduce contaminant toxicity and mobility; volume would not be reduced. Would require an engineered treatment facility; not considered cost-effective.
	Soil washing	Retained	Could reduce contaminant toxicity, mobility, and volume. Could be implemented on-site.
	Soil leaching	Retained	Could reduce contaminant toxicity, mobility, and volume. Would facilitate recovery of lead for recycling. Could be implemented on-site.
	Reduction/oxidation	Rejected	Could reduce toxicity, mobility, and volume (for metals only). Not considered cost-effective.
	Dehalogenation	Rejected	Could reduce toxicity, mobility, and volume (for chlorinated organic compounds only). Effectiveness limited by site conditions.

TABLE 4.9 (Cont.)

General Response Action	Technology Type	Evaluation Result	Comments
Ex-situ treatment (cont.)	Incineration	Retained	Could reduce contaminant toxicity, mobility, and volume (for organics). Would require an engineered treatment facility.
	Thermal desorption	Retained	Could reduce contaminant toxicity, mobility, and volume (for organics).
Biological treatment	In-situ bioremediation	Rejected	Could reduce contaminant toxicity, mobility, and volume (for organics). Effectiveness limited by site conditions.
	Ex-situ bioremediation	Rejected	Could reduce contaminant toxicity, mobility, and volume (for organics). Not considered cost-effective.
Short-term storage	Open and closed structures	Retained	Could effectively reduce contaminant mobility in the short term and support cleanup activities.
Disposal	Land-based facility	Retained	Could effectively provide protection of environment and reduce exposures. Treatment required prior to disposal.

## 5 DEVELOPMENT AND SCREENING OF PRELIMINARY ALTERNATIVES

Preliminary alternatives for remediating surface soil in the J-Field TBP area were developed and screened in accordance with CERCLA, EPA guidance (EPA 1988), and the NCP (EPA 1990a). Five preliminary alternatives, including no action, were developed on the basis of the criteria presented in Section 5.1. These alternatives, identified and described in Section 5.2, were then screened on the basis of the criteria defined in Section 5.3. Each of the five preliminary alternatives was passed through the screening analysis presented in Section 5.4; they are identified as final alternatives and listed in Section 5.5. These final alternatives are further developed and described in Section 6 and evaluated in detail in Section 7. The preferred alternative will be identified in the proposed plan for this interim remedial action.

### 5.1 CRITERIA FOR DEVELOPING ALTERNATIVES

EPA has established an approach for developing remedial action alternatives that are appropriate to the site-specific conditions (EPA 1988, 1990a). In this approach, the scope, characteristics, and complexity of the site are considered in developing a range of alternatives that would be protective of human health and the environment. This protection can be achieved by eliminating, reducing, and/or controlling risks posed by each pathway at a site. Two major categories of response, containment and treatment, are considered in developing remedial action alternatives:

- Containment involves little or no treatment but protects human health and the environment by preventing or controlling exposures to contaminants through engineering measures and by using institutional controls as necessary to ensure the continued effectiveness of a response; and
- Treatment ranges from alternatives that use treatment as the primary element of the response to address the principal threat(s) posed by a site to alternatives that use treatment to reduce the toxicity, mobility, or volume of contaminated material to the maximum extent feasible, minimizing the need for long-term management.

As stated in Section 121(b) of CERCLA, as amended, the most preferred alternatives (1) represent permanent and cost-effective solutions for protecting human health and the environment; (2) permanently and significantly reduce the toxicity, mobility, or volume of contaminated material; and (3) apply alternative treatment or resource recovery technologies to the extent possible. Least preferred alternatives involve the transport and disposal of waste off-site without treatment.

A no-action alternative is also included to provide a baseline for comparison with other alternatives. For the analysis in this FFS, the baseline condition of the J-Field TBP area would include only minor maintenance activities, such as mowing and monitoring.

## **5.2 IDENTIFICATION OF PRELIMINARY ALTERNATIVES**

Technologies potentially applicable to managing contaminated surface soil at the J-Field TBP area are identified and screened in Section 4 (Table 4.9). On the basis of this screening, various technologies were identified as potential components of remedial action alternatives for the site. These technologies have been incorporated into five preliminary alternatives:

- Alternative 1: No Action;
- Alternative 2: Limited Removal and Disposal, and In-Situ Containment;
- Alternative 3: Removal and Short-Term Storage;
- Alternative 4: Removal, On-Site Treatment, and Limited Disposal; and
- Alternative 5: Removal, Off-Site Treatment, and Disposal.

In-situ containment is the primary emphasis of Alternative 2, and source control through removal is the primary emphasis of Alternatives 3, 4, and 5.

The J-Field site would remain secured, and existing institutional controls, such as ownership and use or deed restrictions, are implicitly included in each action alternative during the cleanup period. These controls are also included for the no-action alternative. Controls, such as monitoring, would be increased as needed. Each alternative would require various support activities before implementation, including the design and construction of staging areas, procurement of appropriate equipment, and development of contingency plans and operational controls to minimize contaminant releases. Site preparation activities would include clearing and grubbing contaminated areas, conducting UXO surveys, constructing access roads, and emplacing site perimeter dikes for surface water control. Shoreline stabilization has been included only for Alternatives 2 and 3. Because Alternatives 4 and 5 involve total removal of contaminated surface soil, shoreline stabilization was not included as a component.

### **5.2.1 Alternative 1: No Action**

Alternative 1 is included to provide a baseline for comparison with the other action alternatives. Under this alternative, the site would continue to operate under restricted access. Current conditions of the contaminated surface soil would continue.

### **5.2.2 Alternative 2: Limited Removal and Disposal, and In-Situ Containment**

Under Alternative 2, contamination in the two main pits and the pushout area would be contained in place with a protective cover. Limited excavation and disposal would be implemented to address contaminated soil in the main pits.

The “risk-reduction cover” would involve placing a geotextile fabric over the vegetation-cleared surface (about 5 acres [218,000 ft<sup>2</sup>]), which would then be covered by a layer of soil sufficient to raise the site topography above the 100-year floodplain. The soil layer would be stabilized with a vegetative cover. Runoff from the area would be diverted by surface grading controls. Erosion of contaminated soil from the portion of the pushout area in contact with the marsh would be mitigated by installing a vertical barrier. Because the soil layer would be emplaced incrementally in 2-ft layers, UXO screening most likely would not be required for this component. A UXO visual survey would be required for the limited excavation component. Because the area of excavation is limited, hand removal methods may be used (depending on the density of metal contacts present). The limited disposal component under Alternative 2 would involve shipping about 400 yd<sup>3</sup> of soil to a permitted off-site facility for treatment (stabilization and possibly incineration) and disposal.

Stabilization of the shoreline about 2,000 ft to the south of the TBP area would also be implemented as part of this alternative. A UXO survey would be conducted by a two-man clearance team. Installation of a boulder riprap berm would reduce the potential for long-term erosion along the shoreline.

### **5.2.3 Alternative 3: Removal and Short-Term Storage**

Under Alternative 3, contaminated surface soil in the two main pits and pushout area that exceed soil cleanup criteria would be removed and transported to an on-site, short-term storage facility, where it would be stored until final remediation is addressed at J-Field.

Soil would be excavated to a depth of 2 ft from the source areas with standard construction equipment, such as front-end loaders, scrapers, and backhoes. The excavation area would be surveyed for UXO in the upper 2 to 4 ft. Approximately 16,000 yd<sup>3</sup> of soil would be removed.

Runoff from the area would be diverted by surface grading controls. Following excavation, the area would be backfilled with clean soil. The short-term storage facility would be constructed adjacent to the Prototype Building to minimize the distance over which the material would have to be transferred. This location is the highest topographic area at J-Field. The short-term facility would be a modular building consisting of fabric walls. The base of the structure would require the construction of a bermed and drained concrete or asphalt pad equipped with a leachate collection system. An air infiltration system may also be required.

Stabilization of the shoreline about 2,000 ft to the south of the TBP area would also be implemented as part of this alternative. A UXO survey would be conducted by a two-man clearance team. Installation of a boulder riprap berm would reduce the potential for long-term erosion along the shoreline.

#### **5.2.4 Alternative 4: Removal, On-Site Treatment, and Limited Disposal**

Under Alternative 4, contaminated soil in the two main pits and pushout area that exceeds soil cleanup criteria would be removed and treated by soil washing/leaching to reduce the volume of waste for off-site disposal.

The removal component of Alternative 4 would be similar to that of Alternative 3; however, the excavated soil would be transported to an on-site soil washing/leaching treatment facility, which would be constructed adjacent to the Prototype Building (though I- and H-Fields are other potential sites). For the conceptual design, it was estimated that 16,000 yd<sup>3</sup> of soil would be treated. A portion of the soil from the southern main pit, contaminated with PCBs, would be sent off-site for treatment and disposal. After removal and treatment, the cleaned material would either remain on-site to be used as fill or be shipped to an off-site solid waste disposal facility, in accordance with the State of Maryland's preference. Limited disposal under Alternative 4 would involve shipping recovered lead, scrap metal, and other (nonhazardous) refuse, as necessary, to an off-site facility (smelter and/or municipal landfill).

#### **5.2.5 Alternative 5: Removal, Off-Site Treatment, and Disposal**

Under Alternative 5, contaminated soil in the two main pits and pushout area that exceeds soil cleanup criteria would be removed and transported to an off-site treatment and disposal facility.

The removal component of Alternative 5 would be similar to that of Alternative 3; however, the excavated soil would be temporarily staged on-site following excavation, then transported to an off-site treatment and disposal facility.

### **5.3 CRITERIA FOR SCREENING ALTERNATIVES**

The five preliminary alternatives were evaluated for applicability to remediating the J-Field TBP area on the basis of three general criteria: effectiveness, implementability, and cost. The effectiveness of an alternative is defined by its overall ability to protect human health and the environment in both the short term and long term. Measures of effectiveness include (1) reduction of potential long-term impacts to human health and the environment; (2) reduction of contaminant toxicity, mobility, or volume through treatment; (3) control of potential impacts to human health and the environment during the action period; (4) timeliness; and (5) consistency with regulatory requirements.

The implementability of an alternative is defined by its technical and administrative feasibility and availability of resources. Technical feasibility refers to the ability to construct, reliably operate, and meet technology-specific regulations for process options until the remedial action is complete. It also addresses the operation, maintenance, replacement, and monitoring of the technical components of an alternative, as appropriate; potential constraints associated with the site environment are also considered. Administrative feasibility addresses the acceptability of an alternative by other agencies and groups and pertinent environmental requirements, such as permits, as appropriate. Resource availability addresses the resources required to implement specific components of an alternative and the ability to obtain them.

The cost of an alternative is considered only in a comparative manner at the screening stage by comparing general estimates for each alternative to evaluate relative cost. This comparison helps decision makers to determine whether the cost of one alternative is much greater than that of another alternative of similar effectiveness and implementability. If the cost of an alternative is inordinately excessive compared to the effectiveness it provides, that alternative can be screened from further consideration.

### **5.4 SCREENING OF PRELIMINARY ALTERNATIVES**

#### **5.4.1 Alternative 1: No Action**

Under Alternative 1, the TBP area would remain unchanged. Activities that would continue under the no-action alternative include maintenance and periodic monitoring.

#### **5.4.1.1 Effectiveness**

Alternative 1 would not involve any treatment to reduce the toxicity, mobility, or volume of contaminated surface soil at the TBP area, and it would not provide for a timely or permanent response to the contamination problem. In addition, certain regulatory requirements would not be met. The potential for exposures of wildlife, trespassers, and site workers would continue in the short term and could increase over time if contaminants were released to other media (groundwater, surface water, sediment, or air). Potential long-term health impacts to site workers and the general public would be low as a result of institutional controls; however, adverse impacts to wildlife would be expected due to continued exposure.

#### **5.4.1.2 Implementability**

Minimum site operations, including maintenance activities (e.g., mowing) and monitoring, would continue with readily available resources.

#### **5.4.1.3 Cost**

Costs associated with Alternative 1 (baseline conditions) include those for continuing the general maintenance and security of the site. Monitoring activities would also be included. Annual costs are estimated to be about \$300,000.

### **5.4.2 Alternative 2: Limited Removal and Disposal, and In-Situ Containment**

#### **5.4.2.1 Effectiveness**

The effectiveness of the soil cover could be limited by the shallow water table and its proximity to the marsh and by the potential for flooding, because portions of the TBP area are located within the 100-year floodplain (FEMA 1986). Other factors that could limit the effectiveness of the soil cover include the activities of burrowing animals present at the site and growth of deep-rooted vegetation on the soil cover. Engineering controls (e.g., contouring and landscaping) and maintenance could effectively alleviate these limitations. Regular maintenance and monitoring would be necessary to maintain long-term effectiveness. Some repair might be necessary if the soil cover were to deteriorate.

#### **5.4.2.2 Implementability**

Alternative 2 could be implemented with readily available resources. Technical feasibility of the in-situ containment component and shoreline stabilization would be high. Timeliness would be affected by the potential presence of UXO, which would require labor-intensive removal methods for the localized areas. However, localized removal would take considerably less time than full excavation and removal or excavation and on-site treatment.

Approximately 60% of the site is above the 100-year floodplain; another 20% is above the 5-ft contour and would only require 2 to 3 ft of cover to exceed the 100-year floodplain line. The remaining 20% would have to be raised 6 to 7 ft to exceed the 100-year floodplain line. The edge of the cover along the marsh would be engineered as a berm that would be covered by geotextile fabric and rock riprap to protect against erosion from the 100-year flooding.

The disposal component of Alternative 2 would be relatively straightforward. About 400 yd<sup>3</sup> of contaminated soil would be sent off-site for treatment and disposal.

#### **5.4.2.3 Cost**

The estimated cost of in-situ containment would be about \$2 million. This cost includes site preparation activities (clearing and grubbing, UXO surveying, constructing and improving roads, and limited excavating), construction of the soil cover, limited disposal, direct and indirect costs, remedial design costs, and project management. The cost of Alternative 2 would be comparable to Alternative 3 and lower than Alternatives 4 and 5.

### **5.4.3 Alternative 3: Removal and Short-Term Storage**

#### **5.4.3.1 Effectiveness**

Alternative 3 would not include a treatment component; therefore, contaminant toxicity, mobility, and volume would not be reduced through treatment. However, potential exposures to wildlife, trespassers, and site workers would be reduced through removal of surface soil. The storage component of this alternative would provide for short-term protection, but it would not be protective in the long term.

Short-term risks to on-site workers and the general public would be significant for Alternative 3 because of the removal component. Risks include those related to the potential for encountering UXO and airborne emissions. Potential short-term environmental impacts, mainly a

result of excavation and grading activities, include disturbance to the soil, temporary increases in fugitive dust emissions and ambient noise level, increased sediment transport to the adjacent marsh, and displacement or loss of vegetation and wildlife habitat. Mitigative measures to reduce these impacts are discussed in Section 7.4.

#### **5.4.3.2 Implementability**

Implementing the removal component of Alternative 3 would be relatively straightforward with regard to the availability of resources. Technical feasibility of the on-site storage component and shoreline stabilization would be high. Contaminated surface soil from the main pits and pushout area could be excavated with standard equipment and readily available materials. Timeliness would be affected by the potential presence of UXO, which will require time-consuming surveys in the upper 2 to 4 ft. Implementing the on-site, short-term storage component would also be straightforward. The storage facility could be built by on-site workers with assistance from the manufacturer's technical representative.

#### **5.4.3.3 Cost**

The estimated cost of removal and on-site, short-term storage would be about \$5 million. This cost includes site preparation activities (clearing and grubbing, UXO surveying, extending electric service, and constructing and improving roads), excavation, construction of the storage facility, transporting material to a storage facility, landscaping the excavation area, direct and indirect costs, remedial design costs, and project management. For this estimate, operation of the facility was assumed to be 5 years. The cost of Alternative 3 would be comparable to Alternative 2 and lower than Alternatives 4 and 5. Although the costs associated with Alternative 3 are lower than those for Alternatives 4 and 5, they do not represent the total cost of long-term remediation. Short-term storage following excavation is only a temporary measure to limit exposures to contaminated surface soil; this action would have to be followed by treatment and disposal at some point in the future.

### **5.4.4 Alternative 4: Removal, On-Site Treatment, and Limited Disposal**

#### **5.4.4.1 Effectiveness**

Excavating contaminated surface soil at the TBP area would reduce potential impacts to human health and the environment in a timely manner and would reduce the potential for contaminant migration. Subsequent treatment of the waste (via soil washing/leaching) would reduce

contaminant toxicity, mobility, and volume over the short and long term. Alternative 4 satisfies the statutory preference for treatment as a principal element of the remediation.

Recent treatability studies (ART 1995) have shown that through a combination of physical separation treatment and chemical extraction (leaching) of sand and fines, a volume reduction of about 94% may be achieved. The remaining 6% would consist of oversize material (>2 mm) that may require disposal as a hazardous waste. These studies were based on achieving interim PRGs for metals. Final remediation goals would have to be determined before further studies are conducted so that total effectiveness could be accurately assessed.

Short-term risks to site workers and the general public would be significant for Alternative 4 because of the removal component. Risks include those related to the potential for encountering UXO and airborne emissions. Potential short-term environmental impacts, mainly a result of excavation and grading activities, include disturbance to the soil, temporary increases in fugitive dust emissions and ambient noise level, increased sediment transport to the adjacent marsh, and the displacement or loss of vegetation and wildlife habitat. Mitigative measures to reduce these impacts are discussed in Section 7.4.

#### **5.4.4.2 Implementability**

Implementing the removal component of Alternative 4 would be relatively straightforward with regard to the availability of resources. Contaminated surface soil from the main pits and pushout area could be excavated with standard equipment and readily available materials. Timeliness would be affected by the potential presence of UXO, which will require time-consuming surveys in the upper 2 to 4 ft. Implementing the on-site treatment component (soil washing/leaching) and limited disposal (recovered lead and scrap metal) would also be straightforward.

#### **5.4.4.3 Cost**

The estimated cost of removal, on-site treatment, and limited disposal would be about \$13 million. This cost includes site preparation activities (clearing and grubbing, UXO surveying, extending electric service, and constructing and improving roads), excavation (to 2 ft), construction of the soil washing/leaching facility, transporting and loading material into the facility, landscaping the excavation area, direct and indirect costs, remedial design costs, and project management. The estimate given here is based on a 94% reduction in soil volume; that is, 6% of washed soil volume and all PCB-contaminated soil would be sent off-site. The cost of Alternative 4 is the highest of all the action alternatives.

## **5.4.5 Alternative 5: Removal, Off-Site Treatment, and Disposal**

### **5.4.5.1 Effectiveness**

Excavating contaminated surface soil at the TBP area would reduce potential impacts to human health and the environment in a timely manner and would reduce the potential for contaminant migration. Subsequent treatment of the waste (off-site) would reduce contaminant toxicity, mobility, and volume over the short and long term. Alternative 5 satisfies the statutory preference for treatment as a principal element of the remediation but does not satisfy the statutory preference for on-site treatment; instead, it involves the transport of a large volume of soil to an off-site facility for treatment.

Short-term risks to site workers and the general public would be significant for Alternative 5 because of the removal component. Potential short-term risks to the general public would also exist because of the off-site transport of untreated hazardous material. Risks include those related to the potential for encountering UXO and airborne emissions. Potential short-term environmental impacts, mainly a result of excavation and grading activities, include disturbance to the soil, temporary increases in fugitive dust emissions and ambient noise level, increased sediment transport to the adjacent marsh, and the displacement or loss of vegetation and wildlife habitat. Mitigative measures to reduce these impacts are discussed in Section 7.4.

Leachability tests have been conducted on surface soils (0 to 4 ft) in the pushout area (Peters 1995). Test results indicate that soil fails the TCLP requirements for hazardous waste with respect to lead. Waste determined to be hazardous as defined by RCRA (40 CFR Part 261) must be disposed of according to the requirements of 40 CFR Parts 264 and 268. Because of the high lead concentrations, untreated soils from the TBP pushout area would be categorized as waste code D008 under 40 CFR Part 268 (Subpart D). These soils would require treatment by stabilization before disposal. The semivolatile components most likely will not present a disposal problem for the soils excavated from the main pits (and volatiles are present mainly at depths greater than 2 ft). However, PCB-contaminated soils (found in the southern main pit) would also require treatment before disposal. Depending on concentrations, the PCB-contaminated soils would undergo either stabilization (if less than 50 ppm) or incineration (if greater than 50 ppm). These technologies have been demonstrated to be effective and acceptable for treating hazardous soils before disposal.

### **5.4.5.2 Implementability**

Implementing the removal component of Alternative 5 would be relatively straightforward with regard to the availability of resources. Contaminated surface soil from the main pits and pushout area could be excavated with standard equipment and readily available materials. Timeliness

would be affected by the potential presence of UXO, which will require time-consuming surveys in the upper 2 to 4 ft. Implementing the off-site treatment and disposal components would also be straightforward. Off-site facilities are available to handle the type and volume of waste that would be generated.

#### **5.4.5.3 Cost**

The estimated cost of removal, off-site treatment, and disposal would be about \$11 million. This cost includes site preparation activities (clearing and grubbing, UXO surveying, and constructing and improving roads), excavation (to 2 ft), construction of a temporary staging area, landscaping the excavation area, direct and indirect costs, remedial design costs, and project management. The cost of Alternative 5 is higher than Alternatives 1 through 3 but less than Alternative 4.

### **5.5 SCREENING SUMMARY AND IDENTIFICATION OF FINAL ALTERNATIVES**

The results of the screening analysis for the preliminary alternatives are summarized in Table 5.1. Information for each alternative was evaluated relative to EPA's screening criteria of effectiveness, implementability, and cost.

Although it would not be protective of human health and the environment in the long term, the no-action alternative (Alternative 1) was retained through this screening to provide a basis for comparison with the remaining action alternatives during the subsequent detailed analysis. Alternative 3 was retained because it offers a low-cost option for reducing risk; however, it is not considered effective in the long term and would thus require an additional action at a future date.

On the basis of the screening analysis, all five preliminary alternatives were retained.

TABLE 5.1 Screening Results for Preliminary Alternatives

Alternative	Effectiveness	Implementability	Cost
Alternative 1: No Action	Exposures to humans and wildlife at the contaminated areas would continue, and migration could result in increased exposures over time. No treatment would be implemented to reduce toxicity, mobility, or volume of contaminated material; no permanent solution would be achieved; and certain regulatory requirements would not be met.	Standard practices and equipment would be used to conduct general maintenance activities and maintain current institutional controls, such as access restriction and monitoring.	Annual costs estimated to be \$300,000. The baseline costs would probably increase with inflation.
Alternative 2: Limited Removal and Disposal, and In-Situ Containment	More protective in the long term than Alternative 1. Short-term impacts to workers would be higher than for Alternative 1 because of the potential for exposures during construction and grading activities. Exposures would be reduced in the short term, and this alternative could be implemented in a timely manner. Factors limiting the effectiveness of the cover include the activities of burrowing animals and growth of deep-rooted vegetation. Regular maintenance and monitoring would be required.	Installation of the protective cover would be relatively straightforward and could be implemented with readily available resources. The presence of UXO could affect the timeliness of implementation. For the limited excavation and (off-site) disposal component, transport and disposal of waste material generated from grading activities would be relatively straightforward. Installation of riprap berm at the shoreline would also be straightforward.	Total estimated cost is \$2 million. More expensive than Alternative 1 but less than other action alternatives (4 and 5). Comparable in cost to Alternative 3.

TABLE 5.1 (Cont.)

Alternative	Effectiveness	Implementability	Cost
Alternative 3: Removal and Short-Term Storage	More protective in the short term than Alternative 1 because it would reduce potential exposures to humans and wildlife through removal. No treatment would be implemented to reduce contaminant toxicity, mobility, or volume. Alternative 3 would not be protective in the long term and would require an additional action at a future date. Potential risks to human health and the environment would be significant in the short term because of the removal component but would be reduced in the long term. Good engineering practices and mitigative measures would be implemented to minimize impacts.	Removal and storage would be relatively straightforward and could be implemented with readily available resources and standard procedures. The presence of UXO could affect the timeliness of implementation. Installation of riprap berm at the shoreline would also be straightforward.	Total estimated cost is \$5 million but does not include costs of long-term remediation. More expensive than Alternative 1 but less than other action alternatives (4 and 5). Comparable in cost to Alternative 2.
Alternative 4: Removal, On-Site Treatment, and Limited Disposal	More protective than Alternatives 1 through 3 in the long term because contaminated soil would be removed from the source areas and treated. The statutory preference for treatment as a principal element of remediation would be met. Contaminant toxicity, mobility, and volume would be reduced. Potential risks to human health and environment would be significant in the short term because of the removal component but would be reduced in the long term. Good engineering practices and mitigative measures would be implemented to minimize impacts.	Removal and treatment would be relatively straightforward and could be implemented with readily available resources and standard procedures. The presence of UXO could affect the timeliness of implementation.	Total estimated cost is \$13 million. Alternative 4 is the highest of all the action alternatives.

TABLE 5.1 (Cont.)

Alternative	Effectiveness	Implementability	Cost
Alternative 5: Removal, Off-Site Treatment, and Disposal	<p>More protective than Alternatives 1 through 3 in the long term because contaminated soil would be removed from the source areas and treated. The statutory preference for treatment as a principal element of remediation would be met; however, it would not satisfy the statutory preference for on-site treatment. Contaminant toxicity, mobility, and volume would be reduced. Potential risks to human health and the environment would be significant in the short term because of the removal component but would be reduced in the long term. Potential short-term risks to the general public would also exist because of off-site transport of untreated hazardous material. Good engineering practices and mitigative measures would be implemented to minimize impacts.</p>	<p>Removal, treatment, and disposal would be relatively straightforward and could be implemented with readily available resources and standard procedures. The presence of UXO could affect the timeliness of implementation. Off-site treatment and disposal facilities are available.</p>	<p>Total estimated cost is \$11 million. More expensive than Alternatives 1 through 3 but less than Alternative 5.</p>

## 6 DESCRIPTION OF FINAL ALTERNATIVES

Five interim remedial action alternatives for the J-Field TBP area main pits and pushout area were retained through the screening process:

- Alternative 1: No Action;
- Alternative 2: Limited Removal and Disposal, and In-Situ Containment;
- Alternative 3: Removal and Short-Term Storage;
- Alternative 4: Removal, On-Site Treatment, and Limited Disposal; and
- Alternative 5: Removal, Off-Site Treatment, and Disposal.

The components of these alternatives are described in Sections 6.1 through 6.5. Under Alternative 2, contaminated soil would be contained in place with a protective cover. Under Alternative 3, contaminated surface soil would be removed through excavation and placed in a short-term storage facility. Under Alternatives 4 and 5, contaminated surface soil would be removed through excavation and treated (either on-site or off-site). Treated soil under Alternative 4 would be returned to the site to be used as fill (pending a treatability variance or CERCLA waiver as described in Section 3.2) or disposed of as nonhazardous waste. Metal scrap and metals recovered from the soil washing and leaching processes would be sent to an off-site smelter, and PCB-contaminated soil would be sent to an off-site treatment and disposal facility. Under Alternative 5, all contaminated soil would be sent off-site for disposal. Because contaminated soil would remain on-site under Alternatives 2 and 3, shoreline stabilization would be an additional component as a measure to control erosion of the peninsula south of the TBP area. Engineering procedures and equipment presented in the following sections are provided to compare the feasibility of the alternatives. Final design components, procedures, and equipment selection will be developed during the remedial design phase and will incorporate information developed during the course of detailed design.


### 6.1 ALTERNATIVE 1: NO ACTION

The no-action alternative is included as a final alternative to provide a baseline for comparison with the action alternatives. Under this alternative, no action would be taken at the TBP area, and contaminated surface soil would remain in place. Institutional control measures (described in Section 4.2.1), including access restriction, ownership and use or deed restrictions, and monitoring, would remain in effect at the area.

## 6.2 ALTERNATIVE 2: LIMITED REMOVAL AND DISPOSAL, AND IN-SITU CONTAINMENT

### 6.2.1 Limited Removal

Under Alternative 2, approximately 400 yd<sup>3</sup> of contaminated surface soil would be removed from the two main pits, and the 5-acre area encompassing the main pits and pushout areas would be contained in place (Figure 6.1). An estimated 350 yd<sup>3</sup> of arsenic-contaminated soil would be removed from the northern main pit. The removal would include excavation of soil containing arsenic levels that exceed the EPA Region III noncarcinogenic, industrial risk-based concentration of 610 mg/kg. Confirmation samples would be collected in unexcavated soil to determine whether arsenic has been removed to levels below this criterion.



**FIGURE 6.1** Location of In-Situ Containment Area and Shoreline Stabilization, Alternative 2

At the southern main pit, arsenic concentrations were below the risk-based concentration of 610 mg/kg. However, PCBs (Aroclor 1248) were detected at a concentration of 143 mg/kg in a sample collected at a depth of 2 ft from boring JBP1-E, which is at the western section of the pit (see Figure D.6). Soil would be excavated at this boring. Confirmatory analyses would be performed on the unexcavated soil to ensure that PCB concentrations were below the ARAR value of 50 mg/kg. It is estimated that about 17 yd<sup>3</sup> of PCB-contaminated soil would be removed from the southern main pit. The site would be prepared by personnel performing a visual UXO inspection of the excavation area, grubbing and clearing vegetation in the excavation area, constructing a temporary staging area, and improving existing access roads. A work zone would be designated with temporary fencing. Access routes would be established by relying on the U.S. Army's ordnance avoidance procedures. After excavation activities were completed, the areas would be backfilled with clean soil and prepared for the emplacement of the protective cover.

#### **6.2.1.1 UXO Screening**

The UXO screening effort for Alternative 2 would consist of visually inspecting the two main pits and conducting a UXO survey along the southern shoreline of the Gunpowder Neck Peninsula where erosion control measures would be implemented. The UXO survey for the main pits does not include the use of metal detection devices because the amount of buried metal debris is expected to be high. A UXO supervisor, however, would be on-site throughout the remediation effort. The survey of the shoreline would be conducted by a two-man UXO clearance team with handheld excavation tools, active electromagnetic induction detectors, and passive ferromagnetic detectors. The total area to be surveyed would be 24,000 ft<sup>2</sup> (8 ft wide by 3,000 ft long), to a depth of 2 ft below the surface.

As metal contacts were identified, the following activities would be carried out:

- Explosive-, chemical-, propellant-, or pyrotechnic-loaded UXO would be marked with a yellow survey marker; work would cease; and Emergency Notification Procedures would be implemented immediately; and
- Nonexplosive-loaded ordnance components, including armor-piercing projectiles, empty ejection munitions, and spent rocket motors (separated from warheads), and nonexplosive-loaded training munitions would be segregated for pickup by the U.S. Army Technical Escort personnel.

Other metal debris that is not ordnance-related would not be removed.

### 6.2.1.2 Site Preparation

Following the initial UXO survey, site preparation activities would begin, including grubbing and clearing vegetation, constructing a temporary staging area, and improving existing access roads. Vegetation, which consists mainly of grass and *Phragmites*, would be removed from the entire 5-acre area. The access road would be repaired and resurfaced. The final surfacing of the road would occur after the remediation of the main pit areas is completed and all equipment is demobilized. Construction and improvement of roads would require the placement of 525 yd<sup>3</sup> of fill and gravel obtained from an off-site location.

### 6.2.1.3 Excavation

At the northern main pit, 2 ft of soil would be removed from the entire pit (approximately 350 yd<sup>3</sup>). An additional 10 yd<sup>3</sup> from boring TBPNPBOR1 would be removed because the arsenic concentration (2,290 mg/kg) in a sample collected from a depth of 4 ft exceeds the industrial risk-based concentration. At the southern main pit, 17 yd<sup>3</sup> would be excavated from boring JBP1-E because Aroclor 1248 was detected at a concentration of 143 mg/kg.

### 6.2.1.4 Mitigation and Monitoring

During remediation activities, good engineering practices and mitigative measures would be implemented to control both contaminant releases and potential exposures to workers and the general public. All workers engaged in soil removal activities would be required to wear an appropriate level of personal protective equipment. Work zones would be clearly delineated and monitored to ensure worker safety. Equipment and personnel would be decontaminated before leaving the area. Monitoring and mitigative measures for Alternative 2 are summarized in more detail in Section 7.6. Erosion control measures to be implemented include engineering the soil cover as a berm along the pushout-marsh boundary.

## 6.2.2 Disposal

Soil from the northern main pit would be placed directly into 20-yd<sup>3</sup> rolloffs. Approximately 20 rolloffs would be required for disposal of arsenic-contaminated soil. PCB-contaminated soil would likely be containerized in 55-gal U.S. Department of Transportation–(DOT-) and TSCA-approved drums. Approximately 68 drums would be needed for containerizing the excavated soil. One trailer would be required for transportation off-site. If PCB-contaminated soil is required to be incinerated and containerized, a temporary staging area would be constructed in the work zone. Because the PCB-contaminated soil meets the definition of PCBs and PCB items

that may be stored temporarily for up to 30 days [40 CFR 761.65 (c)(I)(iii)], design specifications of PCB storage areas are not required [40 CFR 761.65(c)(I)].

Soil in the northern main pit has been characterized as Toxicity Characteristic for Lead (D008) under RCRA. The soil would require stabilization prior to land disposal. In addition, because the soil is from a National Priorities List (NPL) site, the soil must be disposed of at a facility that can accept CERCLA wastes. Soil from the northern main pit would be transported to a RCRA Subtitle C Landfill for stabilization and final disposal.

Soil in the southern main pit would be containerized in 55-gal drums and transported to a TSCA-approved incinerator. If the moisture content and PCB concentrations are low (i.e., below 500 ppm), the PCB-contaminated soil can be disposed of in a chemical waste landfill that meets the requirements of 40 CFR 761.75.

Remediation-derived wastes, such as personal protection equipment, decontamination water, debris, and scrap metal, would be characterized and disposed of accordingly (e.g., incineration, stabilization). Because remediation-derived wastes that are RCRA-hazardous would not be stored on-site for more than 90 days, the generator is not required to construct a storage facility that meets the standards of 40 CFR Parts 264 or 265, and the generator is not required to meet the permit requirements of 40 CFR Part 270. Likewise, because remediation-derived wastes that are regulated under TSCA because of PCB concentrations are not expected to be stored on-site for more than 30 days, the generator is not required to construct a PCB storage facility that meets the standards of 40 CFR 761.65(c)(I). The number of 55-gal drums for disposal of remediation-derived waste is not expected to exceed 20.

### **6.2.3 In-Situ Containment**

Once the excavation was completed, the excavated areas would be backfilled with clean soil. The backfill soil would be tested to ensure that it is "clean" prior to use. The 5-acre (218,000-ft<sup>2</sup>) area would be covered with geotextile fabric and then clean soil to an elevation of just about the 100-year floodplain (7.5 ft), compacted (by standard construction equipment), regraded, covered with topsoil, and seeded (the end result would be a natural grass habitat).

### **6.2.4 Shoreline Stabilization**

Shoreline stabilization would include removing debris from the shoreline and placing a fabric liner and riprap over an area 8 ft wide by 3,000 ft long along the southern shoreline (Figure 6.1). After the area has been surveyed for UXO, riprap would be transported by truck to the shore via the unnamed road that extends south from Robins Point Road to the South Beach

Demolition Ground. Front-end loaders (or comparable equipment) would be used to place riprap along the shoreline. The trucks would drive over the riprap to compact it into the sand as the wall is built along the shoreline.

### **6.3 ALTERNATIVE 3: REMOVAL AND SHORT-TERM STORAGE**

#### **6.3.1 Removal**

Under Alternative 3, approximately 16,000 yd<sup>3</sup> of contaminated surface soil would be removed from the two main pits and pushout area to achieve permanent source control and long-term protection of human health and the environment (Figures 3.1 and 3.2). Removal activities would be carried out with standard construction equipment and procedures. Removal activities at the TBP area would begin with a visual surface UXO survey; subsurface UXO surveys would be conducted as required. The site would be prepared by grubbing and clearing vegetation, constructing and/or improving access roads, and extending electric service to the storage facility location. A work zone would be designated with temporary fencing. Access routes would be established by relying on the U.S. Army's ordnance avoidance procedures.

##### **6.3.1.1 UXO Screening**

The work zone would be surveyed for UXO in the upper 2 to 4 ft. The total area to be surveyed would be 218,000 ft<sup>2</sup>. The survey would be conducted by two-man UXO clearance teams with handheld and mechanical excavation tools, active electromagnetic induction detectors, and passive ferromagnetic detectors.

As metal contacts were identified and removed from the excavation area, the following activities would be carried out:

- Explosive-, chemical-, propellant-, or pyrotechnic-loaded UXO would be marked with a yellow survey marker; work would cease; and Emergency Notification Procedures would be implemented immediately;
- Nonexplosive-loaded ordnance components, including armor-piercing projectiles, empty ejection munitions, and spent rocket motors (separated from warheads), and nonexplosive-loaded training munitions would be segregated for pickup by the U.S. Army Technical Escort personnel; and

- Miscellaneous metallic debris would be collected, drummed, and stored at the Prototype Building until it was shipped to an off-site smelter.

Metal contacts would be marked and removed at each depth interval. Removal of metal contacts might proceed during soil excavation to limit “double handling” of the soil.

#### **6.3.1.2 Site Preparation**

Following the initial UXO survey, site preparation activities would begin, including clearing and grubbing vegetated areas, constructing access roads and staging areas, and extending electric service to the site. Site preparation would require clearing and grubbing an estimated 5 acres (218,000 ft<sup>2</sup>) of vegetation. Construction and improvement of access roads connecting the excavation area with the storage facility would require clearing an area of about 15,000 ft<sup>2</sup> (15 ft by 1,000 ft). Construction of roads would require placing approximately 525 yd<sup>3</sup> of fill and gravel base obtained from an off-site location. Vegetation, which consists mainly of grass and *Phragmites*, would be removed from these areas, drummed, and characterized to determine appropriate handling. Electric service would be extended to J-Field; power needs for the storage facility would be 440 V at 580-600 kW.

#### **6.3.1.3 Excavation**

Excavation and transport of the soil from the TBP area would be accomplished by using standard earthmoving equipment. After excavation, soil would be placed in trucks and transported to the storage facility. A fleet of three trucks, each with a 32-yd<sup>3</sup> capacity, would be required. The soil would most likely require dewatering before being loaded onto the trucks. If needed, belt filter presses would be used to dewater soils through a combination of gravity draining and compression between two filter cloth belts. The water resulting from this process would be collected and characterized to determine the appropriate method of disposal. Once the excavation activities were completed, the excavated pit would be backfilled with clean soil. Backfilling activities might be necessary intermittently as the excavation proceeds to prevent sidewall collapse and water infiltration. Additional clean soil would be brought in from off-site to be used as backfill as necessary. The excavated area would be regraded, covered with topsoil, and seeded.

#### **6.3.1.4 Mitigation and Monitoring**

During remediation activities, good engineering practices and mitigative measures would be implemented to control both contaminant releases and potential exposures to workers and the general public. All workers engaged in soil removal activities would be required to wear an


appropriate level of personal protective equipment. Work zones would be clearly delineated and monitored to ensure worker safety. Equipment and personnel would be decontaminated before leaving the area. Monitoring and mitigative measures for Alternative 3 are summarized in more detail in Section 7.6. Dust control measures would include spraying water, covering stockpiles, and covering loads during transport. Erosion control measures would be used to mitigate impacts to both the air and surface water. For air, these measures would include wetting loose material and minimizing construction stockpiles; for surface water, these measures would include isolating work areas with berms, covering stockpiles, and possibly using temporary vegetative covers. An air monitoring program would be implemented for the period of the remediation activities. Biomonitoring would also be employed to assess the impact of excavation activities on biota in the adjacent marsh.

### **6.3.2 Storage Facility Construction**

The excavated soil would be stored in an area adjacent to the Prototype Building (Figure 6.2) in a building consisting of fabric-covered steel arch trusses. Buildings of this type are relatively inexpensive, are durable enough for extended time periods, and can be erected quickly. In addition, they can cover a large area free of interior supports, are weather tight, and can be easily dismantled. A liner and leachate collection system would probably be needed to meet the RCRA waste pile regulations. The design of this type of structure could be patterned after a design for a similar soil storage project performed by the U.S. Army Corps of Engineers in Winfield, West Virginia. The foundation of the storage building would consist of a bottom layer of 3 ft of impermeable clay, a leachate collection system, and a type K concrete pad 1 ft thick with an area of about 48,000 ft<sup>2</sup> for 16,000 yd<sup>3</sup> (25,000 ft<sup>2</sup> for 4,000 yd<sup>3</sup>). Concrete barriers (like those used for highway median dividers) would be placed around the inside perimeter to protect the walls from the trucks and bulldozers piling the soil, and an air scrubber system would be installed to filter any VOCs emitted during the storage period. An excavation of about 5 ft would be needed to accommodate the foundation required for the storage facility. The soil removed from this excavation could then be used to backfill the excavated contaminated area.

### **6.3.3 Shoreline Stabilization**

Shoreline stabilization would include removing debris from the shoreline and placing a fabric liner and riprap over an area 8 ft wide by 3,000 ft long along the southern shoreline (Figure 6.1). After the area has been surveyed for UXO, riprap would be transported by truck to the shore via the unnamed road that extends south from Robins Point Road to the South Beach Demolition Ground. Front-end loaders (or comparable equipment) would be used to place riprap along the shoreline. The trucks would drive over the riprap to compact it into the sand as the wall is built along the shoreline.



**FIGURE 6.2** Location of Fenced Work Zone and Proposed Storage Facility, Alternative 3

## 6.4 ALTERNATIVE 4: REMOVAL, ON-SITE TREATMENT, AND LIMITED DISPOSAL

### 6.4.1 Removal

Under Alternative 4, contaminated surface soil would be removed to a depth of 2 ft from the two main pits and pushout area in the same manner as described for Alternative 3 (Section 6.2.1). The area to be excavated is shown in Figures 3.1 and 3.2. Electric service would be extended to J-Field; power needs for a 15 ton/h soil washing/leaching facility would be 440 V at 580-600 kW. A temporary staging area for excavated soil would be constructed in the work zone. Contaminated soil awaiting treatment would be stockpiled on a bermed and drained concrete or asphalt pad (about

48,000 ft<sup>2</sup>) and covered with plastic laminate to control dust and vapor emissions. Treated soil would be staged at a separate location (in the clean zone) until analytical testing was performed to verify that treatment goals had been achieved. The pad would be decontaminated following remedial activities and would remain in place at the site. Once the excavation and treatment activities were completed, the excavated pit would be backfilled with clean soil. The excavated area would be regraded, covered with topsoil, and seeded.

## **6.4.2 On-Site Treatment**

### **6.4.2.1 Metals- and Semivolatile-Contaminated Soil**


Under Alternative 4, a soil washing/leaching facility would be constructed on-site to treat all contaminated soils except those contaminated with PCBs. The approximate location of the facility is shown in Figure 6.3. The facility would be constructed on a concrete pad, about 100 by 200 ft in area. This area would require clearing and grading before the concrete foundation and necessary utilities (i.e., electricity) are installed. Water used in the process would be trucked to the site.

The soil washing/leaching facility would be used to treat metals- and semivolatile-contaminated soils (approximately 16,000 yd<sup>3</sup>) by (1) physically separating metallic fragments; (2) physically separating soil into various size fractions (coarse sand and gravel, fine sand, and silt and clay); (3) chemically removing metals bound to sand, silt, and clay; and (4) precipitating metals out of the wash for recovery. PCB-contaminated soil, if found, would be excavated and sent off-site for treatment and disposal (see Section 6.4.2.2). The preliminary conceptual design of the soil washing/leaching facility (Figure 6.4) is based on a bench-scale study that used J-Field TBP area soil (ART 1995).

The treated soil product would be placed in a pile located adjacent to the treatment plant. Treated soil would be sampled and analyzed to ensure that treatment goals had been met. Soil failing analysis might be reprocessed. Soil meeting treatment goals would be either returned to the excavated area once all excavation activities were completed (pending a treatability variance or CERCLA waiver) or disposed of as nonhazardous waste.

Delivery trucks would travel on clean access roads to eliminate the need for vehicle decontamination. Vehicles would be decontaminated, as required, before leaving the work zone.


Operation of the soil washing/leaching facility would require supervision, laborers, and laboratory and maintenance personnel. The soil washing/leaching plant would operate for 8 months, assuming a throughput of 15 tons per hour and 6-day work weeks (10-hour shifts).



**FIGURE 6.3 Location of Fenced Work Zone and Proposed Treatment Facility and Staging Area, Alternative 4**

All processing equipment would be contained within the facility area (built on a concrete pad). Air emissions from the facility would be minimized through the use of emission control equipment, such as carbon absorption units. Because of these engineering controls, airborne emissions from the plant would be expected to be very low.

Support facilities would also be maintained on-site to provide potable water, portable sanitary facilities, and offices for the construction management staff. The soil washing/leaching plant would be dismantled at the end of the interim remedial action period and decontaminated for reuse. Process wash water would be sent to a sanitary wastewater treatment facility.



**FIGURE 6.4 Process Flowchart for the Soil Washing/Leaching Facility**  
(Source: Modified from ART 1995)

#### 6.4.2.2 PCB-Contaminated Soil

PCB-contaminated soil, if present, would likely be containerized in 55-gal DOT- and TSCA-approved drums. If PCB-contaminated soil were required to be incinerated and containerized, a temporary staging area would be constructed in the work zone. Because the PCB-contaminated soil meets the definition of PCBs and PCB items that may be stored temporarily for up to 30 days [40 CFR 761.65(c)(I)(iii)], design specifications of PCB storage areas are not required [40 CFR 761.65(c)(I)].

#### 6.4.3 Limited Disposal

All disposal activities would take place at an off-site facility. Under Alternative 4, PCB-contaminated soil would be sent off-site for treatment and disposal immediately following excavation and characterization.

Other disposal activities would include shipping metal scrap and recovered metals (from the treatment process) to an off-site smelter to be recycled.

## **6.5 ALTERNATIVE 5: REMOVAL, OFF-SITE TREATMENT, AND DISPOSAL**

### **6.5.1 Removal**

Under Alternative 5, contaminated surface soil would be removed from the two main pits and pushout area in the same manner as described for Alternative 3 (Section 6.2.1). The area to be excavated is shown in Figures 3.1 and 3.2. A temporary staging area for excavated soil would be constructed in the work zone.

### **6.5.2 Off-Site Treatment and Disposal**

Under Alternative 5, all excavated soil from the TBP area would be sent off-site for treatment and disposal. Following excavation, soil would be stockpiled at a temporary staging area to await loading. Hauling trucks would be decontaminated before leaving the work zone. Soils would be treated by stabilization, then disposed of in a Subtitle C landfill. PCB-contaminated soil would require stabilization or incineration, depending on the concentrations.



## 7 DETAILED EVALUATION OF ALTERNATIVES

The EPA has identified nine criteria in the NCP that must be evaluated for each alternative retained through the screening stage [Section 300.430(e)(9)(iii)]. The criteria are explained as follows.

1. *Overall protection of human health and the environment.* Addresses protection from unacceptable risks in both the short term and the long term by minimizing exposures, in accordance with the purpose and objectives of the proposed action described in Section 3. Because of its broad scope, this criterion also reflects the focus of criteria 2 through 5.
2. *Compliance with ARARs.* Addresses the attainment of federal and state environmental requirements determined to be either applicable or relevant and appropriate to the alternative on the basis of site-specific considerations. Potential ARARs are listed in Appendix B.
3. *Long-term effectiveness and permanence.* Addresses residual risks (i.e., those risks remaining after completion of a remedial action). EPA guidance states that it is usually sufficient to indicate whether an alternative has the potential to achieve the PRGs and not necessary to quantify the risk that would remain after the alternative was implemented (EPA 1991c).
4. *Reduction of contaminant toxicity, mobility, and volume.* Addresses the degree to which treatment is used to address the principal threat(s) at the TBP area; the amount of material treated; the magnitude, significance, and irreversibility of the given reduction; and the nature and quantity of treatment residuals.
5. *Short-term effectiveness.* Addresses the potential impacts of implementing the alternative to site workers, the general public, and the environment during the action period; the effectiveness and reliability of mitigative measures; and the time required to achieve protectiveness.
6. *Implementability.* Addresses technical feasibility, including the availability and reliability of required resources (such as specific technologies, materials and equipment, facility capacities, and skilled workers), the ease of implementation, and the ability to monitor effectiveness. This criterion also addresses administrative feasibility.

7. *Cost.* Addresses both capital costs and annual operation and maintenance costs. Costs for the individual components of the alternatives are also considered. Costs presented for Alternative 1, 3, 4, and 5 were estimated by using the Remedial Action Cost Engineering and Requirements System (RACER). Costs for Alternative 2 were developed by ICF Kaiser Engineers, Inc. Details concerning the structure of the cost estimates and assumptions used are discussed in Appendix F.
8. *State acceptance.* Addresses the comments made by the State of Maryland on the alternatives being considered for site remediation. Because the state's comments will not be received until after this report has been issued for public review, the state acceptance criterion will be addressed in the ROD.
9. *Community acceptance.* Addresses the comments made by the community on the alternatives being considered. Because public comments will not be received until after this report has been issued for public review, the community acceptance criterion will be addressed in the ROD.

Five alternatives (Alternatives 1, 2, 3, 4, and 5) were retained through the screening process presented in Section 5. Section 6 describes these final alternatives. Each alternative is evaluated in detail in the following subsections on the basis of criteria 1 through 7. In each subsection, the evaluation of an alternative against these seven criteria is organized to follow the order in which the criteria are listed in the NCP (EPA 1990a). A comparative analysis is presented in Section 8.

## **7.1 ALTERNATIVE 1: NO ACTION**

### **7.1.1 Overall Protection of Human Health and the Environment**

Alternative 1 would not be protective of human health and the environment over the long term. Under this alternative, the site would continue to be managed as it has been in the past. Current institutional controls, such as restricted access and monitoring, would continue to be implemented. Exposure of biota to surface soil contaminants would continue, as would the potential for exposure of site workers. Under the no-action alternative, contaminant source areas would not be removed or treated and exposures could increase over time, leading to potential adverse environmental impacts. Results of the J-Field ERA (Hlohowskyj et al. 1996) indicate that ecological resources at the TBP area are heavily impacted by past activities and current levels of contamination. The current levels of contamination also pose a risk to wildlife species at J-Field. These impacts and risks would continue under the no-action alternative.

### **7.1.2 Compliance with ARARs**

Potential regulatory requirements that might be applicable or relevant and appropriate to the interim remedial action alternatives are identified and evaluated in Appendix B. Under the no-action alternative, some ARARs would not be met. For example, although RCRA disposal site requirements and LDRs are not applicable under the no-action alternative (because no movement or placement of soil would occur and no waste was placed in J-Field after 1979) (Office of Solid Waste and Emergency Response [OSWER] Directive 9234.1-01, August 8, 1988), they may be relevant and appropriate if the problem to be addressed (i.e., migration of hazardous waste constituents into the environment) is sufficiently similar. In addition, because the remediation at J-Field is being performed under the joint authority of CERCLA and RCRA (EPA and U.S. Department of the Army 1990), under Alternative 1, TBP area soil contaminated with RCRA characteristic hazardous wastes (e.g., lead), and possibly RCRA-listed hazardous wastes, would not meet the corrective action requirement under RCRA. Also, the TSCA cleanup policy (a TBC for J-Field), which requires that PCB-contaminated soil in restricted access areas be cleaned to less than 25 ppm, would not be met.

The no-action alternative also fails to meet the CERCLA-mandated preference for remedies that reduce contaminant toxicity, mobility, or volume through treatment [CERCLA Section 121(b)(1)].

### **7.1.3 Long-Term Effectiveness and Permanence**

Alternative 1 would not be protective of human health and the environment over the long term. Under this alternative, maintenance and monitoring activities would be carried out for an indefinite period. Existing institutional controls would continue to limit access to site workers and other authorized personnel, thus reducing risk to the general public. However, exposures to the general public could occur through unauthorized entry. Exposures to biota and risks associated with these exposures would continue at current levels; adverse ecological impacts would be expected with long-term exposure to surface soil contamination. In addition, contaminant levels in the marsh adjacent to the pushout area could increase because of transport of contaminated material via surface water runoff, resulting in increased risks to biota in the marsh over time.

#### **7.1.3.1 Protection of Human Health**

Workers would be on-site periodically to carry out monitoring (e.g., toxicity testing in the marsh) and maintenance activities (e.g., mowing); the risks to workers involved in these activities are considered to be low. Because the site is restricted, potential impacts to members of the general public over the long term are also considered to be low (ICF Kaiser Engineers 1994b, 1995a).

### **7.1.3.2 Environmental Protection**

Under Alternative 1, the level of contamination and risks to biota in terrestrial and aquatic habitats in the long term would be similar to current levels; however, these levels might increase over time as a result of contaminant transport via surface water runoff.

### **7.1.4 Reduction of Toxicity, Mobility, or Volume**

Reduction of toxicity, mobility, or volume through treatment is not applicable to Alternative 1 because it does not involve treatment.

### **7.1.5 Short-Term Effectiveness**

#### **7.1.5.1 Protection of Human Health**

Under Alternative 1, existing institutional controls would continue to limit access to site workers and other authorized personnel, thus reducing risks to the general public. However, exposures to the general public could occur through unauthorized entry. Short-term risks to workers involved in monitoring and maintenance activities are considered to be low (ICF Kaiser Engineers 1994b).

#### **7.1.5.2 Environmental Protection**

Under Alternative 1, protection of the environment would be minimal. The level of contamination and risks to biota in terrestrial and aquatic habitats in the short term are considered to be significant as indicated by the results of the J-Field ERA (Hlohowskyj et al. 1996). Short-term risks to the environment as a result of monitoring and maintenance activities are considered to be low.

### **7.1.6 Implementability**

Minimum site operations would continue with use of readily available resources for monitoring and maintenance activities.

### **7.1.7 Cost**

Costs for Alternative 1 are associated with continuing the environmental monitoring program and maintenance activities (e.g., mowing). Estimated total annual costs for Alternative 1 would be about \$300,000.

## **7.2 ALTERNATIVE 2: LIMITED REMOVAL AND DISPOSAL, AND IN-SITU CONTAINMENT**

### **7.2.1 Overall Protection of Human Health and the Environment**

Alternative 2 would be protective of human health and the environment over the short term. Under this alternative, local “hot spots” of contamination (in particular, arsenic and PCBs) would be removed from the two main pits and the excavation areas would be backfilled. Following the limited removal and backfilling, surface soils in the main pits and pushout areas would be contained in place with a protective cover of soil (see Section 6.2). Exposures of biota to surface contaminants would be reduced, as would the potential for exposure of site workers and the general public.

### **7.2.2 Compliance with ARARs**

Alternative 2 would comply with pertinent ARARs and TBCs, with waivers as appropriate. Location-specific ARARs and TBCs address the protection of historic sites, archeological and cultural resources, endangered species and habitats, floodplains, and wetlands. No impacts to archeological and cultural resources are expected because the area to be remediated has been subject to disturbances on a massive scale, including open burning/open detonation of high explosives and wastes, plowing, excavation of soil from large areas, and disposal of a variety of hazardous wastes. Because the pushout area, in effect, filled in existing wetlands, removal of soil from the pushout area as part of this alternative could be viewed as a wetland mitigative measure.

No critical habitats have been identified at the TBP area. Most of the area to be addressed by Alternative 2 is located within the 100-year floodplain (FEMA 1986) and borders wetlands. To address the contamination present at the site, wetlands and a portion of the 100-year floodplain would have to be disturbed, and adjacent wetlands could be affected. Mitigative measures may be required, such as wetland replacement.

Action-specific ARARs address the protection of water, sediment, soil, watersheds, and air during implementation of the remedial action. Alternative 2 would involve limited soil movement and covering; state regulations related to sediment and erosion control would apply (Water

Management 4[1] and 4[2]). Installation of the soil protective cover may require the preparation of a sediment and erosion control plan (Water Management 25[09:1] and [09:2]).

Some of the soil excavated at the site may meet the regulatory definition of characteristic waste (e.g., toxic for lead) as determined by the TCLP test. In addition, Maryland lists the following as acute hazardous wastes: CWA, waste CWA, mixtures of any of these substances and any characteristic or listed hazardous waste, and residues from treatment of CWA listed wastes. Because the TBP area was used for the disposal of CWA and CWA treatment residues, soil excavated from the site may be considered a listed acute hazardous waste (i.e., if it contains CWAs listed by Maryland). However, no CWAs have been detected in the TBP area soils to date.

Soil excavated from the southern main pit would likely contain detectable concentrations of PCBs. Because a number of samples from the southern main pit contained soil with PCB concentrations greater than 50 mg/kg (the regulatory “trigger” requiring implementation of the TSCA PCB handling regulations), the soil generated during the excavation of the southern main pit may have to be handled according to TSCA regulations. Areas contaminated with PCBs may have to be remediated to satisfy the PCB spill cleanup policy for a contaminant-specific TBC. However, as stated in the policy, PCB contamination resulting from historical spills is to be decontaminated to levels established at the discretion of EPA regional offices. Because EPA Region III is involved in the regulatory review and public participation process for this FFS, this PCB TBC would be satisfied.

State regulations related to air releases would also be action-specific ARARs. Particulate matter and VOCs would have to be controlled during earthmoving activities in accordance with Maryland requirements (Air Quality 26[11:1], 26[11:3], and 26[11:6]).

Appropriate permits would have to be obtained from the U.S. Army Corps of Engineers before the riprap berm could be constructed along the southern shoreline of the Gunpowder Neck Peninsula.

### **7.2.3 Long-Term Effectiveness and Permanence**

Alternative 2 would be protective of human health and the environment over the long term. Under this alternative, contaminated surface soil from the main pits and pushout area would be contained in place with a “risk-reduction cover,” and maintenance activities would continue. Monitoring activities would be conducted to assess the effectiveness and potential impacts of the protective cover. In-situ containment would reduce contaminant mobility (especially via surface water runoff); therefore, potential exposures due to contaminant releases from these source areas into the marsh would be low. Although the potential for downward leaching of contaminants into the

surficial aquifer would still exist, the flux rate of leaching contaminants is estimated to be fairly slow (see Appendix A).

Shoreline stabilization would be part of this alternative as an erosion control for the southern shoreline of the Gunpowder Neck Peninsula. However, long-term effectiveness may be affected by the potential for flooding because the TBP area is located within the 100-year floodplain (FEMA 1986).

#### **7.2.3.1 Protection of Human Health**

Workers would be on-site periodically to carry out monitoring and maintenance activities. Residual risks would be reduced because contaminated soil exceeding cleanup criteria would be contained in place. Long-term exposures of workers and the general public to contaminants would be negligible because contaminated soil would be covered.

#### **7.2.3.2 Environmental Protection**

Alternative 2 would result in a significant reduction in contaminant levels and exposures to biota. The in-situ containment of contaminated soil would reduce the potential for transport of contaminants to the nearby marsh and pond via surface water runoff, thereby producing a positive benefit to surface water and wetland resources in the long term. In addition, direct exposures to terrestrial wildlife and threatened and endangered species would also be reduced.

#### **7.2.4 Reduction of Toxicity, Mobility, or Volume**

Under Alternative 2, about 400 yd<sup>3</sup> of soil would be removed from the main pits and treated, thereby reducing contaminant toxicity, mobility, and volume in these areas. The in-situ containment component would reduce contaminant mobility via leaching and surface runoff but would not reduce contaminant toxicity or volume.

#### **7.2.5 Short-Term Effectiveness**

##### **7.2.5.1 Duration of Remedial Activities**

Remedial action activities (including limited soil removal and installation of a 2-ft soil cover) under Alternative 2 would be expected to be completed in about 30 days. Monitoring

activities would take place during and after implementation of the action; maintenance activities would begin after the action was implemented.

#### **7.2.5.2 Protection of Human Health**

Short-term risks to site workers and the general public would be significant for Alternative 2, and mitigative measures would need to be employed (see Section 7.6). Excavation of contaminated soil at the TBP area, though not as extensive as that proposed under Alternatives 3 through 5, is complicated by the possible presence of buried UXO, some of which may contain chemical agents. The health and safety implications of encountering UXOs and CWAs or other chemical contaminants would be addressed in the health and safety plan for the selected alternative. Soil would be excavated using conventional equipment following U.S. Army standard operating procedures.

The release of particulate emissions during excavation would need to be minimized. Although workers could wear respiratory protection, off-site dispersion of contaminated dust could present a health risk to other APG personnel and the general public. Engineering controls would be needed to reduce the air concentrations of CWAs and toxic chemicals released during excavation. The use of enclosures to contain airborne emissions may be required.

Monitoring for chemical agents and hazardous chemicals would also be required during excavation. Continuous personal and work-site monitoring for airborne vapors and particulates is a standard industrial hygiene practice. Even if the highest levels of protective clothing and equipment were used, chemical monitoring would be necessary in the event that personal protective gear malfunctioned or was improperly operated. Personal protective clothing and equipment would also be required to prevent dermal exposure through direct contact with contaminated soil.

Alternative 2 also involves the placement of a 2-ft protective layer of soil over geotextile fabric. Because no ground disturbance would occur as part of this component, a UXO survey would not be required for the in-situ containment component. However, respiratory protection would still be needed to protect workers against particulate inhalation.

#### **7.2.5.3 Environmental Protection**

Limited excavation and in-situ containment would disturb approximately 5 acres of soil, vegetation, and wildlife habitat. Soil excavation would disturb less than 0.3 acres, in-situ containment would disturb about 5 acres, and construction and improvement of access roads would disturb an additional 0.3 acres of the TBP area. Adverse impacts associated with these activities include increases in fugitive dust emissions and ambient noise levels and loss of vegetation and wildlife

habitat at the main pits and pushout areas. The construction of a berm along the pushout-marsh boundary would reduce surface water drainage from the pushout area into the marsh. However, the pushout area accounts for only a small portion of the area draining into the marsh, and impacts from the resulting changes in surface water runoff would be localized and minor. Although the reduction of surface water input into the marsh could result in localized adverse impacts to marsh habitat, the berm would benefit the surrounding marsh ecosystem by reducing the erosion and transport of contaminated soils into the marsh. Air quality and noise impacts could disturb ecological resources near the construction areas, but these impacts would be minor and temporary. Although some loss of vegetation and wildlife habitat is expected, the amount of vegetation and habitat that would be affected is small, none of the areas that would be disturbed contained high-quality habitats or support listed biota, and most of the disturbed areas (77%) are contaminated and have been identified to pose risk to ecological receptors at the TBP area and at J-Field as a whole.

Placement of riprap along the southern shoreline of J-Field also has potential impacts to ecological resources, although the degree of impacts would depend upon the final design of the riprap structure. Marsh vegetation that is inundated during high tides often serves as refuge and foraging habitat for many fish species, especially smaller species and juveniles of larger species. Construction of a riprap barrier can curtail or prevent access to such areas. Fishery surveys conducted by the U.S. Fish and Wildlife Service off the southern end of J-Field (Robins Point) determined that nursery habitat for striped bass and marginal nursery habitat for Atlantic croaker and white perch exist in this area (Swihart et al. 1994). The impact to fish populations due to loss of access to this area of marsh habitat is unknown, although it would probably be minor. The presence of riprap could benefit some fish species by providing artificial habitat for a number of invertebrate species that could serve as food. There is also a potential benefit from reduction of erosion along the southern shoreline of J-Field because future erosion of contaminated soils in the TBP area could pose an ecological risk to aquatic organisms.

Potential impacts to air quality and noise levels during implementation of Alternative 2 would be temporary and would cease upon completion of all excavation, construction, and restoration activities. In addition, the magnitude of the potential impacts could be mitigated during all phases of Alternative 2 through the use of good engineering practices. For example, siltation fences, berms, and a runoff collection system could be used to control runoff from excavation and construction areas, mufflers could be used to limit noise levels, and water spraying could be employed to minimize fugitive dust emissions (see Section 7.6). No state or federally listed species would be expected to be disturbed during the implementation of Alternative 2.

#### **7.2.6 Implementability**

Construction and operation of the components of Alternative 2 would be straightforward. Resources are readily available for UXO screening (and safety measures), soil removal, in-situ

containment, and shoreline stabilization. Standard hand excavation tools and UXO screening methods would be used to remove contaminated soil. Soil would be sampled during excavation activities to verify that all contaminated surface soil within the excavation area was removed. The sampling procedures for soil at APG are well established. Standard earthmoving equipment would be used to install the soil cover.

Installation of the riprap berm along the southern shoreline of the Gunpowder Neck Peninsula would be relatively straightforward. Because of the shallow depths offshore, riprap would most likely have to be trucked in via Rickett's Point Road and the unnamed road that runs south toward the South Beach Demolition Ground. The berm would be built across the shoreline from west to east so that trucks could drive over the top of it.

The implementation of Alternative 2 would not adversely affect the performance of additional remedial actions that might be required at the TBP area. The ability to implement future groundwater remediation at the site (if needed) would not be affected by the excavation operations or construction of the soil cover (e.g., the soil cover would be built around the trees currently in place as part of the groundwater phytoremediation pilot study). Any additional wells (e.g., for pumping) or excavation could still be implemented, if needed.

### 7.2.7 Cost

The components that make up Alternative 2 are shown in Table 7.1. The costs provided are for limited excavation to 2 ft, with some localized excavation to 4 ft if needed (for a total of about 400 yd<sup>3</sup>). Because this alternative would involve only limited excavation, estimates for excavation are not broken down for two depths (6 in. and 2 ft) as they are for Alternatives 3 through 5. Cost components of Alternative 2 include obtaining all necessary federal, state, and local permits; repairing and resurfacing the existing access road (final course will be applied when remediation work is complete); UXO screening; clearing and grubbing; constructing a staging area; excavating pits; disposing of materials off-site; and landscaping all excavated areas. Excavations to depths greater than 2 ft may occur if localized contamination is detected at deeper levels. This alternative also would include emplacing a 2-ft protective soil cover with a dike along the pushout-marsh boundary to minimize the impacts of flooding. Shoreline stabilization would also be included. All excavated material would be disposed of in an off-site hazardous waste landfill and TSCA-approved incinerator, as required.

The estimated cost for the UXO screening effort is \$25,000, which would consist of providing UXO supervision of the remediation effort at the main pit area and surveying up to 24,000 ft<sup>2</sup> along the shoreline. The existing access road would be repaired and resurfaced in conjunction with the construction of the staging area. The final surface course would be applied when remediation is complete and all equipment is demobilized. The estimated cost for this work is \$40,000.

**TABLE 7.1 Cost Estimate for Alternative 2 (April 1996 \$)**

Activity	Cost (\$1,000)	
	Subcontract and Other Direct Costs	Contractor <sup>a</sup> Unloaded
Direct costs		
Repair/resurface existing road		40
UXO screening	25	
Clear and grub		5
Excavate/drum/stage soil (PCB)	1.4	12.6
Excavate/drum/stage soil (metals)	5.5	49.5
Off-site disposal, soil (PCB)	30	
Off-site disposal, soil (metals)	195	
Off-site disposal, remediation-derived waste	8.5	
Sampling and analysis	9	
Landscape excavated area		12
Install 2-ft earth cover	194.5	17.5
Site stakeout and control		16
Sediment control plans and specs		5
Perimeter dike with flood protection	46	17
Remedial action professional labor		17
Remedial design		45
Shoreline stabilization	73.4	45.6
Contractor general conditions <sup>b</sup>		125
30-year operation and maintenance	50	
Contractor unloaded cost <sup>a</sup>		407.2
Contractor loaded cost <sup>a</sup>	638.3	
Indirect costs		
Contractor unloaded and overhead		736
Contractor subtotal cost		1,375
Fee (8%)		110
Total contractor cost		1,485
Other		
Contingencies (10%)		148
Project management (8%)		119
Total project cost		1,752

<sup>a</sup> Loaded costs = subcontract and other direct costs; unloaded = contractor costs, less overhead.

<sup>b</sup> For this estimate, ICF Kaiser Engineers, Inc., included contractor general conditions under direct costs.

The cost of metals-contaminated soil disposal in a hazardous waste disposal facility would be about \$286/ton. The cost includes transportation in roll-offs to the facility, stabilization of the material, and all taxes and fees for proper disposal. The cost for PCB-contaminated soil in 55-gal drums at a TSCA-approved incinerator is approximately \$425 per drum, which includes transportation and incineration. The cost of remediation-derived wastes such as personal protective equipment, if it requires incineration, is approximately \$425 per drum, which includes transportation.

The sampling and analysis effort would consist of performing analysis to fully characterize the excavated soil for acceptance into disposal facilities and to confirm that the excavations removed arsenic and PCB to levels at or below the noncarcinogenic industrial risk-based concentration and ARAR, respectively. The estimated cost for sampling and analysis is \$9,000.

The final component of this alternative would be placing erosion control measures along 3,000 ft of beachfront to the south of the TBP area. This component would involve clearing debris, lining the area with geotextile fabric, and then overlaying the fabric with riprap (at a cost of about \$16 per linear foot) over an area of about 8 ft by 3,000 ft. An alternative to riprap is geotube (at a cost of about \$135 per linear foot). To minimize costs, the estimate assumes that riprap would be used. The estimated beachfront stabilization cost is \$119,000.

The final two direct-cost items for this alternative are professional labor and remedial design. Professional labor amounts to \$17,000. Remedial design costs for the 2-ft excavation, soil cover, and shoreline erosion control are estimated at \$45,000 on the basis of a low level of complexity for this alternative.

The total direct and contractor overhead costs for this alternative are estimated to be \$736,000. Loaded costs, which include subcontractor and other direct costs (ODCs), added \$638,300. An 8% fee of the sum of the loaded cost, total direct cost, and overhead cost is included in this project. The sum of the fee, loaded cost, contractor direct cost, and overhead cost is the total contractor cost, which is estimated to be \$1,485,000. A contingency factor of 10% of the total contractor cost adds \$148,000 to the cost of the project. Project management adds an additional 8% of the total contractor cost (\$119,000) to the cost of the alternative. The total project cost of this alternative, which is the sum of the total contractor cost, contingency factor, and project management, is estimated to be \$1,752,000.

### **7.3 ALTERNATIVE 3: REMOVAL AND SHORT-TERM STORAGE**

#### **7.3.1 Overall Protection of Human Health and the Environment**

Alternative 3 would be protective of human health and the environment over the short term. Under this alternative, contaminated surface soil in the main pits and pushout area would be removed and stored in a containment building located north of the TBP area for an estimated five years (see Section 6.3). Exposures of biota to surface contaminants would be reduced, as would the potential for exposure of site workers and the general public.

#### **7.3.2 Compliance with ARARs**

Compliance with location-specific ARARs under Alternative 3 would be the same as for Alternative 2.

Action-specific ARARs address the protection of water, sediment, soil, watersheds, and air during implementation of the remedial action. Alternative 3 would involve moving, grading, transporting, or otherwise disturbing soil; state regulations related to sediment and erosion control would apply (Water Management 4[1] and 4[2]). Implementing the soil excavation component of Alternative 3 would require the preparation of a sediment and erosion control plan (Water Management 25[09:1] and [09:2]).

Some of the soil excavated at the site might meet the regulatory definition of characteristic waste (e.g., toxic for lead) as determined by the TCLP test. In addition, Maryland lists the following as acute hazardous wastes: CWAs, waste CWAs, mixtures of any of these substances and any characteristic or listed hazardous waste, and residues from treatment of CWA wastes listed as acute hazardous waste. Because the TBP area was used for the disposal of CWAs and CWA treatment residues, soil excavated from the site might be considered a listed acute hazardous waste (i.e., if it contains CWAs listed by Maryland). However, no CWAs have been detected in the TBP area soils to date.

If hazardous waste is present, RCRA siting requirements for new treatment, storage, and disposal (TSD) facilities would apply for certain storage unit operations constructed to store waste under Alternative 3, that is, the temporary storage facility. The RCRA requirements and similar state requirements specify that any facility located in a 100-year floodplain should be constructed, operated, and maintained to prevent washout of any waste by a 100-year flood. These requirements might apply to locating and operating the short-term storage facility.

General TSD facility standards, including waste analysis, security, inspections, training, preparedness and prevention, and contingency planning/emergency procedures, would be applicable to such waste management activities. Alternatively, site managers could rely on 40 CFR 264.553 (Temporary Units) to satisfy RCRA ARARs for the storage of wastes. Under this regulation, the EPA regional administrator can determine that temporary tanks and container storage areas used for the treatment or storage of hazardous remediation wastes may meet an alternate design, operating, or closure standard.

Soil excavated from the southern main pit would likely contain detectable concentrations of PCBs. Because a number of samples from the southern main pit contained soil with PCB concentrations greater than 50 mg/kg (the regulatory “trigger” requiring implementation of the TSCA PCB handling regulations), the soil generated during the excavation of the southern main pit might have to be handled according to TSCA regulations. Areas contaminated with PCBs might have to be remediated to satisfy the PCB spill cleanup policy for a contaminant-specific TBC. However, as stated in the policy, PCB contamination resulting from historical spills is to be decontaminated to levels established at the discretion of EPA regional offices. Because EPA Region III is involved in the regulatory review and public participation process for this FFS, this PCB TBC would be satisfied.

State regulations related to air releases would also be action-specific ARARs. Particulate matter and VOCs would have to be controlled during earthmoving activities in accordance with Maryland requirements (Air Quality 26[11:1], 26[11:3], and 26[11:6]).

Appropriate permits would have to be obtained from the U.S. Army Corps of Engineers before the riprap berm could be constructed along the southern shoreline of the Gunpowder Neck Peninsula.

### **7.3.3 Long-Term Effectiveness and Permanence**

#### **7.3.3.1 Protection of Human Health**

Under Alternative 3, workers would be on-site periodically to carry out monitoring and maintenance activities. Residual risks would be reduced because contaminated soil exceeding cleanup criteria would be removed and contained. Long-term exposures of workers and the general public to contaminants would be negligible because contaminated soil would be removed and transported to a storage building and the excavated areas backfilled. Alternative 3 is not considered a long-term or permanent remedy; therefore, another component to this alternative would also involve (at some future date) off-site transport, treatment, and disposal of contaminated soil. Because this component would involve the off-site transport of contaminated materials, the eventual overall

risk of exposure to the general public would be comparable to that expected for Alternative 5. Site workers and off-site contractors responsible for the transport of soil would be equipped with and trained in the use of personal protective equipment. Mitigative measures are further addressed in Section 7.6.

#### **7.3.3.2 Environmental Protection**

Alternative 3 would result in a significant reduction in environmental contaminant concentrations in site soils and thus reduce direct exposure of vegetation and wildlife to surface soil contaminants as well as reduce or eliminate food chain transport of contaminants to ecological receptors in higher trophic levels. Excavation and storage of contaminated surface soils would largely eliminate the transport of soil-bound contaminants by surface runoff to the nearby marsh and pond, thereby producing a long-term benefit to surface water and wetland resources at the site. Restoration of the excavation areas would also establish better-quality wildlife habitat than is currently present at the site.

#### **7.3.4 Reduction of Toxicity, Mobility, or Volume**

Under Alternative 3, about 16,000 yd<sup>3</sup> (27,200 tons) of soil would be removed from the main pits and pushout areas and stored temporarily on-site. Storage would take place over a period of 5 years until soil was sent off-site for permanent treatment and disposal; therefore, the reduction of contaminant toxicity, mobility, and volume through treatment would be deferred.

#### **7.3.5 Short-Term Effectiveness**

##### **7.3.5.1 Duration of Remedial Activities**

Remedial action activities (including construction of storage facility and removal of soil) under Alternative 3 should be completed in about 4 months; the storage facility would operate for about 5 years. Monitoring activities would take place during and after implementation of the action.

##### **7.3.5.2 Protection of Human Health**

The short-term risks to site workers and the general public would be significant for Alternative 3, and mitigative measures would need to be employed (see Section 7.6). Excavation of contaminated soil at the TBP area is complicated by the possible presence of buried UXO, some of

which may contain chemical agents. The health and safety implications of encountering UXO and CWAs or other chemical contaminants would be addressed in the health and safety plan for the selected alternative. Soil would be excavated by using conventional equipment following U.S. Army standard operating procedures.

The release of particulate emissions during excavation would need to be minimized. Although workers could wear respiratory protection, off-site dispersion of contaminated dust could present a health risk to other APG personnel and the general public. Engineering controls would be needed to reduce the air concentrations of CWAs and toxic chemicals released during excavation. The use of enclosures to contain airborne emissions might be required.

Monitoring for chemical agents and hazardous chemicals would also be required during excavation. Continuous personal and work-site monitoring for airborne vapors and particulates is a standard industrial hygiene practice. Even if the highest levels of protective clothing and equipment were used, chemical monitoring would be necessary in the event that personal protective gear malfunctioned or was improperly operated. Personal protective clothing and equipment would also be required to prevent dermal exposure through direct contact with contaminated soil.

Alternative 3 would also involve short-term, on-site storage of excavated soil from the TBP area. Construction of a storage facility would need to incorporate a vapor-phase emission control system to reduce risks to site workers and the general public associated with the inhalation of VOCs. Site workers at the storage facility might need to be equipped with and trained in the use of personal protective equipment, which would reduce the potential for exposure during the storage period. Mitigative measures are further addressed in Section 7.6.

### **7.3.5.3 Environmental Protection**

Excavation of contaminated soil and construction of the interim storage facility would disturb approximately 6.5 acres of soil, vegetation, and wildlife habitat. Soil excavation would disturb about 5 acres, construction of the storage facility would disturb up to 1.1 acres, and construction and improvement of access roads would disturb an additional 0.3 acres of the TBP area. Adverse impacts associated with these activities include increases in fugitive dust emissions and ambient noise levels; potential increased surface soil runoff to the marsh and pond; and loss of vegetation and wildlife habitat at the main pits, pushout area, and interim storage facility areas. Air quality and noise impacts could disturb ecological resources near the construction areas, but these impacts would be minor and temporary. Although some loss of vegetation and wildlife habitat would be expected, the amount of vegetation and habitat that would be affected is small, none of the areas that would be disturbed contain high-quality habitats or support listed biota, and most of the disturbed areas (77%) are contaminated and have been identified to pose a risk to ecological receptors at the TBP

area and at J-Field as a whole. When all excavation activities were completed, the excavated areas would be backfilled with clean fill and revegetated to restore wildlife habitat.

Placement of riprap along the southern shoreline of J-Field also has potential impacts to ecological resources, although the degree of impacts would depend upon the final design of the riprap structure. Marsh vegetation that is inundated during high tides often serves as refuge and foraging habitat for many fish species, especially smaller species and juveniles of larger species. Construction of a riprap barrier can curtail or prevent access to such areas. Fishery surveys conducted by the U.S. Fish and Wildlife Service off the southern end of J-Field (Robins Point) determined that nursery habitat for striped bass and marginal nursery habitat for Atlantic croaker and white perch exist in this area (Swihart et al. 1994). The impact to fish populations due to loss of access to this area of marsh habitat is unknown, although it would probably be minor. The presence of riprap could benefit some fish species by providing artificial habitat for a number of invertebrate species that could serve as food. There is also a potential benefit from reduction of erosion along the southern shoreline of J-Field because future erosion of contaminated soils in the TBP area could pose an ecological risk to aquatic organisms.

Potential impacts to surface water, air quality, and noise levels during implementation of Alternative 3 would be temporary and would cease upon completion of all excavation, construction, and restoration activities. In addition, the magnitude of the potential impacts could be mitigated during all phases of Alternative 3 through the use of good engineering practices. For example, siltation fences, berms, and a runoff collection system could control runoff from excavation and construction areas; mufflers could limit noise levels; and water spraying could minimize fugitive dust emissions (see Section 7.6). No state or federally listed species would be expected to be disturbed during the implementation of Alternative 3.

### **7.3.6 Implementability**

Construction and operation of most components of Alternative 3 would be straightforward. Resources are readily available for UXO screening (and safety measures), soil removal, and off-site treatment and disposal. Standard excavation and construction equipment would be used to remove contaminated soil. Soil would be sampled during excavation activities to verify that all contaminated surface soil within the excavation area was removed. The sampling procedures for soil at APG are well established.

A recent HFA survey of 10- by 10-ft areas in the pushout area showed a range of 1 to 28 contacts per 100-ft<sup>2</sup> area. Twenty-five contacts were found in a burning pit (an area of 100 by 6 ft). It is estimated that about 100 contacts per day would be identified and excavated per two-man team, provided none of the contacts were UXO. If UXO were encountered, work would cease until the UXO was located and destroyed. Downtime for this operation would be from one to four hours.

Once all contacts were excavated or destroyed, conventional earthmoving equipment could be used to excavate the cleared area to a depth of 2 ft.

The storage facility would be relatively straightforward to construct and operate. All necessary equipment is readily available; temporary structures are available through a number of companies and can be purchased as kits, which can be customized to fit project specifications. The facility would require a supervisor and a small inspection/maintenance crew.

Installation of the riprap berm along the southern shoreline of the Gunpowder Neck Peninsula would be relatively straightforward. Because of the shallow depths offshore, riprap would most likely have to be trucked in via Rickett's Point Road and the unnamed road that runs south toward the South Beach Demolition Ground. The berm would be built across the shoreline from west to east such that trucks could drive over the top of it.

Implementation of Alternative 3 would not adversely affect the performance of additional remedial actions that might be required at the TBP area. The ability to implement future groundwater remediation at the site (if needed) would not be affected by the excavation and backfilling operations; however, in the case of phytoremediation, some coordination would be needed in the timing of excavation and planting of vegetation.

### 7.3.7 Cost

The components that make up the treatment train for Alternative 3 are shown in Table 7.2. Costs are given for both the 6-in. and 2-ft excavations. Before the interim remedial action could be performed, several site improvements must be made. The first site improvement is improvement/construction of an access road, which was deemed necessary to handle the heavy equipment that would be required to excavate and haul the soil to the temporary storage building. Construction/improvement of a one-lane gravel road was estimated to cost \$26,000. The second site improvement is extension of electric service to the storage site to provide power to the storage building for the lighting, ventilation system, and air scrubber system. The cost of this site improvement was estimated at \$82,000.

Before the site is excavated, it must be screened for UXO and then cleared of vegetation (clear and grub). Because excavation would not be greater than 2 ft, only one UXO screening is required for either excavation depth. The area screened is about 5 acres (218,000 ft<sup>2</sup>). Because of the potential for CWA, it is assumed that the UXO screening teams would use a MINICAMS to detect the presence of CWA. The total cost of UXO screening is \$156,000, for both the 6-in. and the 2-ft excavations. The cost to clear and grub the site was estimated at \$20,000.

**TABLE 7.2 Cost Estimate for Alternative 3 (April 1996 \$)<sup>a</sup>**

Activity	Cost (\$1,000)	
	6-in. Excavation	2-ft Excavation
Direct costs		
Construct/improve access road	26	26
Extend electric service	82	82
UXO screening	156	156
Clear and grub	20	20
Excavate pushout and pits	81	197
Construct storage building	1,024	1,966
Transport to storage building	7	23
Landscape excavated area	4	4
Remedial action professional labor	15	16
Remedial design	47	87
Beach erosion control	119	119
5-year operation and maintenance (O&M) <sup>b</sup>	66	145
Total direct costs	1,647	2,841
Indirect costs		
Contractor general conditions	501	797
Contractor overhead and profit	410	639
Total contract indirect costs	911	1,436
Total contract cost (direct and indirect)	2,558	4,277
Other		
Contingencies (10%)	256	428
Project management (8%)	205	342
Total project cost	3,019	5,047
Unit cost (\$/yd <sup>3</sup> )	749	313

<sup>a</sup> Costs for the 6-in. excavation are included for comparative purposes only.

<sup>b</sup> Annual O&M cost would be about \$13,000 for the 6-in. excavation and \$29,000 for the 2-ft excavation.

Construction of the storage building would begin before excavation of the contaminated area so that the building would be ready once the excavation took place. To accommodate the different layers used in the special foundation, which include the impermeable clay layer, the leachate collection system, and the concrete pad, the area where the building will be constructed would need to be excavated to a depth of about 5 ft. However, the soil excavated could be stockpiled and used as backfill in the contaminated area. In addition to the foundation excavation and the special foundation, other cost components associated with the storage building are the building fabric, support trusses, and building erection; protective concrete barriers around the inside perimeter; inside ventilation system; air scrubber system; and site work needed for proper drainage around the buildings. The total estimated cost for these activities is about \$1,024,000 for the 6-in. excavation and \$1,966,000 for the 2-ft excavation. These costs were estimated from cost data obtained from the Army Corps of Engineers for a similar soil storage building that was constructed in Winfield, West Virginia. The storage building accounts for 67% of the total direct cost for the 6-in. excavation and 72% of that for the 2-ft excavation.

Also, while the soil is stored, annual costs would be associated with operation and maintenance (O&M) of the scrubber system. These costs were estimated to be about \$13,000/yr for the 6-in. excavation and \$29,000/yr for the 2-ft excavation. The O&M cost shown in Table 7.2 assumes that the soil is stored for 5 years. Consequently, the estimated 5-year O&M cost is \$66,000 for the 6-in. excavation and \$145,000 for the 2-ft excavation.

Excavation is the next component of the treatment train. This cost estimate is for conventional, and not remote, excavation. Because part of the excavation area is adjacent to the marsh, precautions must be taken to prevent infiltration of marsh water into the excavated area. Sheet piling would be used as a mitigative measure. In addition, the area near the marsh would be excavated and backfilled before the rest of the area was excavated. It is also assumed that all areas would be backfilled with clean soil so that potentially contaminated soil would not be exposed. The estimated cost to excavate the area to a depth of 6 in. is \$81,000, while the cost to excavate to a depth of 2 ft is \$197,000. Excavated soil would also need to be transported to the storage building by truck and piled with earthmoving equipment, such as dozers. The cost to transport and pile soil from the 6-in. and 2-ft excavations would be \$7,000 and \$23,000, respectively. After the excavation was complete, the site would be landscaped by grading and seeding, for a cost of \$4,000.

The final component of this alternative is the placement of erosion control measures along 3,000 ft of beachfront to the south of the TBP area. This component would involve clearing debris, lining the area with geotextile fabric, and then overlaying the fabric with riprap (at a cost of about \$16 per linear foot) over an area of about 8 ft by 5,300 ft. An alternative to riprap is geotube (at a cost of about \$135 per linear foot). To minimize costs, the estimate assumes that riprap would be used. The estimated beachfront stabilization cost is \$119,000.

The final two direct-cost items for this alternative are professional labor and remedial design. Professional labor accounts for the professional labor tasks required in all components of the treatment train. This cost was estimated to be \$15,000 and \$16,000 for the 6-in. and 2-ft excavations, respectively. The estimated cost of the remedial design for the 6-in. excavation is \$47,000, and the cost for the 2-ft excavation is \$87,000, assuming a moderate level of complexity for this alternative.

The total direct cost of this alternative is estimated to be \$1,647,000 for the 6-in. excavation and \$2,841,000 for the 2-ft excavation. Indirect costs, such as contractor general conditions and contractor overhead and profit, added \$501,000 and \$410,000, respectively, to the total cost for the 6-in. excavation and \$797,000 and \$639,000, respectively, for the 2-ft excavation. A contingency factor of 10% was assumed for this remedial action to account for unforeseen conditions at the site or changes in the project scope based on more detailed site information. This added \$256,000 to the 6-in. excavation and \$428,000 to the 2-ft excavation. The contingency factor used here is less than in previous draft reports because the site is now better characterized. Because more data have been obtained and analyzed, fewer unknowns and changes are expected. Finally, it is assumed that project management adds an additional 8% or \$205,000 for the 6-in. excavation and \$342,000 for the 2-ft excavation. Consequently, the total estimated cost of this alternative is \$3,019,000 for the 6-in. excavation and \$5,047,000 for the 2-ft excavation. This translates into a unit cost of \$749/yd<sup>3</sup> for the 6-in. excavation and \$313/yd<sup>3</sup> for the 2-ft excavation.

#### **7.4 ALTERNATIVE 4: REMOVAL, ON-SITE TREATMENT, AND LIMITED DISPOSAL**

##### **7.4.1 Overall Protection of Human Health and the Environment**

Alternative 4 would be protective of human health and the environment over the long term. Under this alternative, contaminated surface soil in the main pits and pushout area would be removed and treated. Exposures of biota to surface contaminants would be reduced, as would the potential for exposure of site workers and the general public.

##### **7.4.2 Compliance with ARARs**

Compliance with location-specific and contaminant-specific ARARs under Alternative 4 would be the same as for Alternatives 2 and 3. General TSD facility standards, including waste analysis, security, inspections, training, preparedness and prevention, and contingency planning/emergency procedures, would be applicable to such waste management activities. Alternatively, site managers could rely on 40 CFR 264.553 (Temporary Units) to satisfy RCRA ARARs for the treatment of wastes. Under this regulation, the EPA regional administrator can determine that

temporary tanks and container storage areas used for the treatment or storage of hazardous remediation wastes may meet an alternate design, operating, or closure standard. In addition, should soil be excavated, treated, and replaced, the RCRA LDR would apply.

Action-specific ARARs address the protection of water, sediment, soil, watersheds, and air during implementation of the remedial action. Alternative 4 would involve moving, grading, transporting, or otherwise disturbing soil; state regulations related to sediment and erosion control would apply (Water Management 4[1] and 4[2]). Implementing the soil excavation component of Alternative 4 would require the preparation of a sediment and erosion control plan (Water Management 25[09:1] and [09:2]).

State regulations related to air releases would also be action-specific ARARs. Particulate matter and VOCs would have to be controlled during earthmoving activities in accordance with Maryland requirements (Air Quality 26[11:1], 26[11:3], and 26[11:6]). Emissions resulting from remedial actions, such as soil washing/leaching, would also have to be controlled in accordance with Maryland requirements (Air Quality 26[11:15]).

### **7.4.3 Long-Term Effectiveness and Permanence**

Alternative 4 would be protective of human health and the environment over the long term. Under this alternative, contaminated soil from the main pits and pushout area would be removed and treated, and maintenance activities would continue. Monitoring activities would be conducted to assess the effectiveness and potential impacts of the remedial action. Excavation and treatment by soil washing/leaching would greatly reduce contaminant mobility and volume; therefore, potential for exposures due to contaminant releases from these source areas would be low.

#### **7.4.3.1 Protection of Human Health**

Workers would be on-site periodically to carry out monitoring and maintenance activities (e.g., mowing). Residual risks would be reduced because contaminated soil exceeding cleanup criteria would be removed and treated. Long-term exposures of workers and the general public to contaminants would be negligible because contaminated soil would be removed from the site and the excavated areas backfilled.

#### **7.4.3.2 Environmental Protection**

Alternative 4 would result in a significant reduction in contaminant levels and exposures to biota. The removal and treatment of contaminated soil would reduce the potential for transport

of contaminants to the nearby marsh and pond via surface water runoff, thereby producing a positive benefit to surface water and wetland resources in the long term. In addition, direct exposures to terrestrial wildlife and threatened and endangered species would also be reduced. Restoration of the excavation areas would create wildlife habitat of better quality than is currently present at these locations.

#### **7.4.4 Reduction of Toxicity, Mobility, or Volume**

The treatment technology implemented as part of Alternative 4 would be soil washing/leaching. The physical and chemical treatment of TBP area soils with soil washing/leaching technologies would significantly reduce contaminant mobility and volume.

It is estimated that about 16,000 yd<sup>3</sup> (27,200 tons) of soil would be treated on-site by soil washing/leaching. The soil washing process would separate and treat the oversize and sand fractions from the soil, while concentrating the contaminants in the fines. Treating TBP area soils by soil washing/leaching could reduce the original contaminated soil volume by 94%; the remaining 6% would be sent off-site for disposal. Cleaned soil would be returned to the site, and recovered metals would be recycled. A treatability study would be needed to confirm the effectiveness of the process in achieving PRGs. Toxicity of lead would not be reduced; however, the metal would be removed and recycled.

#### **7.4.5 Short-Term Effectiveness**

##### **7.4.5.1 Duration of Remedial Activities**

Remedial action activities (including construction of the treatment facility and soil removal, treatment, and disposal) under Alternative 4 should be completed in about 8 months; monitoring activities would take place during and after implementation of the action.

##### **7.4.5.2 Protection of Human Health**

The short-term risks to site workers and the general public would be significant for Alternative 4, and mitigative measures would need to be employed (see Section 7.5). Excavation of contaminated soil at the TBP area is complicated by the possible presence of buried UXO, some of which may contain chemical agents. The health and safety implications of encountering UXO and CWAs or other chemical contaminants would be addressed in the health and safety plan for the

selected alternative. Soil would be excavated with conventional equipment following U.S. Army standard operating procedures.

The release of particulate emissions during excavation would need to be minimized. Although workers could wear respiratory protection, off-site dispersion of contaminated dust could present a health risk to other APG personnel and the general public. Engineering controls would be needed to reduce the air concentrations of CWAs and toxic chemicals released during excavation. The use of enclosures to contain airborne emissions might be required.

Monitoring for chemical agents and hazardous chemicals would also be required during excavation. Continuous personal and work-site monitoring for airborne vapors and particulates is a standard industrial hygiene practice. Even if the highest levels of protective clothing and equipment were used, chemical monitoring would be necessary in the event that personal protective gear malfunctioned or was improperly operated. Personal protective clothing and equipment would also be required to prevent dermal exposure through direct contact with contaminated soil.

Another component of Alternative 4 would involve the on-site treatment of excavated soil via soil washing/leaching. The soil washing/leaching facility might need to incorporate a vapor-phase emission control system to reduce risks to site workers and the general public associated with the inhalation of VOCs. Site workers operating the treatment facility would be equipped with and trained in the use of personal protective equipment, which would reduce the potential for exposure during the pretreatment and washing activities. Mitigative measures are further addressed in Section 7.6.

#### **7.4.5.3 Environmental Protection**

Soil, vegetation, and wildlife habitat disturbance would occur as a result of the soil excavation activities, which would cover an area of about 5 acres. An estimated 1.5 acres of land would be disturbed to provide areas for staging soil and operating the soil washing/leaching facility. Adverse impacts associated with these activities include increases in fugitive dust emissions and ambient noise levels; potential increased soil transport via surface runoff to the marsh and pond; and loss of vegetation and wildlife habitat at the main pits, pushout area, and soil staging areas. Air quality and noise impacts could disturb ecological resources near construction areas, but these impacts would be minor and temporary. Although some permanent loss of vegetation and wildlife habitats would be expected, the amount of vegetation and habitat eliminated would be small; moreover, because of the existing contaminant levels and past activities, none of the areas to be excavated represent high-quality habitat or support listed biota. These potential risks are considered acceptable when weighed against the current adverse risk associated with contaminated surface soil (Sections 2.7.3 and 3.3). Upon completion of all treatment activities, the soil washing/leaching facility would be removed and the disturbed land would be backfilled and revegetated to restore

wildlife habitat of better quality than is currently present. Potential impacts to surface water, air quality, and noise levels during implementation of Alternative 4 could be mitigated through the use of good engineering practices. For example, siltation fences could control runoff from the excavation and construction sites, berms and a runoff collection system could control runoff from the staging areas, mufflers could limit noise levels, and water spraying could minimize dust emissions (Section 7.6). No state or federally listed species would be expected to be disturbed during the implementation of Alternative 4.

#### **7.4.6 Implementability**

Construction and operation of most components of Alternative 4 would be straightforward. Resources are readily available for UXO screening (and safety measures), soil removal, and on-site treatment by soil washing/leaching. Standard excavation and construction equipment would be used to remove contaminated soil. Soil would be sampled during excavation activities to verify that all contaminated surface soil within the excavation area was removed. The sampling procedures for soil at APG are well established.

The soil washing/leaching facility would be relatively straightforward to construct and operate. All necessary equipment is readily available because the process has been used frequently in the mining industry and hazardous waste treatment applications. The treatment system would consist of a relatively standard configuration of industrial equipment. The facility would require a supervisor and general laborers with industrial work experience, as well as maintenance personnel and laboratory and administrative employees. Further bench-scale testing is required to define and optimize the design of the system.

The soil washing/leaching process would require delivery of contaminated soil by truck to the facility each day. Most likely, contaminated soil would be stockpiled at a temporary staging area until being transported to the facility for treatment. Clean soil would be stockpiled in a clean zone south of the treatment facility until all excavation activities had been completed; once excavation was complete, the cleaned soil would be used to fill the excavated area. Alternative 4 would use established technologies. The technology for soil washing/leaching has been used at several hazardous waste sites (currently, it is being demonstrated at TCAAP, New Brighton, Minnesota) and probably would not require further development before implementation at the TBP area. From 1986 to 1989, soil washing was one of the selected source control remedies at eight Superfund sites (EPA 1994). Several vendors would be available to submit competitive bids.

Disposal of the waste generated from the soil washing/treatment process is considered to be minimal. Contaminated fines and process residuals generated from soil washing would be further treated through soil leaching. The leachate solution would be cleaned and recycled continuously throughout the process. At the end of treatment, process fluids would be cleaned and put through the

sanitary wastewater system. Metal scrap and recovered metals would be shipped to an off-site smelter.

Implementation of Alternative 4 would not adversely affect the performance of additional remedial actions that might be required at the TBP area. The ability to implement future groundwater remediation at the site (if needed) would not be affected by the excavation and backfilling operations; however, in the case of phytoremediation, some coordination would be needed in the timing of excavation and planting of vegetation.

#### 7.4.7 Cost

The components that make up the treatment train for Alternative 4 are shown in Table 7.3. As for the previous alternative, costs are given for both the 6-in. and 2-ft excavations. Many of the components that make up the soil remediation treatment train for Alternative 4 are identical to those in Alternative 3: UXO and CWA screening, constructing an access road, extending electric service (to provide electric power to the soil washing/leaching facility), clearing and grubbing, excavating all areas, transporting soil to a treatment/storage area, and landscaping all excavated areas. The new components in the treatment train of this alternative are construction of a soil washing/leaching facility and staging area instead of temporary storage.

As soil was excavated, it would be transported by truck to a staging area. A staging area would be necessary because the soil would be excavated faster than it could be washed. With a soil washing facility throughput of 15 tons/h and a 10-hour daily shift working six days a week, 8 weeks would be required to wash the soil from the 6-in. excavation and 31 weeks for the 2-ft excavation. It is assumed that the soil would be stored in a bermed and drained concrete pad and covered with plastic laminate. A pad of about 25,000 ft<sup>2</sup> would be needed to store soil from the 6-in. excavation and a pad of about 48,000 ft<sup>2</sup> for the 2-ft excavation. The pads would cost \$126,000 and \$268,000, respectively. It is assumed that excavated soil would be loaded directly onto a truck and hauled to the staging area. A fleet of about three trucks with a capacity of 32 yd<sup>3</sup> each would be needed to continuously haul the excavated soil to the staging area. The estimated cost to haul the soil is about \$7,000 for the 6-in. excavation and \$23,000 for the 2-ft excavation.

The cost of the soil washing/leaching component was based on a treatability study on the TBP area soil performed by ART (1995). The cost includes both treatment of residual water from the process and disposal of the 6% solid waste fraction resulting from the process. This waste would be disposed of in an off-site hazardous waste landfill and would cost about \$312/ton (Whorton 1996). This cost includes loading onto trucks, transporting to the landfill, stabilizing the waste, and all taxes and fees for landfill disposal. Consequently, the total estimated direct cost of the soil washing/leaching component is \$2,361,000 for the 6-in. excavation and \$6,723,000 for the 2-ft excavation. This accounts for about 79% of the direct cost for the 6-in. excavation and 86% for the 2-ft excavation.

TABLE 7.3 Cost Estimate for Alternative 4 (April 1996 \$)<sup>a</sup>

Activity	Cost (\$1,000)	
	6-in. Excavation	2-ft Excavation
Direct costs		
Construct/improve access road	26	26
Extend electric service	82	82
UXO screening	156	156
Clear and grub	20	20
Excavate pushout and pits	81	197
Construct and operate soil wash/leach facility	2,361	6,723
Construct staging area	126	268
Transport to staging area	7	23
Sampling and analysis	6	11
Landscape excavated area	4	4
Remedial action professional labor	23	23
Remedial design	101	275
Total direct costs	2,994	7,810
Indirect costs		
Contractor general conditions	752	1,562
Contractor overhead and profit	728	1,717
Total contract indirect costs	1,480	3,279
Total contract cost (direct and indirect)	4,473	11,089
Other		
Contingencies (10%)	447	1,109
Project management (8%)	358	887
Total project cost	5,279	13,085
Unit cost (\$/yd <sup>3</sup> )	1,309	811

<sup>a</sup> Costs for the 6-in. excavation are included for comparative purposes only.

Before the solid waste fraction from the soil washing process was shipped to the off-site hazardous waste landfill, sampling and analysis would be required. Random samples of waste would be taken and TCLP analyses performed to characterize the waste, as required by the landfill operator. Sampling and analysis costs \$6,000 for the 6-in. excavation and \$11,000 for the 2-ft excavation.

The final two direct-cost items for this alternative are professional labor and remedial design. Professional labor amounts to \$23,000 for both excavations. Remedial design costs \$101,000 for the 6-in. excavation and \$275,000 for the 2-ft excavation, assuming a moderate level of complexity for this alternative.

The total direct cost of this alternative is estimated to be \$2,994,000 for the 6-in. excavation and \$7,810,000 for the 2-ft excavation. Indirect costs, such as contractor general conditions and contractor overhead and profit, add \$752,000 and \$728,000, respectively, to the total cost for the 6-in. excavation and \$1,562,000 and \$1,717,000, respectively, for the 2-ft excavation. A contingency factor of 10% adds \$447,000 to the cost of the 6-in. excavation and \$1,109,000 to the 2-ft excavation. Finally, it is assumed that project management adds an additional 8%, or \$358,000 for the 6-in. excavation and \$887,000 for the 2-ft excavation. Consequently, the total estimated cost of this alternative is \$5,279,000 for the 6-in. excavation and \$13,085,000 for the 2-ft excavation. This translates into a unit cost of \$1,309/yd<sup>3</sup> for the 6-in. excavation and \$811/yd<sup>3</sup> for the 2-ft excavation.

## **7.5 ALTERNATIVE 5: REMOVAL, OFF-SITE TREATMENT, AND DISPOSAL**

### **7.5.1 Overall Protection of Human Health and the Environment**

Alternative 5 would be protective of human health and the environment over the long term. Under this alternative, contaminated surface soil in the main pits and pushout area would be removed and treated. Exposures of biota to surface contaminants would be reduced, as would the potential for exposure of site workers and the general public.

### **7.5.2 Compliance with ARARs**

Compliance with location-specific and contaminant-specific ARARs under Alternative 5 would be the same as for Alternatives 2, 3, and 4. Alternative 5 would comply with the same action-specific ARARs and TBCs as Alternative 4, except for on-site disposal requirements. The key ARARs related to the off-site disposal component of this alternative would be the RCRA hazardous waste generator and record-keeping regulations and the TSCA PCB generator and record-keeping regulations. In general, the site operator would be required to ensure proper characterization of excavated soil (as soil containing listed hazardous waste, characteristic hazardous waste, and/or

PCBs), proper completion of hazardous waste and PCB manifests, receipt of “come-back” copies of manifests from destination disposal sites, and proper retention of waste characterization and manifest records for at least five years. In addition, under the CERCLA procedures for planning and implementing off-site response action (40 CFR 300.440), any facility chosen to receive CERCLA wastes for treatment, storage, or ultimate disposal must be deemed in compliance with applicable RCRA regulations and have no unpermitted releases of hazardous waste, constituents, or substances into the groundwater, surface water, soil, or air.

### **7.5.3 Long-Term Effectiveness and Permanence**

Alternative 5 would be protective of human health and the environment over the long term. Under this alternative, (1) contaminated soil from the main pits and pushout area would be removed and treated and (2) maintenance activities would continue. Monitoring activities might be conducted to assess the effectiveness and potential impacts of the remedial action. Excavation and off-site treatment by chemical stabilization/solidification would greatly reduce contaminant mobility; therefore, risk of potential exposures due to contaminant releases from these source areas would be low. Restoration of the excavated areas would also create wildlife habitat of better quality than is currently present in these areas.

#### **7.5.3.1 Protection of Human Health**

Workers would be on-site periodically to carry out monitoring and maintenance activities (e.g., mowing). Residual risks would be reduced because contaminated soil exceeding cleanup criteria would be removed and treated. Exposures of workers and the general public to contaminants would be negligible because contaminated soil would be removed from the site and the excavated areas backfilled.

#### **7.5.3.2 Environmental Protection**

Alternative 5 would significantly reduce contaminant levels and exposures to biota. The removal and treatment of contaminated soil would reduce the potential for transport of contaminants to the nearby marsh and pond via surface water runoff, thereby benefiting surface water and wetland resources in the long term. In addition, direct exposures to terrestrial wildlife and threatened or endangered species would be greatly reduced, and restoration activities would create higher-quality habitat at the site.

#### **7.5.4 Reduction of Toxicity, Mobility, or Volume**

The treatment technology implemented as part of Alternative 5 would be chemical stabilization/solidification, and any soils regulated under TSCA (i.e., PCB concentrations that exceed 50 ppm) would require incineration prior to stabilization. The chemical treatment of TBP area soils with stabilization technology would significantly reduce contaminant mobility. Incineration, if needed, would significantly reduce the toxicity of PCB contamination.

It is estimated that about 16,000 yd<sup>3</sup> (27,200 tons) of soil would be excavated and shipped off-site for treatment by chemical stabilization/solidification. The chemical stabilization/solidification process could increase the original soil volume and weight by as much as 30% and 60%, respectively, with the addition of cement and fly ash. This would result in a total treated volume of about 20,800 yd<sup>3</sup> and a total weight of about 35,360 tons, which would be placed in a landfill. Contaminant toxicity would not be reduced.

Limited information is available to quantify the durability of chemically stabilized/solidified waste upon exposure to the environment, that is, if the disposal facility failed and no corrective actions were taken. The durability of the product after failure would depend on the degree of failure and the quantity and quality of infiltrating water. Contaminants could leach from the cement slowly over time, and the leach rate would increase with an increase in dissolution or fracturing of the treated waste. Because the chemically treated product could eventually be leached and degraded if the waste were continuously exposed to the environment over a long period, the chemical stabilization/solidification process could be considered not entirely irreversible. However, appropriate design and good engineering practices (e.g., monitoring and maintenance activities) over the long term would reduce the likelihood of waste exposure and degradation.

#### **7.5.5 Short-Term Effectiveness**

##### **7.5.5.1 Duration of Remedial Activities**

Remedial action activities (including removal of soil, treatment, and disposal) under Alternative 5 should be completed in about 4 months; monitoring activities would take place during and after implementation of the action.

##### **7.5.5.2 Protection of Human Health**

The short-term risks to site workers and the general public would be significant for Alternative 5, and mitigative measures would need to be employed (Section 7.6). Excavation of

contaminated soil at the TBP area is complicated by the possible presence of buried UXO, some of which may contain chemical agents. The health and safety implications of possibly encountering UXO and CWAs or other chemical contaminants would be addressed in the health and safety plan for the selected alternative. Soil would be excavated with conventional equipment following U.S. Army standard operating procedures.

The release of particulate emissions during excavation would need to be minimized. Although workers could wear respiratory protection, off-site dispersion of contaminated dust could present a health risk to other APG personnel and the general public. Engineering controls would be needed to reduce the air concentrations of CWAs and toxic chemicals released during excavation. The use of enclosures to contain airborne emissions might be required.

Monitoring for chemical agents and hazardous chemicals would also be required during excavation. Continuous personal and work-site monitoring for airborne vapors and particulates is a standard industrial hygiene practice. Even if the highest levels of protective clothing and equipment were used, chemical monitoring would be necessary in the event that personal protective gear malfunctioned or was improperly operated. Personal protective clothing and equipment would also be required to prevent dermal exposure through direct contact with contaminated soil.

Another component of Alternative 5 would involve the off-site transport, treatment, and disposal of contaminated soil. Because this component would involve the off-site transport of contaminated materials, the overall risk of exposure to the general public is higher than for Alternative 4. Site workers and off-site contractors responsible for transporting soil would be equipped with and trained in the use of personal protective equipment. Mitigative measures are further addressed in Section 7.6.

#### **7.5.5.3 Environmental Protection**

Soil, vegetation, and wildlife habitat disturbance would occur as a result of the soil excavation activities that would cover an area of about 5 acres. An estimated 0.5 acre of land would be disturbed to provide staging areas for soil awaiting transport to an off-site facility. Adverse impacts associated with these activities would include increases in fugitive dust emissions and ambient noise levels; potential increased sediment transport to the marsh and pond; and loss of vegetation and wildlife habitat at the main pits, pushout area, and soil staging areas. Air quality and noise impacts could disturb ecological resources near construction areas, but these impacts would be minor and temporary. Although some permanent loss of vegetation and wildlife habitat would be expected, the amount of vegetation and habitat eliminated would be small; moreover, none of the areas to be excavated represent a quality habitat, contain important or critical plant species, or support listed biota. These potential risks are considered acceptable when weighed against the current adverse risk associated with contaminated surface soil (Sections 2.7.3 and 3.3). When all

excavation activities were complete, the disturbed land would be backfilled and revegetated to create wildlife habitat of better quality than is currently present at the site.

Potential impacts to surface water, air quality, and noise levels during implementation of Alternative 5 could be mitigated through the use of good engineering practices. For example, siltation fences could control sediment runoff from the excavation and construction sites, berms and a runoff collection system could control runoff from the staging areas, mufflers could limit noise levels, and water spraying could minimize dust emissions (Section 7.6). No state or federally listed species would be expected to be disturbed during the implementation of Alternative 5.

### **7.5.6 Implementability**

Construction and operation of most components of Alternative 5 would be straightforward. Resources are readily available for UXO screening (and safety measures), soil removal, and off-site treatment and disposal. Standard excavation and construction equipment would be used to remove contaminated soil. Soil would be sampled during excavation activities to verify that all contaminated surface soil within the excavation area was removed. The sampling procedures for soil at APG are well established.

Alternative 5 would use established treatment technologies. The stabilization/solidification technology is considered to be a reliable process and would not require further development before implementation. Several off-site treatment/disposal vendors would be available to submit competitive bids.

The implementation of Alternative 5 would not adversely affect the performance of additional remedial actions that might be required at the TBP area. The ability to implement future groundwater remediation at the site (if needed) would not be affected by the excavation and back-filling operations; however, in the case of phytoremediation, some coordination would be needed in the timing of excavation and planting of vegetation.

### **7.5.7 Cost**

The components that make up the treatment train for Alternative 5 are shown in Table 7.4. As for Alternatives 3 and 4, costs are given for both the 6-in. and 2-ft excavations. Many of the components that make up the soil remediation treatment train for Alternative 5 are identical to those in Alternatives 2 through 4: UXO and CWA screening, constructing an access road, clearing and grubbing, excavating all areas, constructing a staging area, transporting soil to the staging area, and landscaping all excavated areas. Extension of electric service is not needed in this alternative. The

**TABLE 7.4 Cost Estimate for Alternative 5 (April 1996 \$)<sup>a</sup>**

Activity	Cost (\$1,000)	
	6-in. Excavation	2-ft Excavation
Direct costs		
Construct/improve access road	26	26
UXO screening	156	156
Clear and grub	20	20
Excavate pushout and pits	81	197
Construct staging area	126	268
Transport to staging area	7	23
Off-site land disposal	2,119	5,660
Sampling and analysis	23	82
Landscape excavated area	4	4
Remedial action professional labor	16	19
Remedial design	93	238
Total direct costs	2,672	6,695
Indirect costs		
Contractor general conditions	444	824
Contractor overhead and profit	618	1,415
Total contract indirect costs	1,062	2,239
Total contract cost (direct and indirect)	3,734	8,934
Other		
Contingencies (10%)	373	893
Project management (8%)	299	715
Total project cost	4,406	10,542
Unit cost (\$/yd <sup>3</sup> )	1,093	653

<sup>a</sup> Costs for the 6-in. excavation are included for comparative purposes only.

new component in the treatment train of this alternative is disposal of all excavated material in an off-site hazardous waste landfill.

As for Alternative 4, a staging area would be needed to stockpile the soil because it would probably be excavated faster than it could be transported to the off-site landfill. The staging area in this alternative was assumed to be the same size and construction as in Alternative 4. Soil would be trucked from the excavation site to the staging area and covered with plastic laminate.

As noted for Alternative 4, the contract cost of soil disposal in a hazardous waste landfill would be about \$208/ton (\$312/ton for the 6-in. excavation, because of the smaller quantities). The cost includes loading onto trucks, transporting to the landfill, stabilizing the waste, and all taxes and fees for landfill disposal. The cost of disposal for the 6-in. excavation would be \$2,119,000, whereas the cost of disposal for the 2-ft excavation would be \$5,660,000. This would amount to nearly 79% of the direct cost for the 6-in. excavation and nearly 85% for the 2-ft excavation.

To characterize the excavated soil before off-site shipment, screening for CWAs and TCLP analyses would be performed. If CWAs were present, additional processing (on-site) would be required. Additional processing costs are not included in this estimate. The estimated cost for sampling and analysis is \$23,000 for the 6-in. excavation and \$82,000 for the 2-ft excavation.

The final two direct-cost items for this alternative are professional labor and remedial design. Professional labor amounts to \$16,000 for the 6-in. excavation and \$19,000 for the 2-ft excavation. Remedial design costs \$93,000 for the 6-in. excavation and \$238,000 for the 2-ft excavation, assuming a low level of complexity for this alternative.

The total direct cost of this alternative is estimated to be \$2,672,000 for the 6-in. excavation and \$6,695,000 for the 2-ft excavation. Indirect costs, such as contractor general conditions and contractor overhead and profit, add \$444,000 and \$618,000, respectively, to the total cost for the 6-in. excavation and \$824,000 and \$1,415,000, respectively, to the total cost for the 2-ft excavation. A contingency factor of 10% adds \$373,000 to the cost of the 6-in. excavation and \$893,000 to the 2-ft excavation. Finally, it is assumed that project management adds an additional 8%, or \$299,000 for the 6-in. excavation and \$715,000 for the 2-ft excavation. Consequently, the total estimated cost of this alternative is \$4,406,000 for the 6-in. excavation and \$10,542,000 for the 2-ft excavation. This translates into a unit cost of about \$1,093/yd<sup>3</sup> for the 6-in. excavation and \$653/yd<sup>3</sup> for the 2-ft excavation.

## 7.6 MONITORING AND MITIGATIVE MEASURES

The primary monitoring and mitigative measures that would be used at the TBP area during remediation are summarized in Table 7.5. These measures would provide a high degree of effectiveness in minimizing the potential for adverse effects associated with remediation activities.

TABLE 7.5 Major Monitoring and Mitigative Measures for Action Alternatives

Factor	Potential Impact	Mitigative Measure
Construction and excavation activities	Transport of contaminated and uncontaminated soil to adjacent marsh by surface water runoff	Good engineering practices would be implemented, including sediment barriers, dikes, siltation ponds, and drainage channels to direct runoff away from marsh; surface would be backfilled upon completion of excavation.
		In addition, surface water and sediment would continue to be monitored for related contaminants so contaminated media could be addressed appropriately (through removal or treatment), as needed.
	Loss of terrestrial habitats	Habitats would be restored, as appropriate. The final form of mitigation would be determined in consultation with appropriate state and federal agencies.
	Disturbance of local biota and site workers by noise	Vehicle and equipment mufflers would be checked periodically and maintained in good condition.
	Disturbance of local biota, site workers, and general public and impacts to local air quality as a result of fugitive dust emissions	Dust would be controlled by using wet methods and covers at the excavation site, along access roads, and at staging areas. Work areas would be covered, as needed (e.g., at night and during high winds).
	Accidental spill (release) of contaminated material as a result of equipment failure or vehicular accident	Soil would be transported in covered trucks traveling at low speeds. Soil would be dewatered before transport. Contingency plans would be in place to address any spills that might occur during transport.
Transport of contaminated soil from TBP area to on-site storage or treatment facility	Inadvertent transport of contaminated material on haul vehicle surfaces or tires leaving work zone	Haul vehicles would be decontaminated and inspected before leaving the work zone.

TABLE 7.5 (Cont.)

Factor	Potential Impact	Mitigative Measure
Transport of contaminated soil to an off-site treatment and disposal facility	Accidental spill (release) of contaminated material as a result of equipment failure or vehicular accident	Soil would be transported in closed containers. Contingency plans would be in place to address any spills that might occur during transport.
	Inadvertent transport of contaminated material on haul vehicle surfaces or tires leaving work zone	Haul vehicles and containers would be decontaminated and inspected before leaving the work zone.
All phases of remedial activities	Protection of site workers	All activities would be conducted in accordance with project health and safety plans and would include continuous monitoring of the work environment, UXO screening, and the use of protective equipment, as needed.
	Protection of the general public	Air and water would be monitored at the site and vicinity, and appropriate responses would be implemented if measured contaminant levels increased significantly above background. Access to construction and excavation areas would be limited; public vehicle access would also be limited along some of the off-site haul routes. Engineering controls would be applied to minimize dust and erosion during remedial action activities. Decontamination methods would be employed to minimize vehicle tracking of contaminants to surrounding uncontaminated areas. All traffic associated with the remedial action would be coordinated to minimize impacts on nearby facilities.

TABLE 7.5 (Cont.)

Factor	Potential Impact	Mitigative Measure
All phases of remedial activities (cont.)	Environmental monitoring	Air quality would be monitored for contaminated particulates at the site perimeter. Surface water downgradient of excavation and construction areas would be monitored for contaminants. Appropriate responses would be implemented as indicated by monitoring results.
	Environmental restoration	Disturbed areas would be restored by backfilling with clean fill, regrading, and revegetating with native and/or forage species. If necessary, wetlands would be constructed, as indicated, on the basis of consultation with the appropriate state and federal agencies.



## 8 COMPARATIVE ANALYSIS OF ALTERNATIVES

The comparative analysis of final interim remedial action alternatives for the J-Field TBP area compares the alternatives according to the nine evaluation criteria described in Section 7. This analysis is the second stage of the detailed evaluation process and provides information for making a balanced decision for site cleanup. For this analysis, the nine criteria are grouped into three general categories that make up the tiered evaluation system identified in the NCP (EPA 1990a): threshold criteria, primary balancing criteria, and modifying criteria.

The alternatives are compared in Sections 8.1 and 8.2 according to the threshold and primary balancing criteria, and Table 8.1 presents the results of this analysis. Section 8.3 introduces the modifying criteria. The comparative analysis is summarized in Section 8.4.

### 8.1 THRESHOLD CRITERIA

The threshold criteria category contains the two criteria that must be satisfied by the selected alternative:

- Overall protection of human health and the environment and
- Compliance with ARARs, unless a waiver condition applies.

These criteria are of greatest importance in the comparative analysis because they reflect the key statutory mandates of CERCLA. If an alternative does not satisfy both criteria, it cannot be selected as the cleanup remedy.

#### 8.1.1 Overall Protection of Human Health and the Environment

Alternatives 2, 4, and 5 would provide long-term protection of human health and the environment. This protection could not be ensured by the no-action alternative (Alternative 1) because only general baseline maintenance and monitoring activities would continue, and contaminants could migrate over time (e.g., from surface runoff into the marsh) and result in possible future adverse impacts. Alternative 3, intended to be an interim measure only, would also not provide long-term protection of human health and the environment, although it would meet project objectives by reducing exposures and minimizing contaminant migration by removing the sources of contamination. Alternative 2 would limit exposures to contaminants by removing “hot spots” in the main pits and covering remaining contaminated surface soil. Arsenic- and PCB-contaminated soil would be sent off-site for treatment and disposal. Shoreline stabilization would be an adjunct to this

TABLE 8.1 Comparative Analysis of Alternatives

Alternative 1: No Action	Alternative 2: Limited Removal and Disposal, and In-Situ Containment	Alternative 3: Removal and Short-Term Storage	Alternative 4: Removal, On-Site Treatment, and Limited Disposal	Alternative 5: Removal, Off-Site Treatment, and Disposal
<b>Overall Protection of Human Health and the Environment</b>				
Would not ensure protection of human health and the environment in the long term. Source areas would not be removed or treated, and exposures could increase over time.	Engineering and mitigative measures would be employed during the remedial action period so that no significant adverse impacts would occur to the general public or environment. Worker exposures would be similarly controlled to levels within health-protective limits. Long-term exposures would be minimized by removing "hot spots" (arsenic and PCBs) from the main pits and by covering remaining contaminated soil with a protective soil cover.	Somewhat greater than Alternative 2. Long-term exposures would be minimized by removing and storing contaminated soil from the main pits and pushout area for about 5 years. At the end of that time, an additional component (e.g., off-site treatment and disposal) would be needed to ensure long-term protection.	Generally similar to Alternative 3. Long-term exposures would be minimized by removing and treating contaminated soil from the main pits and pushout area.	Generally similar to Alternatives 3 and 4. Treatment and disposal of a large volume of contaminated soil would be conducted off-site; therefore, the overall risk of exposure to the general public would be higher than that for Alternatives 2, 3, and 4.
<b>Compliance with ARARs</b>				
Would not meet all ARARs, including the corrective action requirements of RCRA and TSCA. In addition, would not satisfy the CERCLA-mandated preference for remedies that reduce contaminant toxicity, mobility, or volume through treatment.	Would meet all pertinent ARARs (with waivers as appropriate), including those that address protection of endangered species and habitats, floodplains, and wetlands. Implementing Alternative 2 might require preparation of a sediment and erosion control plan.	Same as Alternative 2. The on-site storage facility would be operated to ensure compliance with RCRA.	Same as Alternatives 2 and 3. The on-site treatment facility would be operated to ensure compliance with RCRA.	Same as Alternatives 2, 3, and 4, with additional disposal requirements that would be met, including RCRA hazardous waste generator.

TABLE 8.1 (Cont.)

Alternative 1: No Action	Alternative 2: Limited Removal and Disposal, and In-Situ Containment	Alternative 3: Removal and Short-Term Storage	Alternative 4: Removal, On-Site Treatment, and Limited Disposal	Alternative 5: Removal, Off-Site Treatment, and Disposal
<i>Long-Term Effectiveness and Permanence</i>				
Current exposures and impacts would continue and could increase over time because of continued contaminant migration. Existing institutional controls would continue to limit access to site workers and other authorized personnel, thereby reducing risk to the general public.	More protective than Alternative 1 because contaminated soil would be partially removed; the remaining soil then would be covered to reduce exposure of human and environmental receptors to surface contamination. Soil cleanup criteria would be applied to the removal of soils and to the delineation of the area to be covered.	More protective than Alternative 1 because contaminated soil would be removed and stored in an enclosed facility to provide an interim solution for risk posed by contaminated surface soil. Soil cleanup criteria would be applied as appropriate to the removal of soils, so the action would reduce contaminant concentrations remaining in soil to the most protective levels practicable.	More protective than Alternatives 1, 2, and 3 because contaminated surface soil would be removed and treated (soil washing/leaching) to provide a permanent solution for risk posed by contaminated surface soil. Soil cleanup criteria would be applied as appropriate to the removal of soils, so the action would reduce contaminant concentrations remaining in soil to the most protective levels practicable.	Similar to Alternative 4, except that exposure of stabilized/solidified waste to the environment could result in contaminants leaching from the waste over time.
<i>Reduction of Toxicity, Mobility, or Volume</i>				
Toxicity, mobility, and volume of contaminated soil would not change.	The in-situ containment component would significantly reduce contaminant mobility. Contaminant volume would be somewhat reduced by the limited removal and disposal component. Contaminant toxicity would not be reduced.	Short-term storage of soil in an on-site facility would significantly reduce contaminant mobility. An estimated 16,000 yd <sup>3</sup> (27,200 tons) of soil would be stored on-site for about 5 years. Contaminant toxicity and volume would not be reduced.	Chemical treatment of soil by soil washing/leaching would significantly reduce contaminant mobility and volume. An estimated 16,000 yd <sup>3</sup> (27,200 tons) of soil would be treated on-site by soil washing/leaching. This process could reduce original soil volume by about 94%; the remaining 6% could then be sent off-site for disposal. Toxicity of PCBs would be reduced. Lead toxicity would not be reduced; however, the metal would be removed and recycled.	Chemical treatment of soil with the stabilization/solidification technology would significantly reduce contaminant mobility. An estimated 16,000 yd <sup>3</sup> (27,200 tons) of soil would be treated off-site by chemical stabilization/solidification. This process could increase the original soil volume and weight by as much as 30% and 60%, respectively. This would result in a total treated volume of about 20,800 yd <sup>3</sup> and total weight of about 35,360 tons to be placed in a landfill. Contaminant toxicity would not be reduced.

TABLE 8.1 (Cont.)

Alternative 1: No Action	Alternative 2: Limited Removal and Disposal, and In-Situ Containment	Alternative 3: Removal and Short-Term Storage	Alternative 4: Removal, On-Site Treatment, and Limited Disposal	Alternative 5: Removal, Off-Site Treatment, and Disposal
<b>Short-Term Effectiveness</b>				
Current exposures and adverse impacts would continue. Existing institutional controls would continue to limit access to site workers and other authorized personnel, thus reducing risks to the general public. Short-term risks to site workers and the environment as a result of monitoring and maintenance activities are considered low.	Exposures would be lower than for Alternatives 3, 4, and 5, which involve large-scale excavation. Mitigative measures would still be required in the short term because of particulate and VOC emissions associated with removal and transportation activities. No adverse impacts to the general public are expected from contaminant releases during implementation of this alternative. Soil, vegetation, and wildlife disturbances would be significant during soil excavation activities. An estimated 5 acres would be affected. Most impacts to biota would be temporary. Surface water impacts associated with the construction of a berm along the pushout-marsh boundary would be minimal (and localized). Surface water input would be reduced, but reduction in erosion and transport of soils into the marsh would be a benefit to the marsh ecosystem. Mitigative measures would be implemented to minimize impacts to air quality and those associated with noise levels.	Exposures could be higher than Alternatives 1 and 2 in the short term because of particulate and VOC emissions associated with removal, transportation, and storage activities. Mitigative measures would be implemented to minimize potential human health and environmental impacts. Risks to a site worker would increase compared to Alternative 1; however, worker health and safety precautions would be used to control exposures. No adverse impacts to the general public are expected from contaminant releases during implementation of this alternative. Soil, vegetation, and wildlife disturbances would be significant during soil excavation activities. An estimated 5 acres would be affected. Most impacts to biota would be temporary. Activities are not expected to affect threatened or endangered species. Mitigative measures would be employed to minimize impacts to surface water resources (including the adjacent marsh), air quality, and those associated with noise levels.	Similar to Alternative 3.	Similar to Alternatives 3 and 4, except that overall risk to the general public would be higher because this alternative would involve the off-site transport of a large volume of contaminated soil. Additional mitigative measures would be implemented to reduce related impacts.

TABLE 8.1 (Cont.)

Alternative 1: No Action	Alternative 2: Limited Removal and Disposal, and In-Situ Containment	Alternative 3: Removal and Short-Term Storage	Alternative 4: Removal, On-Site Treatment, and Limited Disposal	Alternative 5: Removal, Off-Site Treatment, and Disposal
<i>Implementability</i>				
Minimum site operations (monitoring and maintenance) would continue with the use of readily available resources.	Fairly straightforward to implement. Resources are readily available for UXO screening, soil removal, in-situ containment, and shoreline stabilization.	Fairly straightforward to implement. Resources are readily available for UXO screening, soil removal, and on-site storage. Short-term storage facilities are available as kits and can be customized to meet project specifications.	Similar to Alternative 3. Soil washing/leaching has been used at several hazardous waste sites and probably would not require further development before it could be implemented at the TBP area. Further bench-scale testing would be required to refine and optimize the design of the treatment system.	Similar to Alternatives 3 and 4. Chemical stabilization/solidification is an established technology and would not require further development before it could be implemented.
<i>Cost</i>				
The total cost would be the lowest in the short term (about \$3 million over a 10-year period), but the comparative level of effectiveness would be low. In addition, the cost could be potentially higher than the action alternatives over the long term because conditions could worsen over time, necessitating an expensive expanded response in the future.	The total cost would be about \$1.8 million, the lowest cost of all the action alternatives. This cost, however, reflects only O&M costs for the next 30 years. Because contaminated soil will remain in place, O&M costs will likely extend indefinitely into the future. Repairs associated with the catastrophic effects of a 100-year flood are also not reflected in this estimate.	The total cost would be about \$5.0 million (for 16,000 yd <sup>3</sup> of soil), the second lowest of all the action alternatives. This cost, however, does not include the cost of an additional component (off-site treatment and disposal) that would be needed to ensure long-term protectiveness and permanence. Therefore, while this alternative would achieve project objectives of reducing exposures and minimizing contaminant migration at a low cost, it is considered the least cost-effective because additional components would be required when the 5-year storage period ended.	The total cost would be about \$13.0 million (for 16,000 yd <sup>3</sup> of soil), which is the highest of the action alternatives. The soil washing/leaching component would account for 86% of the total direct cost of this alternative.	The total cost would be about \$10.5 million (for 16,000 yd <sup>3</sup> of soil), which is lower than Alternative 4 for the same overall level of effectiveness. Off-site treatment and disposal would account for 85% of the total direct cost of this alternative.

activity to prevent erosion of the shoreline to the south of the TBP area. Alternative 4 would limit exposures to contaminants by removing the sources of contamination, treating the contaminated soil on-site (via soil washing/leaching), then returning the cleaned soil to the site to be used as fill. In addition, PCB-contaminated soil would be sent off-site for treatment (incineration or stabilization) and disposal. Alternative 5 is similar to Alternative 4, except that the soil would be sent off-site for treatment (via stabilization/solidification) and disposal. Clean soil would be brought in to fill the excavated areas.

The two main differences between Alternatives 4 and 5 are the treatment method and disposal location, which includes a transportation component for off-site disposal. Under both Alternatives 4 and 5, PCB-contaminated soil would be sent off-site for treatment and disposal. Under Alternative 4, contaminated soil (an estimated 16,000 yd<sup>3</sup> for an excavation to a depth of 2 ft) would be treated on-site with a small volume of material sent off-site for disposal. Under Alternative 5, all of the 16,000 yd<sup>3</sup> of contaminated soil would be sent off-site for treatment and disposal.

Although potential health impacts during cleanup activities could be significant for all the alternatives, mitigative measures would be employed to control exposures to levels within health-protective limits. Impacts to the general public would be relatively higher for Alternative 5 than for Alternatives 2, 3, and 4 because of the increased likelihood of exposures and accidents during the waste handling and transportation activities associated with off-site disposal. Impacts to site workers would be highest for Alternatives 3, 4, and 5 because these alternatives involve large-scale excavation components.

Environmental impacts for all the alternatives could be significant. Each alternative involves excavating soil from source areas and constructing temporary staging areas, although excavation for Alternative 2 is fairly limited. Potential environmental impacts include increased fugitive dust and VOC emissions, increased ambient noise levels, increased sediment transport to the marsh and pond, and loss of vegetation and wildlife habitat. Most of these impacts are considered short term, although some loss of habitat may result. This impact would be offset by backfilling and revegetating the site, creating a wildlife habitat of better quality than is currently present at the site. Mitigative measures, such as those described in Section 7.6, would be employed to minimize these impacts.

### **8.1.2 Compliance with ARARs**

Except for Alternative 1, the attainment of ARARs under each final alternative would be comparable; applicable requirements would be met both during and following cleanup unless a waiver condition is applied. A comprehensive list of potential ARARs for this remedial action is presented in Appendix B; key requirements are discussed in Section 7 within the evaluation of each alternative against this criterion.

Alternative 1 would not attain certain applicable requirements, including RCRA corrective action requirements and TSCA. Alternatives 2, 3, 4, and 5 would meet applicable standards.

## **8.2 PRIMARY BALANCING CRITERIA**

The primary balancing criteria category contains the five criteria used to assess the relative advantages and disadvantages of the alternatives to determine the most appropriate solution for a given site:

- Long-term effectiveness and permanence;
- Reduction of toxicity, mobility, or volume through treatment;
- Short-term effectiveness;
- Implementability; and
- Cost.

The first and second criteria address the statutory preference for treatment as a principal element of the remedy and the bias against off-site disposal of untreated waste. Together with the third and fourth criteria, they form the basis for determining the general feasibility of the remedy and whether costs are proportional to the overall effectiveness, considering both the cleanup period and the time following cleanup. By this means, it can be determined whether the remedy is cost-effective.

### **8.2.1 Long-Term Effectiveness and Permanence**

Alternative 1 would not ensure long-term protection of human health or the environment because contaminants would be left in place, resulting in continued exposures to site workers and biota. In addition, contaminant levels in the marsh adjacent to the pushout area could increase due to contaminant migration from the source areas. Alternative 3, an interim measure, also would not ensure long-term protection, although it would accomplish project objectives. A long-term and more permanent component (such as off-site disposal) would be required to ensure long-term effectiveness. In contrast, Alternative 2 would provide long-term protection by limited removal and treatment and in-situ containment; however, long-term effectiveness could be affected by the potential for flooding. Alternatives 4 and 5 also would provide a permanent solution and long-term protection because they both involve removing and treating contaminated soil. The cleanup activities under all alternatives would reduce risks to levels considered protective of both human health and the environment.

### **8.2.2 Reduction of Toxicity, Mobility, or Volume**

The toxicity, mobility, or volume of contaminated material at the TBP area would not change under Alternative 1. In contrast, Alternative 2 would reduce contaminant mobility; however, because Alternative 2 involves only limited removal and treatment, contaminant toxicity and volume would be only somewhat reduced. Alternatives 3, 4, and 5 would remove contaminated soil, and the overall reduction in contaminant mobility would be higher than Alternative 2 and generally similar for each alternative. The toxicity and volume of contaminated soils would not be affected by Alternative 3. The volume of contaminated soils would be reduced by about 94% under Alternative 4; cleaned soil would be returned to the site, and recovered metals would be recycled. Under Alternative 5, soil volume would increase because of the addition of cement and fly ash to the soil matrix to stabilize it before disposal. Soil volume could increase by as much as 30% under this alternative. The toxicity of PCB-contaminated soil would be reduced by incineration under Alternatives 2, 4, and 5. Toxicity of lead would not be reduced under any alternative; however, the metal would be removed and recycled under Alternative 4.

### **8.2.3 Short-Term Effectiveness**

For Alternative 1, conditions would remain essentially the same in the short term, and no significant changes in potential exposures would be expected. Estimated risks associated with these exposures have been reported in the BRA (ICF Kaiser Engineers 1995b) and ERA (Hlohowskyj et al. 1996). For Alternatives 2, 3, 4, and 5, the various removal, treatment, and disposal activities would result in increased short-term exposures compared with Alternative 1. The short-term impacts associated with excavating and constructing temporary staging areas would be similar for all alternatives because the same procedures would be used. Potential impacts to the public would be minimized through the use of protective mitigative measures (Section 7.5). The risk of transportation accidents and related exposures would be highest for Alternative 5 because the greatest volume of soil would be sent off-site for disposal (resulting in a larger number of truck trips to the treatment and disposal facilities). The berm to be built as part of the in-situ containment component under Alternative 2 would result in a reduction of surface water input into the adjacent marsh but would produce the overall benefit of reducing erosion transport of contaminated soils into the marsh.

Potential short-term environmental impacts for all alternatives include increased fugitive dust and VOC emissions, increased ambient noise levels, increased sediment transport to the marsh and pond, and temporary loss of vegetation and wildlife habitat. Mitigative measures, such as those described in Section 7.6, would be employed to minimize these impacts.

#### 8.2.4 Implementability

All the action alternatives would be fairly straightforward to implement. The UXO screening, removal, treatment, disposal, and in-situ containment activities could be carried out with standard equipment and procedures and readily available resources. The storage facility under Alternative 3 can be purchased as a kit and customized according to project specifications. The soil washing/leaching technology under Alternative 4 has been used at several hazardous waste sites and probably would not require further development for implementation at the TBP area, although further pilot-scale testing would be required. The stabilization/solidification treatment technology under Alternative 5 is well established and reliable.

The implementation of Alternative 2, 3, 4, or 5 would not adversely affect the performance of any future remedial actions that might be required at the TBP area. For example, the ability to implement future groundwater remediation (if needed) at the site would not be affected by excavation and backfilling operations or by emplacement of the “risk-reduction cover.”

#### 8.2.5 Cost

Alternative 1 would include monitoring and maintenance costs and would be the least expensive of all the alternatives in the short term. However, total costs are expected to be highest in the long term because site conditions could worsen over time in the absence of cleanup, such that the potential impacts and the magnitude of the cleanup effort could increase in the future. Therefore, the cost-effectiveness of the no-action alternative is low.

Preliminary costs estimated for Alternatives 2, 3, 4, and 5 allow a balanced comparison for considering overall effectiveness. Final costs will be developed during the detailed design stage after the remedy for site cleanup is selected. The costs presented in this report were estimated by using the RACER model (Appendix F) and information supplied by vendors. Table 8.2 lists comparative costs for the removal, storage, treatment, and disposal components of Alternatives 2, 3, 4, and 5. Alternative 2 has the lowest total costs. Alternative 4 costs more than Alternative 5 because higher costs are associated with on-site treatment (soil washing/leaching) and disposal. Although Alternative 4 offers no increased benefit for overall protectiveness, it does satisfy EPA’s preference for on-site treatment. Of concern for Alternative 5 is the continued, long-term monitoring and maintenance of the off-site disposal facility. Because it would be a commercial facility, the maintenance of institutional controls at the site would be the responsibility of a private company instead of the federal government. Breakdowns in institutional controls resulting in contaminant releases from U.S. Army waste could lead to future liability issues. This concern does not exist for the on-site treatment of contaminated soil under Alternative 4 because soil would be cleaned and returned to the site (pending a treatability variance), and metals would be recovered and recycled.

**TABLE 8.2 Comparative Costs for Cleanup Activities under Alternatives 2, 3, 4, and 5**

Activity	Estimated Cost (\$ million)			
	Alternative 2	Alternative 3	Alternative 4	Alternative 5
Removal	0.1	0.4 (0.3) <sup>a</sup>	0.4 (0.3)	0.4 (0.3)
In-situ containment	0.4	NA <sup>b</sup>	NA <sup>b</sup>	NA <sup>b</sup>
Storage	NA <sup>c</sup>	2.2 (1.2)	NA <sup>c</sup>	NA <sup>c</sup>
Treatment	— <sup>d</sup>	NA <sup>e</sup>	6.4 (2.5)	— <sup>d</sup>
Disposal	0.3	NA <sup>e</sup>	0.3 (0.1)	6.1 (2.3)
Other <sup>f</sup>	1.0	2.4 (1.5)	6.0 (2.4)	4.0 (1.8)
Total	1.8	5.0 (3.0)	13.1 (5.3)	10.5 (4.4)

<sup>a</sup> Cleanup costs listed are for excavation to 2 ft (total soil volume of 16,000 yd<sup>3</sup>); numbers in parentheses represent cleanup costs for excavation to 6 in. (total soil volume of 4,000 yd<sup>3</sup>) for Alternatives 3, 4, and 5.

<sup>b</sup> Not applicable; in-situ containment is not a component of Alternative 3, 4, or 5.

<sup>c</sup> Not applicable; storage facility is not a component of Alternative 4 or 5.

<sup>d</sup> Treatment and disposal costs are estimated together for Alternatives 3 and 5.

<sup>e</sup> Not applicable; treatment and disposal is not a component of Alternative 3.

<sup>f</sup> Other costs include indirect costs, such as contractor overhead and profit, remedial design, labor and project management, and contingencies.

Cost estimates for Alternative 4 were based on the assumption that soil volume would be reduced by 94%, resulting in 6% of the soil being sent off-site for further treatment and disposal.

Alternative 2 is considered the most cost-effective alternative because it provides overall protection for human health and the environment and has the lowest total cost as compared to Alternatives 3, 4, and 5. However, because this alternative has only been costed to 30 years, it is not directly comparable to the costs for Alternatives 3, 4, and 5.

### 8.3 MODIFYING CRITERIA

The modifying criteria include:

- State acceptance and
- Community acceptance.

As discussed in Section 7, this category can be fully considered only after this FFS has been issued to the state and the public for formal comment. Therefore, these modifying criteria are not addressed in this comparative analysis. They will be addressed in detail in the Responsiveness Summary for the ROD for this remedial action.

### 8.4 SUMMARY

In summary, all of the final remedial action alternatives for the TBP area, except for the no-action alternative (Alternative 1), satisfy the threshold criteria for protecting human health and the environment and complying with regulatory requirements, with waivers as appropriate. Under each alternative, exposures and risks would be minimized by removing the sources of contamination and treating the contaminated soil. Alternative 2 would also involve covering contaminated soil in place to reduce surface exposures. Overall protectiveness under Alternatives 4 and 5 would be comparable to and somewhat greater than that under Alternative 2 because contaminant removal and treatment would be the major components of these alternatives. Alternative 3, while protective in the short term, would require an additional component (e.g., off-site treatment and disposal) to be as protective as Alternatives 4 and 5.

With regard to the primary balancing criteria, only Alternatives 2, 4, and 5 are expected to provide a permanent solution that would ensure protection for a very long time, although long-term effectiveness under Alternative 2 could be affected by the potential for flooding. It is possible that the soil washing/leaching treatment under Alternative 4 would be more protective than Alternative 5 if, at some future date, the stabilized/solidified waste were to be exposed to the environment and contaminants leached. However, appropriate design and good engineering practices would minimize the likelihood of such an occurrence.

Each action alternative would reduce contaminant mobility. Waste toxicity and volume would be only somewhat reduced under Alternative 2. Waste volume would not be affected by Alternative 3. Waste volume would decrease under Alternative 4. Waste volume would increase under Alternative 5 because of the addition of cement and fly ash to stabilize the waste. Treatment methods (under Alternatives 4 and 5) would reduce contaminant toxicity; under Alternative 4, metals would be recovered and recycled.

The short-term effectiveness of Alternatives 2, 3, 4, and 5 is comparable, except that the overall risk to the general public would be higher for Alternative 5 because it would involve off-site transport of contaminated soil. Environmental impacts at the TBP area from excavation and construction activities would be common for all action alternatives, and comparable impacts would be expected. Mitigative measures would be used to minimize potential short-term impacts.

Emplacement of the “risk-reduction cover” would be fairly straightforward. Construction of the storage facility under Alternative 3 also would be fairly straightforward. The implementation of Alternative 4 would be fairly straightforward, although additional studies would be required to refine the soil washing/leaching treatment system design and cost estimates. The chemical stabilization/solidification treatment that would be performed off-site under Alternative 5 is fairly well established and would not require further development before implementation.

Alternative 2 has the lowest overall cost (\$1.8 million) of the action alternatives; however, this cost is not directly comparable to Alternatives 3, 4, and 5. Alternative 5 is considered more cost-effective than Alternative 4 for site cleanup. The estimated total cost of Alternative 5 is \$10.5 million (for excavation to 2 ft), and it would provide a similar level of overall effectiveness as Alternative 4, with an estimated cost of \$13.1 million.

## 9 REFERENCES

- Alternative Remedial Technologies, Inc., 1995, *Soil Washing Technology Screening Study at the Aberdeen Proving Ground Pushout Area at J-Field*, prepared by Alternative Remedial Technologies, Inc., Tampa, Fla., for Argonne National Laboratory, Argonne, Ill., July 21.
- ART — See Alternative Remedial Technologies, Inc.
- Bradbury, K.R., and M.A. Muldoon, 1990, "Hydraulic Conductivity Determinations in Unlithified Glacial and Fluvial Materials," in *Ground Water and Vadose Zone Monitoring*, D.M. Nielsen and A.I. Johnson (editors), ASTM STP 1053, American Society for Testing and Materials, Philadelphia, Pa., pp. 138-151.
- Daudt, C.R., et al., 1994, *Environmental Geophysics at J-Field, Aberdeen Proving Ground, Maryland*, ANL/ESD/TM-77, Argonne National Laboratory, Argonne, Ill.
- Davies, B.E., et al., 1995, *Phase II Environmental Geophysics at J-Field, Aberdeen Proving Ground, Maryland*, ANL/ESD/TM-97, Argonne National Laboratory, Argonne, Ill.
- Davis, R.S., 1994, *Region III Interim Ecological Risk Assessment Guidelines*, Draft, U.S. Environmental Protection Agency, Region III, Philadelphia, Pa., July.
- DOE — See U.S. Department of Energy.
- EPA — See U.S. Environmental Protection Agency.
- Federal Emergency Management Agency, 1986, *Flood Insurance Study, Harford County, Maryland*, June 17.
- FEMA — See Federal Emergency Management Agency.
- Freeze, R.A., and J.A. Cherry, 1979, *Groundwater*, Prentice-Hall, Inc., Englewood Cliffs, N.J.
- Hlohowskyj, I., et al., 1995, *Work Plan for Conducting an Ecological Risk Assessment at J-Field, Aberdeen Proving Ground, Maryland*, ANL/EAD/TM-45, prepared by Argonne National Laboratory, Argonne, Ill., for U.S. Army, Directorate of Safety, Health, and Environment, Aberdeen Proving Ground, Md., March.
- Hlohowskyj, I., et al., 1996, *Remedial Investigation Report for J-Field, Aberdeen Proving Ground, Maryland, Volume 2: Ecological Risk Assessment*, draft prepared by Argonne National Laboratory, Argonne, Ill., for U.S. Army, Directorate of Safety, Health, and Environment, Aberdeen Proving Ground, Md.
- Huang, S., 1994, *Microbiological Characterization and Nutrient Interaction Tests on Impacted Soils at the Toxic Burning Pits*, draft report, Chester Environmental, Pittsburgh, Pa., May 27.

Hughes, W.B., 1991, "Application of Marine Seismic Profiling to a Ground Water Contamination Study, Aberdeen Proving Ground, Maryland," *Ground Water Monitoring Review* 11(1):97-102.

Hughes, W.B., 1992, "Use of Marine-Seismic Profiling to Study Ground-Water Contamination at Aberdeen Proving Ground, Maryland," in *Proceedings of the Symposium on the Application of Geophysics to Engineering and Environmental Problems*, R.S. Bell (editor), pp. 163-172.

Hughes, W.B., 1993a, *Hydrogeology and Soil Gas at J-Field, Aberdeen Proving Ground, Maryland*, Water Resources Investigations Report 92-4087, U.S. Geological Survey, Towson, Md.

Hughes, W.B., 1993b, personal communication from Hughes (U.S. Geological Survey, Towson, Md.) to J.J. Quinn (Argonne National Laboratory, Argonne, Ill.), Nov. 9.

Hughes, W.B., 1993c, personal communication from Hughes (U.S. Geological Survey, Towson, Md.) to J.J. Quinn (Argonne National Laboratory, Argonne, Ill.), Oct. 5.

ICF Kaiser Engineers, 1994a, *Comparison of Chemical Concentrations at Selected Sites at J-Field with Risk-Based Concentrations*, draft report, submitted to U.S. Army Environmental Center, Aberdeen Proving Ground Installation Restoration Risk Assessment Support, Aberdeen Proving Ground, Md., Feb.

ICF Kaiser Engineers, 1994b, *Workplan for Conducting a Human Health Risk Assessment at the J-Field Study Area*, final draft, submitted to U.S. Army Environmental Center, Aberdeen Proving Ground Installation Restoration Risk Assessment Support, Aberdeen Proving Ground, Md., May.

ICF Kaiser Engineers, 1995a, *Reference Sampling and Analysis Program at the U.S. Army Aberdeen Proving Ground, Soil, Sediment, and Surface Water Reference Data Report*, prepared for U.S. Army Environmental Center, Aberdeen Proving Ground, Md., July.

ICF Kaiser Engineers, 1995b, *J-Field Toxic Burning Pits Area Baseline Human Health Risk Assessment*, draft, prepared for U.S. Army Environmental Center, Aberdeen Proving Ground, Md., Aug.

ICF Kaiser Engineers, 1996, *Volume II: Human Health Risk Assessment for J-Field Edgewood Area, Aberdeen Proving Ground*, prepared by ICF Kaiser Engineers, Abingdon, Md., for U.S. Army Environmental Center, Aberdeen Proving Ground, Md., Jan.

Kerhin, R.T., et al., 1988, *The Surficial Sediments of the Chesapeake Bay, Maryland: Physical Characteristics and Sediment Budget*, Report of Investigations No. 48, Maryland Geological Survey, Towson, Md.

Lemaster, K., 1995, personal communication from Lemaster (Maryland Department of the Environment, Baltimore) to J. Wrobel (U.S. Army Directorate of Safety, Health, and Environment, Aberdeen Proving Ground, Md.), June 15.

Lorah, M.M., and J.S. Clark, 1992, *Contamination of Groundwater, Surface Water, and Soil, and Evaluation of Selected Pumpage Scenarios in the Canal Creek Area of Aberdeen Proving Ground, Maryland*, draft open-file report, U.S. Geological Survey, Towson, Md.

Maryland Department of Natural Resources, 1992, *Rare, Threatened, and Endangered Animals of Maryland*, Annapolis, Md., May.

McKegg, J., 1992, letter with attachments from McKegg (Director of Maryland Natural Heritage Program) to C. Dunn (Argonne National Laboratory, Argonne, Ill.), Oct. 8.

MDNR — See Maryland Department of Natural Resources.

National Oceanic and Atmospheric Administration, 1993, "Chesapeake Bay Approaches to Baltimore Harbor," map 12278, 1:40,000, Washington, D.C.

National Oceanic and Atmospheric Administration/HAZMAT, undated, *NOA Screening Guidelines for Organics and Inorganics, NOAA Quick Screening Reference Cards*, NOAA/HAZMAT, Seattle, Wash.

Nemeth, G., 1989, *RCRA Facility Assessment Report, Edgewood Area, Aberdeen Proving Ground, Maryland*, 39-26-0490-90, U.S. Army Environmental Hygiene Agency, Waste Disposal Engineering Division, Aberdeen Proving Ground, Md.

NOAA — See National Oceanic and Atmospheric Administration.

Oliveros, J.P., and D.A. Vroblesky, 1989, *Hydrogeology of Canal Creek Area, Aberdeen Proving Ground, Maryland*, Water-Resources Investigation Report 89-4021, U.S. Geological Survey, Towson, Md.

Opresko, D.M., et al., 1994, *Toxicological Benchmarks for Wildlife: 1994 Revision*, ES/ER/TM-86/R1, prepared by Oak Ridge National Laboratory, Oak Ridge, Tenn., for the U.S. Department of Energy, Sept.

Patton, T.L., 1994, *Installation of Well 173 at J-Field, Aberdeen Proving Ground, Maryland*, TU-2/ANL/APG/J-F/RI, Argonne National Laboratory, Argonne, Ill., Jan.

Perkins, S.O., and H.B. Winant, 1927, *Soil Survey of Harford County, Maryland*, U.S. Department of Agriculture, Beltsville, Md.

Peters, R., 1995, *Feasibility/Treatability Studies for Soil Washing and Solidification/Stabilization at J-Field, Aberdeen Proving Ground, Maryland*, TU-18/ANL/APG/J-F/RI-FFS, draft, Argonne National Laboratory, Argonne, Ill., May.

Princeton Aqua Science, 1984, *Munitions Disposal Study*, prepared for U.S. Department of the Army, Directorate of Engineering and Housing, Environmental Management Office, Aberdeen Proving Ground, Md., Nov.

Quinn, J., 1995, *Pump Test of Well 183 at J-Field, Aberdeen Proving Ground, Maryland*, TU-17/ANL/APG/J-F/RI, Argonne National Laboratory, Argonne, Ill., April.

Smith, H., and E.D. Matthews, 1975, *Soil Survey of Harford County Area, Maryland*, U.S. Department of Agriculture Soil Conservation Service, in cooperation with Maryland Agricultural Experiment Station, Beltsville, Md.

Sonntag, W., 1991, *Sampling and Analysis Plan for the Investigation of Ground-Water Contamination at J-Field, Aberdeen Proving Ground, Maryland*, draft report, U.S. Geological Survey, Reston, Va.

Swihart, G.L., et al., 1994, *Fishery Inventory and Baseline Water Quality of the Aberdeen Proving Ground, Aberdeen, Maryland*, U.S. Fish and Wildlife Service, White Marsh, Va.

U.S. Army, 1965, aerial photographs of Edgewood Area, roll no. G&O 85047, frames no. 8-1, 8-2, and 9-1 to 9-4, Environmental Hygiene Agency, Aberdeen Proving Ground, Md.

U.S. Army Toxic and Hazardous Materials Agency, 1993, *Risk and Biological Impact Assessment at U.S. Army Aberdeen Proving Ground, Maryland, Technical Plan*, Vol. I, prepared by ICF Kaiser Engineers, Abingdon, Md., March.

USATHAMA — See U.S. Army Toxic and Hazardous Materials Agency.

U.S. Department of Energy, 1993/1994, *Technology Profiles*, Technology Search Program, Office of Environmental Restoration, Washington, D.C.

U.S. Environmental Protection Agency, 1988, *Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA*, Interim Final, EPA/540/G-89/004 (OSWER Directive 9355.3-01), Office of Emergency and Remedial Response, Washington, D.C., Oct.

U.S. Environmental Protection Agency, 1989a, *Risk Assessment Guidance for Superfund*, Vol. I, *Human Health Evaluation Manual*, Part A, EPA/540/1-89/002, Office of Emergency and Remedial Response, Washington, D.C., Dec.

U.S. Environmental Protection Agency, 1989b, *Risk Assessment Guidance for Superfund*, Vol. II, *Environmental Evaluation Manual*, EPA/540/1-89/001, Office of Emergency and Remedial Response, Washington, D.C., March.

U.S. Environmental Protection Agency, 1990a, "National Oil and Hazardous Substances Pollution Contingency Plan; Final Rule (40 CFR Part 300)," *Federal Register*, 55(35):6154-6176, Feb. 21.

U.S. Environmental Protection Agency, 1990b, *Obtaining a Soil and Debris Treatability Variance for Removal Actions*, Superfund LDR Guide #6B, Office of Emergency and Remedial Response, Sept.

- U.S. Environmental Protection Agency, 1991a, *Human Health Evaluation Manual, Supplemental Guidance: Standard Default Exposure Factors*, OSWER Directive 9285.6-03, Office of Emergency and Remedial Response, Washington, D.C., March 25.
- U.S. Environmental Protection Agency, 1991b, *Risk Assessment Guidance for Superfund*, Vol. 1, *Human Health Evaluation Manual*, Part B, *Development of Risk-Based Preliminary Remediation Goals*, EPA/540/R-92/003, Office of Emergency and Remedial Response, Washington, D.C., Dec.
- U.S. Environmental Protection Agency, 1991c, *Risk Assessment Guidance for Superfund*, Vol. 1, *Human Health Evaluation Manual*, Part C, *Risk Evaluation of Remedial Alternatives*, EPA/540/R-92/004, Office of Emergency and Remedial Response, Washington, D.C., Dec.
- U.S. Environmental Protection Agency, 1993a, *Selecting Exposure Routes and Contaminants of Concern by Risk-Based Screening*, EPA/903/R-93-001, EPA Region III, Hazardous Waste Management Division, Office of Superfund Programs, Philadelphia, Pa., Jan.
- U.S. Environmental Protection Agency, 1993b, *Superfund Innovative Technology Evaluation Program, Technology Profiles, 6th edition*, EPA/540/R-93/526, Office of Research and Development, Washington, D.C., Nov.
- U.S. Environmental Protection Agency, 1993c, *Remediation Technologies Screening Matrix and Reference Guide*, EPA 542-B-93-005, Office of Solid Waste and Emergency Response, Washington, D.C., July.
- U.S. Environmental Protection Agency, 1993d, *VISITT Vendor Information System for Innovative Treatment Technologies*, Version 2.0, User Manual Report No. EPA 512-R-93-001, Office of Solid Waste and Emergency Response, Washington, D.C., April.
- U.S. Environmental Protection Agency, 1993e, *Wildlife Exposure Factors Handbook*, Vols. I and II, EPA/600/R-93/187a and b, Office of Research and Development, Washington, D.C., Dec.
- U.S. Environmental Protection Agency, 1994, *Revised Interim Soil Lead Guidance for CERCLA Sites and RCRA Corrective Action Sites*, OSWER Directive 9355.4-12, Office of Emergency and Remedial Response, Washington, D.C., Aug.
- U.S. Environmental Protection Agency, 1995, *Risk-Based Concentration Table, January-June 1995*, EPA Region III, Hazardous Waste Management Division, Office of Superfund Programs, Philadelphia, Pa., Jan.
- U.S. Environmental Protection Agency and U.S. Department of the Army, 1990, "Federal Facility Agreement, Aberdeen Proving Ground," Administrative Docket Number III-FCA-CERC-004.
- Van Lonkhuyzen, R., 1994, *Wetland Delineation at the Toxic Burn Pits, J-Field*, TU-12/ANL/APG/J-F/RI-ERA, Argonne National Laboratory, Argonne, Ill., July.

Vroblesky, D.A., et al., 1989, *Ground-Water, Surface-Water, and Bottom-Sediment Contamination in the O-Field Area, Aberdeen Proving Ground, Maryland, and the Possible Effects of Selected Remedial Actions on Ground Water*, Open-File Report 89-399, U.S. Geological Survey, Towson, Md.

Whorton, R., 1996, personal communication from Whorton (Advanced Environmental Technical Services) to K. Bankerd (Directorate of Contracting, U.S. Army Aberdeen Proving Ground, Md.), April 24.

Will, M.E., and G.W. Suter, 1994, *Toxicological Benchmarks for Screening Potential Contaminants of Concern for Effects on Terrestrial Plants: 1994 Revision*, ES/ER/TM-85/R1, prepared by Oak Ridge National Laboratory, Oak Ridge, Tenn., for the U.S. Department of Energy, Sept.

Wolflin, J.P., 1992, letter from Wolflin (Supervisor, Chesapeake Bay Field Office, U.S. Fish and Wildlife Service) to C.P. Dunn (Argonne National Laboratory, Argonne, Ill.), Oct. 7.

Wrobel, J., 1994, personal communication from Wrobel (Directorate of Safety, Health, and Environment, U.S. Army Aberdeen Proving Ground, Md.) to J. Quinn (Argonne National Laboratory, Argonne, Ill.), Aug. 23.

Wrobel, J., 1995, personal communication from Wrobel (Directorate of Safety, Health, and Environment, U.S. Army Aberdeen Proving Ground, Md.) to L. Martino (Argonne National Laboratory, Argonne, Ill.), July 15.

Yuen, R., et al., 1996, *Remedial Investigation Report for J-Field, Aberdeen Proving Ground, Maryland, Volume 1: Remedial Investigation Results*, draft prepared by Argonne National Laboratory, Argonne, Ill., for U.S. Army, Aberdeen Proving Ground, Md., Directorate of Safety, Health, and Environment.

Zar, J.H., 1984, *Biostatistical Analysis*, second edition, Prentice Hall, Inc., Englewood Cliffs, N.J.

## 10 LIST OF PREPARERS

This FFS report was prepared for the U.S. Army Directorate of Safety, Health, and Environment by ANL's Environmental Assessment Division. Larry Thebeau and Prakash Ramaswamy of ICF Kaiser Engineers, Inc., developed Alternative 2 (Limited Removal and Disposal, and In-Situ Containment). The following ANL staff contributed to the preparation of this report.

Name	Education/Experience	Contribution
Louis Martino	M.S., environmental toxicology; 16 years experience in environmental assessment.	J-Field project manager; description of site characterization; contamination source identification and characterization; data analysis.
Terri Patton	M.S., geology; 13 years experience in environmental research and assessment.	FFS task leader; development of remedial action objectives; description of alternatives; engineering evaluation; comparative summary.
Paul Benioff	Ph.D., nuclear chemistry; 17 years experience in theoretical chemistry; 16 years experience in environmental assessment.	Technology screening; assessment of soil impacts.
Carole Biang	B.S., chemical engineering; 16 years experience in management and remediation of hazardous waste sites, environmental assessment.	Description of alternatives; engineering evaluation; comparative summary.
James Butler	Ph.D., environmental health sciences; 15 years experience in health risk assessment.	Assessment of human health impacts; identification of COCs; development of human health risk-based interim PRGs.
William Davies	M.S., hydrogeology; 11 years experience conducting environmental investigations.	Description of alternatives; contamination source identification and characterization; data analysis; engineering evaluation.
Rebecca Haffenden	J.D., 6 years experience in environmental law, specializing in RCRA and CERCLA; 11 years experience in energy law.	Assessment of ARARs.

Name	Education/Experience	Contribution
John Hayse	Ph.D., zoology; 13 years experience in ecology; 5 years experience in environmental assessment.	Assessment of ecological impacts; identification of COECs; modeling of contaminant uptake by ecological receptors.
Ihor Hlohowskyj	Ph.D., zoology; 20 years experience in ecological research; 16 years experience in environmental and ecological risk assessment.	Assessment of ecological impacts; identification of COCs; development of ecological risk-based interim PRGs.
Margy Ortigara	M.A., English; 6 years experience in technical editing.	Overall editorial responsibility.
Leslie Poch	M.S., nuclear engineering; 11 years experience in technology assessment and cost engineering.	Evaluation of costs for alternatives.
Edgar Portante	M.S., electrical engineering; M.S., business management; 16 years experience in power system and energy planning.	Evaluation of costs for alternatives.
John Quinn	M.S., hydrogeology; 7 years experience in hydrogeologic analysis.	Description of site geological conditions.
Cheong-Yip Yuen	Ph.D., geology (hydrogeology and environmental geology); 7 years experience in hydrological analysis; 13 years experience in process geomorphology.	Technology screening; contamination source identification and characterization; estimates of soil volumes to be calculated.
Yug-Yea Wang	Ph.D., civil engineering/environmental engineering; 11 years experience in environmental research; 3 years experience in environmental assessment.	Data analysis.
Gus Williams	Ph.D., environmental geotechnology; 8 years experience in numerical modeling development and application.	Vadose zone modeling.

**APPENDIX A:**

**VADOSE ZONE MODEL OF METAL TRANSPORT FOR THE  
TOXIC BURNING PITS AREA OF J-FIELD**



## **APPENDIX A:**

### **VADOSE ZONE MODEL OF METAL TRANSPORT FOR THE TOXIC BURNING PITS AREA OF J-FIELD**

#### **A.1 INTRODUCTION**

A model of the vadose zone of the Toxic Burning Pits (TBP) area of J-Field was developed to evaluate transport of metal contamination from the surface to the water table (i.e., vadose zone) by using the TRACR3D code (Travis and Birdsell 1991). The vadose zone model assumed a depth to water table of 2 m. Simulations were performed for a 50-year period. The model calculates saturation and concentration values at 2-cm vertical intervals through the vadose zone.

The objective of this modeling study was to evaluate the various processes that may affect the transport of metals from the near-surface to the water table and estimate approximate travel times for selected contaminants of concern (e.g., arsenic, cadmium, lead, zinc).

Surface contamination can reach groundwater via pathways other than those modeled by vadose zone transport models. In the vadose zone, numerous preferential pathways exist for contaminant and fluid transport, especially in the near-surface; these include such common features as desiccation cracks, holes that result from the decay of a former plant root, and animal burrows. These features can provide a means for surface contamination to reach the groundwater much faster than predicted by using vadose zone matrix flow and the transport mechanisms. In general, these types of features are difficult to model because it is difficult to characterize their location and properties in the field.

#### **A.2 CONCEPTUAL MODEL**

A conceptual model of the vadose zone was developed on the basis of the results of field investigations performed at the TBP area (Yuen et al. 1996). Metal transport within the vadose zone to the water table was assumed to occur because of near-surface metal contamination in the top 10 cm of the soil. The metal was assumed to undergo linear, instantaneous, equilibrium sorption-desorption between the aqueous and solid phases as it was transported through the vadose zone. The area contaminated with metals was assumed to be large, so that transport within the vadose zone could be assumed to be vertically downward with no lateral dispersion (i.e., one-dimensional). This assumption is conservative, because lateral dispersion and diffusion would tend to lower the concentration and delay the arrival time of a contaminant at the water table given a finite duration source, such as that assumed for this model.

The vadose zone comprised a homogeneous silty loam material 2 m thick (Perkins and Winant 1927), with a hydraulic conductivity of 2.0 Darcies<sup>1</sup> (Quinn 1995), a porosity of 0.45 (Guymon 1994), and an irreducible water saturation of 0.067 (Guymon 1994).

This model assumed a monthly rainfall of 10.0 cm (Smith and Matthews 1975), which occurred in a single event at the start of each month. This assumption is conservative because a single wetting event will transport material faster and further than constant infiltration, given the same total volume over the entire month.

### A.3 MODEL DESIGN AND INPUT PARAMETERS

A finite-difference grid was designed to model a depth to groundwater of 2 m, which is representative of the TBP area. The grid developed for this model contains 10 divisions in the horizontal direction and 100 in the vertical. The cell size is 2.0 cm square. The results from these simulations can be used to evaluate the transport of metals in areas where the depth to groundwater is less than 2 m by using the results for the 1-m depth. These estimates will not be conservative because of faster transport times in more saturated soils. As the depth to water table decreases, the saturation of the model increases due to capillary effects. However, these estimates should be relatively accurate. When depth to the water table becomes shallower (less than 1 m), these assumptions become worse and the model simulations reported here cannot be used to estimate contaminant transport. At shallow depths, a conservative estimate would be to assume that concentrations in the vadose zone water at the groundwater table are equal to the initial vadose zone concentrations. Dilution would occur as the vadose zone fluids mix with the saturated zone fluids, and concentrations would be lowered further as contaminants are transported within the saturated zone because of dilution, sorption onto the solid phases, and other geochemical and physical processes.

The model grid is two-dimensional; however, initial and boundary conditions are such that the flow regime modeled is one-dimensional. The left and right sides of the model are no-flow boundaries, creating a one-dimensional flow regime. No lateral dispersion is modeled. The bottom boundary represents the water table and is modeled by using a constant-pressure/constant-saturation condition for fluid flux and a zero-gradient condition for contaminant transport. This boundary condition allows continuous contaminant outflow when a contaminant plume reaches it. The surface boundary (top of the model) models the total monthly precipitation event as a single ponded water condition. This boundary condition applies a fluid saturation and pressure equal to a given depth of water. The ponded water depth automatically decreases as fluid leaves the surface by infiltration and enters the subsurface. When all of the water has infiltrated the subsurface, air pressure at the upper

---

<sup>1</sup> 2.0 Darcies is equivalent to a saturated hydraulic conductivity of  $1.9 \times 10^{-3}$  cm/s.

boundary is set to 0 gage pressure, and air saturation is set to 1.0 (completely air-saturated). Surface infiltration occurred once per month for the entire 50-year run.

The material distribution in the vadose zone is assumed to be homogeneous, with a permeability of 2.0 Darcies in the horizontal and vertical directions. This aspect of the model setup adds a degree of conservatism, because vertical saturated permeability is generally less than horizontal saturated permeability (typically 1/10) (Domenico and Schwartz 1990).

Determining the saturation-permeability relationship for soils is a difficult task that requires special laboratories and considerable time and effort. In addition, the results of these tests can have large uncertainty (Guymon 1994). For this study, the relationship between saturation and permeability developed by van Genuchten (1980) was used. Values for porosity, irreducible soil moisture, and the van Genuchten parameters from Guymon (1994) were used because no site-specific data were available. The porosity is 0.45, and the irreducible water content is 0.067. The van Genuchten parameters are 0.2908 and 50 cm for  $(1-1/\beta)$  and  $1/\alpha$ , respectively. These parameters match those of a silty loam (Guymon 1994).

Initial water saturations approximate equilibrium values, with the soils near the water table more water-saturated than soils near the surface. The values used for initial water saturations approximate a drained condition for the soil.

#### A.4 TRANSPORT STUDIES

For all computations, the fluid in the top 10 cm of the vadose zone was assumed to be a tracer at a concentration ratio,  $C/C_0$  equal to 1, in equilibrium with sorbed tracer on the solid matrix.<sup>2</sup> In one-dimensional studies, the  $C/C_0$  parameter is a way to nondimensionalize concentration measurements, providing general information that is invariant with respect to the initial concentration. Model-computed values of  $C/C_0$  can be multiplied by a chosen initial concentration to arrive at model-predicted concentrations. As a conservative estimate, the solubility limit of a compound is typically used as an initial concentration. Multiplying the computed  $C/C_0$  value by a compound's solubility gives a conservative estimate of subsurface contamination values.

A set of simulations was completed by using a range of  $K_d$  values: 0, 5, 15, and 150 mL/g (Table A.1). This range covers the estimated  $K_d$  values for the metal contaminants present at the TBP area. In the following sections, these simulations are discussed. The metal that could be modeled by a given  $K_d$  is identified in each section along with reported  $K_d$  ranges from the literature. No site-specific values exist for  $K_d$  at the TBP area.

---

<sup>2</sup> C is the current concentration of a tracer, and  $C_0$  is the initial concentration.

TABLE A.1  $K_d$  Values and Results

Description	$K_d$ (mL/g)	Depth after 50 years (cm)	Notes
Conservative tracer	0.0	-	Tracer was flushed from the vadose zone after approximately 4 months
Lead	150.0	~ 45	Very immobile
Cadmium	15.0	~ 85	Relatively immobile, after 50 years the contamination has moved less than 1 m
Zinc	5.0	-	Tracer was flushed from the vadose zone after approximately 30 years

#### A.4.1 Nonreactive Tracers

An initial set of simulations was run as a base-case assuming a conservative tracer (i.e., nondegrading, nonreactive, and nonsorbing [ $K_d = 0$ ]). Nonreactive tracer transport was rapid. The tracer reached the groundwater table in approximately two months. After four months, all the tracer had been flushed from the vadose zone. The model was configured to produce output at the end of each 30-day period. At the end of the third period, tracer concentrations were still measurable in the vadose zone. By the end of the fourth period, no tracers were present in the model — they had all been transported across the lower boundary.

#### A.4.2 Lead

$K_d$  values for lead range from  $1.8 \times 10^2$  to  $6.3 \times 10^4$  mL/g (Sheppard et al. 1984), with the higher values generally occurring in soils rich in organic matter. In sand, the highest reported value is  $3.5 \times 10^3$  mL/g. For this study, a conservative value<sup>3</sup> of 150 mL/g was used to model lead transport in the vadose zone. Under these conditions, the lead was not mobile.


Pure lead is insoluble (Chemical Rubber Company [CRC] 1968); however, various lead compounds are soluble to varying degrees. The solubility of lead-oxide (PbO) is 0.0017 g/100 cc, while red lead-oxide (Pb<sub>3</sub>O<sub>4</sub>) is insoluble (CRC 1968). Lead is mostly present in the lead-oxide form (Peters 1995).

<sup>3</sup> Lower values of  $K_d$  allow the contaminant to be more mobile in the subsurface.

Figure A.1 shows the results of a calculation spanning 50 years. The initial depth of contamination was 10 cm with a concentration ratio,  $C/C_0$ , of 1. After 50 years, the center of mass of the lead plume is at a depth of approximately 20 cm, while the leading edge is at a depth of less than 40 cm.

#### A.4.3 Cadmium

Reported  $K_d$  values for cadmium range from 47.6 to 500 mL/g in sands, 9.8 to 76 mL/g in silty soils, and 23 to  $1.7 \times 10^4$  mL/g in soils rich in organic matter (Sheppard et al. 1984; Thibault et al. 1990). For this study, a value of 15 mL/g was used to model cadmium transport, which is near the low end of the range for silty soils. Cadmium is slightly soluble, and the compound cadmium-sulfide has a solubility of 0.00013 g/100 cc (CRC 1968).




**FIGURE A.1** Concentration Profiles for Lead Using a  $K_d$  Value of 150 mL/g for a 50-Year Period

Figure A.2 shows the results of a calculation spanning 50 years. The initial depth of contamination was 10 cm with a concentration ratio,  $C/C_0$ , of 1. After 50 years, the center of mass of the cadmium plume is at a depth of approximately 85 cm, while the leading edge is at a depth of less than 130 cm.

#### A.4.4 Zinc


Reported  $K_d$  values for zinc range from 0.1 to 2,120 mL/g in sands, 3.6 to 100 mL/g in silty soils, and 70 to  $1.3 \times 10^4$  mL/g in soils rich in organic matter (Sheppard et al. 1984; Thibault et al. 1990). For this study, a value of 5 mL/g was used, which is near the low end of the range for silty soils. The results of the calculations for lead and cadmium, which used  $K_d$  values of 150 and 15 mL/g, respectively, can be used to estimate the effects of a higher  $K_d$  on zinc transport.



**FIGURE A.2** Concentration Profiles for Cadmium Using a  $K_d$  Value of 15 mL/g (Shown are  $C/C_0$  values versus depth for 0, 25, and 50 years)

Figure A.3 shows the results of a calculation spanning 20 years. The initial depth of contamination was 10 cm with a concentration ratio,  $C/C_0$ , of 1. After 30 years, the zinc plume has been flushed from the vadose zone; no zinc occurs in solution in any of the vadose zone water. During this 30-year period, the maximum  $C/C_0$  ratio at the water table was approximately 0.38.

Assuming the zinc is present as zinc-oxide, with a maximum solubility of 0.00016 g/100 cc (CRC 1968), the maximum concentration at the water table would be below  $6.0 \times 10^{-7}$  g/mL. This is calculated by assuming that the initial concentration of zinc in the vadose zone fluid was equal to the maximum solubility limit of zinc-oxide and multiplying this value by the computed ratio of the current concentration to the initial concentration,  $C/C_0$ , which in this case was 0.38.



**FIGURE A.3** Concentration Profiles for Zinc Using a  $K_d$  Value of 5.0 mL/g (Shown are  $C/C_0$  versus depth profiles for 0, 10, and 20 years)

## A.5 OTHER CONTAMINANTS

Table A.2 lists some inorganic materials of concern at J-Field. Estimates of how these materials would behave during vadose zone transport can be made by determining which of the modeled  $K_d$  values most closely approximates that of the material of interest. The reported values of  $K_d$  span a large range because of the sensitivity of  $K_d$  values to soil types and other factors. Generally, the lowest reported values are for clean sands (no organics, clays, or silts) or clean gravels. The highest values reported are generally for clay and organic-rich soils.

## A.6 CONCLUSIONS

The model assumptions made in this study were conservative (i.e., tended to encourage transport at higher rates); however, even using these assumptions, lead contamination of the groundwater due to vadose zone transport from surface soil contamination was unlikely to be above levels of concern. Because of the high affinity of lead to sorb onto solids (especially clays and organic particles), lead is only slightly mobile in the subsurface. If lead is transported through the vadose zone to the water table, it would take several hundreds of years and be at low concentrations because of dispersion and dilution. Because of the estimated time required for lead to reach the groundwater, simulations were not performed to predict concentrations at the groundwater table.

**TABLE A.2 Inorganic Materials of Concern  $K_d$  Values<sup>a</sup>**

Material	$K_d$ Range (mL/g)	Material	$K_d$ Range (mL/g)
Antimony	180 - 4,000	Copper	76 - 266
Arsenic	1.0 - 18	Lead	180 - 63,000
Barium	0.4 - 6.0	Selenium	36 - 310
Cadmium	9.0 - 17,000	Silver	75 - 1,000
Chromium	50 - 1,000	Zinc	0.1 - 13,000
Cobalt	10 - 2,500		

<sup>a</sup>  $K_d$  values cover a large range. Generally, the lowest values reported here are for either a laboratory clean sand or gravel, while the highest values are for a clay or organic-rich soil. Typical field values are generally toward the higher portion of the range.

Source: Thibault et al. (1990).

These low concentrations would be further reduced by dilution that would occur as the vadose zone fluids mixed with the fluids below the water table. This dilution would be significant during any lateral transport, such as moving from the TBP area to the nearby marsh. Given the results of these calculations and the low concentrations of lead in groundwater samples from the TBP area,<sup>4</sup> the transport of lead through the vadose zone to the groundwater table presents a low risk of contamination at levels of concern (50 µg/L).

Cadmium, or other metals with a  $K_d$  of 15 mL/g, is only slightly mobile, with the center of the contamination plume moving less than 1.5 m during the 50-year period modeled.

Zinc, or metals with small  $K_d$  values (5 mL/g), reached the groundwater in approximately 20 years. Under the conditions modeled, the maximum concentration was estimated to be  $6.0 \times 10^{-7}$  g/mL.

This model simulates only transport of metals via matrix flow in the vadose zone. If preferential pathways for flow exist, highly retarded metals, such as lead, could reach the groundwater in a much shorter time. This will, however, be a local event, and the groundwater should dilute the contaminant to below levels of concern. This is the most likely pathway for the lead contamination measured in the groundwater at the TBP area.

This study does not look at the effects of saturated zone transport of metal contaminants. Metals undergoing transport in the saturated zone would undergo a number of processes that would lower the initial concentrations at the source, if the source existed for a finite time (was not continuous). Thus, concentrations in the groundwater at points of concern may be lower than those estimated at the groundwater table by this model.

## A.7 REFERENCES FOR APPENDIX A

Chemical Rubber Company, 1968, *CRC Handbook of Chemistry and Physics 1968-69*, R.C. Weast, editor, Cleveland, Ohio.

CRC: See Chemical Rubber Company.

Domenico, P.A., and F.W. Schwartz, 1990, *Physical and Chemical Hydrogeology*, John Wiley and Sons, New York, N.Y.

Guymon, G.L., 1994, *Unsaturated Zone Hydrology*, Prentice Hall, Englewood Cliffs, N.J.

---

<sup>4</sup> The maximum concentration found was 92 µg/L (in only one sample); most samples have lead values below the MCL of 50 µg/L ( $5 \times 10^{-3}$  mg/L).

Hughes, W.B., 1993, *Hydrogeology and Soil Gas at J-Field, Aberdeen Proving Ground, Maryland*, Water Resources Investigations Report 92-4087, U.S. Geological Survey, Towson, Md.

Hughes, W.B., 1995, *Ground-Water Flow and the Possible Effects of Remedial Actions at J-Field, Aberdeen Proving Ground, Maryland*, Water Resources Investigations Report 95-4075, U.S. Geological Survey, Towson, Md.

Perkins, S.O., and H.B. Winant, 1927, *Soil Survey of Harford County, Maryland*, U.S. Department of Agriculture, Washington, D.C.

Peters, R., 1995, *Feasibility/Treatability Studies for Soil Washing and Solidification/Stabilization at J-Field, Aberdeen Proving Ground, Maryland*, TU-18/ANL/APG/J-F/RI-FFS, Argonne National Laboratory, Argonne, Ill.

Quinn, J.J., 1995, *Pump Test of Well 183 at J-Field, Aberdeen Proving Ground, Maryland: J-Field Remedial Investigation Technical Update*, TU-17/ANL/APG/J-F/RI, Argonne National Laboratory, Argonne, Ill.

Sheppard, M.L., et al., 1984, *Soil Nuclide Distribution Coefficients and Their Statistical Distributions*, Whiteshell Nuclear Research Establishment, Atomic Energy of Canada Limited, Pinawa, Manitoba, Canada.

Smith, H., and E.D. Matthews, 1975, *Soil Survey of Harford County Area, Maryland*, U.S. Department of Agriculture and Soil Conservation Service, Washington, D.C., in cooperation with the Maryland Agricultural Experiment Station.

Thibault, D.H., et al., 1990, *A Critical Compilation and Review of Default Soil Solid/Liquid Partition Coefficients,  $K_d$ , for Use in Environmental Assessments*, Whiteshell Nuclear Research Establishment, Atomic Energy of Canada Limited, Pinawa, Manitoba, Canada.

Travis, B.J., and K.H. Birdsall, 1991, *TRACR3D: A Model of Flow and Transport in Porous Media, Model Description and User's Manual*, LA-11798-M UC-814, Los Alamos National Laboratory, Los Alamos, N.M.

van Genuchten, M.Th., 1980, "A Closed-Form Equation for Predicting the Hydraulic Conductivity of Unsaturated Soils," *Soil Science of America Journal* 44:892-898.

Yuen, R., et al., 1996, *Remedial Investigation Report for J-Field, Aberdeen Proving Ground, Maryland, Volume 1: Remedial Investigation Results*, draft prepared by Argonne National Laboratory, Argonne, Ill., for U.S. Army, Aberdeen Proving Ground, Md., Directorate of Safety, Health, and Environment.

**APPENDIX B:**  
**APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS**



TABLE B.1 State Regulations and To-Be-Considered Requirements for J-Field

Potential ARAR	Medium	Requirements	Preliminary Determination	Remarks
Chesapeake Bay Critical Area Protection Program, Annotated Code of Maryland, NR § 8-1801 et seq.; COMAR 27	Water, sediment, and soil	Protection of the bay, and criteria for any development in the bay area. Hazardous waste collection or disposal facilities are not permitted in the Critical Area unless no environmentally acceptable alternative exists.	Potentially applicable	Applies to Chesapeake Bay only. The bay borders the site to the south and may receive discharge from groundwater aquifers. Potential impacts will depend on the remedial actions.
Maryland Nonpoint Source Pollution Control Laws, Annotated Code of Maryland EN § 4-101 et seq.	Soil and sediment	Construction, including soil movement, grading, transporting, or otherwise disturbing land, requires a grading and building permit, issued after review and approval of the Department of the Environment.	Potentially applicable	Any excavation of soils may require compliance with this law.
Maryland Nonpoint Source Pollution Control Laws, Stormwater Management, Annotated Code of Maryland, EN § 4-201 et seq.; COMAR 26.09.05	Stormwater	A federal agency may not clear land, move soil, or engage in construction without submitting a stormwater management plan for approval to the Department of the Environment.	Potentially applicable	Any soil movement may require compliance with these requirements, including mitigation.
Maryland Wetland Law, Annotated Code of Maryland, EN § 9-301 et seq.; COMAR 08.07	Wetlands	Any person proposing to conduct any activity not authorized in the wetland regulations must apply for a permit from the Department of Natural Resources.	Potentially applicable	Because the definition of "person" does not include the federal government, these regulations would not be applicable; however, any clearing, filling, excavation, or dredging within wetland areas may require consultation with the Department.

TABLE B.1 (Cont.)

Potential ARAR	Medium	Requirements	Preliminary Determination	Remarks
Nontidal Wetlands Protection Act, Annotated Code of Maryland, NR § 8-1201 et seq.; COMAR 08.05.04	Nontidal wetlands	No person may conduct a regulated activity, including removal, excavation, or dredging of soil; grading; or destroying or removing plant life, without first obtaining a permit from the Department of Natural Resources. No activity may (1) degrade the aquatic ecosystem, diversity, productivity and stability, wildlife, recreational and economic value, and public welfare; (2) violate any applicable State water quality standard or the Clean Water Act; or (3) degrade surface or groundwater quality. An activity must be consistent with any applicable comprehensive watershed management plan.	Potentially applicable	Any excavation, dredging, or dumping of soil in a nontidal wetland area must comply with these regulations.
COMAR 26.08.04	Water	No person may construct a wastewater treatment plant that discharges to the waters of the State without first obtaining an NPDES permit from the Department of the Environment.	Potentially applicable	If construction of a new wastewater treatment plant at J-Field is part of the proposed action, permit discharge limits would be applicable. If wastewater from a J-Field soil washing/leaching facility is to be treated at the O-Field treatment plant or discharged through the POTW, a permit modification may be necessary.

TABLE B.1 (Cont.)

Potential ARAR	Medium	Requirements	Preliminary Determination	Remarks
Maryland Air Quality Control Act, Annotated Code of Maryland, EN § 2-101 et seq.; COMAR 26.11.01, 26.11.03, and 26.11.06	Air	State-adopted national ambient air quality standards and guidelines must be met for the following: PM <sub>10</sub> – 50 µg/m <sup>3</sup> annual mean, 150 µg/m <sup>3</sup> 24-hour average; sulfur dioxide – 80 µg/m <sup>3</sup> annual arithmetic mean, 365 µg/m <sup>3</sup> maximum 24-hour concentration; nitrogen dioxide – 100 µg/m <sup>3</sup> annual arithmetic mean; lead – 1.5 µg/m <sup>3</sup> maximum mean over calendar quarter; carbon monoxide – 10 µg/m <sup>3</sup> maximum 8-hour concentration, 40 µg/m <sup>3</sup> maximum 1-hour concentration; ozone – 235 µg/m <sup>3</sup> . For particulate matter from materials handling and construction, reasonable precautions must be taken to prevent matter from becoming airborne; i.e., use of water or chemicals for dust control and covering open-bodied vehicles transporting soils.	Potentially relevant and appropriate	These requirements do not apply directly to sources of emissions; rather, they are limitations on ambient concentrations. The site is an unconfined source in what is termed an Area III (per 26.11.01). Particulate matter must be controlled during demolition or other earth-moving activities.
COMAR 26.11.15	Air	Any installation or source that discharges Class I or II toxic air pollutants into the ambient air and must obtain a permit under this subtitle must meet the requirements of these regulations. Even if the installation need not obtain a permit, the Department of the Environment may require any source that is not subject to permit or approval to meet these requirements if the Department determines that the installation has the potential to discharge toxic air pollutants in quantities that may unreasonably endanger the public health (COMAR 26.11.15.03(A)(4)).	Potentially applicable	Potentially applicable to any emissions resulting from remedial actions, such as in-situ treatment and pump-and-treat actions. In addition, VX, GB, and mustard gas are Class I toxic air pollutants (COMAR 26.11.15.11). Potential emissions may occur in the marshes where chemical agents and UXO may exist and during emergency use of the TBP and WPP.

TABLE B.1 (Cont.)

Potential ARAR	Medium	Requirements	Preliminary Determination	Remarks
Maryland Air Quality Control Act, Annotated Code of Maryland, EN § 2-101 et seq.; COMAR 26.11.01, 26.11.03	Air	No person may construct a new source protection source, including a sewage treatment plant, without a permit to construct from the Department of Environment.	Potentially applicable	If construction of a new wastewater treatment plant at J-Field is part of the proposed action, permit discharge limits would be applicable.
COMAR 26.11.04(A)(44)	Air	A person may not operate any petroleum-contaminated soil treatment facility without first obtaining a permit to operate from the Department of the Environment.	Potentially applicable	If treatment of petroleum-contaminated soil will be part of the proposed action at J-Field, permit requirements would be applicable.
COMAR 26.11.06.06	Air	A person may not treat or dispose of waste containing VOCs in a manner that results in evaporation of greater than 20 lb/day into the atmosphere.	Potentially applicable	If treatment of contaminated soil will be part of the proposed action at J-Field, VOC emissions must meet these requirements.
Maryland Landfill Siting Law, Annotated Code of Maryland, EN § 9-209 et seq.; COMAR 26.04.07	Solid waste	General regulations for disposing of solid waste in a land-based unit, including procedures for closure and postclosure. Also, sites that act as a transfer station or processing facility for on-site disposal must follow these regulations.	Potentially applicable	Should the remedial action involve landfilling, transferring, and/or processing the waste (as defined by COMAR 26.04.07.02), these regulations must be followed.

TABLE B.1 (Cont.)

Potential ARAR	Medium	Requirements	Preliminary Determination	Remarks
COMAR 26.13.02	Hazardous waste	<p>These regulations identify and list hazardous waste and define hazardous waste.</p> <p>Maryland-listed acute hazardous wastes include the chemicals GA (tabun), GB (sarin), GD (soman), VX, L (lewisite), DM (adamtsite), HD (sulfur mustard), and T, waste military chemical warfare agents (Hazardous waste codes K991 through K999) having any of these substances as their active or principal ingredient, or mixtures of any of these substances and any characteristic or listed hazardous waste or residues from the treatment of wastes K991 through K999. Maryland-listed hazardous waste from specific sources includes residues from the treatment of the above-listed wastes, except when treated at the following:</p> <ul style="list-style-type: none"> <li>• U.S. Army Aberdeen Proving Ground/U.S. Army Chemical Research Development and Engineering Center;</li> <li>• U.S. Army Product Assurance Directorate, Aberdeen Proving Ground; or</li> <li>• U.S. Army Aberdeen Proving Ground/Medical Research Institute of Chemical Defense</li> </ul>	Potentially applicable	<p>These requirements are applicable to any removal actions if the waste at the site meets the prerequisites for definition as characteristic or listed hazardous waste.</p> <p>These requirements would apply to any interim waste storage or treatment facilities or to groundwater monitoring for such storage or treatment facilities, such as a contaminated soil waste pile.</p>

TABLE B.1 (Cont.)

Potential ARAR	Medium	Requirements	Preliminary Determination	Remarks
		under the following protocol: "To Support the Delisting of Decontaminated Liquid Chemical Surety Materials as Hazardous Waste from Specific Sources COMAR 26.13.02.167 and 26.13.02.18 K991-K999 and Residues from K991-K999" (U.S. Army Chemical Research Development and Engineering Center, Aberdeen Proving Ground, Md., 1988).		
COMAR 26.13.05	Waste treatment, storage, and disposal	General requirements are established for storage, treatment, and disposal facility location, design, and inspection; waste compatibility determination; emergency contingency plans; preparedness plans; recordkeeping; reporting; and worker training.	Potentially applicable	These requirements are potentially applicable because storage, treatment, or disposal, as defined under RCRA, may be included in the scope of a remedial action.
COMAR 26.13.05	Waste treatment, storage, and disposal	Location requirements include that (1) facilities must not be located within 61 m (200 ft) of an active fault and (2) facilities located in a 100-year floodplain must be constructed, operated, and maintained to prevent washout of any hazardous waste by a 100-year flood.	Potentially applicable	These requirements would be applicable to the siting of any waste storage or treatment facility constructed for the remedial action.
COMAR 26.13.05.06	Waste disposal	A groundwater monitoring system must be maintained for a SWMU. The concentration of a hazardous constituent in the uppermost aquifer beneath a regulated unit is not to exceed the existing background concentration or the following maximum concentration if higher than the background level, or an	Potentially applicable	These requirements are potentially applicable if the scope of a remedial action includes maintaining a surface impoundment, waste pile, land treatment, or landfill SWMU.

TABLE B.1 (Cont.)

Potential ARAR	Medium	Requirements	Preliminary Determination	Remarks						
		alternative concentration limit, unless an exemption is granted:								
		<table><tr><th>Constituent</th><th>Maximum Concentration for Groundwater Protection (<math>\mu\text{g/L}</math>)</th></tr><tr><td>Arsenic</td><td>0.05</td></tr><tr><td>Lead</td><td>0.05</td></tr></table>	Constituent	Maximum Concentration for Groundwater Protection ( $\mu\text{g/L}$ )	Arsenic	0.05	Lead	0.05		
Constituent	Maximum Concentration for Groundwater Protection ( $\mu\text{g/L}$ )									
Arsenic	0.05									
Lead	0.05									
COMAR 26.13.05.09	Waste storage	Containers used to store hazardous waste must be closed and in good condition.	Potentially applicable	These requirements may be applicable to the remedial action, container storage, and transportation of site waste that meets the prerequisites for definition as characteristic hazardous waste.						
COMAR 26.13.05.12	Waste storage	A waste pile that is inside or under a structure that provides protection from precipitation so that neither runoff nor leachate is generated need not meet the design and operating requirements of this Subpart if certain controls are established.	Potentially applicable	If contaminated soils are to be excavated and stored in a waste pile, these regulations would apply.						
COMAR 26.13.05.10	Waste storage	Wastes stored in tanks must meet specific integrity and design requirements such that leaks can be detected and spills responded to.	Potentially applicable	If contaminated wastewaters meet the definition of hazardous waste and are to be stored in tanks before transfer to the O-Field treatment plant, these regulations would apply.						
COMAR 26.13.03	Waste management	Standards for accumulating labeling, marking, and shipping hazardous waste. Also, requirements for record keeping and reporting hazardous waste activities.	Potentially applicable	If hazardous wastes are generated due to remedial actions, these wastes must be managed pursuant to these requirements.						

TABLE B.1 (Cont.)

Potential ARAR	Medium	Requirements	Preliminary Determination	Remarks
COMAR 26.13.05.07	Waste management	All treatment, storage, and disposal facilities must have a closure plan; all waste must be removed and equipment decontaminated. For certain facilities, postclosure requirements for monitoring and notification are necessary.	Potentially applicable	If storage or treatment facilities are a part of the remedial action, closure requirements must be met.
Maryland Hazardous Waste Facilities Siting Law, Annotated Code of Maryland, NR § 3-701 et seq.	Waste management	The Hazardous Waste Facilities Siting Board must issue a certificate of public necessity for siting HW facilities.	Potentially applicable	If an HW storage or treatment facility is to be constructed at J-Field, the requirements for these would be applicable.

TABLE B.2 Federal Regulations and To-Be-Considered Requirements for J-Field — Potential Contaminant-Specific Requirements

Potential ARARs	Contaminant	Medium	Requirements	Preliminary Determination	Remarks
Clean Air Act, as amended (42 USC 7401-7642); National Primary and Secondary Ambient Air Quality Standards (40 CFR Part 50)	Particulate matter	Air	Federal standards for ambient air quality include the following: sulfur dioxide – 80 $\mu\text{g}/\text{m}^3$ annual arithmetic mean, 365 $\mu\text{g}/\text{m}^3$ maximum 24-hour concentration; particulate matter – 150 $\mu\text{g}/\text{m}^3$ 24-hour average concentration, 50 $\mu\text{g}/\text{m}^3$ annual arithmetic mean; carbon monoxide – 10 $\text{mg}/\text{m}^3$ 8-hour average concentration, 35 $\text{mg}/\text{m}^3$ 1-hour average concentration; ozone – 235 $\mu\text{g}/\text{m}^3$ maximum hourly average concentration; nitrogen dioxide – 100 $\mu\text{g}/\text{m}^3$ annual arithmetic mean; lead – 1.5 $\mu\text{g}/\text{m}^3$ maximum arithmetic mean averaged over calendar quarter.	Potentially relevant and appropriate	These requirements do not apply directly to source-specific emissions; rather, they are national limitations on ambient concentrations. However, they will be addressed in controlling particulate emissions and ozone (VOC) emissions that could result from implementing a remedial action.
	Lead	Air	As for the above conditions, the standard for lead and its compounds, as elemental lead, is 1.5 $\mu\text{g}/\text{m}^3$ maximum arithmetic mean averaged over one calendar quarter.	Potentially relevant and appropriate	These requirements do not apply directly to source-specific emissions; rather, they are national limitations on ambient concentrations. However, they will be addressed in controlling lead emissions that could result from implementing a remedial action.

TABLE B.2 (Cont.)

Potential ARARs	Contaminant	Medium	Requirements	Preliminary Determination	Remarks
TSCA, as amended (15 USC 2607-2629, PL 94-469 et seq.); Poly- chlorinated Biphenyls Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions [40 CFR Part 761 (Subpart G)]	PCBs	Soil	For spills of materials contaminated with >50 ppm PCBs in unrestricted access areas (e.g., residential areas), soil within the spill area must be excavated and backfilled with soil containing <1 ppm PCBs. Contami- nated soil may be decontaminated to 10 ppm by weight by excavating a minimum of 10 in. and backfilling with soil containing <1 ppm PCBs. For spills at outdoor electrical sub- stations, the soil must be cleaned to 25 ppm by weight (as for other restricted access areas) or to 50 ppm by weight with posting of a visible notice.	To be considered	Any such spills at the site would have preceded the effective date of this requirement; hence, it is not applicable. Because the EPA policy on PCBs is not an enforceable requirement, it is not considered relevant and appropriate. However, these regulations are the guidelines used by the EPA for setting preliminary remediation goals for PCBs in soil at a remediation site.

TABLE B.3 Federal Regulations and To-Be-Considered Requirements for J-Field — Potential Location-Specific Requirements

Potential ARARs	Location	Requirements	Preliminary Determination	Remarks
Antiquity Act, Historic Sites Act [16 USC 431-433, 16 USC 461-467, 40 CFR 6.301(a)]	Land	Cultural resources, such as historic buildings and sites and natural landmarks, must be preserved on federal land to avoid adverse impacts.	Potentially applicable	Should this site be identified as a cultural resource, the requirement could be potentially applicable during a remedial action.
National Historic Preservation Act, as amended [16 USC 470 et seq., 40 CFR 6.301(b), 36 CFR Part 800]	Land	The effect of any federally assisted undertaking must be taken into account for any district, site, building, structure, or object included in or eligible for the <i>National Register of Historic Places</i> .	Potentially applicable	Should such a property be identified, the requirement would be potentially applicable during a remedial action.
Archeological and Historic Preservation Act [16 USC 469, 40 CFR 6.301(c), PL 93-291, 88 Stat. 174]	Land	Prehistoric, historic, and archeological data that might be destroyed as a result of a federal, federally assisted, or federally licensed activity or program must be preserved.	Potentially applicable	Should such data be identified, the requirement would be potentially applicable during a remedial action.
Archeological Resources Protection Act [16 USC 470(a)]	Land	A permit must be obtained if an action on public or Native American lands could affect archeological resources.	Potentially applicable	Should such resources be identified, the requirement would be potentially applicable during a remedial action.
Protection and Enhancement of the Cultural Environment (EO 11593, 40 CFR 6.301)	Land	Historic, architectural, archeological, and cultural resources must be preserved, restored, and maintained and must be evaluated for inclusion in the <i>National Register</i> .	Potentially applicable	Should such resources be identified, the requirement would be potentially applicable during a remedial action.
Endangered Species Act, as amended [16 USC 1531-1543, 50 CFR 17.402, 40 CFR 6.302(h)]	Any	Federal agencies must ensure that any action authorized, funded, or carried out by the agency is not likely to jeopardize the continued existence of any threatened or endangered species or destroy or adversely modify any critical habitat.	Potentially applicable	Should such species or habitat exist, the requirement would be potentially applicable during a remedial action.

TABLE B.3 (Cont.)

Potential ARARs	Location	Requirements	Preliminary Determination	Remarks
Fish and Wildlife Coordination Act [14 USC 441-444, 40 CFR 4.302(a)]	Any	Adequate protection of fish and wildlife resources is required when any federal department or agency proposes or authorizes any modification (e.g., diversion or channeling) of any stream or other water body or any modification of areas affecting any stream or other water body.	Potentially applicable	Should modification of any stream or any other water bodies or areas affecting water bodies be required during a remedial action, the requirement would be potentially applicable.
Bald and Golden Eagle Protection Act (16 USC 668-668d)	Any	It is unlawful to take, pursue, molest, or disturb bald eagles, their nests, or eggs.	Potentially applicable	If any remedial activities would disturb the habitat of the bald eagle, consultation with the U.S. Department of the Interior would be necessary.
Floodplain Management (EO 11988, 40 CFR Part 6)	Floodplain	Federal agencies must avoid, to the maximum extent possible, any adverse impacts associated with direct and indirect development of a floodplain.	Potentially applicable	The site is within the 100-year floodplain.
Protection of Wetlands (EO 11990, 40 CFR Part 6)	Wetlands	Federal agencies must avoid, to the extent possible, any adverse impacts associated with the destruction or loss of wetlands and the support of new construction in wetlands if a practicable alternative exists.	Potentially applicable	Wetlands exist in the affected area.

TABLE B.4 Federal Regulations and To-Be-Considered Requirements for J-Field — Potential Action-Specific Requirements

Potential ARARs	Action	Requirements	Preliminary Determination	Remarks
Hazardous Material Transportation Act, as amended (49 USC 1801-1812); DOT HAZMAT Transportation Regulations (49 CFR Parts 172-179)	Transportation	Generic requirements are established for minimizing the environmental impacts of spills or releases of hazardous materials, as are procedures for transporting hazardous waste.	Potentially applicable	These requirements are not part of an environmental law and hence are not subject to evaluation for attainment or waiver as part of the ARAR process. However, they could be pertinent to any remedial action in which hazardous waste is transported off-site. In this case, the pertinent requirements (e.g., for spill response) would be addressed during implementation.
Noise Control Act, as amended; Noise Pollution and Abatement Act (42 USC 4901 et seq.)	Detonation, heavy equipment usage	The public must be protected from noises (e.g., that could result from remedial action activities) that jeopardize health or welfare.	Potentially applicable	This requirement is potentially applicable if, during a remedial action, any heavy equipment is used.
OSHA Standards, Occupational Health and Environmental Control [29 CFR 1910.95(g)]	Noise, air	The permissible occupational exposure level for noise is 90 dBA (slow response) for an 8-hour day; with decreasing times of exposure, the levels increase to 115 dBA per 15-minute day.	Potentially applicable	These requirements are part of an employee protection law (rather than an environmental law) with which all CERCLA response actions should comply. Because this compliance is directly required, as promulgated in the NCP, these requirements are not subject to evaluation for attainment or waiver as part of the ARAR process. However, they constitute requirements for worker protection with which any remedial action will comply.

TABLE B.4 (Cont.)

Potential ARARs	Action	Requirements	Preliminary Determination	Remarks
OSHA Standards for Hazardous Waste Operations and Emergency Response (29 CFR Part 1910)	Waste management	General worker protection requirements are established, as are requirements for worker training and the development of an emergency response plan and a safety and health program for employees. In addition, procedures are established for hazardous waste operations — including decontamination and drum/container handling.	Potentially applicable	These requirements are parts of an employee protection law (rather than an environmental law) with which all CERCLA response actions should comply. Because this compliance is directly required, as promulgated in the NCP, these requirements are not subject to evaluation for attainment or waiver as part of the ARAR process. However, they constitute requirements for worker protection with which a remedial action will comply.
TSCA, as amended (15 USC 2607-2629, PL 94-469 et seq.); Polychlorinated Biphenyls Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions [40 CFR Part 761 (Subpart A)]	PCB testing	Inspection and testing are required for material contaminated with PCBs.	Potentially applicable	This requirement may be applicable to characterization of site waste for PCBs.
TSCA, as amended (15 USC 2607-2629, PL 94-499 et seq.) Polychlorinated Biphenyls Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions [40 CFR Part 761 (Subpart D)]	PCB storage and disposal	When material contaminated with PCBs >50 ppm is stored, the facility used for storage must be marked as such and must not be located in a 100-year floodplain. Disposal of material contaminated with PCBs >50 ppm requires either incineration or chemical waste landfilling at EPA-approved facilities.	Potentially applicable	These requirements are potentially applicable because disposal of material from the site that may be contaminated with PCBs may be included in the scope of the remedial action.

TABLE B.4 (Cont.)

Potential ARARs	Action	Requirements	Preliminary Determination	Remarks
Solid Waste Disposal Act, as amended (42 USC 6901 et seq.); Waste Characterization [40 CFR Part 261 (Subparts C and D)]	Solid waste	A waste must be evaluated to determine whether it is a hazardous waste, i.e., either a listed waste or a characteristic waste. A characteristic waste is determined by its (1) ignitability, (2) corrosivity, (3) reactivity, or (4) toxicity, as defined by TCLP for several contaminants. See 40 CFR Part 261.	Potentially applicable	This requirement is applicable to the characterization and management of site waste.
Standards for Owners and Operators [40 CFR Part 264 (Subparts B through E)]	Waste treatment, storage, and disposal	General requirements are established for storage, treatment, and disposal facility location, design, and inspection; waste compatibility determination; emergency contingency plans; preparedness plans; record keeping; reporting; and worker training. Location requirements include (1) facilities must not be located within 61 m (200 ft) of an active fault and (2) facilities located in a 100-year floodplain must be constructed, operated, and maintained to prevent washout of any hazardous waste by a 100-year flood.	Potentially applicable	These requirements are potentially applicable because storage, treatment, or disposal, as defined under RCRA, may be included in the scope of a remedial action.
Releases from Solid Waste Management Units [40 CFR Part 264 (Subpart F)]	Waste disposal	A groundwater monitoring system must be maintained for a SWMU. The concentration of a hazardous constituent in the uppermost aquifer beneath a regulated unit is not to exceed the existing background concentration or a listed maximum concentration if higher than the background level, or an alternative concentration limit, unless an exemption is granted.	Potentially applicable	These requirements are potentially applicable if the scope of a remedial action includes maintaining a surface impoundment, waste pile, land treatment, or landfill SWMU.
Use and Management of Containers [40 CFR Part 264 (Subpart I)]	Waste storage	Containers used to store hazardous waste must be closed and in good condition.	Potentially applicable	These requirements may be applicable to the remedial action, container storage, and transportation of site waste that meets the prerequisites for definition as characteristic hazardous waste.

TABLE B.4 (Cont.)

Potential ARARs	Action	Requirements	Preliminary Determination	Remarks
Prohibitions on Land Disposal [40 CFR Part 268 (Subpart C)]	Waste disposal	The land disposal of certain hazardous waste (e.g., contaminated soil and debris) without proper treatment is restricted, unless a treatability variance is appropriate. Such treatment must attain levels achievable by the "best demonstrated available technologies" for each hazardous constituent in the listed waste.	Potentially applicable	These requirements are potentially applicable for any remedial action at J-Field that includes disposal or any consolidation of site waste into a new disposal or storage area.
Waste Piles [40 CFR Part 264 (Subpart L)]	Waste storage	A waste pile that is inside or under a structure that provides protection from precipitation so that neither runoff nor leachate is generated need not meet the design and operating requirements of this Subpart if certain controls are established.	Potentially applicable	If contaminated soils are to be excavated and stored in a waste pile, these regulations would apply.
Containment Buildings [40 CFR Part 264 (Subpart DD)]	Waste storage	Wastes stored within a completely enclosed, self-supporting structure that has a primary barrier to contain all wastes must conform to these regulations.	Potentially applicable	If contaminated soils are to be excavated and stored in a containment building, these regulations would apply.
Tanks [40 CFR Part 264 (Subpart J)]	Waste storage	Wastes stored in tanks must meet specific integrity and design requirements such that leaks can be detected and spills responded to.	Potentially applicable	If contaminated wastewaters meet the definition of hazardous waste and are to be stored in tanks before transfer to the O-Field treatment plant, these regulations would apply.
Corrective Action for Solid Waste Management Units [40 CFR Part 264 (Subpart S)]	Waste storage	Temporary tanks and container storage areas for treatment or storage of hazardous remediation wastes generated during RCRA corrective actions may meet alternative requirements contained in this Subpart.	Potentially applicable	These regulations would apply if tank or container storage is a part of the proposed action at J-Field.
Closure and Post-Closure [40 CFR Part 264 (Subpart G)]	Waste management	All treatment, storage, and disposal facilities must have a closure plan; all waste must be removed and equipment decontaminated. For certain facilities, postclosure requirements for monitoring and notification are necessary.	Potentially applicable	If storage or treatment facilities are a part of the remedial action, closure requirements must be met.

**APPENDIX C:**  
**SAMPLING DATA FOR THE TOXIC BURNING PITS AREA**  
**JANUARY 1993–JUNE 1995**



**APPENDIX C:**  
**SAMPLING DATA FOR THE TOXIC BURNING PITS AREA**  
**JANUARY 1993–JUNE 1995**

This appendix presents the sampling data for surface water, sediment, soil, and groundwater collected at the J-Field Toxic Burning Pits (TBP) area between January 1993 and June 1995. Soil-gas measurements are not presented here. A complete data set for all J-Field areas of concern, including the TBP area, is summarized and discussed in the *Remedial Investigation Report for J-Field, Aberdeen Proving Ground, Maryland, Volume 1: Remedial Investigation Results* (Yuen, R., et al., 1996, prepared by Argonne National Laboratory, Argonne, Ill., for U.S. Army, Aberdeen Proving Ground, Md., Directorate of Safety, Health, and Environment), which is currently in draft form.

Table C.1 provides an index to the data tables.

**TABLE C.1 Index to Data Tables for the J-Field TBP Area**

Table No.	Sample Medium	Analyses	Date	Page Number
C.2a	Surface water	Volatile organics	Apr 1993	C-6
C.2b	Surface water	Volatile organics	Sept 1993	C-8
C.2c	Surface water	Volatile organics	Feb 1994	C-10
C.2d	Surface water	Volatile organics	May 1994	C-13
C.3a	Surface water	Semivolatile organics	Apr 1993	C-14
C.3b	Surface water	Semivolatile organics	Sept 1993	C-17
C.3c	Surface water	Semivolatile organics	May 1994	C-19
C.4a	Surface water	Inorganics	Sept 1993	C-21
C.4b	Surface water	Inorganics	May 1994	C-23
C.5a	Surface water	Pesticides and PCBs	Apr 1993	C-24
C.5b	Surface water	Pesticides and PCBs	Sept 1993	C-26
C.5c	Surface water	Pesticides and PCBs	May 1994	C-28
C.6a	Surface water	General chemistry	May 1994	C-29
C.6b	Surface water	Explosive compounds	May 1994	C-30
C.6c	Surface water	CWA degradation products Organosulfur compounds	Apr 1993	C-31
C.7a	Sediment	Volatile organics	Apr 1994	C-32
C.7b	Sediment	Volatile organics	June 1995	C-38
C.8a	Sediment	Semivolatile organics	Apr 1994	C-40
C.8b	Sediment	Semivolatile organics	June 1995	C-53
C.9a	Sediment	Inorganics	Apr 1994	C-55
C.9b	Sediment	Inorganics	June 1995	C-60
C.10	Sediment	Pesticides and PCBs	June 1995	C-62
C.11	Sediment	Explosive compounds	June 1995	C-63
C.12	Sediment	CWA degradation products Organosulfur compounds	June 1995	C-64
C.13a	Soil	Volatile organics	Jan 1993	C-65
C.13b	Soil	Volatile organics	Jan 1994	C-71
C.13c	Soil	Volatile organics	May 1994	C-77
C.13d	Soil	Volatile organics	May 1995	C-91
C.14a	Soil	Semivolatile organics	Jan 1993	C-102
C.14b	Soil	Semivolatile organics	Jan 1994	C-116
C.14c	Soil	Semivolatile organics	May 1994	C-126
C.14d	Soil	Semivolatile organics	May 1995	C-142
C.15a	Soil	Inorganics	Jan 1993	C-160
C.15b	Soil	Inorganics	Jan 1994	C-165
C.15c	Soil	Inorganics	May 1994	C-169
C.15d	Soil	Inorganics	May 1995	C-176

TABLE C.1 (Cont.)

Table No.	Sample Medium	Analytes	Date	Page Number
C.16a	Soil	Pesticides and PCBs	Jan 1993	C-188
C.16b	Soil	Pesticides and PCBs	May 1995	C-193
C.17	Soil	On-site analytical suite	Dec 1993– May 1994	C-195
C.18	Soil	Explosives	May 1995	C-198
C.19	Soil	CWA degradation products Organosulfur compounds	May 1995	C-200
C.20	Soil	Dioxins Total petroleum hydrocarbons	May 1995	C-202
C.21a	Groundwater	Volatile organics	May 1994	C-203
C.21b	Groundwater	Volatile organics	Sept 1994	C-208
C.22	Groundwater	Semivolatile organics	May 1994	C-211
C.23	Groundwater	Inorganics	May 1994	C-215
C.24	Groundwater	General chemistry	May 1994	C-220
C.25	Groundwater	Pesticides and PCBs	May 1994	C-223
C.26	Groundwater	Explosive compounds	June 1994	C-224
C.27	Groundwater	Radiochemistry	June 1994	C-225

TABLE C.2a Volatile Organics Analyses for Surface Water, April 1993<sup>a</sup>

Compound	Surface Water Concentrations (µg/L)										
	SW-6	SW-7	SW-8	SW-10	SW-10-Dup	SW-11	SW-12	SW-13			
Acetone	9 J	10	6 J	32 J	110 DJ	8 J	8 J	11			
Benzene	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
Bromodichloromethane	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
Bromoform	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
Bromomethane	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
2-Butanone	2 J	2 J	10 U	62 U	250 U	10 U	10 U	5 J			
Carbon disulfide	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
Carbon tetrachloride	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
Chlorobenzene	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
Chloroethane	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
Chloroform	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
Chloromethane	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
Dibromochloromethane	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
1,1-Dichloroethane	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
1,2-Dichloroethane	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
1,1,1-Dichloroethene	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
1,2-Dichloroethene (total)	10 U	19	10 U	1,400	1,400 D	16	10 U	10 U			
1,2-Dichloropropane	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
cis-1,3-Dichloropropene	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
trans-1,3-Dichloropropene	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
Ethylbenzene	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
2-Hexanone	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
4-Methyl-2-pentanone	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
Methylene chloride	10 U	1 BJ	10 U	62 U	27 BDJ	10 U	10 U	10 U			
Styrene	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
1,1,2,2-Tetrachloroethane	10 U	190	2 J	2,200	2,300 D	8 J	10 U	10 U			
Tetrachloroethene	10 U	1 J	10 U	44 J	40 DJ	10 U	10 U	10 U			
Toluene	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
1,1,1-Trichloroethane	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U			
1,1,2-Trichloroethane	10 U	13	10 U	93	250 U	1 J	10 U	10 U			

TABLE C.2a (Cont.)

Compound	Surface Water Concentrations (µg/L)									
	SW-6	SW-7	SW-8	SW-10	SW-10-Dup	SW-11	SW-12	SW-13		
Trichloroethene	10 U	59	10 U	2,100	250 U	6 J	10 U	10 U		
Vinyl chloride	10 U	10 U	10 U	62 U	250 U	2 J	10 U	10 U		
Xylenes (total)	10 U	10 U	10 U	62 U	250 U	10 U	10 U	10 U		

<sup>a</sup> Sampled by ANL and USGS, analyzed by Enesco, CLP/HSL volatile organics. Provisional data, validation in progress.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

J = estimated value.

B = analyte was found in the associated blank.

D = sample was diluted for analysis.

**TABLE C.2b Volatile Organics Analyses for  
Surface Water, September 1993<sup>a</sup>**

Compound	Surface Water Concentrations (µg/L)	
	SW-7	
Acetone	17	
Benzene	10	U
Bromodichloromethane	10	U
Bromoform	10	U
Bromomethane	10	U
2-Butanone	10	U
Carbon disulfide	10	U
Carbon tetrachloride	10	U
Chlorobenzene	10	U
Chloroethane	10	U
Chloroform	10	U
Chloromethane	10	U
Dibromochloromethane	10	U
1,1-Dichloroethane	10	U
1,2-Dichloroethane	10	U
1,1-Dichloroethene	10	U
1,2-Dichloroethene (total)	10	U
1,2-Dichloropropane	10	U
cis-1,3-Dichloropropene	10	U
trans-1,3-Dichloropropene	10	U
Ethylbenzene	10	U
2-Hexanone	10	U
4-Methyl-2-pentanone	10	U
Methylene chloride	1	BJ
Styrene	10	U
1,1,2,2-Tetrachloroethane	10	U
Tetrachloroethene	10	U
Toluene	1	J
1,1,1-Trichloroethane	10	U
1,1,2-Trichloroethane	10	U

TABLE C.2b (Cont.)

Compound	Surface Water Concentrations (µg/L)	
	SW-7	
Trichloroethene	10	U
Vinyl chloride	10	U
Xylenes (total)	10	U

<sup>a</sup> Sampled by USGS, analyzed by Enseco, CLP/HSL volatile organics. Provisional data, validation in progress.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

B = analyte was found in the associated blank.

J = estimated value.

**TABLE C.2c Volatile Organics Analyses for Surface Water, February 1994<sup>a</sup>**

[illegible]

TABLE C.2c (Cont.)

Compound	Surface Water Concentrations (µg/L)								
	Q55SW	Q55SW-Dup	Q56SW	Q58SW	Q59SW	Q60SW	Q62SW	Q65SW	Q93SW
Trichloroethene	10 U	10 U	10 U	10 U	10 U	10	7 J	10 U	6 J
Vinyl acetate	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U
Vinyl chloride	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U
m- and p-Xylene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U
o-Xylene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U

Compound	Surface Water Concentrations (µg/L)						
	Q95SW	SW-7	SW-10	SW-10-Dup	SW-11		
Acetone	22 B	10 U	10 U	30	10 U		
Benzene	10 U	10 U	10 U	10 U	10 U		
Bromodichloromethane	10 U	10 U	10 U	10 U	10 U		
Bromoform	10 U	10 U	10 U	10 U	10 U		
Bromomethane	10 U	10 U	10 U	10 U	10 U		
2-Butanone	10 U	10 U	10 U	10 U	10 U		
Carbon disulfide	10 U	10 U	10 U	10 U	10 U		
Carbon tetrachloride	10 U	10 U	10 U	10 U	10 U		
Chlorobenzene	10 U	10 U	10 U	10 U	10 U		
Chloroethane	10 U	10 U	10 U	10 U	10 U		
Chloroform	10 U	10 U	3 J	3 J	10 U		
Chloromethane	10 U	10 U	10 U	10 U	10 U		
Dibromochloromethane	10 U	10 U	10 U	10 U	10 U		
1,1-Dichloroethane	10 U	10 U	10 U	10 U	10 U		
1,2-Dichloroethane	10 U	10 U	10 U	10 U	10 U		
1,1-Dichloroethene	10 U	10 U	5 J	4 J	10 U		
cis-1,2-Dichloroethene	11	7 J	1,724	1,809	2 J		
trans-1,2-Dichloroethene	10 U	2 J	173	239	10 U		
1,2-Dichloropropane	10 U	10 U	10 U	10 U	10 U		

TABLE C.2c (Cont.)

Compound	Surface Water Concentrations (µg/L)					
	Q95SW	SW-7	SW-10	SW-10-Dup	SW-11	
cis-1,3-Dichloropropene	10 U	10 U	10 U	10 U	10 U	
trans-1,3-Dichloropropene	10 U	10 U	10 U	10 U	10 U	
Ethyl benzene	10 U	10 U	10 U	10 U	10 U	
2-Hexanone	10 U	10 U	56	59	10 U	
4-Methyl-2-pentanone	10 U	10 U	10 U	10 U	10 U	
Methylene chloride	10 U	10 U	10 U	10 U	10 U	
Styrene	10 U	10 U	10 U	10 U	10 U	
1,1,2,2-Tetrachloroethane	15	211	3,220	4,348	10 U	
Toluene	10 U	10 U	10 U	10 U	10 U	
1,1,1-Trichloroethane	10 U	10 U	10 U	10 U	10 U	
1,1,2-Trichloroethane	1 J	10 U	124	138	10 U	
Trichloroethene	15	37	3,214	3,615	2 J	
Vinyl acetate	10 U	10 U	10 U	10 U	10 U	
Vinyl chloride	10 U	10 U	26	29	10 U	
m- and p-Xylene	10 U	10 U	10 U	10 U	10 U	
o-Xylene	10 U	10 U	10 U	10 U	10 U	

<sup>a</sup> Sampled by ANL, analyzed by ANL-ACL, CLP/HSL volatile organics.

Data qualifiers:

U = analyte was analyzed for but not detected

B = analyte was found in the associated blank.

J = estimated value.

TABLE C.2d Volatile Organics Analyses for Surface Water, May 1994<sup>a</sup>

Compound	Surface Water Concentrations (µg/L)									
	SW-7		SW-10		SW-11		SW-11 Dup		SW-12	
Acetone	10	U	10	U	10	U	10	U	10	U
Benzene	10	U	10	U	10	U	10	U	10	U
Bromodichloromethane	10	U	10	U	10	U	10	U	10	U
Bromoform	10	U	10	U	10	U	10	U	10	U
Bromomethane	10	U	10	U	10	U	10	U	10	U
2-Butanone	10	U	10	U	10	U	10	U	10	U
Carbon disulfide	10	U	10	U	10	U	10	U	10	U
Carbon tetrachloride	10	U	10	U	10	U	10	U	10	U
Chlorobenzene	10	U	10	U	10	U	10	U	10	U
Chloroethane	10	U	10	U	18		12		10	U
Chloroform	10	U	10	U	10	U	10	U	10	U
Chloromethane	10	U	10	U	10	U	10	U	10	U
Dibromochloromethane	10	U	10	U	10	U	10	U	10	U
1,1-Dichloroethane	10	U	10	U	10	U	10	U	10	U
1,2-Dichloroethane	10	U	10	U	10	U	10	U	10	U
1,1-Dichloroethene	10	U	3	J	10	U	10	U	10	U
1,2-Dichloroethene (total)	10	U	1,700	E	86		56		10	U
1,2-Dichloropropane	10	U	10	U	10	U	10	U	10	U
cis-1,3-Dichloropropene	10	U	10	U	10	U	10	U	10	U
trans-1,3-Dichloropropene	10	U	10	U	10	U	10	U	10	U
Ethylbenzene	10	U	10	U	10	U	10	U	10	U
2-Hexanone	10	U	10	U	10	U	10	U	10	U
4-Methyl-2-pentanone	10	U	10	U	10	U	10	U	10	U
Methylene chloride	10	U	10	U	10	U	10	U	10	U
Styrene	10	U	10	U	10	U	10	U	10	U
1,1,2,2-Tetrachloroethane	10	U	910	E	3	J	10	U	10	U
Tetrachloroethene	10	U	10	U	10	U	10	U	10	U
Toluene	10	U	10	U	10	U	10	U	10	U
1,1,1-Trichloroethane	10	U	10	U	10	U	10	U	10	U
1,1,2-Trichloroethane	10	U	95		3	J	10	U	10	U
Trichloroethene	3	J	94		13		9	J	10	U
Vinyl chloride	10	U	26		22		14		10	U
Xylenes (total)	10	U	10	U	10	U	10	U	10	U

<sup>a</sup> Sampled by ANL, analyzed by EA Laboratories, CLP/HSL volatile organics.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

J = estimated value.

E = analyte concentration exceeded calibration range of instrument; concentration is greater than value given.

TABLE C.3a Semivolatile Organics Analyses for Surface Water, April 1993<sup>a</sup>

Compound	Surface Water Concentrations (µg/L)									
	SW-6	SW-7	SW-8	SW-9	SW-10	SW-11	SW-12	SW-13		
Acenaphthene	10	U	10	U	10	U	10	U	10	U
Acenaphthylene	10	U	10	U	10	U	10	U	10	U
Anthracene	10	U	10	U	10	U	10	U	10	U
Benz(a)anthracene	10	U	10	U	10	U	10	U	10	U
Benz(a)pyrene	10	U	10	U	10	U	10	U	10	U
Benz(b)fluoranthene	10	U	10	U	10	U	10	U	10	U
Benz(g,h,i)perylene	10	U	10	U	10	U	10	U	10	U
Benz(k)fluoranthene	10	U	10	U	10	U	10	U	10	U
Bis(2-chloroethyl)ether	10	U	10	U	10	U	10	U	10	U
Bis(2-chloroisopropyl)ether	10	U	10	U	10	U	10	U	10	U
Bis(2-ethylhexyl)phthalate	2	J	10	U	10	U	10	U	1	J
4-Bromophenyl phenyl ether	10	U	10	U	10	U	10	U	10	U
Butylbenzylphthalate	10	U	10	U	10	U	10	U	10	U
Carbazole	10	U	10	U	10	U	10	U	10	U
4-Chloro-3-methylphenol	10	U	10	U	10	U	10	U	10	U
4-Chloroaniline	10	U	10	U	10	U	10	U	10	U
cis(2-Chloroethoxy) methane	10	U	10	U	10	U	10	U	10	U
2-Chloronaphthalene	10	U	10	U	10	U	10	U	10	U
2-Chlorophenol	10	U	10	U	10	U	10	U	10	U
4-Chlorophenyl phenyl ether	10	U	10	U	10	U	10	U	10	U
Chrysene	10	U	10	U	10	U	10	U	10	U
Di-n-butylphthalate	10	U	10	U	10	U	10	U	10	U
Di-n-octyl phthalate	10	U	10	U	10	U	10	U	10	U
Dibenz[a,h]anthracene	10	U	10	U	10	U	10	U	10	U
Dibenzofuran	10	U	10	U	10	U	10	U	10	U
1,2-Dichlorobenzene	10	U	10	U	10	U	10	U	10	U
1,3-Dichlorobenzene	10	U	10	U	10	U	10	U	10	U
1,4-Dichlorobenzene	10	U	10	U	10	U	10	U	10	U
3,3'-Dichlorobenzidine	10	U	10	U	10	U	10	U	10	U
2,4-Dichlorophenol	10	U	10	U	10	U	10	U	10	U

TABLE C.3a (Cont.)

Compound	Surface Water Concentrations (µg/L)											
	SW-6	SW-7	SW-8	SW-9	SW-10	SW-11	SW-12	SW-13				
Diethylphthalate	10	U	10	U	10	U	10	U	10	U	10	U
2,4-Dimethylphenol	10	U	10	U	10	U	10	U	10	U	10	U
Dimethylphthalate	10	U	10	U	10	U	10	U	10	U	10	U
4,6-Dinitro-2-methylphenol	25	U	25	U	25	U	25	U	25	U	25	U
2,4-Dinitrophenol	25	U	25	U	25	U	25	U	25	U	25	U
2,4-Dinitrotoluene	10	U	10	U	10	U	10	U	10	U	10	U
2,6-Dinitrotoluene	10	U	10	U	10	U	10	U	10	U	10	U
Fluoranthene	10	U	10	U	10	U	10	U	10	U	10	U
Fluorene	10	U	10	U	10	U	10	U	10	U	10	U
Hexachlorobenzene	10	U	10	U	10	U	10	U	10	U	10	U
Hexachlorobutadiene	10	U	10	U	10	U	10	U	10	U	10	U
Hexachlorocyclopentadiene	10	U	10	U	10	U	10	U	10	U	10	U
Hexachloroethane	10	U	10	U	10	U	10	U	10	U	10	U
Indeno[1,2,3-c,d]pyrene	10	U	10	U	10	U	10	U	10	U	10	U
Isophorone	10	U	10	U	10	U	10	U	10	U	10	U
2-Methylnaphthalene	10	U	10	U	10	U	10	U	10	U	10	U
2-Methylphenol	10	U	10	U	10	U	10	U	10	U	10	U
4-Methylphenol	10	U	10	U	10	U	10	U	10	U	10	U
Naphthalene	10	U	10	U	10	U	10	U	10	U	10	U
2-Nitroaniline	25	U	25	U	25	U	25	U	25	U	25	U
3-Nitroaniline	25	U	25	U	25	U	25	U	25	U	25	U
4-Nitroaniline	25	U	25	U	25	U	25	U	25	U	25	U
Nitrobenzene	10	U	10	U	10	U	10	U	10	U	10	U
2-Nitrophenol	10	U	10	U	10	U	10	U	10	U	10	U
4-Nitrophenol	25	U	25	U	25	U	25	U	25	U	25	U
N-Nitrosodiphenylamine (1)	2	J	1	J	2	J	2	J	2	J	1	J
N-Nitroso-di-n-propylamine	10	U	10	U	10	U	10	U	10	U	10	U
Pentachlorophenol	25	U	25	U	25	U	25	U	25	U	25	U
Phenanthrene	10	U	10	U	10	U	10	U	10	U	10	U
Phenol	10	U	10	U	10	U	10	U	10	U	10	U

TABLE C.3a (Cont.)

Compound	Surface Water Concentrations (µg/L)									
	SW-6	SW-7	SW-8	SW-9	SW-10	SW-11	SW-12	SW-13		
Pyrene	10	U	10	U	10	U	10	U	10	U
1,2,4-Trichlorobenzene	10	U	10	U	10	U	10	U	10	U
2,4,5-Trichlorophenol	25	U	25	U	25	U	25	U	25	U
2,4,6-Trichlorophenol	10	U	10	U	10	U	10	U	10	U

<sup>a</sup> Sampled by ANL and USGS, analyzed by Enseco, CLP/HSL semivolatile organics. Provisional data, validation in progress.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

J = estimated value.

**TABLE C.3b Semivolatile Organics Analyses for  
Surface Water, September 1993<sup>a</sup>**

Compound	Surface Water Concentrations (µg/L)	
	SW-7	
Acenaphthene	10	U
Acenaphthylene	10	U
Anthracene	10	U
Bis(2-chloroethoxy)methane	10	U
Bis(2-chloroisopropyl)ether	10	U
Bis(2-chloroethyl)ether	10	U
4-Bromophenyl phenyl ether	10	U
4-Chloro-3-methylphenol	10	U
4-Chloroaniline	10	U
2-Chloronaphthalene	10	U
2-Chlorophenol	10	U
4-Chlorophenyl phenyl ether	10	U
Dibenzofuran	10	U
1,2-Dichlorobenzene	10	U
1,3-Dichlorobenzene	10	U
1,4-Dichlorobenzene	10	U
2,4-Dichlorophenol	10	U
Diethylphthalate	10	U
Dimethyl phthalate	10	U
2,4-Dimethylphenol	10	U
4,6-Dinitro-2-methylphenol	5	J
2,4-Dinitrophenol	10	U
2,4-Dinitrotoluene	10	U
2,6-Dinitrotoluene	10	U
Fluorene	10	U
Hexachlorobenzene	10	U
Hexachlorobutadiene	10	U
Hexachlorocyclopentadiene	10	U
Hexachloroethane	10	U
Isophorone	10	U
2-Methylnaphthalene	10	U
2-Methylphenol	3	J

TABLE C.3b (Cont.)

Compound	Surface Water Concentrations (µg/L)	
	SW-7	
4-Methylphenol	9	J
Naphthalene	10	U
2-Nitroaniline	10	U
3-Nitroaniline	10	U
4-Nitroaniline	10	U
Nitrobenzene	10	U
2-Nitrophenol	10	U
4-Nitrophenol	10	U
N-Nitroso-di-n-propylamine	10	U
N-Nitrosodiphenylamine	10	U
Pentachlorophenol	10	U
Phenanthrene	10	U
Phenol	6	J
1,2,4-Trichlorobenzene	10	U
2,4,5-Trichlorophenol	10	U
2,4,6-Trichlorophenol	10	U

<sup>a</sup> Sampled by ANL and USGS, analyzed by Enseco, CLP/HSL volatile organics. Provisional data, validation in progress.

Data qualifiers:

J = estimated value.

U = analyte was analyzed for but not detected; detection limit given.

TABLE C.3c Semivolatile Organics Analyses for Surface Water, May 1994<sup>a</sup>

Compound	Surface Water Concentrations (µg/L)									
	SW-7		SW-10		SW-11		SW-11-Dup		SW-12	
Acenaphthene	10	U	10	U	10	U	10	U+	10	U
Acenaphthylene	10	U	10	U	10	U	10	U+	10	U
Anthracene	10	U	10	U	10	U	10	U+	10	U
Benz[a]anthracene	10	U	10	U	10	U	10	U+	10	U
Benzo[a]pyrene	10	U	10	U	10	U	10	U+	10	U
Benzo[b]fluoranthene	10	U	10	U	10	U	10	U+	10	U
Benzo[g,h,i]perylene	10	U	10	U	10	U	10	U+	10	U
Benzo[k]fluoranthene	10	U	10	U	10	U	10	U+	10	U
Bis(2-chloroethoxy)methane	10	U	10	U	10	U	10	U+	10	U
Bis(2-chloroethyl)ether	10	U	10	U	10	U	10	U+	10	U
Bis(2-ethylhexyl)phthalate	10	U	10	U	10	U	10	U+	10	U
4-Bromophenyl phenyl ether	10	U	10	U	10	U	10	U+	10	U
Butylbenzylphthalate	10	U	10	U	10	U	10	U+	10	U
Carbazole	10	U	10	U	10	U	10	U+	10	U
4-Chloro-3-methylphenol	10	U	10	U	10	U	10	U+	10	U
4-Chloroaniline	10	U	10	U	10	U	10	U+	10	U
2-Chloronaphthalene	10	U	10	U	10	U	10	U+	10	U
2-Chlorophenol	10	U	10	U	10	U	10	U+	10	U
4-Chlorophenyl phenyl ether	10	U	10	U	10	U	10	U+	10	U
Chrysene	10	U	10	U	10	U	10	U+	10	U
Di-n-butylphthalate	10	U	10	U	10	U	10	U+	10	U
Di-n-octyl phthalate	10	U	10	U	10	U	10	U+	10	U
Dibenz[a,h]anthracene	10	U	10	U	10	U	10	U+	10	U
Dibenzofuran	10	U	10	U	10	U	10	U+	10	U
1,2-Dichlorobenzene	10	U	10	U	10	U	10	U+	10	U
1,3-Dichlorobenzene	10	U	10	U	10	U	10	U+	10	U
1,4-Dichlorobenzene	10	U	10	U	10	U	10	U+	10	U
3,3'-Dichlorobenzidine	10	U	10	U	10	U	10	U+	10	U
2,4-Dichlorophenol	10	U	10	U	10	U	10	U+	10	U
Diethylphthalate	10	U	10	U	10	U	10	U+	10	U
2,4-Dimethylphenol	10	U	10	U	10	U	10	U+	10	U
Dimethylphthalate	10	U	10	U	10	U	10	U+	10	U
2,4-Dinitrophenol	25	U	25	U	25	U	25	U+	25	U

TABLE C.3c (Cont.)

Compound	Surface Water Concentrations (µg/L)									
	SW-7		SW-10		SW-11		SW-11-Dup		SW-12	
2,4-Dinitrotoluene	10	U	10	U	10	U	10	U+	10	U
2,6-Dinitrotoluene	10	U	10	U	10	U	10	U+	10	U
Fluoranthene	10	U	10	U	10	U	10	U+	10	U
Fluorene	10	U	10	U	10	U	10	U+	10	U
Hexachlorobenzene	10	U	10	U	10	U	10	U+	10	U
Hexachlorobutadiene	10	U	10	U	10	U	10	U+	10	U
Hexachlorocyclopentadiene	10	U	10	U	10	U	10	U+	10	U
Hexachloroethane	10	U	10	U	10	U	10	U+	10	U
Indeno[1,2,3-c,d]pyrene	10	U	10	U	10	U	10	U+	10	U
Isophorone	10	U	10	U	10	U	10	U+	10	U
2-Methyl-4,6-Dinitrophenol	25	U	25	U	25	U	25	U+	25	U
2-Methylnaphthalene	10	U	10	U	10	U	10	U+	10	U
2-Methylphenol	10	U	10	U	10	U	10	U+	10	U
4-Methylphenol	10	U	10	U	10	U	10	U+	10	U
Naphthalene	10	U	10	U	10	U	10	U+	10	U
2-Nitroaniline	25	U	25	U	25	U	25	U+	25	U
3-Nitroaniline	25	U	25	U	25	U	25	U+	25	U
4-Nitroaniline	25	U	25	U	25	U	25	U+	25	U
Nitrobenzene	10	U	10	U	10	U	10	U+	10	U
2-Nitrophenol	10	U	10	U	10	U	10	U+	10	U
4-Nitrophenol	25	U	25	U	25	U	25	U+	25	U
N-Nitroso-di-n-propylamine	10	U	10	U	10	U	10	U+	10	U
N-Nitrosodiphenylamine	10	U	10	U	10	U	10	U+	10	U
2,2'-Oxybis(1-Chloropropane)	10	U	10	U	10	U	10	U+	10	U
Pentachlorophenol	25	U	25	U	25	U	25	U+	25	U
Phenanthrene	10	U	10	U	10	U	10	U+	10	U
Phenol	10	U	10	U	10	U	10	U+	10	U
Pyrene	10	U	10	U	10	U	10	U+	10	U
1,2,4-Trichlorobenzene	10	U	10	U	10	U	10	U+	10	U
2,4,5-Trichlorophenol	25	U	25	U	25	U	25	U+	25	U
2,4,6-Trichlorophenol	10	U	10	U	10	U	10	U+	10	U

<sup>a</sup> Sampled by ANL, analyzed by EA Laboratories, CLP/HSL semivolatile organics.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

+ = surrogate recoveries were outside QC limit(s).

**TABLE C.4a Inorganic Analyses for Surface Water, September 1993<sup>a</sup>**

[illegible]

TABLE C.4a (Cont.)

Parameter	Surface Water Concentrations (µg/L)	
	SW-14	SW-15
<b>Metals</b>		
Aluminum	1,090	237
Antimony	54 U	54 U
Arsenic	3.4 B	2.9 B
Barium	173 B	173 B
Beryllium	3.4 U	3.4 U
Cadmium	2.5 U	2.5 U
Calcium	101,000	99,500
Chromium	5.2 U	5.2 U
Cobalt	3.6 U	3.6 U
Copper	4.0 U	4.7 B
Iron	2,900	1,310
Lead	2.4 B	1.0 U
Magnesium	218,000	224,000
Manganese	2,530	2,620
Mercury	0.05 U	0.05 U
Nickel	8.0 U	8.0 U
Potassium	53,900	61,300
Selenium	1.0 U	1.0 U
Silver	5.6 U	5.6 U
Sodium	1,530,000	1,620,000
Thallium	5.0 U	5.0 U
Vanadium	9.1 B	6.9 B
Zinc	57.1	30
<b>Other parameter</b>		
Cyanide	10 U	10 U

<sup>a</sup> Sampled by USGS, analyzed by Ensco, CLPTAL metals and cyanide.  
Provisional data, validation in progress.

Data qualifiers:

U = analyte was analyzed for but not detected, detection limit given.

B = reported value is less than the contract-required detection limit but greater than the instrument detection limit.

TABLE C.4b Inorganic Analyses for Surface Water, May 1994<sup>a</sup>

Metal	Surface Water Concentrations (µg/L)									
	SW-7		SW-10		SW-11		SW-11 Dup		SW-12	
Aluminum	429		226		18,000		2,000		731	
Antimony	20	U	20	U	32.9	B	20	U	20	U
Arsenic	2.4	B	6.4	B	36.3		9.4	B	18.2	
Barium	69.5	B	43.4	B	559		167	B	234	
Beryllium	1	U	1	U	1	U	1	U	1	U
Cadmium	3	U	3	U	4	U	4	U	4	U
Calcium	35,800		106,000		98,700		90,700		33,800	
Chromium	5	U	5.6	B	64.8		7.6	B	8	B
Cobalt	8.4	B	9.7	B	7	U	7.0	U	7	U
Copper	3	U	3	U	525		57.6		105	
Iron	21,100		3,470		128,000		27,800		13,000	
Lead	2.1	B	6.5		1,590		210	S	169	
Magnesium	44,500		28,500		110,000		97,300		68,900	
Manganese	664		239		1,080		759		496	
Mercury	0.2	U	0.2	U	1.7		0.31		0.2	U
Nickel	12	U	12	U	22.4	B	12	U	12.1	B
Potassium	12,800		4,430	B	17,000		15,300		9,000	
Selenium	1	UW	1	UW	1	U	1	UW	1	U
Silver	4	U	5.3	B	4	U	4	U	4	U
Sodium	347,000		127,000		228,000		197,000		129,000	
Thallium	2.00	UNW	2	UNW	2	U	2	UW	2	U
Vanadium	6.3	B	5	U	42.7	B	5	U	6.8	B
Zinc	11.8	B*@	18.4	B*@	4,040		1,670	E	968	

<sup>a</sup> Sampled by ANL, analyzed by EA Laboratories, CLP/TAL metals.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

B = reported value is less than contract-required detection limit but greater than the instrument detection limit.

W = postdigestion spike out of control limits.

N = spiked sample recovery is not within control limits.

\* = duplicate analyses are not within control limits.

@ = percent RPD of sample duplicate was outside of control limits.

S = reported value is determined by method of standard additions.

E = reported value is estimated because of the presence of interference.

TABLE C.5a Pesticide and Polychlorinated Biphenyl (PCB) Analyses for Surface Water, April 1993<sup>a</sup>

Compound	Surface Water Concentrations (µg/L)							
	SW-6	SW-7	SW-9	SW-10	SW-11	SW-12	SW-13	
Aldrin	0.05	U	0.05	U	0.05	U	0.05	U
Aroclor 1016	1.00	U	1.00	U	1.00	U	1.00	U
Aroclor 1221	2.00	U	2.00	U	2.00	U	2.00	U
Aroclor 1232	1.00	U	1.00	U	1.00	U	1.00	U
Aroclor 1242	1.00	U	1.00	U	1.00	U	1.00	U
Aroclor 1248	1.00	U	1.00	U	1.00	U	1.00	U
Aroclor 1254	1.00	U	1.00	U	1.00	U	1.00	U
Aroclor 1260	1.00	U	1.00	U	1.00	U	1.00	U
α-BHC	0.05	U	0.05	U	0.05	U	0.05	U
β-BHC	0.05	U	0.05	U	0.05	U	0.05	U
δ-BHC	0.05	U	0.05	U	0.05	U	0.05	U
γ-BHC (Lindane)	0.05	U	0.05	U	0.05	U	0.05	U
α-Chlordane	0.05	U	0.05	U	0.05	U	0.05	U
γ-Chlordane	0.05	U	0.05	U	0.05	U	0.05	U
4,4'-DDD	0.10	U	0.10	U	0.10	U	0.10	U
4,4'-DDE	0.10	U	0.10	U	0.10	U	0.10	U
4,4'-DDT	0.10	U	0.10	U	0.10	U	0.10	U
Dieldrin	0.10	U	0.10	U	0.10	U	0.10	U
Endosulfan I	0.05	U	0.05	U	0.05	U	0.05	U
Endosulfan sulfate	0.10	U	0.10	U	0.10	U	0.10	U
Endosulfan II	0.10	U	0.10	U	0.10	U	0.10	U

TABLE C.5a (Cont.)

Compound	Surface Water Concentrations (µg/L)							
	SW-6	SW-7	SW-9	SW-10	SW-11	SW-12	SW-13	
Endrin	0.10	U	0.10	U	0.10	U	0.10	U
Endrin aldehyde	0.10	U	0.10	U	0.10	U	0.10	U
Endrin ketone	0.10	U	0.10	U	0.10	U	0.10	U
Heptachlor	0.05	U	0.05	U	0.05	U	0.05	U
Heptachlor epoxide	0.05	U	0.05	U	0.05	U	0.05	U
Methoxychlor	0.50	U	5.00	U	0.50	U	0.50	U
Toxaphene	5.00	U	5.00	U	5.00	U	5.00	U

<sup>a</sup> Sampled by ANL and USGS, analyzed by Enseco, CLP/HSL organochloride pesticides and PCBs. Provisional data, validation in progress.

Data qualifier:

U = analyte was analyzed for but not detected.

**TABLE C.5b Pesticide and PCB  
Analyses for Surface Water,  
September 1993<sup>a</sup>**

Compound	Surface Water Concentrations (µg/L)	
	SW-7	
Aldrin	0.05	U
Aroclor 1016	1.00	U
Aroclor 1221	2.00	U
Aroclor 1232	1.00	U
Aroclor 1242	1.00	U
Aroclor 1248	1.00	U
Aroclor 1254	1.00	U
Aroclor 1260	1.00	U
α-BHC	0.05	U
β-BHC	0.05	U
δ-BHC	0.05	U
γ-BHC (Lindane)	0.05	U
α-Chlordane	0.05	U
γ-Chlordane	0.05	U
4,4'-DDD	0.10	U
4,4'-DDE	0.10	U
4,4'-DDT	0.10	U
Dieldrin	0.10	U
Endosulfan I	0.05	U
Endosulfan sulfate	0.10	U
Endosulfan II	0.10	U
Endrin	0.10	U
Endrin aldehyde	0.10	U
Endrin ketone	0.10	U

TABLE C.5b (Cont.)

Compound	Surface Water Concentrations (µg/L)	
	SW-7	
Heptachlor	0.05	U
Heptachlor epoxide	0.05	U
Methoxychlor	0.50	U
Toxaphene	5.00	U

<sup>a</sup> Sampled by USGS, analyzed by Enseco, CLP/HSL organochloride pesticides and PCBs. Provisional data, validation in progress.

Data qualifier:

U = analyte was analyzed for but not detected; detection limit given.

TABLE C.5c Pesticide and PCB Analyses for Surface Water, May 1994<sup>a</sup>

Compound	Surface Water Concentrations (µg/L)									
	SW-7		SW-10		SW-11		SW-11 Dup		SW-12	
Aldrin	0.05	U+	0.05	U+	0.05	U+	0.05	U+	0.05	U+
Aroclor 1016	1	U+	1	U+	1	U+	1	U+	1	U+
Aroclor 1221	2	U+	2	U+	2	U+	2	U+	2	U+
Aroclor 1232	1	U+	1	U+	1	U+	1	U+	1	U+
Aroclor 1242	1	U+	1	U+	1	U+	1	U+	1	U+
Aroclor 1248	1	U+	1	U+	1	U+	1	U+	1	U+
Aroclor 1254	1	U+	1	U+	1	U+	1	U+	1	U+
Aroclor 1260	1	U+	1	U+	1	U+	1	U+	1	U+
α-BHC	0.05	U+	0.05	U+	0.05	U+	0.05	U+	0.05	U+
β-BHC	0.05	U+	0.05	U+	0.05	U+	0.05	U+	0.05	U+
δ-BHC	0.05	U+	0.05	U+	0.05	U+	0.05	U+	0.05	U+
γ-BHC	0.05	U+	0.05	U+	0.05	U+	0.05	U+	0.05	U+
α-Chlordane	0.05	U+	0.05	U+	0.05	U+	0.05	U+	0.05	U+
γ-Chlordane	0.05	U+	0.05	U+	0.05	U+	0.05	U+	0.05	U+
4,4'-DDD	0.10	U+	0.10	U+	0.10	U+	0.10	U+	0.10	U+
4,4'-DDE	0.10	U+	0.10	U+	0.10	U+	0.10	U+	0.10	U+
4,4'-DDT	0.10	U+	0.10	U+	0.10	U+	0.10	U+	0.10	U+
Dieldrin	0.10	U+	0.10	U+	0.10	U+	0.10	U+	0.10	U+
Endosulfan I	0.05	U+	0.05	U+	0.05	U+	0.05	U+	0.05	U+
Endosulfan sulfate	0.10	U+	0.10	U+	0.10	U+	0.10	U+	0.10	U+
Endosulfan II	0.10	U+	0.10	U+	0.10	U+	0.10	U+	0.10	U+
Endrin	0.10	U+	0.10	U+	0.10	U+	0.10	U+	0.10	U+
Endrin aldehyde	0.10	U+	0.10	U+	0.10	U+	0.10	U+	0.10	U+
Endrin ketone	0.10	U+	0.10	U+	0.10	U+	0.10	U+	0.10	U+
Heptachlor	0.05	U+	0.05	U+	0.05	U+	0.05	U+	0.05	U+
Heptachlor epoxide	0.05	U+	0.05	U+	0.05	U+	0.05	U+	0.05	U+
Methoxychlor	0.50	U+	0.50	U+	0.50	U+	0.50	U+	0.50	U+
Toxaphene	5	U+	5	U+	5	U+	5	U+	5	U+

<sup>a</sup> Sampled by ANL, analyzed by EA Laboratories, CLP/HSL organochloride pesticides and PCBs.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

+ = surrogate recoveries were outside QC limit(s).

TABLE C.6a General Chemistry Analyses for Surface Water, May 1994<sup>a</sup>

Analyte	Surface Water Concentrations (mg/L) <sup>b</sup>									
	SW-7		SW-10		SW-11		SW-11 Dup		SW-12	
Alkalinity	60.8		222		207		210		248	
Bicarbonate	60.8		222		206		210		247	
Bromide	3.0		1.3		1.3		1.3		1.0	
Carbonate	1.0	U	1.0	U	1.0	U	1.0	U	1.0	U
Chloride	810		270		720		630		330	
Cyanide	0.01	U	0.01	U	0.01	U	0.01	U *	0.01	U
Fluoride	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U
Nitrate	0.1	U	0.1	U	0.1	U	3.6		2.2	
Nitrite	5.0	U	2.5	U	2.5	U	2.5	U	0.5	U
Orthophosphate	0.1	U	0.1	U	0.1	U	0.1	U	0.1	U
pH (SI)	6.2		7.0		6.6	+	6.8	+	7.1	+
Phosphate, total	1.9		0.13		2.7		0.57		0.75	
Sulfate	64		100		190		190		37	
TDS	1,400		775		1,510		1,460		790	
Turbidity (NTU)	7.5		2.6		69		28		13.8	
Total organic halogens (µg/L)	120		2,600		NT		NT		NT	

<sup>a</sup> Sampled by ANL, analyzed by EA Laboratories, CLP/TAL metals.

<sup>b</sup> Units are mg/L, except where indicated.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

+

\* = cyanide sample was not preserved in field with NaOH.

NT = not tested.

**TABLE C.6b Explosive Compounds Analyses for Surface Water, May 1994<sup>a</sup>**

Compound	Surface Water Concentrations (µg/L)									
	SW-7		SW-10		SW-11		SW-11 Dup		SW-12	
1,3-DNB	0.62	U	0.62	U	0.62	U	0.62	U	0.62	U
2,4-DNT	0.43	U	0.43	U	0.43	U	0.43	U	0.43	U
2,6-DNT	1.2	U	1.2	U	1.2	U	1.2	U	1.2	U
HMX	1.1	U	1.1	U	1.1	U	1.1	U	1.1	U
NB	0.45	U	0.45	U	0.45	U	0.45	U	0.45	U
RDX	1.7	U	1.7	U	0.48	J I	0.98	J I	1.0	J I
TETRYL	1.9	U	1.9	U	1.9	U	1.9	U	1.9	U
1,3,5-TNB	0.86	U	0.86	U	0.86	U	0.86	U	0.86	U
2,4,6-TNT	1.3	U	1.3	U	1.3	U	1.3	U	1.3	U

<sup>a</sup> Sampled by ANL, analyzed by EA Laboratories.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

J = estimated value.

I = interferences in sample cause the quantitation and/or identification to be suspect.

**TABLE C.6c Chemical Warfare Agent (CWA) Degradation Products and Organosulfur Compounds Analyses for Surface Water, April 1993<sup>a</sup>**

Compound	Surface Water Concentrations (µg/L)							
	SW-7		SW-10		SW-12		SW-13	
CWA degradation products								
Diisopropyl methylphosphonate (DIMP)	0.43	U	0.45		0.43	U	0.43	U
Dimethyl methylphosphate (DMMP)	0.2	U	0.2	U	0.2	U	0.2	U
Thiodiglycol	10	U	10	U	10	U	10	U
Organosulfur compounds								
Benzothiozole (BTZ)	5.22	U	5.22	U	5.22	U	5.22	U
p-Chlorophenylmethyl sulfide (CPMS)	6.04	U	6.04	U	6.04	U	6.04	U
p-Chlorophenylmethyl sulfone (CPMSO2)	6.43	U	6.43	U	6.43	U	6.43	U
p-Chlorophenylmethyl sulfoxide (CPMSO)	11.9	U	11.9	U	11.9	U	11.9	U
Dimethyl disulfide (DMDS)	0.55	U	0.55	U	0.55	U	0.55	U
Dithiane (DITH)	1.57	U	2.49		1.57	U	1.57	U
1,1 Oxathiane (OXAT)	2.55	U	12.2		2.55	U	2.55	U

<sup>a</sup> Sampled by ANL and USGS, analyzed by EA Laboratories.

Data qualifier:

U = analyte was analyzed for but not detected; detection limit given.

TABLE C.7a Volatile Organics Analyses for Sediment Borings, April 1994<sup>a</sup>

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals						
	BOR1-1 (6-8 ft)	BOR1-2 (8-10 ft)	BOR1-3 (10-12 ft)	BOR2-1 (3-5 ft)	BOR2-2 (5-8 ft)	BOR2-3 (8-10 ft)	BOR3-1 (6-8 ft)
Acetone	15 U	43 B	14 U	1,100 *	40 B	12 U	17 B
Benzene	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
Bromodichloromethane	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
Bromoform	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
Bromomethane	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
2-Butanone	15 U	13 U	12 U	150 *	14 U	12 U	13 U
Carbon disulfide	15 U	13 U	12 U	26 U*	14 U	12 U	7 J
Carbon tetrachloride	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
Chlorobenzene	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
Chloroethane	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
Chloroform	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
Chloromethane	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
Dibromochloromethane	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
1,1-Dichloroethane	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
1,2-Dichloroethane	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
1,1-Dichloroethene	15 U	13 U	12 U	26 U*	14 U	12 U	18
1,2-Dichloroethene (total)	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
1,2-Dichloropropane	15 U	13 U	12 U	26 U*	14 U	12 U	89
cis-1,3-Dichloropropene	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
trans-1,3-Dichloropropene	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
Ethylbenzene	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
2-Hexanone	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
4-Methyl-2-pentanone	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
Methylene chloride	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
Styrene	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
1,1,2,2-Tetrachloroethane	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
Tetrachloroethene	15 U	13 U	12 U	26 U*	14 U	12 U	13 U
Toluene	15 U	13 U	12 U	150 *	20	12 U	13 U
1,1,1-Trichloroethane	15 U	13 U	12 U	26 U*	14 U	12 U	13 U

TABLE C.7a (Cont.)

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals					
	BOR1-1 (6-8 ft)	BOR1-2 (8-10 ft)	BOR1-3 (10-12 ft)	BOR2-1 (3-5 ft)	BOR2-2 (5-8 ft)	BOR3-1 (6-8 ft)
1,1,2-Trichloroethane	15 U	13 U	12 U	26 U*	14 U	13 U
Trichloroethene	15 U	13 U	12 U	26 U*	14 U	170 U
Vinyl chloride	15 U	13 U	12 U	26 U*	14 U	13 U
Xylenes (total)	15 U	13 U	12 U	26 U*	14 U	13 U

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals					
	BOR3-2 (8-10 ft)	BOR4-1 (5-8 ft)	BOR4-2 (8-10 ft)	BOR5-1 (2-4 ft)	BOR5-2 (4-6 ft)	BOR5-3 (6-8 ft)
Acetone	12 U	20 U	19 B*	12 U	16 B	12 U
Benzene	12 U	20 U	13 U*	12 U	12 U	12 U
Bromodichloromethane	12 U	20 U	13 U*	12 U	12 U	12 U
Bromoform	12 U	20 U	13 U*	12 U	12 U	12 U
Bromomethane	12 U	20 U	13 U*	12 U	12 U	12 U
2-Butanone	12 U	20 U	13 U*	12 U	12 U	12 U
Carbon disulfide	12 U	20 U	13 U*	12 U	12 U	12 U
Carbon tetrachloride	12 U	20 U	13 U*	12 U	12 U	12 U
Chlorobenzene	12 U	20 U*	13 U*	12 U	12 U	12 U
Chloroethane	12 U	20 U	13 U*	12 U	12 U	12 U
Chloroform	12 U	20 U	13 U*	12 U	12 U	12 U
Chloromethane	12 U	20 U	13 U*	12 U	12 U	12 U
Dibromochloromethane	12 U	20 U	13 U*	12 U	12 U	12 U
1,1-Dichloroethane	12 U	20 U	13 U*	12 U	12 U	12 U
1,2-Dichloroethane	12 U	20 U	13 U*	12 U	12 U	12 U
1,1,1-Dichloroethene	12 U	20 U	13 U*	12 U	12 U	12 U
1,2-Dichloroethene (total)	12 U	2,200	360 *	12 U	12 U	12 U
1,2-Dichloropropane	12 U	20 U	13 U*	12 U	12 U	12 U
cis-1,3-Dichloropropene	12 U	20 U	13 U*	12 U	12 U	12 U
trans-1,3-Dichloropropene	12 U	20 U	13 U*	12 U	12 U	12 U

TABLE C.7a (Cont.)

Compound	Sediment Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals						
	BOR3-2 (8-10 ft)	BOR4-1 (5-8 ft)	BOR4-2 (8-10 ft)	BOR5-1 (2-4 ft)	BOR5-2 (4-6 ft)	BOR5-3 (6-8 ft)	
Ethylbenzene	12 U	20 U*	13 U*	12 U	12 U	12 U	
2-Hexanone	12 U	20 U*	13 U*	12 U	12 U	12 U	
4-Methyl-2-pentanone	12 U	20 U*	13 U*	12 U	12 U	12 U	
Methylene chloride	12 U	20 U	13 U*	12 U	12 U	12 U	
Styrene	12 U	20 U*	13 U*	12 U	12 U	12 U	
1,1,2,2-Tetrachloroethane	31	99 *	13 U*	12 U	12 U	12 U	
Tetrachloroethene	12 U	20 U*	13 U*	12 U	12 U	12 U	
Toluene	12 U	20 U*	13 U*	12 U	12 U	12 U	
1,1,1-Trichloroethane	12 U	20 U	13 U*	12 U	12 U	12 U	
1,1,2-Trichloroethane	10 J	76	13 U*	12 U	12 U	12 U	
Trichloroethene	91	12 J	13 U*	12 U	12 U	12 U	
Vinyl chloride	12 U	54	13 U*	12 U	12 U	12 U	
Xylenes (total)	12 U	20 U*	13 U*	12 U	12 U	12 U	

Compound	Sediment Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals						
	BOR5-4 (8-10 ft)	BOR5-4Dup (8-10 ft)	BOR6-1 (2-4 ft)	BOR6-2 (4-6 ft)	BOR6-3 (6-8 ft)	BOR6-4 (8-10 ft)	BOR7-1 (2-4 ft)
Acetone	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Benzene	12 U	12 U+	3 J	12 U	4 J	12 U	14 U
Bromodichloromethane	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Bromoform	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Bromomethane	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
2-Butanone	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Carbon disulfide	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Carbon tetrachloride	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Chlorobenzene	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Chloroethane	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Chloroform	12 U	12 U+	12 U	12 U	12 U	12 U	14 U

TABLE C.7a (Cont.)

Sediment Concentrations (µg/kg) at Various Depth Intervals							
Compound	BOR5-4 (8-10 ft)	BOR5-4Dup (8-10 ft)	BOR6-1 (2-4 ft)	BOR6-2 (4-6 ft)	BOR6-3 (6-8 ft)	BOR6-4 (8-10 ft)	BOR7-1 (2-4 ft)
Chloromethane	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Dibromochloromethane	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
1,1-Dichloroethane	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
1,2-Dichloroethane	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
1,1-Dichloroethene	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
1,2-Dichloroethene (total)	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
1,2-Dichloropropane	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
cis-1,3-Dichloropropene	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
trans-1,3-Dichloropropene	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Ethylbenzene	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
2-Hexanone	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
4-Methyl-2-pentanone	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Methylene chloride	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Styrene	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
1,1,2,2-Tetrachloroethane	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Tetrachloroethene	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Toluene	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
1,1,1-Trichloroethane	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
1,1,2-Trichloroethane	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Trichloroethene	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Vinyl chloride	12 U	12 U+	12 U	12 U	12 U	12 U	14 U
Xylenes (total)	12 U	12 U+	12 U	12 U	12 U	12 U	14 U

TABLE C.7a (Cont.)

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals								
	BOR7-2 (4-6 ft)	BOR7-3 (6-8 ft)	BOR7-4 (8-10 ft)	BOR8-1 (0-2 ft)	BOR8-2 (2-4 ft)	BOR8-3 (4-6 ft)	BOR8-3Dup (4-6 ft)	BOR8-4 (6-8 ft)	BOR8-5 (8-10 ft)
Acetone	12	U	1,100	B	12	U	23	B	88
Benzene	12	U	12	U	12	U	12	U	12
Bromodichloromethane	12	U	12	U	12	U	12	U	12
Bromoform	12	U	12	U	12	U	12	U	12
Bromomethane	12	U	12	U	12	U	12	U	12
2-Butanone	12	U	180		12	U	12	U	12
Carbon disulfide	12	U	12	U	12	U	12	U	12
Carbon tetrachloride	12	U	12	U	12	U	12	U	12
Chlorobenzene	12	U	12	U	12	U	12	U	12
Chloroethane	12	U	12	U	12	U	12	U	12
Chloroform	12	U	12	U	12	U	12	U	12
Chloromethane	12	U	12	U	12	U	12	U	12
Dibromochloromethane	12	U	12	U	12	U	12	U	12
1,1-Dichloroethane	12	U	12	U	12	U	12	U	12
1,2-Dichloroethane	12	U	12	U	12	U	12	U	12
1,1-Dichloroethene	12	U	12	U	12	U	12	U	12
1,2-Dichloroethene (total)	12	U	12	U	12	U	12	U	12
1,2-Dichloropropane	12	U	12	U	12	U	12	U	12
cis-1,3-Dichloropropene	12	U	12	U	12	U	12	U	12
trans-1,3-Dichloropropene	12	U	12	U	12	U	12	U	12
Ethylbenzene	12	U	12	U	12	U	12	U	12
2-Hexanone	12	U	12	U	12	U	12	U	12
4-Methyl-2-pentanone	12	U	12	U	12	U	12	U	12
Methylene chloride	12	U	12	U	12	U	12	U	12
Styrene	12	U	12	U	12	U	12	U	12
1,1,2,2-Tetrachloroethane	12	U	12	U	12	U	12	U	12
Tetrachloroethene	12	U	12	U	12	U	12	U	12
Toluene	12	U	12	U	12	U	12	U	12

TABLE C.7a (Cont.)

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals								
	BOR7-2 (4-6 ft)	BOR7-3 (6-8 ft)	BOR7-4 (8-10 ft)	BOR8-1 (0-2 ft)	BOR8-2 (2-4 ft)	BOR8-3 (4-6 ft)	BOR8-3Dup (4-6 ft)	BOR8-4 (6-8 ft)	BOR8-5 (8-10 ft)
1,1,1-Trichloroethane	12 U	12 U	12 U	13 U	12 U	12 U	12 U	12 U	12 U
1,1,2-Trichloroethane	12 U	12 U	12 U	13 U	12 U	12 U	12 U	12 U	12 U
Trichloroethene	12 U	12 U	12 U	13 U	12 U	12 U	12 U	12 U	12 U
Vinyl chloride	12 U	12 U	12 U	13 U	12 U	12 U	12 U	12 U	12 U
Xylenes (total)	12 U	12 U	12 U	13 U	12 U	12 U	12 U	12 U	12 U

<sup>a</sup> Sampled by ANL, analyzed by Weston Gulf Coast, CLP/HSL volatile organics.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

B = analyte found in associated blank.

\* = internal standard area counts are outside QC limits.

J = estimated value.

+ = surrogate recoveries were outside QC limit(s).

TABLE C.7b Volatile Organics Analyses for Sediment Borings, June 1995<sup>a</sup>

Compound	Sediment Concentrations (µg/kg) at 0-6 in.							
	TPSED 1	TPSED 2	TPSED 3	TPSED 4	TPSED 5	TPSED 6	TPSED 7	TPSED 8
Acetone	61	170	200	120	20	22	2	14
Benzene	32	U	24	24	20	22	15	14
Bromodichloromethane	32	U	24	U	20	22	U	14
Bromoform	32	U	24	U	20	22	15	14
Bromomethane	32	U	24	U	20	22	15	14
2-Butanone	32	U	24	200	20	22	15	14
Carbon disulfide	32	U	24	24	20	22	15	14
Carbon tetrachloride	32	U	24	U	20	22	15	14
Chlorobenzene	32	U	24	24	20	22	15	14
Chloroethane	32	U	24	U	20	22	15	14
Chloroform	32	U	24	24	20	22	15	14
Chloromethane	32	U	24	U	20	22	15	14
Dibromochloromethane	32	U	24	24	20	22	15	14
1,1-Dichloroethane	32	U	24	U	20	22	15	14
1,2-Dichloroethane	32	U	24	U	20	22	3	14
1,1-Dichloroethene	32	U	24	U	20	22	15	14
1,2-Dichloroethene (total)	32	U	45	24	20	22	4	14
1,2-Dichloropropane	32	U	24	U	20	22	15	14
cis-1,3-Dichloropropene	32	U	24	U	20	22	15	14
trans-1,3-Dichloropropene	32	U	24	U	20	22	15	14
Ethyl benzene	32	U	24	U	20	22	15	14
2-Hexanone	32	U	24	U	20	22	3	14
4-Methyl-2-pentanone	32	U	24	U	20	22	2	14
Methylene chloride	32	U	24	13	6	13	9	7

TABLE C.7b (Cont.)

Compound	Sediment Concentrations (µg/kg) at 0-6 in.							
	TPSED 1	TPSED 2	TPSED 3	TPSED 4	TPSED 5	TPSED 6	TPSED 7	TPSED 8
Styrene	32 U	17 U	24 U	24 U	20 U	22 U	15 U	14 U
1,1,2,2-Tetrachloroethane	32 U	17 U	23 J	24 U	20 U	22 U	6	14 U
Tetrachloroethene	32 U	17 U	24 U	24 U	20 U	22 U	15 U	14 U
Toluene	32 U	2 J	24 U	7	20 U	22 U	15 U	14 U
1,1,1-Trichloroethane	32 U	17 U	24 U	24 U	20 U	22 U	15 U	14 U
1,1,2-Trichloroethane	32 U	17 U	4 J	24 U	20 U	22 U	9	14 U
Trichloroethene	32 U	11 J	29	24 U	20 U	22 U	15	14 U
Vinyl chloride	32 U	54	18 J	24 U	20 U	22 U	15 U	14 U
Xylenes (total)	32 U	17 U	24 U	24 U	20 U	22 U	15 U	14 U

<sup>a</sup> Sampled by ANL and analyzed by GP Environmental Services.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

B = analyte was found in the associated blank.

J = estimated value.

TABLE C.8a Semivolatile Organics Analyses for Sediment Borings, April 1994<sup>a</sup>

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals					
	BOR1-1 (6-8 ft)	BOR1-2 (8-10 ft)	BOR1-3 (10-12 ft)	BOR2-1 (3-5 ft)	BOR2-2 (5-8 ft)	BOR2-3 (8-10 ft)
Acenaphthene	480 U	440 U	410 U	850 U	460 U	400 U
Acenaphthylene	480 U	440 U	410 U	850 U	460 U	400 U
Anthracene	480 U	440 U	410 U	850 U	460 U	400 U
Benz[a]anthracene	480 U	440 U	410 U	850 U	460 U	400 U
Benzo[a]pyrene	480 U	440 U	410 U	850 U	460 U	400 U
Benzo[b]fluoranthene	480 U	440 U	410 U	850 U	460 U	400 U
Benzo[g,h,i]perylene	480 U	440 U	410 U	850 U	460 U	400 U
Benzo[k]fluoranthene	480 U	440 U	410 U	850 U	460 U	400 U
Bis(2-chloroethoxy)methane	480 U	440 U	410 U	850 U	460 U	400 U
Bis(2-chloroethyl)ether	480 U	440 U	410 U	850 U	460 U	400 U
Bis(2-chloroisopropyl)ether	480 U	440 U	410 U	850 U	460 U	400 U
Bis(2-ethylhexyl)phthalate	180 J	78 J	140 J	46 J	140 J	43 J
4-Bromophenyl phenyl ether	480 U	440 U	410 U	850 U	460 U	400 U
Butylbenzylphthalate	480 U	440 U	410 U	850 U	460 U	400 U
Carbazole	480 U	440 U	410 U	850 U	460 U	400 U
4-Chloro-3-methylphenol	480 U	440 U	410 U	850 U	460 U	400 U
4-Chloroaniline	480 U	440 U	410 U	850 U	460 U	400 U
2-Chloronaphthalene	480 U	440 U	410 U	850 U	460 U	400 U
2-Chlorophenol	480 U	440 U	410 U	850 U	460 U	400 U
4-Chlorophenyl phenyl ether	480 U	440 U	410 U	850 U	460 U	400 U
Chrysene	480 U	440 U	410 U	850 U	460 U	400 U
Di-n-butylphthalate	150 J	130 J	120 J	260 J	140 J	130 J
Di-n-octyl phthalate	480 U	440 U	410 U	850 U	460 U	400 U
Dibenz[a,h]anthracene	480 U	440 U	410 U	850 U	460 U	400 U
Dibenzofuran	480 U	440 U	410 U	850 U	460 U	400 U
1,2-Dichlorobenzene	480 U	440 U	410 U	850 U	460 U	400 U
1,3-Dichlorobenzene	480 U	440 U	410 U	850 U	460 U	400 U
1,4-Dichlorobenzene	480 U	440 U	410 U	850 U	460 U	400 U

TABLE C.8a (Cont.)

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals					
	BOR1-1 (6-8 ft)	BOR1-2 (8-10 ft)	BOR1-3 (10-12 ft)	BOR2-1 (3-5 ft)	BOR2-2 (5-8 ft)	BOR2-3 (8-10 ft)
3,3'-Dichlorobenzidine	480 U	440 U	410 U	850 U	460 U	400 U
2,4-Dichlorophenol	480 U	440 U	410 U	850 U	460 U	400 U
Diethylphthalate	480 U	440 U	410 U	850 U	460 U	400 U
Dimethylphthalate	480 U	440 U	410 U	850 U	460 U	400 U
2,4-Dimethylphenol	480 U	440 U	410 U	850 U	460 U	400 U
4,6-Dinitro-2-methylphenol	1,200 U	1,100 U	1,000 U	2,100 U	1,200 U	1,000 U
2,4-Dinitrophenol	1,200 U	1,100 U	1,000 U	2,100 U	1,200 U	1,000 U
2,4-Dinitrotoluene	480 U	440 U	410 U	850 U	460 U	400 U
2,6-Dinitrotoluene	480 U	440 U	410 U	850 U	460 U	400 U
Fluoranthene	480 U	440 U	410 U	850 U	460 U	400 U
Fluorene	480 U	440 U	410 U	850 U	460 U	400 U
Hexachlorobenzene	480 U	440 U	410 U	850 U	460 U	400 U
Hexachlorobutadiene	480 U	440 U	410 U	850 U	460 U	400 U
Hexachlorocyclopentadiene	480 U	440 U	410 U	850 U	460 U	400 U
Hexachloroethane	480 U	440 U	410 U	850 U	460 U	400 U
Indeno[1,2,3-c,d]pyrene	480 U	440 U	410 U	850 U	460 U	400 U
Isophorone	480 U	440 U	410 U	850 U	460 U	400 U
2-Methylnaphthalene	480 U	440 U	410 U	850 U	460 U	400 U
2-Methylphenol	480 U	440 U	410 U	850 U	460 U	400 U
4-Methylphenol	480 U	440 U	410 U	850 U	460 U	400 U
Naphthalene	480 U	440 U	410 U	850 U	460 U	400 U
2-Nitroaniline	1,200 U	1,100 U	1,000 U	2,100 U	1,200 U	1,000 U
3-Nitroaniline	1,200 U	1,100 U	1,000 U	2,100 U	1,200 U	1,000 U
4-Nitroaniline	1,200 U	1,100 U	1,000 U	2,100 U	1,200 U	1,000 U
Nitrobenzene	480 U	440 U	410 U	850 U	460 U	400 U
2-Nitrophenol	480 U	440 U	410 U	850 U	460 U	400 U
4-Nitrophenol	1,200 U	1,100 U	1,000 U	2,100 U	1,200 U	1,000 U
N-Nitroso-di-n-propylamine	480 U	440 U	410 U	850 U	460 U	400 U

TABLE C.8a (Cont.)

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals					
	BOR1-1 (6-8 ft)	BOR1-2 (8-10 ft)	BOR1-3 (10-12 ft)	BOR2-1 (3-5 ft)	BOR2-2 (5-8 ft)	BOR2-3 (8-10 ft)
N-Nitrosodiphenylamine	480 U	440 U	410 U	850 U	460 U	400 U
Pentachlorophenol	1,200 U	1,100 U	1,000 U	2,100 U	1,200 U	1,000 U
Phenanthrene	480 U	440 U	410 U	850 U	460 U	400 U
Phenol	480 U	440 U	410 U	850 U	460 U	53 J
Pyrene	480 U	440 U	410 U	850 U	460 U	400 U
1,2,4-Trichlorobenzene	480 U	440 U	410 U	850 U	460 U	400 U
2,4,5-Trichlorophenol	1,200 U	1,100 U	1,000 U	2,100 U	1,200 U	1,000 U
2,4,6-Trichlorophenol	480 U	440 U	410 U	850 U	460 U	400 U

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals					
	BOR3-1 (6-8 ft)	BOR3-2 (8-10 ft)	BOR4-1 (5-8 ft)	BOR4-2 (8-10 ft)	BOR5-1 (2-4 ft)	BOR5-2 (4-6 ft)
Acenaphthene	420 U	390 U	660 U	440 U	400 U	400 U
Acenaphthylene	420 U	390 U	660 U	440 U	400 U	400 U
Anthracene	420 U	390 U	660 U	440 U	400 U	400 U
Benz[a]anthracene	420 U	390 U	660 U	440 U	400 U	400 U
Benzo[a]pyrene	420 U	390 U	660 U	440 U	400 U	400 U
Benzo[b]fluoranthene	420 U	390 U	660 U	440 U	400 U	400 U
Benzo[g,h,i]perylene	420 U	390 U	660 U	440 U	400 U	400 U
Benzo[k]fluoranthene	420 U	390 U	660 U	440 U	400 U	400 U
Bis(2-chloroethoxy)methane	420 U	390 U	660 U	440 U	400 U	400 U
Bis(2-chloroethyl)ether	420 U	390 U	660 U	440 U	400 U	400 U
Bis(2-chloroisopropyl)ether	420 U	390 U	660 U	440 U	400 U	400 U
Bis(2-ethylhexyl)phthalate	420 U	44 U	660 U	72 J	400 U	400 U
4-Bromophenyl-phenylether	420 U	390 U	660 U	440 U	400 U	400 U
Butylbenzylphthalate	420 U	390 U	660 U	440 U	400 U	400 U

TABLE C.8a (Cont.)

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals					
	BOR3-1 (6-8 ft)	BOR3-2 (8-10 ft)	BOR4-1 (5-8 ft)	BOR4-2 (8-10 ft)	BOR5-1 (2-4 ft)	BOR5-2 (4-6 ft)
Carbazole	420 U	390 U	660 U	440 U	400 U	400 U
4-Chloro-3-methylphenol	420 U	390 U	660 U	440 U	400 U	400 U
4-Chloroaniline	420 U	390 U	660 U	440 U	400 U	400 U
2-Chloronaphthalene	420 U	390 U	660 U	440 U	400 U	400 U
2-Chlorophenol	420 U	390 U	660 U	440 U	400 U	400 U
4-Chlorophenyl phenyl ether	420 U	390 U	660 U	440 U	400 U	400 U
Chrysene	420 U	390 J	660 U	440 U	400 U	400 U
Di-n-butylphthalate	140 J	130 J	230 J	440 U	170 J	190 J
Di-n-octylphthalate	420 U	390 U	660 U	440 U	400 U	400 U
Dibenz[a,h]anthracene	420 U	390 U	660 U	440 U	400 U	400 U
Dibenzofuran	420 U	390 U	660 U	440 U	400 U	400 U
1,2-Dichlorobenzene	420 U	390 U	660 U	440 U	400 U	400 U
1,3-Dichlorobenzene	420 U	390 U	660 U	440 U	400 U	400 U
1,4-Dichlorobenzene	420 U	390 U	660 U	440 U	400 U	400 U
3,3'-Dichlorobenzidine	420 U	390 U	660 U	440 U	400 U	400 U
2,4-Dichlorophenol	420 U	390 U	660 U	440 U	400 U	400 U
Diethylphthalate	420 U	390 U	660 U	440 U	400 U	400 U
Dimethyl phthalate	420 U	390 U	660 U	440 U	400 U	400 U
2,4-Dimethylphenol	420 U	390 U	660 U	440 U	400 U	400 U
4,6-Dinitro-2-methylphenol	1,000 U	980 U	1,700 U	1,100 U	1,000 U	1,000 U
2,4-Dinitrophenol	1,000 U	980 U	1,700 U	1,100 U	1,000 U	1,000 U
2,4-Dinitrotoluene	420 U	390 U	660 U	440 U	400 U	400 U
2,6-Dinitrotoluene	420 U	390 U	660 U	440 U	400 U	400 U
Fluoranthene	420 U	390 U	660 U	440 U	400 U	400 U
Fluorene	420 U	390 U	660 U	440 U	400 U	400 U
Hexachlorobenzene	420 U	390 U	660 U	440 U	400 U	400 U
Hexachlorobutadiene	420 U	390 U	660 U	440 U	400 U	400 U
Hexachlorocyclopentadiene	420 U	390 U	660 U	440 U	400 U	400 U

TABLE C.8a (Cont.)

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals					
	BOR3-1 (6-8 ft)	BOR3-2 (8-10 ft)	BOR4-1 (5-8 ft)	BOR4-2 (8-10 ft)	BOR5-1 (2-4 ft)	BOR5-2 (4-6 ft)
Hexachloroethane	420 U	390 U	660 U	440 U	400 U	400 U
Indeno[1,2,3-c,d]pyrene	420 U	390 U	660 U	440 U	400 U	400 U
Isophorone	420 U	390 U	660 U	440 U	400 U	400 U
2-Methylnaphthalene	420 U	390 U	660 U	440 U	400 U	400 U
2-Methylphenol	420 U	390 U	660 U	440 U	400 U	400 U
4-Methylphenol	420 U	390 U	660 U	440 U	400 U	400 U
N-Nitrosodiphenylamine	420 U	390 U	660 U	440 U	400 U	400 U
N-Nitroso-di-n-propylamine	420 U	390 U	660 U	440 U	400 U	400 U
Naphthalene	420 U	390 U	660 U	440 U	400 U	400 U
2-Nitroaniline	1,000 U	980 U	1,700 U	1,100 U	1,000 U	1,000 U
3-Nitroaniline	1,000 U	980 U	1,700 U	1,100 U	1,000 U	1,000 U
4-Nitroaniline	1,000 U	980 U	1,700 U	1,100 U	1,000 U	1,000 U
Nitrobenzene	420 U	390 U	660 U	440 U	400 U	400 U
2-Nitrophenol	420 U	390 U	660 U	440 U	400 U	400 U
4-Nitrophenol	1,000 U	980 U	1,700 U	1,100 U	1,000 U	1,000 U
Pentachlorophenol	1,000 U	980 U	1,700 U	1,100 U	1,000 U	1,000 U
Phenanthrene	420 U	390 U	660 U	440 U	400 U	400 U
Phenol	420 U	390 U	660 U	440 U	400 U	400 U
Pyrene	420 U	390 U	660 U	440 U	400 U	400 U
1,2,4-Trichlorobenzene	420 U	390 U	660 U	440 U	400 U	400 U
2,4,5-Trichlorophenol	1,000 U	980 U	1,700 U	1,100 U	1,000 U	1,000 U
2,4,6-Trichlorophenol	420 U	390 U	660 U	440 U	400 U	400 U

TABLE C.8a (Cont.)

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals					
	BOR5-3 (6-8 ft)	BOR5-4 (8-10 ft)	BOR5-4Dup (8-10 ft)	BOR6-1 (2-4 ft)	BOR6-2 (4-6 ft)	BOR6-3 (6-8 ft)
Acenaphthene	400 U	390 U	400 U	410 U	400 U	400 U
Acenaphthylene	400 U	390 U	400 U	410 U	400 U	400 U
Anthracene	400 U	390 U	400 U	410 U	400 U	400 U
Benz[a]anthracene	400 U	390 U	400 U	410 U	400 U	400 U
Benzo[a]pyrene	400 U	390 U	400 U	410 U	400 U	400 U
Benzo[b]fluoranthene	400 U	390 U	400 U	410 U	400 U	400 U
Benzo[g,h,i]perylene	400 U	390 U	400 U	410 U	400 U	400 U
Benzo[k]fluoranthene	400 U	390 U	400 U	410 U	400 U	400 U
Bis(2-chloroethoxy)methane	400 U	390 U	400 U	410 U	400 U	400 U
Bis(2-chloroethyl)ether	400 U	390 U	400 U	410 U	400 U	400 U
Bis(2-chloroisopropyl)ether	400 U	390 U	400 U	410 U	400 U	400 U
Bis(2-ethylhexyl)phthalate	400 U	65 J	41 J	410 U	400 U	400 U
4-Bromophenyl phenyl ether	400 U	390 U	400 U	410 U	400 U	400 U
Butylbenzylphthalate	400 U	390 U	400 U	410 U	400 U	400 U
Carbazole	400 U	390 U	400 U	410 U	400 U	400 U
4-Chloro-3-methylphenol	400 U	390 U	400 U	410 U	400 U	400 U
4-Chloroaniline	400 U	390 U	400 U	410 U	400 U	400 U
2-Chloronaphthalene	400 U	390 U	400 U	410 U	400 U	400 U
2-Chlorophenol	400 U	390 U	400 U	410 U	400 U	400 U
4-Chlorophenyl phenyl ether	400 U	390 U	400 U	410 U	400 U	400 U
Chrysene	400 U	390 U	400 U	410 U	400 U	400 U
Di-n-butylphthalate	170 J	160 J	140 J	170 J	140 J	98 J
Di-n-octylphthalate	400 U	390 U	400 U	410 U	400 U	400 U
Dibenz[a,h]anthracene	400 U	390 U	400 U	410 U	400 U	400 U
Dibenzofuran	400 U	390 U	400 U	410 U	400 U	400 U

TABLE C.8a (Cont.)

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals					
	BOR5-3 (6-8 ft)	BOR5-4 (8-10 ft)	BOR5-4Dup (8-10 ft)	BOR6-1 (2-4 ft)	BOR6-2 (4-6 ft)	BOR6-3 (6-8 ft)
1,2-Dichlorobenzene	400 U	390 U	400 U	410 U	400 U	400 U
1,3-Dichlorobenzene	400 U	390 U	400 U	410 U	400 U	400 U
1,4-Dichlorobenzene	400 U	390 U	400 U	410 U	400 U	400 U
3,3'-Dichlorobenzidine	400 U	390 U	400 U	410 U	400 U	400 U
2,4-Dichlorophenol	400 U	390 U	400 U	410 U	400 U	400 U
Diethylphthalate	400 U	390 U	400 U	410 U	400 U	400 U
Dimethylphthalate	400 U	390 U	400 U	410 U	400 U	400 U
2,4-Dimethylphenol	400 U	390 U	400 U	410 U	400 U	400 U
4,6-Dinitro-2-methylphenol	1,000 U	980 U	990 U	1,000 U	1,000 U	1,000 U
2,4-Dinitrophenol	1,000 U	980 U	990 U	1,000 U	1,000 U	1,000 U
2,4-Dinitrotoluene	400 U	390 U	400 U	410 U	400 U	400 U
2,6-Dinitrotoluene	400 U	390 U	400 U	410 U	400 U	400 U
Fluoranthene	400 U	390 U	400 U	410 U	400 U	400 U
Fluorene	400 U	390 U	400 U	410 U	400 U	400 U
Hexachlorobenzene	400 U	390 U	400 U	410 U	400 U	400 U
Hexachlorobutadiene	400 U	390 U	400 U	410 U	400 U	400 U
Hexachlorocyclopentadiene	400 U	390 U	400 U	410 U	400 U	400 U
Hexachloroethane	400 U	390 U	400 U	410 U	400 U	400 U
Indeno[1,2,3-c,d]pyrene	400 U	390 U	400 U	410 U	400 U	400 U
Isophorone	400 U	390 U	400 U	410 U	400 U	400 U
2-Methylnaphthalene	400 U	390 U	400 U	410 U	400 U	400 U
2-Methylphenol	400 U	390 U	400 U	410 U	400 U	400 U
4-Methylphenol	400 U	390 U	400 U	410 U	400 U	400 U
Naphthalene	400 U	390 U	400 U	410 U	400 U	400 U
2-Nitroaniline	1,000 U	980 U	990 U	1,000 U	1,000 U	1,000 U
3-Nitroaniline	1,000 U	980 U	990 U	1,000 U	1,000 U	1,000 U
4-Nitroaniline	1,000 U	980 U	990 U	1,000 U	1,000 U	1,000 U
Nitrobenzene	400 U	390 U	400 U	410 U	400 U	400 U

TABLE C.8a (Cont.)

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals					
	BOR5-3 (6-8 ft)	BOR5-4 (8-10 ft)	BOR5-4Dup (8-10 ft)	BOR6-1 (2-4 ft)	BOR6-2 (4-6 ft)	BOR6-3 (6-8 ft)
2-Nitrophenol	400 U	390 U	400 U	410 U	400 U	400 U
4-Nitrophenol	1,000 U	980 U	990 U	1,000 U	1,000 U	1,000 U
N-Nitroso-di-n-propylamine	400 U	390 U	400 U	410 U	400 U	400 U
N-Nitrosodiphenylamine	400 U	390 U	400 U	410 U	400 U	400 U
Pentachlorophenol	1,000 U	980 U	990 U	1,000 U	1,000 U	1,000 U
Phenanthrene	400 U	390 U	400 U	410 U	400 U	400 U
Phenol	400 U	390 U	400 U	70 J	400 U	400 U
Pyrene	400 U	390 U	400 U	410 U	400 U	400 U
1,2,4-Trichlorobenzene	400 U	390 U	400 U	410 U	400 U	400 U
2,4,5-Trichlorophenol	1,000 U	980 U	990 U	1,000 U	1,000 U	1,000 U
2,4,6-Trichlorophenol	400 U	390 U	400 U	410 U	400 U	400 U

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals					
	BOR6-4 (8-10 ft)	BOR7-1 (2-4 ft)	BOR7-2 (4-6 ft)	BOR7-3 (6-8 ft)	BOR7-4 (8-10 ft)	BOR8-1 (0-2 ft)
Acenaphthene	390 U	380 J	390 U	400 U	400 U	420 U
Acenaphthylene	390 U	130 J	390 U	400 U	400 U	420 U
Anthracene	390 U	280 J	390 U	400 U	400 U	420 U
Benz[a]anthracene	390 U	1,200	390 U	110 J	400 U	420 U
Benzo[a]pyrene	390 U	900	390 U	76 J	400 U	420 U
Benzo[b]fluoranthene	390 U	1,700	390 U	150 J	400 U	420 U
Benzo[g,h,i]perylene	390 U	490	390 U	46 J	400 U	420 U
Benzo[k]fluoranthene	390 U	700	390 U	56 J	400 U	420 U
Bis(2-chloroethoxy)methane	390 U	460 U	390 U	400 U	400 U	420 U
Bis(2-chloroethyl)ether	390 U	460 U	390 U	400 U	400 U	420 U
Bis(2-chloroisopropyl)ether	390 U	460 U	390 U	400 U	400 U	420 U
Bis(2-ethylhexyl)phthalate	390 U	1,100	230 J	400 U	400 U	420 U

TABLE C.8a (Cont.)

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals					
	BOR6-4 (8-10 ft)	BOR7-1 (2-4 ft)	BOR7-2 (4-6 ft)	BOR7-3 (6-8 ft)	BOR7-4 (8-10 ft)	BOR8-1 (0-2 ft)
4-Bromophenyl phenyl ether	390	U	390	U	400	U
Butylbenzylphthalate	390	U	390	U	400	U
Carbazole	390	U	390	U	400	U
4-Chloro-3-methylphenol	390	U	390	U	400	U
4-Chloroaniline	390	U	390	U	400	U
2-Chloronaphthalene	390	U	390	U	400	U
2-Chlorophenol	390	U	390	U	400	U
4-Chlorophenyl phenyl ether	390	U	390	U	400	U
Chrysene	390	U	390	U	400	U
Di-n-butylphthalate	100	J	110	J	98	J
Di-n-octylphthalate	390	U	390	U	400	U
Dibenz[a,h]anthracene	390	U	390	U	400	U
Dibenzofuran	390	U	390	U	400	U
1,2-Dichlorobenzene	390	U	390	U	400	U
1,3-Dichlorobenzene	390	U	390	U	400	U
1,4-Dichlorobenzene	390	U	390	U	400	U
3,3'-Dichlorobenzidine	390	U	390	U	400	U
2,4-Dichlorophenol	390	U	390	U	400	U
Diethylphthalate	390	U	390	U	400	U
Dimethylphthalate	390	U	390	U	400	U
2,4-Dimethylphenol	390	U	390	U	400	U
4,6-Dinitro-2-methylphenol	960	U	960	U	1,000	U
2,4-Dinitrophenol	960	U	960	U	1,000	U
2,4-Dinitrotoluene	390	U	390	U	400	U
2,6-Dinitrotoluene	390	U	390	U	400	U
Fluoranthene	390	U	390	U	400	U
Fluorene	390	U	390	U	400	U
Hexachlorobenzene	390	U	390	U	400	U

TABLE C.8a (Cont.)

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals					
	BOR6-4 (8-10 ft)	BOR7-1 (2-4 ft)	BOR7-2 (4-6 ft)	BOR7-3 (6-8 ft)	BOR7-4 (8-10 ft)	BOR8-1 (0-2 ft)
Hexachlorobutadiene	390 U	460 U	390 U	400 U	400 U	420 U
Hexachlorocyclopentadiene	390 U	460 U	390 U	400 U	400 U	420 U
Hexachloroethane	390 U	460 U	390 U	400 U	400 U	420 U
Indeno[1,2,3-c,d]pyrene	390 U	610	390 U	58 J	400 U	420 U
Isophorone	390 U	460 U	390 U	400 U	400 U	420 U
2-Methylnaphthalene	390 U	210 J	390 U	400 U	400 U	420 U
2-Methylphenol	390 U	460 U	390 U	400 U	400 U	420 U
4-Methylphenol	390 U	460 U	390 U	400 U	400 U	420 U
Naphthalene	390 U	460 U	390 U	400 U	400 U	420 U
2-Nitroaniline	960 U	1,200 U	960 U	1,000 U	1,000 U	1,000 U
3-Nitroaniline	960 U	1,200 U	960 U	1,000 U	1,000 U	1,000 U
4-Nitroaniline	960 U	1,200 U	960 U	1,000 U	1,000 U	1,000 U
Nitrobenzene	390 U	460 U	390 U	400 U	400 U	420 U
2-Nitrophenol	390 U	460 U	390 U	400 U	400 U	420 U
4-Nitrophenol	960 U	1,200 U	960 U	1,000 U	1,000 U	1,000 U
N-Nitroso-di-n-propylamine	390 U	460 U	390 U	400 U	400 U	420 U
N-Nitrosodiphenylamine	390 U	460 U	390 U	400 U	400 U	420 U
Pentachlorophenol	960 U	1,200 U	960 U	1,000 U	1,000 U	1,000 U
Phenanthrene	390 U	1,400	390 U	400 U	400 U	420 U
Phenol	390 U	460 U	390 U	400 U	400 U	420 U
Pyrene	390 U	1,800	390 U	160 J	400 U	420 U
1,2,4-Trichlorobenzene	390 U	460 U	390 U	400 U	400 U	420 U
2,4,5-Trichlorophenol	960 U	1,200 U	960 U	1,000 U	1,000 U	1,000 U
2,4,6-Trichlorophenol	390 U	460 U	390 U	400 U	400 U	420 U

TABLE C.8a (Cont.)

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals				
	BOR8-2 (2-4 ft)	BOR8-3 (4-6 ft)	BOR8-3Dup (4-6 ft)	BOR8-4 (6-8 ft)	BOR8-5 (8-10 ft)
Acenaphthene	410 U	400 U	400 U	390 U	410 U
Acenaphthylene	410 U	400 U	400 U	390 U	410 U
Anthracene	410 U	400 U	400 U	390 U	410 U
Benz[a]anthracene	410 U	400 U	400 U	390 U	410 U
Benzo[a]pyrene	410 U	400 U	400 U	390 U	410 U
Benzo[b]fluoranthene	410 U	400 U	400 U	390 U	410 U
Benzo[g,h,i]perylene	410 U	400 U	400 U	390 U	410 U
Benzo[k]fluoranthene	410 U	400 U	400 U	390 U	410 U
Bis(2-chloroethoxy)methane	410 U	400 U	400 U	390 U	410 U
Bis(2-chloroethyl)ether	410 U	400 U	400 U	390 U	410 U
Bis(2-chloroisopropyl)ether	410 U	400 U	400 U	390 U	410 U
Bis(2-ethylhexyl)phthalate	410 U	400 U	400 U	390 U	410 U
4-Bromophenyl phenylether	410 U	400 U	400 U	50 J	410 U
Butylbenzylphthalate	410 U	400 U	400 U	390 U	410 U
Carbazole	410 U	400 U	400 U	390 U	410 U
4-Chloro-3-methylphenol	410 U	400 U	400 U	390 U	410 U
4-Chloroaniline	410 U	400 U	400 U	390 U	410 U
2-Chloronaphthalene	410 U	400 U	400 U	390 U	410 U
2-Chlorophenol	410 U	400 U	400 U	390 U	410 U
4-Chlorophenyl phenyl ether	410 U	400 U	400 U	390 U	410 U
Chrysene	410 U	400 U	400 U	390 U	410 U
Di-n-butylphthalate	110 J	150 J	200 J	390 U	67 J
Di-n-octylphthalate	410 U	400 U	400 U	390 U	410 U
Dibenz[a,h]anthracene	410 U	400 U	400 U	390 U	410 U
Dibenzofuran	410 U	400 U	400 U	390 U	410 U
1,2-Dichlorobenzene	410 U	400 U	400 U	390 U	410 U
1,3-Dichlorobenzene	410 U	400 U	400 U	390 U	410 U
1,4-Dichlorobenzene	410 U	400 U	400 U	390 U	410 U

TABLE C.8a (Cont.)

Compound	Sediment Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals				
	BOR8-2 (2-4 ft)	BOR8-3 (4-6 ft)	BOR8-3Dup (4-6 ft)	BOR8-4 (6-8 ft)	BOR8-5 (8-10 ft)
3,3'-Dichlorobenzidine	410 U	400 U	400 U	390 U	410 U
2,4-Dichlorophenol	410 U	400 U	400 U	390 U	410 U
Diethylphthalate	410 U	400 U	400 U	390 U	410 U
Dimethylphthalate	410 U	400 U	400 U	390 U	410 U
2,4-Dimethylphenol	410 U	400 U	400 U	390 U	410 U
4,6-Dinitro-2-methylphenol	1,000 U	1,000 U	1,000 U	980 U	1,000 U
2,4-Dinitrophenol	1,000 U	1,000 U	1,000 U	980 U	1,000 U
2,4-Dinitrotoluene	410 U	400 U	400 U	390 U	410 U
2,6-Dinitrotoluene	410 U	400 U	400 U	390 U	410 U
Fluoranthene	410 U	400 U	400 U	390 U	410 U
Fluorene	410 U	400 U	400 U	390 U	410 U
Hexachlorobenzene	410 U	400 U	400 U	390 U	410 U
Hexachlorobutadiene	410 U	400 U	400 U	390 U	410 U
Hexachlorocyclopentadiene	410 U	400 U	400 U	390 U	410 U
Hexachloroethane	410 U	400 U	400 U	390 U	410 U
Indeno[1,2,3-c,d]pyrene	410 U	400 U	400 U	390 U	410 U
Isophorone	410 U	400 U	400 U	390 U	410 U
2-Methylnaphthalene	410 U	400 U	400 U	390 U	410 U
2-Methylphenol	410 U	400 U	400 U	390 U	410 U
4-Methylphenol	410 U	400 U	400 U	390 U	410 U
Naphthalene	410 U	400 U	400 U	390 U	410 U
2-Nitroaniline	1,000 U	1,000 U	1,000 U	980 U	1,000 U
3-Nitroaniline	1,000 U	1,000 U	1,000 U	980 U	1,000 U
4-Nitroaniline	1,000 U	1,000 U	1,000 U	980 U	1,000 U
Nitrobenzene	410 U	400 U	400 U	390 U	410 U
2-Nitrophenol	410 U	400 U	400 U	390 U	410 U
4-Nitrophenol	1,000 U	1,000 U	1,000 U	980 U	1,000 U

TABLE C.8a (Cont.)

Compound	Sediment Concentrations (µg/kg) at Various Depth Intervals				
	BOR8-2 (2-4 ft)	BOR8-3 (4-6 ft)	BOR8-3Dup (4-6 ft)	BOR8-4 (6-8 ft)	BOR8-5 (8-10 ft)
N-Nitroso-di-n-propylamine	410 U	400 U	400 U	390 U	410 U
N-Nitrosodiphenylamine	410 U	400 U	400 U	390 U	410 U
Pentachlorophenol	1,000 U	1,000 U	1,000 U	980 U	1,000 U
Phenanthrene	410 U	400 U	400 U	390 U	410 U
Phenol	410 U	400 U	400 U	390 U	410 U
Pyrene	410 U	400 U	400 U	390 U	410 U
1,2,4-Trichlorobenzene	410 U	400 U	400 U	390 U	410 U
2,4,5-Trichlorophenol	1,000 U	1,000 U	1,000 U	980 U	1,000 U
2,4,6-Trichlorophenol	410 U	400 U	400 U	390 U	410 U

<sup>a</sup> Samples by ANL, analyzed by Weston Gulf Coast, CLP/HSL semivolatile organics.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

J = indicates an estimated value.

TABLE C.8b Semivolatile Organics Analyses for Sediment Borings, June 1995<sup>a</sup>

Compound	Sediment Concentrations (µg/kg) at 0-6 in.									
	TPSED 2		TPSED 3		TPSED 4		TPSED 5		TPSED 7	
Acenaphthene	558	U	805	U	805	U	674	U	485	U
Acenaphthylene	558	U	805	U	805	U	674	U	485	U
Anthracene	558	U	805	U	805	U	674	U	485	U
Benz(a)anthracene	558	U	805	U	805	U	674	U	485	U
Benzo(a)pyrene	558	U	805	U	805	U	674	U	485	U
Benzo(b)fluoranthene	558	U	805	U	805	U	674	U	485	U
Benzo(g,h,i)perylene	558	U	805	U	805	U	674	U	485	U
Benzo(k)fluoranthene	558	U	805	U	805	U	674	U	485	U
Bis(2-chloroethoxy)methane	558	U	805	U	805	U	674	U	485	U
Bis(2-chloroethyl)ether	558	U	805	U	805	U	674	U	485	U
Bis(2-ethylhexyl)phthalate	558	U	805	U	805	U	674	U	485	U
4-Bromophenyl phenyl ether	558	U	805	U	805	U	674	U	485	U
Butylbenzylphthalate	558	U	805	U	805	U	674	U	485	U
Carbazole	558	U	805	U	805	U	674	U	485	U
4-Chloro-3-methylphenol	558	U	805	U	805	U	674	U	485	U
4-Chloroaniline	558	U	805	U	805	U	674	U	485	U
2-Chloronaphthalene	558	U	805	U	805	U	674	U	485	U
2-Chlorophenol	558	U	805	U	805	U	674	U	485	U
4-Chlorophenyl phenyl ether	558	U	805	U	805	U	674	U	485	U
Chrysene	558	U	805	U	805	U	674	U	485	U
Di-n-butylphthalate	558	U	805	U	805	U	674	U	485	U
Di-n-octylphthalate	558	U	805	U	805	U	674	U	485	U
Dibenz(a,h)anthracene	558	U	805	U	805	U	674	U	485	U
Dibenzofuran	558	U	805	U	805	U	674	U	485	U
1,2-Dichlorobenzene	558	U	805	U	805	U	674	U	485	U
1,3-Dichlorobenzene	558	U	805	U	805	U	674	U	485	U
1,4-Dichlorobenzene	558	U	89	J	805	U	674	U	485	U
3,3'-Dichlorobenzidine	558	U	805	U	805	U	674	U	485	U
2,4-Dichlorophenol	558	U	805	U	805	U	674	U	485	U
Diethyl phthalate	558	U	805	U	805	U	674	U	485	U
Dimethyl phthalate	558	U	805	U	805	U	674	U	485	U
2,4-Dimethylphenol	558	U	805	U	805	U	674	U	485	U
4,6-Dinitro-2-methylphenol	1,400	U	2,020	U	2,020	U	1,690	U	1,220	U
2,4-Dinitrophenol	1,400	U	2,020	U	2,020	U	1,690	U	1,220	U
2,4-Dinitrotoluene	558	U	805	U	805	U	674	U	485	U
2,6-Dinitrotoluene	558	U	805	U	805	U	674	U	485	U

TABLE C.8b (Cont.)

Compound	Sediment Concentrations (µg/kg) at 0-6 in.									
	TPSED 2		TPSED 3		TPSED 4		TPSED 5		TPSED 7	
Fluoranthene	61	J	805	U	805	U	674	U	485	U
Fluorene	558	U	805	U	805	U	674	U	485	U
Hexachlorobenzene	84	J	805	U	805	U	674	U	485	U
Hexachlorobutadiene	558	U	805	U	805	U	674	U	485	U
Hexachlorocyclopentadiene	558	U	805	U	805	U	674	U	485	U
Hexachloroethane	558	U	805	U	805	U	674	U	485	U
Indeno(1,2,3-cd)pyrene	558	U	805	U	805	U	674	U	485	U
Isophorone	558	U	805	U	805	U	674	U	485	U
2-Methylnaphthalene	558	U	805	U	805	U	674	U	485	U
2-Methylphenol	558	U	805	U	805	U	674	U	485	U
4-Methylphenol	558	U	805	U	805	U	674	U	485	U
Naphthalene	558	U	805	U	805	U	674	U	485	U
2-Nitroaniline	1,400	U	2,020	U	2,020	U	1,690	U	1,220	U
3-Nitroaniline	1,400	U	2,020	U	2,020	U	1,690	U	1,220	U
4-Nitroaniline	1,400	U	2,020	U	2,020	U	1,690	U	1,220	U
Nitrobenzene	558	U	805	U	805	U	674	U	485	U
2-Nitrophenol	558	U	805	U	805	U	674	U	485	U
4-Nitrophenol	1,400	U	2,020	U	2,020	U	1,690	U	1,220	U
N-Nitroso-di-n-propylamine	558	U	805	U	805	U	674	U	485	U
N-Nitrosodiphenylamine	558	U	805	U	805	U	674	U	485	U
2,2'-Oxybis-(1-chloropropane)	558	U	805	U	805	U	674	U	485	U
Pentachlorophenol	1,400	U	2,020	U	2,020	U	1,690	U	1,220	U
Phenanthrene	558	U	805	U	805	U	674	U	485	U
Phenol	558	U	805	U	805	U	674	U	485	U
Pyrene	64	J	805	U	805	U	674	U	485	U
1,2,4-Trichlorobenzene	558	U	805	U	805	U	674	U	485	U
2,4,5-Trichlorophenol	1,400	U	2,020	U	2,020	U	1,690	U	1,220	U
2,4,6-Trichlorophenol	558	U	805	U	805	U	674	U	485	U

<sup>a</sup> Sampled by ANL and analyzed by GP Environmental Services.

Data Qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

J = indicates an estimated value.

TABLE C.9a Inorganic Analyses for Sediment Borings, April 1994<sup>a</sup>

Parameter	Sediment Concentrations (mg/kg) at Various Depth Intervals									
	BOR1-1 (6-8 ft)	BOR1-2 (8-10 ft)	BOR1-3 (10-12 ft)	BOR2-1 (3-5 ft)	BOR2-2 (5-8 ft)	BOR2-3 (8-10 ft)	BOR3-1 (6-8 ft)	BOR3-2 (8-10 ft)		
<b>Metals</b>										
Aluminum	11,800	10,100	8,110	9,820	10,000	6,990	5,330	4,400	N	N
Antimony	6	6.2	5.4	10.5	6.1	5.0	4.8	5.0	UN	UN
Arsenic	4.4	10.5	1.2	14.4	5.6	1.4	0.96	0.31		
Barium	77.6	64.6	55.5	202	78.2	51	26.7	30.6		
Beryllium	0.62	0.97	0.36	0.35	0.36	0.68	0.28	0.28		
Cadmium	0.57	0.59	0.51	2.6	0.58	0.48	0.46	0.48	U	U
Calcium	596	421	351	1,300	691	471	413	275		
Chromium	18.4	20	13.5	36.3	14.1	11.9	7.0	7.1		
Cobalt	5.8	5.1	3.5	4.1	3.2	4.9	1.5	2.2		
Copper	17.8	18.2	10.8	319	11.4	11.3	1.5	3.5		
Iron	14,100	16,500	9,350	14,200	9,750	14,000	6,710	4,530		
Lead	13.1	20.6	12.3	318	13	7.9	5.6	8.3	@N	@N
Magnesium	2,200	2,370	1,360	2,030	1,630	1,650	552	973		
Manganese	55.5	62.1	35.8	51.6	43.3	53	13.9	34.3		
Mercury	0.11	0.11	0.09	0.38	0.14	0.09	0.09	0.11	U	U
Nickel	12.7	11.3	9.5	15.2	7.2	10.6	3.3	8.1		
Potassium	969	978	699	796	732	602	447	473		
Selenium	0.36	0.28	0.16	1.0	0.36	0.15	0.18	0.17	U	U
Silver	0.58	0.59	0.51	2.8	0.58	0.48	0.46	0.48	U	U
Sodium	1,020	801	636	2,280	1,270	738	190	78		
Thallium	0.32	0.33	0.26	0.59	0.31	0.25	0.29	0.27	U	U
Vanadium	19.4	22.3	11.4	21	21.4	14.3	11	6.5		
Zinc	56.9	45.7	60.1	445	31.7	64.4	11.9	38.6	E	E
<b>Other Parameters</b>										
Cyanide (mg/kg)	0.69	0.57	0.55	1.2	0.69	0.56	0.57	0.54	U	U
Solids (%)	68.6	75.9	80.8	39	70.4	82.7	78.7	84.1		

TABLE C.9a (Cont.)

Sediment Concentrations (mg/kg) at Various Depth Intervals								
Parameter	BOR4-1 (5-8 ft)	BOR4-2 (8-10 ft)	BOR5-1 (2-4 ft)	BOR5-2 (4-6 ft)	BOR5-3 (6-8 ft)	BOR5-4 (8-10 ft)	BOR5-4Dup (8-10 ft)	
Metals								
Aluminum	3,480	N	1,850	N	9,830	12,400	6,780	6,080
Antimony	9.0	UN	5.7	UN	5.5	UN	5.6	UN
Arsenic	6.7		1.9		3.4		3.9	2.1
Barium	34.1		11		50.3		36.9	38.5
Beryllium	0.54		0.42		0.51		0.62	0.54
Cadmium	0.85	U	0.54	U	0.52	U	0.53	U
Calcium	1,150		346		503		258	225
Chromium	10.3		5.4		12.2		12	9.6
Cobalt	14.4		2.7		7.4		5.9	5.4
Copper	16.2		4.5		5.4		7.4	6.8
Iron	10,600		4,800		10,900	17,400	12,000	9,480
Lead	61.6	@N	7.4	@N	11.2	8.7	10.7	6.2
Magnesium	907		350		1,620	1,980	1,360	1,230
Manganese	40.4		16.8		431	@	49.6	@
Mercury	0.15	U	0.12	U	0.08	U@	0.1	U@
Nickel	8.5		3.1		9.4	10.8	11.7	10.7
Potassium	402		218		624	925	533	556
Selenium	0.73		0.25		0.28	0.16	0.19	0.18
Silver	0.85	U	0.54	U	0.52	U	0.49	U
Sodium	1130		226		592	E	648	E
Thallium	0.45	U	0.3	U	0.31	U	0.3	U
Vanadium	6.3		3.9		17.9	24.4	15	8.1
Zinc	193	E	42.9	E	26.5	32.7	46	36.6
Other Parameters								
Cyanide (mg/kg)	0.92	U	0.62	U	0.58	U	0.59	U
Solids (%)	49.1		75.4		81.9	81.7	83.7	83.5

TABLE C.9a (Cont.)

Parameter	Sediment Concentrations (mg/kg) at Various Depth Intervals						
	BOR6-1 (2-4 ft)	BOR6-2 (4-6 ft)	BOR6-3 (6-8 ft)	BOR6-4 (8-10 ft)	BOR7-1 (2-4 ft)	BOR7-2 (4-6 ft)	BOR7-3 (6-8 ft)
<b>Metals</b>							
Aluminum	9,180	7,680	5,990	10,100	6,430	7,530	6,960
Antimony	5.9	5.6	5.3	5.1	6.3	5.0	5.9
Arsenic	3.1	3.8	2.1	2.6	1.9	1.2	3.1
Barium	34.1	46.2	22.7	34.9	36.6	35	57.6
Beryllium	0.37	0.51	0.32	0.62	0.49	0.44	0.73
Cadmium	0.56	0.52	0.5	0.48	0.6	0.47	0.55
Calcium	427	493	369	614	754	504	428
Chromium	11.7	14.6	8.8	17.1	9.5	12.4	14.2
Cobalt	4.6	5.6	3.5	5.8	3.5	4.9	8.2
Copper	4.3	8.3	5.0	9.0	5.8	5.8	8.7
Iron	12,300	14,600	8,430	12,000	8,570	8,070	11,600
Lead	6.7	10.3	4.4	7.4	7.7	5.6	10.4
Magnesium	1,390	1,560	1,200	2,050	1,260	1,160	1,400
Manganese	113	88.4	71.9	80.3	37.6	20.2	33.7
Mercury	0.11	0.09	0.1	0.1	0.11	0.1	0.12
Nickel	8.8	8.6	6.6	11.9	7.6	7.4	12.6
Potassium	563	682	457	636	467	462	537
Selenium	0.2	0.18	0.19	0.19	0.34	0.18	0.26
Silver	0.56	0.52	0.5	0.52	0.6	0.47	0.57
Sodium	825	762	571	803	1,290	990	878
Thallium	0.32	0.29	0.3	0.27	0.33	0.3	0.31
Vanadium	16.4	16.4	12.1	17.7	12.6	9.3	19.9
Zinc	21.2	23.9	24	43.1	32.5	26.4	46.6
<b>Other Parameters</b>							
Cyanide (mg/kg)	0.58	0.56	0.54	0.58	0.68	0.57	0.61
Solids (%)	80	82.9	83.1	85.3	70.6	84	81.6

TABLE C.9a (Cont.)

Parameter	Sediment Concentrations (mg/kg) at Various Depth Intervals						
	BOR7-4 (8-10 ft)	BOR8-1 (0-2 ft)	BOR8-2 (2-4 ft)	BOR8-3 (4-6 ft)	BOR8-3Dup (4-6 ft)	BOR8-4 (6-8 ft)	BOR8-5 (8-10 ft)
<b>Metal</b>							
Aluminum	8,670	9,090	3,690	2,230	2,640	2,530	1,900
Antimony	5.5	6.1	5.2	UN	5.6	5.8	UN
Arsenic	3.1	3.4	3.5	1.7	1.7	3.5	2.7
Barium	35.5	88.3	15.5	9.4	11.5	11.9	9.9
Beryllium	0.46	0.67	0.49	0.24	0.25	0.31	0.31
Cadmium	0.52	0.58	0.49	U	0.53	0.54	U
Calcium	393	606	253	115	141	131	94.4
Chromium	16.3	13.3	7.1	4.9	5.2	4.9	4.0
Cobalt	5.9	3.0	1.9	1.3	1.2	1.6	0.99
Copper	7.7	21.9	3.9	2.3	3.2	2.6	2.2
Iron	11,500	6,600	6,020	2,930	3,740	4,110	3,250
Lead	9.6	19.9	3.5	2.9	4.2	3.6	2.4
Magnesium	1,570	1,050	642	472	515	519	436
Manganese	40.1	38.8	23	@	20.5	23.3	@
Mercury	0.08	0.11	0.11	U@	0.1	0.12	U@
Nickel	12.6	6.2	3.5	2.6	2.7	4.1	2.8
Potassium	626	477	335	293	288	322	168
Selenium	0.17	0.32	0.19	U	0.19	0.18	U
Silver	0.52	0.58	0.49	U	0.53	0.54	U
Sodium	861	441	124	E	55.3	38.4	E
Thallium	0.27	0.32	0.3	U	0.31	0.3	U
Vanadium	16.9	14.5	8.7	4.8	5.6	6.4	4.9
Zinc	32.5	63.7	27.2	15.4	16.9	13.7	16.5

TABLE C.9a (Cont.)

Sediment Concentrations (mg/kg) at Various Depth Intervals							
Parameter	BOR7-4 (8-10 ft)	BOR8-1 (0-2 ft)	BOR8-2 (2-4 ft)	BOR8-3 (4-6 ft)	BOR8-3Dup (4-6 ft)	BOR8-4 (6-8 ft)	BOR8-5 (8-10 ft)
Other Parameters							
Cyanide (mg/kg)	0.54	U	0.6	U	0.57	U	0.57
Solids (%)	82.6	79.5	81.6	81.8	82.3	83.8	81.1

<sup>a</sup> Sampled by ANL, analyzed by Weston Gulf Coast, CLP/TAL metals and cyanide.

Data qualifiers:

N = spike and spike duplicate recovery of percent RPD were outside the control limits.

U = analyte was analyzed for but not detected; detection limit given.

@ = percent RPD of sample duplicate was outside of control limits.

E = serial dilution percent difference was outside QC limit.

TABLE C.9b Inorganic Analyses for Sediment Borings, June 1995<sup>a</sup>

	Sediment Concentrations (mg/kg) at 0-6 in.							
Parameter	TPSED 1		TPSED 2		TPSED 3		TPSED 4	
Metals								
Aluminum	26,900	*	20,800	*	5,260	*		
Antimony	15.9	BJN	10.9	JN	0.412	UJN	6,120	
Arsenic	12.3		14.1		6.98		0.599	
Barium	927	N	267	N	104	N	1.48	
Beryllium	1.05	BJ	0.89	J	0.379	BJ	50.4	
Cadmium	7.04	J	1.32	J	1.55	J	0.291	
Calcium	2,470		1,530		3,300		1.06	
Chromium	80.2	N	45.9	N	8.74	N	5,720	
Cobalt	9	BJ	8.08	BJ	3.15	UJ	7.19	
Copper	515		209		54.7		3.17	U
Iron	33,400		25,700		9,870		15.3	
Lead	1,780	*	1,260	*	34.9	*	5,740	
Magnesium	5,110		3,080		994		24.2	
Manganese	160		91.2		84.7	B	1,760	
Mercury	1.71		0.748		0.159	B	66.4	
Nickel	35.2		16.2		5.08	U	0.247	
Potassium	1,640		1,080		246	B	9.04	
Selenium	1.76	JN	0.614	BJN	0.972	BJN	429	
Silver	3.74	JN	1.3	BJN	0.169	UJN	0.482	
Sodium	430	B	162	B	716	B	0.171	U
Solids (%)	30.6		58.5		41.3		1,020	
Thallium	0.915	U	0.479	U	0.678	U	0.683	U
Vanadium	50.2	J	31.5	J	15.4	J	14.1	
Zinc	3,410		1,410		240		107	
Other Parameters								
Cyanide (total)	3.27		NT		2.42		NT	
pH (SI)	7.22		6.47		6.32		6.23	
Solids (%)	NT		NT		NT		41	

Parameter	Sediment Concentrations (mg/kg) at 0-6 in.							
	TPSED 5		TPSED 6		TPSED 7		TPSED 8	
Metals								
Aluminum	5600	@J	6,380		9,750		5,450	
Antimony	0.344	UNJ	0.372	U	0.248	U	0.232	U
Arsenic	1.65	B	2.91		3.02		1.11	

TABLE C.9b (Cont.)

Parameter	Sediment Concentrations (mg/kg) at 0-6 in.			
	TPSED 5	TPSED 6	TPSED 7	TPSED 8
Metals (Cont.)				
Barium	35.4 B	49.1	42.6	146
Beryllium	0.323 B	0.414	0.491	0.464
Cadmium	0.886 B	0.656 U	0.565	0.654
Calcium	2,720	3,870	3,520	1,020
Chromium	8.67	10.3	46.2	9.02
Cobalt	2.63 U	4.88	3.76	2.23
Copper	12.6	16	13.4	34
Iron	4,920	9,620	35,600	5,780
Lead	18	21	8.26	20.9
Magnesium	1,700 E	1,840	1,080	793
Manganese	41.9 E	80.9	40.9	31.4
Mercury	0.101 U	0.112	0.072 U	0.056 U
Nickel	10.9	10.2	9.02	6.54
Potassium	410 B	473	394	277
Selenium	0.46 B	1.08	0.289	0.271
Silver	0.142 U	0.153 U	0.102 U	0.096 U
Sodium	1,130	1,780	328	180
Thallium	0.567 U	0.613 U	0.409 U	0.383 U
Vanadium	17.1	13.7	13.3	11.8
Zinc	69	66.7	51.8	28.7
Other Parameters				
Cyanide (total)	2.02	NT	1.46	NT
pH (SI)	6.15	NT	4.79	NT
Solids (%)	49.4	45.7	68.4	73.1

<sup>a</sup> Sampled by ANL and analyzed by GP Environmental Services.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

\* = internal standard area counts were outside QC limits.

B = analyte was found in the associated blank.

J = estimated value.

N = spike and spike duplicate recovery of percent RPD were outside the control limits.

NT = not tested.

@ = percent RPD of sample duplicate was outside of the control limits.

E = serial dilution percent difference was outside QC limit.

TABLE C.10 Pesticide and PCB Analyses for Sediment, June 1995<sup>a</sup>

Compound	Sediment Concentrations (µg/kg) at 0-6 in.									
	TPSED 2		TPSED 3		TPSED 4		TPSED 5		TPSED 7	
Aldrin	2.91	U	4.08	U	4.05	U	3.43	U	2.48	U
alpha-BHC	2.91	U	4.08	U	4.05	U	3.43	U	2.48	U
alpha-Chlordane	2.91	U	4.08	U	4.05	U	3.43	U	2.48	U
Aroclor 1016	56.4	U	79.2	U	78.5	U	66.7	U	48.2	U
Aroclor 1221	114	U	161	U	159	U	135	U	97.8	U
Aroclor 1232	56.4	U	79.2	U	78.5	U	66.7	U	48.2	U
Aroclor 1242	56.4	U	79.2	U	78.5	U	66.7	U	48.2	U
Aroclor 1248	56.4	U	79.2	U	78.5	U	66.7	U	48.2	U
Aroclor 1254	56.4	U	79.2	U	78.5	U	66.7	U	48.2	U
Aroclor 1260	56.4	U	79.2	U	78.5	U	66.7	U	48.2	U
beta-BHC	2.91	U	4.08	U	4.05	U	3.43	U	2.48	U
4,4'-DDD	11		22		3.1		6.5		3	
4,4'-DDE	7.3		16		8.2		9.3		4.2	
4,4'-DDT	1.6	J	7.92	U	7.85	U	6.67	U	4.82	U
delta-BHC	2.91	U	4.08	U	4.05	U	3.43	U	2.48	U
Dieldrin	5.64	U	7.92	U	7.85	U	6.67	U	4.82	U
Endosulfan I	2.91	U	4.08	U	4.05	U	3.43	U	2.48	U
Endosulfan II	5.64	U	7.92	U	7.85	U	6.67	U	4.82	U
Endosulfan sulfate	5.64	U	7.92	U	7.85	U	6.67	U	4.82	U
Endrin	5.64	U	7.92	U	7.85	U	6.67	U	4.82	U
Endrin aldehyde	5.64	U	7.92	U	7.85	U	6.67	U	4.82	U
Endrin ketone	5.64	U	7.92	U	7.85	U	6.67	U	4.82	U
gamma-Chlordane	2.91	U	4.08	U	4.05	U	3.43	U	2.48	U
Heptachlor	2.91	U	4.08	U	4.05	U	3.43	U	2.48	U
Heptachlor epoxide	2.91	U	4.08	U	4.05	U	3.43	U	2.48	U
Lindane (gamma-BHC)	2.91	U	4.08	U	4.05	U	3.43	U	2.48	U
Methoxychlor	29.1	U	40.8	U	40.5	U	34.3	U	24.8	U
Toxaphene	291	U	408	U	405	U	343	U	248	U

<sup>a</sup> Sampled by ANL and analyzed by GP Environmental Services.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

J = estimated value.

TABLE C.11 Explosive Compounds Analyses for Sediment, June 1995<sup>a</sup>

Compound	Sediment Concentrations (µg/kg) at 0-6 in.							
	TPSED 1	TPSED 2	TPSED 3	TPSED 4	TPSED 5	TPSED 6	TPSED 7	TPSED 8
4-Amino-2,6-dinitrotoluene	40.8 U	40.8 U	40.8 U	40.8 U	40.8 U	40.8 U	40.8 U	40.8 U
2-Amino-4,6-dinitrotoluene	46.7 U	46.7 U	46.7 U	46.7 U	46.7 U	46.7 U	46.7 U	46.7 U
1,3-Dinitrobenzene	37.2 U	37.2 U	37.2 U	37.2 U	37.2 U	37.2 U	37.2 U	37.2 U
2,4-Dinitrotoluene	2110	51.6 U	51.6 U	51.6 U	51.6 U	51.6 U	51.6 U	51.6 U
2,6-Dinitrotoluene	47.6 U	47.6 U	47.6 U	47.6 U	47.6 U	47.6 U	47.6 U	47.6 U
HMX	70.5 U	70.5 U	70.5 U	70.5 U	70.5 U	70.5 U	70.5 U	70.5 U
Nitrobenzene	35.2 U	35.2 U	35.2 U	35.2 U	35.2 U	35.2 U	35.2 U	35.2 U
Nitroglycerin	10,000 U	10,000 U	10,000 U	10,000 U	10,000 U	10,000 U	10,000 U	10,000 U
2-Nitrotoluene	81.4 U	81.4 U	81.4 U	81.4 U	81.4 U	81.4 U	81.4 U	81.4 U
3-Nitrotoluene	81.7 U	81.7 U	81.7 U	81.7 U	81.7 U	81.7 U	81.7 U	81.7 U
4-Nitrotoluene	87.2 U	87.2 U	87.2 U	87.2 U	87.2 U	87.2 U	87.2 U	87.2 U
Pentaerythritol tetranitrate	250 U	250 U	250 U	250 U	250 U	250 U	250 U	250 U
RDX	50.9 U	50.9 U	50.9 U	50.9 U	50.9 U	50.9 U	50.9 U	50.9 U
Tetryl	163 U	163 U	163 U	163 U	163 U	163 U	163 U	163 U
Thiodiglycol (TDGCL)	NT	NT	NT	9.62 U	7.98 U	8.62 U	5.76 U	5.39 U
1,3,5-Trinitrobenzene	40.2 U	40.2 U	40.2 U	40.2 U	40.2 U	40.2 U	40.2 U	40.2 U
2,4,6-Trinitrotoluene	35.6 U	35.6 U	35.6 U	35.6 U	35.6 U	35.6 U	35.6 U	35.6 U

<sup>a</sup> Sampled by ANL and analyzed by GP Environmental Services.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

NT = not tested.

**TABLE C.12 CWA Degradation Products and Organosulfur Compounds Analyses for Sediment, June 1995<sup>a</sup>**

Sediment Concentrations (µg/kg) at 0-6 in.														
Compound	TPSED 1	TPSED 2	TPSED 3	TPSED 4	TPSED 5	TPSED 6	TPSED 7	TPSED 8						
CWA degradation products														
Diisopropyl methylphosphonate (DIMP)	0.373	U	1.85	U	2.61	U	2.64	U	2.36	U	1.58	U	1.48	U
Dimethyl methylphosphate (DMMP)	0.435	U	3.51	U	5.15	U	2.79	U	2.64	U	2.29	U	1.54	U
Isopropyl methylphosphonic acid (IMPA)	8.15	U	6.73	U	9.54	U	NT	NT	NT	NT	NT	NT	NT	NT
Methyl phosphonic acid	8.15	U	1.18	U	1.67	U	1.69	U	1.4	U	1.52	U	1.01	U
Thiodiglycol (TDGCL)	12.9	U	0.195	U	0.276	U	0.278	U	0.23	U	0.25	U	0.166	U
Organosulfur compounds														
Benzothiozole (BTZ)	3.53	U	2.51	U	3.56	U	3.59	U	2.97	U	3.22	U	2.15	U
p-Chlorophenylmethyl sulfide (CPMS)	3.53	U	1.46	U	2.07	U	2.09	U	1.73	U	1.87	U	1.25	U
p-Chlorophenylmethyl sulfone (CPMSO2)	7.75	U	3.85	U	5.44	U	5.49	U	4.54	U	4.93	U	3.28	U
p-Chlorophenylmethyl sulfoxide (CPMSO)	7.36	U	4.05	U	5.74	U	5.78	U	4.79	U	5.19	U	3.46	U
Dimethyl disulfide (DMDS)	2.26	U	3.51	U	5.15	U	2.79	U	2.64	U	2.29	U	1.54	U
1,4-Dithiane	4.81	U	0.227	U	0.322	U	0.324	U	0.269	U	0.291	U	0.194	U
1,4-Oxathiane	2.8	U	1.85	U	2.61	U	2.64	U	2.18	U	2.36	U	1.58	U

<sup>a</sup> Sampled by ANL and analyzed by GP Environmental Services.

**Data qualifiers:**

U = analyte was analyzed for but not detected; detection limit given.

NT = not tested.

	Borehole Concentrations ( $\mu\text{g/kg}$ ) at Various Depths							
Compound	JBP1-E-2' (2 ft)	JBP1-E-2'Dup (2 ft)	JBP1-E-4' (4 ft)	JBP1-W-2' (2 ft)	JBP1-W-4' (4 ft)	JBP2-E-2' (2 ft)	JBP2-E-4' (4 ft)	JBP2-E-4'Dup (4 ft)
Acetone	16	14	B	22	11	B	116	18
Benzene	6 U	6 U	U	6 U	6 U	U	6 U	6 U
Bromodichloromethane	6 U	6 U	U	6 U	6 U	U	6 U	6 U
Bromoform	6 U	6 U	U	6 U	6 U	U	6 U	6 U
Bromomethane	12 U	12 U	U	12 U	12 U	U	12 U	12 U
2-Butanone	12 U	12 U	U	12 U	12 U	U	12 U	12 U
Carbon disulfide	6 U	6 U	U	6 U	6 U	U	6 U	6 U
Carbon tetrachloride	6 U	6 U	U	6 U	6 U	U	6 U	6 U
Chlorobenzene	6 U	6 U	U	6 U	6 U	U	6 U	6 U
Chloroethane	12 U	12 U	U	12 U	12 U	U	12 U	12 U
2-Chloroethylvinyl ether	12 U	12 U	U	12 U	12 U	U	12 U	12 U
Chloroform	6 U	6 U	U	6 U	6 U	U	6 U	6 U
Chloromethane	12 U	12 U	U	12 U	12 U	U	12 U	12 U
Dibromochloromethane	6 U	6 U	U	6 U	6 U	U	6 U	6 U
1,1-Dichloroethane	6 U	6 U	U	6 U	6 U	U	6 U	6 U
1,2-Dichloroethane	6 U	6 U	U	6 U	6 U	U	6 U	6 U
1,1,1-Trichloroethane	6 U	6 U	U	6 U	6 U	U	6 U	6 U
trans-1,2-Dichloroethane	2 J	6 U	U	6 U	6 U	U	6 U	6 U
1,2-Dichloropropane	6 U	6 U	U	6 U	6 U	U	6 U	6 U
cis-1,3-Dichloropropene	6 U	6 U	U	6 U	6 U	U	6 U	6 U
trans-1,3-Dichloropropene	6 U	6 U	U	6 U	6 U	U	6 U	6 U
Ethylbenzene	6 U	6 U	U	6 U	6 U	U	6 U	6 U
2-Hexanone	12 U	12 U	U	12 U	12 U	U	12 U	12 U
4-Methyl-2-pentanone	12 U	12 U	U	12 U	12 U	U	12 U	12 U
Methylene chloride	4 J	6 BJ	B	7 B	5 BJ	BJ	6 B	3 BJ
Styrene	6 U	6 U	U	6 U	6 U	U	6 U	6 U

TABLE C.13a (Cont.)

Borehole Concentrations (µg/kg) at Various Depths													
Compound	JBP1-E-2' (2 ft)	JBP1-E-2'Dup (2 ft)	JBP1-E-4' (4 ft)	JBP1-W-2' (2 ft)	JBP1-W-4' (4 ft)	JBP2-E-2' (2 ft)	JBP2-E-4' (4 ft)	JBP2-E-4'Dup (4 ft)					
1,1,1,2-Tetrachloroethane	7	3	J	3	BJ	3	J	6	U				
Tetrachloroethene	6	U	6	U	6	U	6	U	6	U			
Toluene	2	J	3	J	6	U	6	U	6	U			
1,1,1-Trichloroethane	6	U	6	U	6	U	6	U	6	U			
1,1,2-Trichloroethane	6	U	6	U	6	U	6	U	6	U			
Trichloroethene	28	5	J	6	U	6	U	6	U	6	U		
Vinyl acetate	12	U	12	U	12	U	12	U	12	U	12	U	
Vinyl chloride	12	U	12	U	12	U	12	U	12	U	12	U	
Xylenes (total)	6	U	12	6	U	6	U	6	U	6	U	6	U

Borehole Concentrations (µg/kg) at Various Depths								
Compound	JBP2-C-2' (2 ft)	JBP2-C-4' (4 ft)	JBP2-W-2' (2 ft)	JBP2-W-4' (4 ft)	JHDP-C-4' (4 ft)	JHDP-C-6' (6 ft)	JHDP-C-6'Dup (6 ft)	
Acetone	19	B	18	B	17	B	76	113
Benzene	7	U	6	U	6	U	83	58
Bromodichloromethane	7	U	6	U	6	U	2	J
Bromoform	7	U	6	U	6	U	6	U
Bromomethane	14	U	12	U	12	U	12	U
2-Butanone	14	U	12	U	12	U	12	U
Carbon disulfide	7	U	6	U	6	U	1	J
Carbon tetrachloride	7	U	6	U	6	U	172	107
Chlorobenzene	7	U	6	U	6	U	6	U
Chloroethane	14	U	12	U	12	U	12	U
2-Chloroethylvinyl ether	14	U	12	U	12	U	12	U
Chloroform	17	U	6	U	1	J	445	444
Chloromethane	14	U	12	U	12	U	12	U
Dibromochloromethane	7	U	6	U	6	U	6	U

TABLE C.13a (Cont.)

Borehole Concentrations (µg/kg) at Various Depths							
Compound	JBP2-C-2' (2 ft)	JBP2-C-4' (4 ft)	JBP2-W-2' (2 ft)	JBP2-W-4' (4 ft)	JHDP-C-4' (4 ft)	JHDP-C-6' (6 ft)	JHDP-C-6'Dup (6 ft)
1,1-Dichloroethane	7 U	6 U	6 U	6 U	6 U	7	9
1,2-Dichloroethane	2 J	6 U	6 U	6 U	40	53	62
1,1-Dichloroethene	14	6 U	6 U	6 U	31	78	77
trans-1,2-Dichloroethene	92	5 J	16	62	3,860 D	1,710 D	3,220 D
1,2-Dichloropropane	7 U	6 U	6 U	6 U	6 U	6 U	6 U
cis-1,3-Dichloropropene	7 U	6 U	6 U	6 U	6 U	6 U	6 U
trans-1,3-Dichloropropene	7 U	6 U	6 U	6 U	6 U	6 U	6 U
Ethylbenzene	7 U	6 U	6 U	6 U	6 U	6 U	6 U
2-Hexanone	14 U	12 U	12 U	12 U	12 U	12 U	11 U
4-Methyl-2-pentanone	14 U	12 U	12 U	12 U	12 U	12 U	11 U
Methylene chloride	7 B	5 BJ	6 B	6 BJ	45 B	40 B	41 B
Styrene	7 U	6 U	6 U	6 U	6 U	6 U	6 U
1,1,2,2-Tetrachloroethane	7 U	6 U	26 U	16	289,000 D	1,890,000 D	3,270,000 D
Tetrachloroethene	582 D	40	26	9	682	5,730 D	25,700 D
Toluene	7 U	6 U	6 U	6 U	2 J	6 U	6 U
1,1,1-Trichloroethane	7 U	6 U	6 U	6 U	6 U	6 U	6 U
1,1,2-Trichloroethane	7 U	6 U	6 U	6 U	2,100 D	7,860 D	8,540 D
Trichloroethene	499 D	39	176 D	168 D	6,780 D	33,100 D	263,000 D
Vinyl acetate	14 U	12 U	12 U	12 U	12 U	12 U	11 U
Vinyl chloride	14 U	12 U	12 U	12 U	315	170	302
Xylenes (total)	7 U	6 U	6 U	6 U	6 U	6 U	6 U

Borehole Concentrations (µg/kg) at Various Depths								
Compound	JVXP-C-4' (4 ft)	JVXP-C-6' (6 ft)	JSDP-C-4' (4 ft)	JSDP-C-6' (6 ft)	JBPM-A-3" (3 in.)	JBPM-A-3"Dup (3 in.)	JBPM-A-1' (1 ft)	JBPM-B-3" (3 in.)
Acetone	13 U	14 U	344	13 U	67	275	1,460 BJ	324
Benzene	7 U	7 U	33 U	7 U	27 U	30 U	743 U	29 U
Bromodichloromethane	7 U	7 U	33 U	7 U	27 U	30 U	743 U	29 U

TABLE C.13a (Cont.)

Compound	Borehole Concentrations (µg/kg) at Various Depths									
	JVXP-C-4' (4 ft)	JVXP-C-6' (6 ft)	JSDP-C-4' (4 ft)	JSDP-C-6' (6 ft)	JBPM-A-3" (3 in.)	JBPM-A-1' (1 ft)	JBPM-B-3" (3 in.)			
Bromoform	7 U	7 U	33 U	7 U	27 U	743 U	29 U			
Bromomethane	13 U	14 U	67 U	13 U	54 U	1,490 U	57 U			
2-Butanone	13 U	14 U	67 U	13 U	54 U	1,490 U	57 U			
Carbon disulfide	7 U	7 U	33 U	7 U	27 U	743 U	29 U			
Carbon tetrachloride	7 U	7 U	33 U	7 U	27 U	743 U	29 U			
Chlorobenzene	7 U	7 U	33 U	7 U	27 U	743 U	29 U			
Chloroethane	13 U	14 U	67 U	13 U	54 U	1,490 U	57 U			
2-Chloroethylvinyl ether	13 U	14 U	67 U	13 U	54 U	1,490 U	57 U			
Chloroform	7 U	6 J	33 U	7 U	27 U	743 U	29 U			
Chloromethane	13 U	14 U	67 U	13 U	54 U	1,490 U	57 U			
Dibromochloromethane	7 U	7 U	33 U	7 U	27 U	743 U	29 U			
1,1-Dichloroethane	7 U	7 U	33 U	7 U	27 U	743 U	29 U			
1,2-Dichloroethane	7 U	7 U	33 U	7 U	27 U	743 U	29 U			
1,1-Dichloroethene	7 U	7 U	33 U	7 U	27 U	743 U	29 U			
trans-1,2-Dichloroethene	7 U	7 U	78	7 U	27 U	743 U	50			
1,2-Dichloropropane	7 U	7 U	33 U	7 U	27 U	743 U	29 U			
cis-1,3-Dichloropropene	7 U	7 U	33 U	7 U	27 U	743 U	29 U			
trans-1,3-Dichloropropene	7 U	7 U	33 U	7 U	27 U	743 U	29 U			
Ethylbenzene	7 U	7 U	33 U	7 U	27 U	743 U	29 U			
2-Hexanone	13 U	14 U	67 U	13 U	54 U	1,490 U	57 U			
4-Methyl-2-pentanone	13 U	14 U	67 U	13 U	54 U	1,490 U	57 U			
Methylene chloride	7 B	8 B	44 B	12 B	21 BJ	467 BJ	36 B			
Styrene	7 U	7 U	33 U	7 U	27 U	743 U	29 U			
1,1,2,2-Tetrachloroethane	16	39	15,200	26	123	1,460 D	13,200 D			
Tetrachloroethene	7 U	7 U	27 J	7 U	27 U	530 J	17 J			
Toluene	3 J	4 J	33 U	4 J	11 J	743 U	29 U			
1,1,1-Trichloroethane	7 U	7 U	33 U	7 U	27 U	743 U	29 U			
1,1,2-Trichloroethane	7 U	7 U	81	7 U	33	367 J	80			
Trichloroethene	3 J	16	345 D	3 J	245	26,000 D	517			

TABLE C.13a (Cont.)

Borehole Concentrations (µg/kg) at Various Depths								
Compound	JVXP-C-4' (4 ft)	JVXP-C-6' (6 ft)	JSDP-C-4' (4 ft)	JSDP-C-6' (6 ft)	JBPM-A-3" (3 in.)	JBPM-A-3"Dup (3 in.)	JBPM-A-1' (1 ft)	JBPM-B-3" (3 in.)
Vinyl acetate	13 U	14 U	67 U	13 U	54 U	59 U	1,490 U	57 U
Vinyl chloride	13 U	14 U	67 U	13 U	54 U	59 U	1,490 U	57 U
Xylenes (total)	13 U	7 U	33 U	7 U	27 U	30 U	743 U	29 U

Borehole Concentrations (µg/kg) at Various Depths								
Compound	JBPM-B-1' (1 ft)	JBPM-C-3" (3 in.)	JBPM-C-1' (1 ft)	JBPP-A-3" (3 in.)	JBPP-A-1' (1 ft)	JBPP-B-3" (3 in.)	JBPP-B-1' (1 ft)	JBPP-C-1' (1 ft)
Acetone	1,060 BJ	13 U	57	8 BJ	32 B	14 U	20	20
Benzene	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U
Bromodichloromethane	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U
Bromoform	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U
Bromomethane	1,460 U	13 U	11 U	12 U	12 U	14 U	12 U	12 U
2-Butanone	1,460 U	13 U	11 U	12 U	12 U	14 U	12 U	12 U
Carbon disulfide	731 U	1 J	6 U	6 U	6 U	7 U	6 U	6 U
Carbon tetrachloride	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U
Chlorobenzene	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U
Chloroethane	1,460 U	13 U	11 U	12 U	12 U	14 U	12 U	12 U
2-Chloroethylvinyl ether	1,460 U	13 U	11 U	12 U	12 U	14 U	12 U	12 U
Chloroform	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U
Chloromethane	1,460 U	13 U	11 U	12 U	12 U	14 U	12 U	12 U
Dibromochloromethane	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U
1,1-Dichloroethane	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U
1,2-Dichloroethane	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U
1,1-Dichloroethene	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U
trans-1,2-Dichloroethene	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U
1,2-Dichloropropane	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U
cis-1,3-Dichloropropene	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U
trans-1,3-Dichloropropene	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U

TABLE C.13a (Cont.)

Compound	Borehole Concentrations (µg/kg) at Various Depths								
	JBPM-B-1' (1 ft)	JBPM-C-3" (3 in.)	JBPM-C-1' (1 ft)	JBPP-A-3" (3 in.)	JBPP-A-1' (1 ft)	JBPP-B-3" (3 in.)	JBPP-B-1' (1 ft)	JBPP-C-3" (3 in.)	JBPP-C-1' (1 ft)
Ethylbenzene	731 U	2 J	6 U	6 U	6 U	7 U	6 U	6 U	6 U
2-Hexanone	1,460 U	13 U	11 U	12 U	12 U	14 U	12 U	12 U	12 U
4-Methyl-2-pentanone	1,460 U	13 U	11 U	12 U	12 U	14 U	12 U	12 U	12 U
Methylene chloride	451 BJ	9 B	6 B	7 B	8 B	8 B	8	5 J	6
Styrene	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U	6 U
1,1,2,2-Tetrachloroethane	15,200	71	41	7	5 J	4 J	2 J	6 U	9
Tetrachloroethene	731 U	6 U	6 U	6 U	6 U	24	99	6 U	6 U
Toluene	731 U	7	6 U	6 U	2 J	7 U	3 J	6 U	6 U
1,1,1-Trichloroethane	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U	6 U
1,1,2-Trichloroethane	731 U	6 U	6 U	6 U	6 U	7 U	6 U	6 U	6 U
Trichloroethene	251 J	10	3 J	6 J	6 U	9	31	6 U	6 U
Vinyl acetate	1,460 U	13 U	11 U	12 U	12 U	14 U	12 U	12 U	12 U
Vinyl chloride	1,460 U	13 U	11 U	12 U	12 U	14 U	12 U	12 U	12 U
Xylenes (total)	731 U	9	6 U	6 U	6 U	7 U	6 U	6 U	6 U

<sup>a</sup> Sampled by Weston, analyzed by GP Environmental Services, TCL volatile organics-SW846 8240s; provisional data.

Data qualifiers:

U = analyte was analyzed for but not detected.

J = estimated value.

B = analyte was found in the associated blank.

D = sample was diluted for analysis.

TABLE C.13b Volatile Organics Analyses for Soil Borings, January 1994<sup>a</sup>

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals						
	CLP1 (0-6 in.)	CLP1 (6-24 in.)	CLP1-RE (6-24 in.)	CLP1 (24-40 in.)	CLP2 (0-6 in.)	CLP2 (6-24 in.)	CLP2-RE (6-24 in.)
Acetone	21 B	9 JB	24 B	13 U	13 U	28 B	54 B
Benzene	15 U	13 U	13 U	13 U	13 U	13 U	13 U
Bromodichloromethane	15 U	13 U	13 U	13 U	13 U	13 U	13 U
Bromoform	15 U	13 U	13 U	13 U	13 U	13 U	13 U
Bromomethane	15 U	13 U	13 U	13 U	13 U	13 U	13 U
2-Butanone	15 U	13 U	13 U	13 U	13 U	13 U	13 U
Carbon disulfide	15 U	13 U	13 U	13 U	13 U	13 U	13 U
Carbon tetrachloride	15 U	13 U	13 U	13 U	13 U	13 U	13 U
Chlorobenzene	15 U	8 J	5 J	7 J	13 U	13 U	13 U
Chloroethane	15 U	13 U	13 U	13 U	13 U	13 U	13 U
Chloroform	15 U	13 U	13 U	13 U	13 U	13 U	13 U
Chloromethane	15 U	13 U	13 U	13 U	13 U	13 U	13 U
Dibromochloromethane	15 U	13 U	13 U	13 U	13 U	13 U	13 U
1,1-Dichloroethane	15 U	13 U	13 U	13 U	13 U	13 U	13 U
1,2-Dichloroethane	15 U	13 U	13 U	13 U	13 U	13 U	13 U
1,1-Dichloroethene	15 U	13 U	13 U	13 U	13 U	13 U	13 U
1,2-Dichloroethene (total)	15 U	13 U	13 U	13 U	13 U	13 U	13 U
cis-1,3-Dichloropropene	15 U	13 U	13 U	13 U	13 U	13 U	13 U
1,2-Dichloropropene	15 U	13 U	13 U	13 U	13 U	13 U	13 U
trans-1,3-Dichloropropene	15 U	13 U	13 U	13 U	13 U	13 U	13 U
Ethylbenzene	15 U	13 U	13 U	13 U	13 U	13 U	13 U
2-Hexanone	15 U	13 U	13 U	13 U	13 U	13 U	13 U
4-Methyl-2-pentanone	15 U	13 U	13 U	13 U	13 U	13 U	13 U
Methylene chloride	15 U	13 U	13 U	13 U	13 U	13 U	13 U
Styrene	15 U	13 U	13 U	13 U	13 U	13 U	13 U
1,1,2,2- Tetrachloroethane	15 U	13 U	13 U	13 U	13 U	13 U	13 U
Tetrachloroethene	15 U	3 J	3 J	13 U	13 U	13 U	13 U

TABLE C.13b (Cont.)

Soil Concentrations (µg/kg) at Various Depth Intervals							
Compound	CLP1 (0-6 in.)	CLP1 (6-24 in.)	CLP1-RE (6-24 in.)	CLP1 (24-40 in.)	CLP2 (0-6 in.)	CLP2 (6-24 in.)	CLP2-RE (6-24 in.)
Toluene	15 U	4 J	4 J	5 J	13 U	13 U	13 U
1,1,1-Trichloroethane	15 U	13 U	13 U	13 U	13 U	13 U	13 U
1,1,2-Trichloroethane	15 U	13 U	13 U	13 U	13 U	13 U	13 U
Trichloroethene	5 J	5 J	4 J	3 J	13 U	13 U	13 U
Vinyl chloride	15 U	13 U	13 U	13 U	13 U	13 U	13 U
Xylenes (total)	15 U	13 U	13 U	13 U	13 U	13 U	13 U

Soil Concentrations (µg/kg) at Various Depth Intervals							
Compound	CLP2 (24-48 in.)	CLP2-RE (24-48 in.)	CLP3 (0-6 in.)	CLP3 (6-24 in.)	CLP3-RE (6-24 in.)	CLP3-Dup (6-24 in.)	CLP3 (24-48 in.)
Acetone	150 U	220 B	55 B	23 B	27 B	15 U	29 U
Benzene	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Bromodichloromethane	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Bromoform	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Bromomethane	15 U	15 U	18 U	15 U	15 U	15 U	29 U
2-Butanone	26	36	18 U	15 U	15 U	15 U	29 U
Carbon disulfide	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Carbon tetrachloride	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Chlorobenzene	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Chloroethane	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Chloroform	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Chloromethane	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Dibromochloromethane	15 U	15 U	18 U	15 U	15 U	15 U	29 U
1,1-Dichloroethane	15 U	15 U	18 U	15 U	15 U	15 U	29 U
1,2-Dichloroethane	15 U	15 U	18 U	15 U	15 U	15 U	29 U
1,1-Dichloroethene	15 U	15 U	18 U	15 U	15 U	15 U	29 U

TABLE C.13b (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals						
	CLP2 (24-48 in.)	CLP2-RE (24-48 in.)	CLP3 (0-6 in.)	CLP3 (6-24 in.)	CLP3-RE (6-24 in.)	CLP3-Dup (6-24 in.)	CLP3 (24-48 in.)
1,2-Dichloroethene (total)	15 U	15 U	18 U	15 U	15 U	15 U	29 U
1,2-Dichloropropane	15 U	15 U	18 U	15 U	15 U	15 U	29 U
cis-1,3-Dichloropropane	15 U	15 U	18 U	15 U	15 U	15 U	29 U
trans-1,3-Dichloropropene	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Ethylbenzene	15 U	15 U	18 U	15 U	15 U	15 U	29 U
2-Hexanone	15 U	15 U	18 U	15 U	15 U	15 U	29 U
4-Methyl-2-pentanone	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Methylene chloride	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Styrene	15 U	15 U	18 U	15 U	15 U	15 U	29 U
1,1,2,2-Tetrachloroethane	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Tetrachloroethene	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Toluene	8 J	6 J	18 U	15 U	15 U	15 U	60
1,1,1-Trichloroethane	15 U	15 U	18 U	15 U	15 U	15 U	29 U
1,1,2-Trichloroethane	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Trichloroethene	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Vinyl chloride	15 U	15 U	18 U	15 U	15 U	15 U	29 U
Xylenes (total)	15 U	15 U	18 U	15 U	15 U	15 U	29 U

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals						
	CLP3-RE (24-48 in.)	CLP4 (0-6 in.)	CLP4 (6-24 in.)	CLP4 (24-48 in.)	CLP5 (0-6 in.)	CLP5 (6-24 in.)	CLP5-Dup (24-48 in.)
Acetone	29 U	14 U	16 B	62 B	13 U	12 U	13 U
Benzene	29 U	14 U	13 U	26 U	13 U	12 U	13 U
Bromodichloromethane	29 U	14 U	13 U	26 U	13 U	12 U	13 U
Bromoform	29 U	14 U	13 U	26 U	13 U	12 U	13 U
Bromomethane	29 U	14 U	13 U	26 U	13 U	12 U	13 U

TABLE C.13b (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals									
	CLP3-RE (24-48 in.)	CLP4 (0-6 in.)	CLP4 (6-24 in.)	CLP4 (24-48 in.)	CLP5 (0-6 in.)	CLP5 (6-24 in.)	CLP5 (24-48 in.)	CLP5-Dup (24-48 in.)		
2-Butanone	29 U	14 U	13 U	26 U	13 U	12 U	20	13 U		
Carbon disulfide	29 U	14 U	13 U	29	13 U	12 U	14 U	13 U		
Carbon tetrachloride	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
Chlorobenzene	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
Chloroethane	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
Chloroform	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
Chloromethane	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
Dibromochloromethane	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
1,1-Dichloroethane	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
1,2-Dichloroethane	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
1,1,1-Trichloroethane	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
1,2-Dichloroethene (total)	29 U	14 U	13 U	600	16	13	180	83		
1,2-Dichloropropane	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
cis-1,3-Dichloropropene	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
trans-1,3-Dichloropropene	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
Ethylbenzene	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
2-Hexanone	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
4-Methyl-2-pentanone	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
Methylene chloride	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
Styrene	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
1,1,2,2-Tetrachloroethane	29 U	14 U	13 U	5,600	13 U	12 U	14 U	13 U		
Tetrachloroethene	29 U	14 U	13 U	1,500	13 U	12 U	14 U	13 U		
Toluene	29 U	14 U	13 U	99	12 J	27	33	6 J		
1,1,1-Trichloroethane	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
1,1,2-Trichloroethane	29 U	14 U	13 U	500	13 U	12 U	14 U	13 U		
Trichloroethene	29 U	14 U	13 U	3,100	22	17	9 J	3 J		
Vinyl chloride	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		
Xylenes (total)	29 U	14 U	13 U	26 U	13 U	12 U	14 U	13 U		

TABLE C.13b (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals									
	CLP6 (0-6 in.)	CLP6 (6-24 in.)	CLP7 (0-6 in.)	CLP7 (6-24 in.)	CLP7 (24-48 in.)	CLP8 (0-6 in.)	CLP8-RE (0-6 in.)	CLP9 (0-6 in.)		
Acetone	13 U	20	16 U	13 U	13 U	31 U	31 U	12 U		
Benzene	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
Bromodichloromethane	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
Bromoform	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
Bromomethane	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
2-Butanone	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
Carbon disulfide	13 U	4 J	16 U	13 U	13 U	31 U	31 U	12 U		
Carbon tetrachloride	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
Chlorobenzene	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
Chloroethane	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
Chloroform	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
Chloromethane	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
Dibromochloromethane	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
1,1-Dichloroethane	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
1,2-Dichloroethane	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
1,1,1-Dichloroethene	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
1,2-Dichloroethene (total)	11 J	48	16 U	13 U	13 U	28 J	8 J	20 J		
1,2-Dichloropropane	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
cis-1,3-Dichloropropene	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
trans-1,3-Dichloropropene	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
Ethylbenzene	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
2-Hexanone	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
4-Methyl-2-pentanone	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
Methylene chloride	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
Styrene	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
1,1,2,2-Tetrachloroethane	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
Tetrachloroethene	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U		
Toluene	17	24	16 U	13 U	13 U	31 U	31 U	12 U		

TABLE C.13b (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals							
	CLP6 (0-6 in.)	CLP6 (6-24 in.)	CLP7 (0-6 in.)	CLP7 (6-24 in.)	CLP7 (24-48 in.)	CLP8 (0-6 in.)	CLP8-RE (0-6 in.)	CLP9 (0-6 in.)
1,1,1-Trichloroethane	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U
1,1,2-Trichloroethane	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U
Trichloroethene	5 J	5 J	16 U	13 U	13 U	31 U	31 U	11 J
Vinyl chloride	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U
Xylenes (total)	13 U	13 U	16 U	13 U	13 U	31 U	31 U	12 U

<sup>a</sup> Sampled by ANL, analyzed by Weston Gulf Coast, TCL volatile organics-SW846 8240s.

Data qualifiers:

U = analyte was analyzed for but not detected.

B = analyte was found in the associated blank.

J = estimated value.

E = analyte concentration exceeded calibration range of instrument; concentration estimated.

TABLE C.13c Volatile Organics Analyses for Soil Borings, May 1994<sup>a</sup>

Soil Concentrations (µg/kg) at Various Depth Intervals						
Compound	TBSPBOR1 (0-2 ft)	TSBPBOR1-RE (0-2 ft)	TBSPBOR1-Dup (0-2 ft)	TSBPBOR1-Dup-RE (0-2 ft)	TBSPBOR1 (2-4 ft)	TSBPBOR1-RE (2-4 ft)
Acetone	350	B*	12	U**	18	B
Benzene	12	U*	12	U**	12	U
Bromodichloromethane	12	U*	12	U**	12	J
Bromoform	12	U*	12	U**	12	U
Bromomethane	12	U*	12	U**	12	U
2-Butanone	37	*	12	U**	12	U
Carbon disulfide	12	U*	12	U**	12	U
Carbon tetrachloride	12	U*	12	U**	12	U
Chlorobenzene	12	U*	12	U**	12	U
Chloroethane	12	U*	12	U**	12	U
Chloroform	12	U*	12	U**	12	U
Chloromethane	12	U*	12	U**	12	U
Dibromochloromethane	12	U*	12	U**	12	U
1,1-Dichloroethane	12	U*	12	U**	12	U
1,2-Dichloroethane	12	U*	12	U**	12	U
1,1-Dichloroethene	12	U*	12	U**	12	U
1,2-Dichloroethene (total)	86	*	170	**	12	U
1,2-Dichloropropane	12	U*	12	U**	14	J
cis-1,3-Dichloropropene	12	U*	12	U**	12	U
trans-1,3-Dichloropropene	12	U*	12	U**	12	U
Ethylbenzene	12	U*	12	U**	12	U
2-Hexanone	12	U*	12	U**	12	U
4-Methyl-2-pentanone	12	U*	12	U**	12	U
Methylene chloride	4	J*	12	U**	12	U
		83			12	U
						63

TABLE C.13c (Cont.)

Soil Concentrations (µg/kg) at Various Depth Intervals						
Compound	TBSPBOR1 (0-2 ft)	TBSPBOR1-RE (0-2 ft)	TBSPBOR1-Dup (0-2 ft)	TBSPBOR1-Dup-RE (0-2 ft)	TBSPBOR1 (2-4 ft)	TBSPBOR1-RE (2-4 ft)
Styrene	12 U*	12 U	12 U**	12 U	12 U	12 U
1,1,2,2-Tetrachloroethane	49 *	9 J	100 **	19	8 J	14
Tetrachloroethene	12 U*	12 U	12 U**	12 U	12 U	12 U
Toluene	12 U*	12 U	12 U**	12 U	12 U	12 U
1,1,1-Trichloroethane	12 U*	12 U	12 U**	12 U	12 U	12 U
1,1,2-Trichloroethane	12 U*	12 U	12 U**	12 U	12 U	12 U
Trichloroethene	50 *	4 J	37 **	10 J	12 U	12 U
Vinyl chloride	12 U*	12 U	12 U**	12 U	12 U	12 U
Xylenes (total)	12 U*	12 U	12 U**	12 U	12 U	12 U

Soil Concentrations (µg/kg) at Various Depth Intervals						
Compound	TBSPBOR1 (4-6 ft)	TBSPBOR1 (6-8 ft)	TBSPBOR1 (8-10 ft)	TBSPBOR1 (10-12 ft)	TBSPBOR2 (0-2 ft)	TBSPBOR2-Dup (0-2 ft)
Acetone	280 B	42	42	30	12 U	12 U
Benzene	12 U	5 J	12 U	12 U	12 U	12 U*
Bromodichloromethane	12 U	12 U	12 U	12 U	12 U	12 U*
Bromoform	12 U	12 U	12 U	12 U	12 U	12 U*
Bromomethane	12 U	12 U	12 U	12 U	12 U	12 U
2-Butanone	12 U	12 U	12 U	12 U	12 U	12 U
Carbon disulfide	6 J	4 J	12 U	12 U	12 U	12 U
Carbon tetrachloride	12 U	12 U	12 U	12 U	12 U	12 U*
Chlorobenzene	12 U	12 U	12 U	12 U	12 U	12 U*

TABLE C.13c (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	TBSPBOR1 (4-6 ft)	TBSPBOR1 (6-8 ft)	TBSPBOR1 (8-10 ft)	TBSPBOR1 (10-12 ft)	TBSPBOR2 (0-2 ft)	TBSPBOR2- Dup (0-2 ft)
Chloroethane	12 U	12 U	12 U	12 U	12 U	12 U
Chloroform	12 U	12 U	12 U	12 U	12 U	12 U
Chloromethane	12 U	12 U	12 U	12 U	12 U	12 U
Dibromochloromethane	12 U	12 U	12 U	12 U	12 U	12 U*
1,1-Dichloroethane	12 U	12 U	12 U	12 U	12 U	12 U
1,2-Dichloroethane	12 U	4 J	12 U	12 U	12 U	12 U
1,1,1-Dichloroethene	12 U	15	12 U	12 U	12 U	12 U
1,2-Dichloroethene (total)	68	4,400	1,500	11 J	12 U	12 U
1,2-Dichloropropane	12 U	12 U	12 U	12 U	12 U	12 U*
cis-1,3-Dichloropropene	12 U	12 U	12 U	12 U	12 U	12 U*
trans-1,3-Dichloropropene	12 U	12 U	12 U	12 U	12 U	12 U*
Ethylbenzene	12 U	19	12 U	12 U	12 U	12 U*
2-Hexanone	12 U	12 U	12 U	12 U	12 U	12 U*
4-Methyl-2-pentanone	12 U	12 U	12 U	12 U	12 U	12 U*
Methylene chloride	12 U	12 U	12 U	12 U	12 U	12 U
Styrene	12 U	12 U	12 U	12 U	12 U	12 U*
1,1,2,2-Tetrachloroethane	9 J	7 J	600	280	12	2 J*
Tetrachloroethene	12 U	12 U	41	12 U	12 U	12 U*
Toluene	12 U	8 J	12 U	12 U	12 U	12 U*
1,1,1-Trichloroethane	12 U	12 U	12 U	12 U	12 U	12 U*
1,1,2-Trichloroethane	12 U	3 J	140	15	12 U	12 U*
Trichloroethene	4 J	370	550	12	12 U	12 U*
Vinyl chloride	19	180	16	12 U	12 U	12 U
Xylenes (total)	16	12 J	12 U	12 U	12 U	12 U

TABLE C.13c (Cont.)

Compound	Soil Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals					
	TSBPBOR2-REDup (0-2 ft)	TBSPBOR2 (2-4 ft)	TBSPBOR2 (4-6 ft)	TBSPBOR2 (6-8 ft)	TBSPBOR2 (8-10 ft)	
Acetone	12	12	97	120	130	B
Benzene	12	12	120	120	120	U
Bromodichloromethane	12	12	120	120	120	U
Bromoform	12	12	120	120	120	U
Bromomethane	12	12	120	120	120	U
2-Butanone	12	12	120	120	120	U
Carbon disulfide	12	12	120	120	120	U
Carbon tetrachloride	12	12	120	120	120	U
Chlorobenzene	12	12	120	120	120	U
Chloroethane	12	12	120	120	120	U
Chloroform	12	12	120	120	120	U
Chloromethane	12	12	120	120	120	U
Dibromochloromethane	12	12	120	120	120	U
1,1-Dichloroethane	12	12	120	120	120	U
1,2-Dichloroethane	12	12	120	120	120	U
1,1-Dichloroethene	12	12	120	120	120	U
1,2-Dichloroethene (total)	12	12	120	460	8,400	U
1,2-Dichloropropane	12	12	120	120	120	U
cis-1,3-Dichloropropene	12	12	120	120	120	U
trans-1,3-Dichloropropene	12	12	120	120	120	U
Ethylbenzene	12	12	120	120	120	U
2-Hexanone	12	12	120	120	120	U
4-Methyl-2-pentanone	12	12	120	120	120	U

TABLE C.13c (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	TBSPBOR2-REDup (0-2 ft)	TBSPBOR2 (2-4 ft)	TBSPBOR2 (4-6 ft)	TBSPBOR2 (6-8 ft)	TBSPBOR2 (8-10 ft)	
Methylene chloride	12 U	12 U	120 U	120 U	120 U	
Styrene	12 U	12 U	120 U	120 U	120 U	
1,1,2,2-Tetrachloroethane	14	130	4,600	24,000	220,000	
Tetrachloroethene	12 U	12 U	25 J	140	2,500	
Toluene	12 U	12 U	120 U	120 U	120 U	
1,1,1-Trichloroethane	12 U	12 U	120 U	120 U	120 U	
1,1,2-Trichloroethane	12 U	12 U	140	330	1,600	
Trichloroethene	12 U	12 U	350	1,200	21,000 J	
Vinyl chloride	12 U	12 U	120 U	120 U	120 U	
Xylenes (total)	12 U	12 U	120 U	120 U	120 U	

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	HBOR1 (0-2 ft)	HBOR1 (2-4 ft)	HBOR1 (4-6 ft)	HBOR1 (6-8 ft)	HBOR1 (8-10 ft)	HBOR2 (0-2 ft)
Acetone	13 U*	15 B*	120 U	58 U	14 B	12 U
Benzene	13 U*	12 U*	120 U	58 U	12 U	12 U
Bromodichloromethane	13 U*	12 U*	120 U	58 U	12 U	12 U
Bromoform	13 U*	12 U*	120 U	58 U	12 U	12 U
Bromomethane	13 U*	12 U*	120 U	58 U	12 U	12 U
2-Butanone	13 U*	12 U*	120 U	58 U	12 U	12 U
Carbon disulfide	13 U*	12 U*	120 U	58 U	12 U	12 U
Carbon tetrachloride	13 U*	12 U*	120 U	58 U	12 U	12 U
Chlorobenzene	13 U*	5 J*	120 U	58 U	12 U	12 U
Chloroethane	13 U*	12 U*	120 U	58 U	12 U	12 U
Chloroform	13 U*	12 U*	120 U	58 U	12 U	12 U

TABLE C.13c (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	HBOR1 (0-2 ft)	HBOR1 (2-4 ft)	HBOR1 (4-6 ft)	HBOR1 (6-8 ft)	HBOR1 (8-10 ft)	HBOR2 (0-2 ft)
Chloromethane	13 U*	12 U*	120 U	58 U	12 U	12 U
Dibromochloromethane	13 U*	12 U*	120 U	58 U	12 U	12 U
1,1-Dichloroethane	13 U*	12 U*	120 U	58 U	12 U	12 U
1,2-Dichloroethane	13 U*	12 U*	120 U	58 U	12 U	12 U
1,1-Dichloroethene	13 U*	12 U*	120 U	58 U	12 U	12 U
1,2-Dichloroethene (total)	120 U*	17 *	120 U	58 U	12 U	12 U
1,2-Dichloropropane	13 U*	12 U*	120 U	58 U	12 U	12 U
cis-1,3-Dichloropropene	13 U*	12 U*	120 U	58 U	12 U	12 U
trans-1,3-Dichloropropene	13 U*	12 U*	120 U	58 U	12 U	12 U
Ethylbenzene	13 U*	12 U*	120 U	58 U	12 U	12 U
2-Hexanone	13 U*	12 U*	120 U	58 U	12 U	12 U
4-Methyl-2-pentanone	13 U*	12 U*	120 U	58 U	12 U	12 U
Methylene chloride	13 U*	12 U*	120 U	58 U	12 U	12 U
Styrene	13 U*	12 U*	120 U	58 U	12 U	12 U
1,1,2,2-Tetrachloroethane	18 U*	44 *	120 U	17 J	96	12 U
Tetrachloroethene	13 U*	12 U*	120 U	58 U	12 U	12 U
Toluene	13 U*	12 U*	120 U	58 U	12 U	12 U
1,1,2-Trichloroethane	13 U*	12 U*	120 U	58 U	12 U	12 U
1,1,1-Trichloroethane	13 U*	12 U*	120 U	58 U	12 U	12 U
Trichloroethene	130 U*	9 J*	120 U	60	22	12 U
Vinyl chloride	13 U*	12 U*	120 U	58 U	30	3 J
Xylenes (total)	13 U*	12 U*	120 U	58 U	12 U	12 U



TABLE C.13c (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	HBOR2 (2-4 ft)	HBOR2 (4-6 ft)	HBOR2 (6-8 ft)	HBOR2 (8-10 ft)	TBNPBOR1 (0-2 ft)	TBNPBOR1 (2-4 ft)
Tetrachloroethene	12 U	12 U	12 U	12 U	9 J*	19
Toluene	12 U	12 U	12 U	12 U	12 U*	12 U
1,1,1-Trichloroethane	12 U	12 U	12 U	12 U	12 U*	12 U
1,1,2-Trichloroethane	12 U	12 U	12 U	12 U	12 U*	12 U
Trichloroethene	12 U	12 U	12 U	12 U	5 J	230
Vinyl chloride	12 U	12 U	12 U	12 U	12 U	12 U
Xylenes (total)	12 U	12 U	12 U	12 U	12 U*	12 U

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals			
	TBNPBOR1 (4-6 ft)	TBNPBOR1 (6-8 ft)	TBNPBOR1 (8-10 ft)	
Acetone	22 B	12 U	12 U	
Benzene	12 U	12 U	12 U	
Bromodichloromethane	12 U	12 U	12 U	
Bromoform	12 U	12 U	12 U	
Bromomethane	12 U	12 U	12 U	
2-Butanone	12 U	12 U	12 U	
Carbon disulfide	12 U	12 U	12 U	
Carbon tetrachloride	12 U	12 U	12 U	
Chlorobenzene	12 U	12 U	12 U	
Chloroethane	12 U	12 U	12 U	
Chloroform	9 J	12 U	12 U	
Chloromethane	12 U	12 U	12 U	
Dibromochloromethane	12 U	12 U	12 U	

TABLE C.13c (Cont.)

Soil Concentrations (µg/kg) at Various Depth Intervals				
Compound	TBNPBOR1 (4-6 ft)	TBNPBOR1 (6-8 ft)	TBNPBOR1 (8-10 ft)	
1,1-Dichloroethane	12 U	12 U	12 U	
1,2-Dichloroethane	12 U	12 U	12 U	
1,1-Dichloroethene	12 U	12 U	12 U	
1,2-Dichloroethene (total)	490	190	23	
1,2-Dichloropropane	12 U	12 U	12 U	
cis-1,3-Dichloropropene	12 U	12 U	12 U	
trans-1,3-Dichloropropene	12 U	12 U	12 U	
Ethylbenzene	12 U	12 U	12 U	
2-Hexanone	12 U	12 U	12 U	
4-Methyl-2-pentanone	12 U	12 U	12 U	
Methylene chloride	12 U	12 U	12 U	
Styrene	12 U	12 U	12 U	
1,1,2,2-Tetrachloroethane	160	17	4 J	
Tetrachloroethene	2 J	12 U	12 U	
Toluene	12 U	12 U	12 U	
1,1,1-Trichloroethane	12 U	12 U	12 U	
1,1,2-Trichloroethane	12 U	12 U	12 U	
Trichloroethene	140	58	12	
Vinyl chloride	12 U	12 U	12 U	
Xylenes (total)	12 U	12 U	12 U	

Soil Concentrations (µg/kg) at Various Depth Intervals					
Compound	VXBOR1 (0-2 ft)	VXBOR1 (4-6 ft)	VXBOR1 (6-8 ft)	VXBOR1 (8-10 ft)	VXBOR2 (0-2 ft)
Acetone	12 U	26	14 U	12 U	12 U
Benzene	12 U	12 U	14 U	12 U	12 U

TABLE C.13c (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	VXBOR1 (0-2 ft)	VXBOR1 (4-6 ft)	VXBOR1 (6-8 ft)	VXBOR1 (8-10 ft)	VXBOR1 (9.5-10 ft)	VXBOR2 (0-2 ft)
Bromodichloromethane	12	U	14	U	12	U
Bromoform	12	U	14	U	12	U
Bromomethane	12	U	14	U	12	U
2-Butanone	12	U	14	U	12	U
Carbon disulfide	12	U	14	U	12	U
Carbon tetrachloride	12	U	14	U	12	U
Chlorobenzene	12	U	14	U	12	U
Chloroethane	12	U	14	U	12	U
Chloroform	12	U	14	U	12	U
Chloromethane	12	U	14	U	12	U
Dibromochloromethane	12	U	14	U	12	U
1,2-Dichloroethane	12	U	14	U	12	U
1,1-Dichloroethane	12	U	14	U	12	U
1,1-Dichloroethene	12	U	14	U	12	U
trans-1,2-Dichloroethene	12	U	14	U	12	U
cis-1,2-Dichloroethene	12	U	14	U	12	U
1,2-Dichloropropane	12	U	14	U	12	U
trans-1,3-Dichloropropene	12	U	14	U	12	U
cis-1,3-Dichloropropene	12	U	14	U	12	U
Ethyl benzene	12	U	14	U	12	U
2-Hexanone	12	U	14	U	12	U
4-Methyl-2-pentanone	12	U	14	U	12	U
Methylene chloride	17	U	10	J	12	U
Styrene	12	U	14	U	12	U
1,1,2,2-Tetrachloroethane	12	U	14	U	12	U

TABLE C.13c (Cont.)

Soil Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals						
Compound	VXBOR1 (0-2 ft)	VXBOR1 (4-6 ft)	VXBOR1 (6-8 ft)	VXBOR1 (8-10 ft)	VXBOR1 (9.5-10 ft)	VXBOR2 (0-2 ft)
Tetrachloroethene	12 U	12 U	14 U	12 U	12 U	12 U
Toluene	12 U	12 U	14 U	12 U	12 U	12 U
1,1,2-Trichloroethane	12 U	12 U	14 U	12 U	12 U	12 U
1,1,1-Trichloroethane	12 U	12 U	14 U	12 U	12 U	12 U
Trichloroethene	12 U	12 U	14 U	12 U	12 U	12 U
Vinyl acetate	12 U	12 U	14 U	12 U	12 U	12 U
Vinyl chloride	12 U	12 U	14 U	12 U	12 U	12 U
m- and p-Xylene	12 U	12 U	14 U	12 U	12 U	12 U
o-Xylene	12 U	12 U	14 U	12 U	12 U	12 U
Soil Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals						
Compound	VXBOR2 (2-4 ft)	VXBOR2 (4-6 ft)	FTBOR1 (0-2 ft)	FTBOR1-Dup (0-2 ft)	FTBOR1 (2-4 ft)	FTBOR1-Dup (2-4 ft)
Acetone	12 U	12 U	12 U	12 U	12 U	11 U
Benzene	12 U	12 U	12 U	12 U	12 U	11 U
Bromodichloromethane	12 U	12 U	12 U	12 U	12 U	11 U
Bromoform	12 U	12 U	12 U	12 U	12 U	11 U
Bromomethane	12 U	12 U	12 U	12 U	12 U	11 U
2-Butanone	12 U	12 U	12 U	12 U	12 U	11 U
Carbon disulfide	12 U	12 U	12 U	12 U	12 U	11 U
Carbon tetrachloride	12 U	12 U	12 U	12 U	12 U	11 U
Chlorobenzene	12 U	12 U	12 U	12 U	12 U	11 U
Chloroethane	12 U	12 U	12 U	12 U	12 U	11 U
Chloroform	12 U	12 U	12 U	12 U	12 U	11 U
Chloromethane	12 U	12 U	12 U	12 U	12 U	11 U

TABLE C.13c (Cont.)

Soil Concentrations (µg/kg) at Various Depth Intervals						
Compound	VXBOR2 (2-4 ft)	VXBOR2 (4-6 ft)	FTBOR1 (0-2 ft)	FTBOR1-Dup (0-2 ft)	FTBOR1 (2-4 ft)	FTBOR1-Dup (2-4 ft)
Dibromochloromethane	12 U	12 U	12 U	12 U	12 U	11 U
1,1-Dichloroethane	12 U	12 U	12 U	12 U	12 U	11 U
1,2-Dichloroethane	12 U	12 U	12 U	12 U	12 U	11 U
1,1-Dichloroethene	12 U	12 U	12 U	12 U	12 U	11 U
cis-1,2-Dichloroethene	12 U	12 U	12 U	12 U	12 U	11 U
trans-1,2-Dichloroethene	12 U	12 U	12 U	12 U	12 U	11 U
1,2-Dichloropropane	12 U	12 U	12 U	12 U	12 U	11 U
cis-1,3-Dichloropropene	12 U	12 U	12 U	12 U	12 U	11 U
trans-1,3-Dichloropropene	12 U	12 U	12 U	12 U	12 U	11 U
Ethyl benzene	12 U	12 U	12 U	12 U	12 U	11 U
2-Hexanone	12 U	12 U	12 U	12 U	12 U	11 U
4-Methyl-2-pentanone	12 U	12 U	12 U	12 U	12 U	11 U
Methylene chloride	12 U	12 U	12 U	12 U	12 U	11 U
Styrene	12 U	12 U	12 U	12 U	10 J	11 U
1,1,2,2-Tetrachloroethane	12 U	12 U	12 U	12 U	12 U	11 U
Tetrachloroethene	12 U	12 U	12 U	12 U	12 U	11 U
Toluene	12 U	12 U	12 U	12 U	12 U	11 U
1,1,2-Trichloroethane	12 U	12 U	12 U	12 U	12 U	11 U
1,1,1-Trichloroethane	12 U	12 U	12 U	12 U	12 U	11 U
Trichloroethene	12 U	12 U	12 U	12 U	12 U	11 U
Vinyl acetate	12 U	12 U	12 U	12 U	12 U	11 U
Vinyl chloride	12 U	12 U	12 U	12 U	12 U	11 U
m- and p-Xylene	12 U	12 U	12 U	12 U	12 U	11 U
o-Xylene	12 U	12 U	12 U	12 U	12 U	11 U

TABLE C.13c (Cont.)

Compound	Soil Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals			
	FTBORI (4-6 ft)	FTBORI (6-8 ft)	FTBORI (8-10 ft)	FTBORI (10-12 ft)
Acetone	12 U	12 U	17 B	12 U
Benzene	12 U	12 U	14 U	12 U
Bromodichloromethane	12 U	12 U	14 U	12 U
Bromoform	12 U	12 U	14 U	12 U
Bromomethane	12 U	12 U	14 U	12 U
2-Butanone	12 U	12 U	14 U	12 U
Carbon disulfide	12 U	12 U	14 U	12 U
Carbon tetrachloride	12 U	12 U	14 U	12 U
Chlorobenzene	12 U	12 U	14 U	12 U
Chloroethane	12 U	12 U	14 U	12 U
Chloroform	12 U	12 U	14 U	12 U
Chloromethane	12 U	12 U	14 U	12 U
Dibromochloromethane	12 U	12 U	14 U	12 U
1,1-Dichloroethane	12 U	12 U	14 U	12 U
1,2-Dichloroethane	12 U	12 U	14 U	12 U
1,1,1-Trichloroethane	12 U	12 U	14 U	12 U
cis-1,2-Dichloroethene	12 U	12 U	14 U	12 U
trans-1,2-Dichloroethene	12 U	12 U	14 U	12 U
1,2-Dichloropropane	12 U	12 U	14 U	12 U
cis-1,3-Dichloropropene	12 U	12 U	14 U	12 U
trans-1,3-Dichloropropene	12 U	12 U	14 U	12 U
Ethyl benzene	12 U	12 U	14 U	12 U
2-Hexanone	12 U	12 U	14 U	12 U
4-Methyl-2-pentanone	12 U	12 U	14 U	12 U
Methylene chloride	12 U	12 U	14 U	12 U
Styrene	12 U	12 U	14 U	12 U

TABLE C.13c (Cont.)

Compound	Soil Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals			
	FTBOR1 (4-6 ft)	FTBOR1 (6-8 ft)	FTBOR1 (8-10 ft)	FTBOR1 (10-12 ft)
1,1,2,2-Tetrachloroethane	12 U	12 U	5 J	12 U
Tetrachloroethene	12 U	12 U	14 U	12 U
Toluene	12 U	12 U	14 U	12 U
1,1,1-Trichloroethane	12 U	12 U	14 U	12 U
1,1,2-Trichloroethane	12 U	12 U	14 U	12 U
Trichloroethene	12 U	12 U	14 U	12 U
Vinyl acetate	12 U	12 U	NT	12 U
Vinyl chloride	12 U	12 U	14 U	12 U
m- and p-Xylene	12 U	12 U	14 U	12 U
o-Xylene	12 U	12 U	14 U	12 U

<sup>a</sup> Sampled by ANL, analyzed by Weston Gulf Coast or ANL/ACL, CLP/HSL volatile organics.

## Data qualifiers:

U = analyte was analyzed for but not detected; detection limits given.

\* = internal standard area counts were outside QC limits.

J = estimated value.

B = analyte was found in the associated blank.

+ = surrogate recoveries were outside QC limits.

NT = not tested.

TABLE C.13d Volatile Organics Analyses for Soil Borings, May 1995<sup>a</sup>

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals				
	HBOR4 (4-6 ft)	HBOR4 (6-8 ft)	HBOR4 (8-10 ft)	HBOR4 (14-16 ft)	
Acetone	67	27	2,100	780	*E
Benzene	12.1	11.8	56.8	12.3	UJ
Bromodichloromethane	12.1	11.8	56.8	12.3	UJ
Bromoform	12.1	11.8	56.8	12.3	UJ
Bromomethane	12.1	11.8	56.8	12.3	UJ
2-Butanone	12.1	11.8	56.8	12.3	UJ
Carbon disulfide	12.1	11.8	56.8	2.8	J
Carbon tetrachloride	12.1	11.8	56.8	12.3	UJ
Chlorobenzene	12.1	11.8	56.8	12.3	UJ
Chloroethane	12.1	11.8	56.8	12.3	UJ
Chloroform	12.1	11.8	56.8	12.3	UJ
Chloromethane	12.1	11.8	56.8	12.3	UJ
Dibromochloromethane	12.1	11.8	56.8	12.3	UJ
1,1-Dichloroethane	12.1	11.8	56.8	12.3	UJ
1,2-Dichloroethane	12.1	11.8	56.8	1	J
1,1-Dichloroethene	12.1	11.8	56.8	12.3	UJ
1,2-Dichloroethene (total)	12.1	11.8	56.8	450	*E
1,2-Dichloropropane	12.1	11.8	56.8	12.3	UJ
cis-1,3-Dichloropropene	12.1	11.8	56.8	12.3	UJ
trans-1,3-Dichloropropene	12.1	11.8	56.8	12.3	UJ
Ethyl benzene	12.1	11.8	56.8	12.3	UJ
2-Hexanone	12.1	11.8	56.8	12.3	UJ

TABLE C.13d (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals				
	HBOR4 (4-6 ft)	HBOR4 (6-8 ft)	HBOR4 (8-10 ft)	HBOR4 (14-16 ft)	
4-Methyl-2-pentanone	12.1 U	11.8 U	56.8 U	12.3 UJ	
Methylene chloride	6 BJ	4 BJ	38 J	8 J	
Styrene	12.1 U	11.8 U	56.8 U	12.3 UJ	
1,1,2,2-Tetrachloroethane	12.1 U	11.8 U	56.8 U	480 @JE	
Tetrachloroethene	12.1 U	11.8 U	56.8 U	32 J	
Toluene	12.1 U	11.8 U	56.8 U	12.3 UJ	
1,1,1-Trichloroethane	12.1 U	11.8 U	56.8 U	12.3 UJ	
1,1,2-Trichloroethane	12.1 U	11.8 U	56.8 U	57 J	
Trichloroethene	12.1 U	11.8 U	56.8 U	450 *E	
Vinyl chloride	12.1 U	11.8 U	56.8 U	12.3 UJ	
Xylenes (total)	12.1 U	11.8 U	56.8 U	12.3 UJ	

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals				
	TBNPBOR2 (0-2 ft)	TBNPBOR2 (2-6 ft)	TBNPBOR2 (10-12 ft)	TBNPBOR3 (0-2 ft)	TBNPBOR3 (2-4 ft)
Acetone	10 J	6 J	1020 B	67 B	210 J*
Benzene	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
Bromodichloromethane	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
Bromoform	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
Bromomethane	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
2-Butanone	12 U	11.6 U	61.7 U	12 U	67.6 UJ*

TABLE C.13d (Cont.)

Compound	Soil Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals				
	TBNPBOR2 (0-2 ft)	TBNPBOR2 (2-6 ft)	TBNPBOR2 (10-12 ft)	TBNPBOR3 (0-2 ft)	TBNPBOR3 (2-4 ft)
Carbon disulfide	2 J	11.6 U	61.7 U	4 J	8 J*
Carbon tetrachloride	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
Chlorobenzene	12 U	11.6 U	61.7 U	12 U	980 J*
Chloroethane	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
Chloroform	12 U	11.6 U	61.7 U	12 U	20 J*
Chloromethane	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
Dibromochloromethane	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
1,1-Dichloroethane	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
1,2-Dichloroethane	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
1,1-Dichloroethene	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
1,2-Dichloroethene (total)	4 J	11.6 U	61.7 U	22	280 J*
1,2-Dichloropropane	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
cis-1,3-Dichloropropene	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
trans-1,3-Dichloropropene	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
Ethyl benzene	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
2-Hexanone	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
4-Methyl-2-pentanone	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
Methylene chloride	10 BJ	8 BJ	31 BJ	11.9 BJ	41 BJ*
Styrene	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
1,1,2,2-Tetrachloroethane	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
Tetrachloroethene	6 J	11.6 U	61.7 U	2 J	43 J*
Toluene	12 U	11.6 U	61.7 U	12 U	7 J*

TABLE C.13d (Cont.)

Soil Concentrations (µg/kg) at Various Depth Intervals					
Compound	TBNPBOR2 (0-2 ft)	TBNPBOR2 (2-6 ft)	TBNPBOR2 (10-12 ft)	TBNPBOR3 (0-2 ft)	TBNPBOR3 (2-4 ft)
1,1,1-Trichloroethane	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
1,1,2-Trichloroethane	12 U	11.6 U	61.7 U	12 U	67.6 UJ*
Trichloroethene	8 J	11.6 U	61.7 U	13	105 J*
Vinyl chloride	12 U	11.6 U	61.7 U	12 U	37 J*
Xylenes (total)	12 U	11.6 U	61.7 U	12 U	67.6 UJ*

Soil Concentrations (µg/kg) at Various Depth Intervals					
Compound	TBNPBOR3 (4-6 ft)	TBNPBOR3 (6-8 ft)	TBNPBOR3 (8-10 ft)	TBNPBOR3 (10-12 ft)	
Acetone	70.5 UJ	1,500	6,000 @	140	B
Benzene	51 J	67	63.3 U	61.5 UJ	
Bromodichloromethane	70.5 UJ	59.5 U	63.3 U	61.5 UJ	
Bromoform	70.5 UJ	59.5 U	63.3 U	61.5 UJ	
Bromomethane	70.5 UJ	59.5 U	63.3 U	61.5 UJ	
2-Butanone	70.5 UJ	59.5 U	63.3 U	61.5 UJ	
Carbon disulfide	70.5 UJ	59.5 U	63.3 U	61.5 UJ	
Carbon tetrachloride	70.5 UJ	59.5 U	63.3 U	61.5 UJ	
Chlorobenzene	23,000 ~J,E	9,600 @	140	1,000 J	
Chloroethane	70.5 UJ	59.5 U	63.3 U	61.5 UJ	
Chloroform	19 J	59.5 U	63.3 U	61.5 UJ	
Chloromethane	70.5 UJ	59.5 U	63.3 U	61.5 UJ	

TABLE C.13d (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals			
	TBNPBOR3 (4-6 ft)	TBNPBOR3 (6-8 ft)	TBNPBOR3 (8-10 ft)	TBNPBOR3 (10-12 ft)
Dibromochloromethane	70.5 UJ	59.5 U	63.3 U	61.5 UJ
1,1-Dichloroethane	70.5 UJ	59.5 U	63.3 U	61.5 UJ
1,2-Dichloroethane	70.5 UJ	59.5 U	63.3 U	61.5 UJ
1,1-Dichloroethene	70.5 UJ	59.5 U	63.3 U	61.5 UJ
1,2-Dichloroethene (total)	980 J	2,000	230	350 J
1,2-Dichloropropane	70.5 UJ	59.5 U	63.3 U	61.5 UJ
trans-1,3-Dichloropropene	70.5 UJ	59.5 U	63.3 U	61.5 UJ
cis-1,3-Dichloropropene	70.5 UJ	59.5 U	63.3 U	61.5 UJ
Ethyl benzene	250 J	6,600 @	90	1,100
2-Hexanone	70.5 UJ	59.5 U	63.3 U	61.5 UJ
4-Methyl-2-pentanone	70.5 UJ	59.5 U	63.3 U	61.5 UJ
Methylene chloride	23 BJ	59.5 U	27 BJ	35 BJ
Styrene	70.5 UJ	59.5 U	63.3 U	61.5 U
1,1,2,2-Tetrachloroethane	70.5 UJ	59.5 U	63.3 U	61.5 UJ
Tetrachloroethene	70.5 UJ	750	10 J	160 J
Toluene	320 J	4,200 @	55 J	660
1,1,1-Trichloroethane	70.5 UJ	59.5 U	63.3 U	61.5 UJ
1,1,2-Trichloroethane	70.5 UJ	59.5 U	63.3 U	61.5 UJ
Trichloroethene	58 J	59.5 U	63.3 U	61.5 UJ
Vinyl chloride	750 J	59.5 U	63.3 U	61.5 UJ
Xylenes (total)	680 J	46,000 @	540	2,400

TABLE C.13d (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals				
	VXBOR3 (2-4 ft)	VXBOR4 (2-4 ft)	VXBOR4 (4-6 ft)	VXBOR5 (0-2 ft)	VXBOR5 (4-6 ft)
Acetone	18	130 J	260	12 U	160
Benzene	42	63.6 UJ	61.2 U	12 U	65.1 U
Bromodichloromethane	12 U	63.6 UJ	61.2 U	12 U	65.1 U
Bromoform	12 U	63.6 UJ	61.2 U	12 U	65.1 U
Bromomethane	12 U	63.6 UJ	61.2 U	12 U	65.1 U
2-Butanone	12 U	63.6 UJ	61.2 U	12 U	65.1 U
Carbon disulfide	11 J	63.6 UJ	61.2 U	2 J	65.1 U
Carbon tetrachloride	12 U	63.6 UJ	61.2 U	12 U	65.1 U
Chlorobenzene	12 U	63.6 UJ	61.2 U	12 U	65.1 U
Chloroethane	12 U	63.6 UJ	61.2 U	12 U	65.1 U
Chloroform	12 U	63.6 UJ	61.2 U	12 U	65.1 U
Chloromethane	12 U	63.6 UJ	61.2 U	12 U	65.1 U
Dibromochloromethane	12 U	63.6 UJ	61.2 U	12 U	65.1 U
1,1-Dichloroethane	12 U	63.6 UJ	61.2 U	12 U	65.1 U
1,2-Dichloroethane	12 U	63.6 UJ	61.2 U	12 U	65.1 U
1,1-Dichloroethene	12 U	63.6 UJ	61.2 U	12 U	65.1 U
1,2-Dichloroethene (total)	5 J	63.6 UJ	61.2 U	12 U	65.1 U
1,2-Dichloropropane	12 U	63.6 UJ	61.2 U	12 U	65.1 U
cis-1,3-Dichloropropene	12 U	63.6 UJ	61.2 U	12 U	65.1 U
trans-1,3-Dichloropropene	12 U	63.6 UJ	61.2 U	12 U	65.1 U
Ethyl benzene	58	1,300 J@E	2,900 @	12 U	65.1 U
2-Hexanone	12 U	63.6 UJ	61.2 U	12 U	65.1 U

TABLE C.13d (Cont.)

Compound	Soil Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals				
	VXBOR3 (2-4 ft)	VXBOR4 (2-4 ft)	VXBOR4 (4-6 ft)	VXBOR5 (0-2 ft)	VXBOR5 (4-6 ft)
4-Methyl-2-pentanone	12 U	63.6 UJ	61.2 U	12 U	65.1 U
Methylene chloride	12 U	53 J	52 J	7 J	39 J
Styrene	12 U	63.6 UJ	61.2 U	12 U	65.1 U
1,1,2,2-Tetrachloroethane	12 U	63.6 UJ	61.2 U	12 U	65.1 U
Tetrachloroethene	12 U	63.6 UJ	61.2 U	12 U	17 J
Toluene	12 U	63.6 UJ	61.2 U	12 U	65.1 U
1,1,1-Trichloroethane	12 U	63.6 UJ	61.2 U	12 U	65.1 U
1,1,2-Trichloroethane	12 U	63.6 UJ	61.2 U	12 U	65.1 U
Trichloroethene	15	63.6 UJ	61.2 U	12 U	8 J
Vinyl chloride	12 U	63.6 UJ	61.2 U	12 U	65.1 U
Xylenes (total)	27	1,200 J	2,300	12 U	65.1 U

Compound	Soil Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals				
	VXBOR5 (6-8 ft)	VXBOR5 (8-10 ft)	VXBOR5 (10-12 ft)	VXBOR5 (12-14 ft)	VXBOR5 (14-16 ft)
Acetone	20	210	14	550 *	1,100
Benzene	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
Bromodichloromethane	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
Bromoform	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
Bromomethane	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
2-Butanone	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U

TABLE C.13d (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals				
	VXBOR5 (6-8 ft)	VXBOR5 (8-10 ft)	VXBOR5 (10-12 ft)	VXBOR5 (12-14 ft)	VXBOR5 (14-16 ft)
Carbon disulfide	12.4 U	12.4 U	12.5 U	11 J	61.8 U
Carbon tetrachloride	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
Chlorobenzene	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
Chloroethane	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
Chloroform	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
Chloromethane	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
Dibromochloromethane	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
1,1-Dichloroethane	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
1,2-Dichloroethane	12.4 U	12.4 U	12.5 U	2 J	61.8 U
1,1-Dichloroethene	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
1,2-Dichloroethene (total)	2 J	12.4 U	3 J	3 J	61.8 U
1,2-Dichloropropane	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
cis-1,3-Dichloropropene	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
trans-1,3-Dichloropropene	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
Ethyl benzene	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
2-Hexanone	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
4-Methyl-2-pentanone	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
Methylene chloride	6 BJ	7 BJ	11 BJ	8 BJ	28 J
Styrene	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
1,1,2,2-Tetrachloroethane	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
Tetrachloroethene	5 J	3 J	4 J	12.5 U	61.8 U
Toluene	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U

TABLE C.13d (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals				
	VXBOR5 (6-8 ft)	VXBOR5 (8-10 ft)	VXBOR5 (10-12 ft)	VXBOR5 (12-14 ft)	VXBOR5 (14-16 ft)
1,1,1-Trichloroethane	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
1,1,2-Trichloroethane	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
Trichloroethene	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U
Vinyl chloride	12.4 U	12.4 U	12.5 U	3 J	61.8 U
Xylenes (total)	12.4 U	12.4 U	12.5 U	12.5 U	61.8 U

Compound	Soil Concentrations (µg/kg) at 0-6 in.	
	SQPS 5	SQPS-8
Acetone	3	13 BJ*
Benzene	12 U	24 U
Bromodichloromethane	12 U	24 U
Bromoform	12 U	24 U
Bromomethane	12 U	24 U
2-Butanone	12 U	24 U
Carbon disulfide	12 U	38 *
Carbon tetrachloride	12 U	24 U
Chlorobenzene	12 U	24 U
Chloroethane	12 U	24 U
Chloroform	12 U	24 U
Chloromethane	12 U	24 U

TABLE C.13d (Cont.)

Compound	Soil Concentrations ( $\mu\text{g/kg}$ ) at 0-6 in.		
	SQPS 5	SQPS-8	
Dibromochloromethane	12 U	24 U	
1,1-Dichloroethane	12 U	24 U	
1,2-Dichloroethane	12 U	24 U	
1,1-Dichloroethene	12 U	24 U	
1,2-Dichloroethene (total)	12 U	24 U	
1,2-Dichloropropane	12 U	24 U	
cis-1,3-Dichloropropene	12 U	24 U	
trans-1,3-Dichloropropene	12 U	24 U	
Ethyl benzene	12 U	24 U	
2-Hexanone	12 U	24 U	
4-Methyl-2-pentanone	12 U	24 U	
Methylene chloride	6	11 BJ*	
Styrene	12 U	24 U	
1,1,2,2-Tetrachloroethane	12 U	24 U	
Tetrachloroethene	12 U	24 U	
Toluene	12 U	24 U	
1,1,1-Trichloroethane	12 U	24 U	
1,1,2-Trichloroethane	12 U	24 U	
Trichloroethene	12 U	24 U	
Vinyl chloride	12 U	24 U	
Xylenes (total)	12 U	24 U	

See next page for footnotes.

TABLE C.13d (Cont.)

<sup>a</sup> Sampled by ANL and analyzed by GP Environmental Services.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limits given.

B = analyte was found in the associated blank.

J = estimated value.

@ = value obtained from a 1:125 dilution.

E = concentration exceeded the calibration range of the instrument.

\* = QC result outside the laboratory control limits.

~ = value obtained from a 1:100 dilution.

TABLE C.14a Semivolatile Organics Analyses for Soil Borings, January 1993<sup>a</sup>

Borehole Concentrations (µg/kg) at Various Depths							
Compound	JB1-E-2' (2 ft)	JB1-E-2'Dup (2 ft)	JB1-E-4' (4 ft)	JB1-W-2' (2 ft)	JB1-W-4' (4 ft)	JB2-E-2' (2 ft)	JB2-E-4' (4 ft)
Acenaphthene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Acenaphthylene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Anthracene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Benz[a]anthracene	234 J	392 U	402 U	402 U	409 U	396 U	396 U
Benzoic acid	2,010 U	1,960 U	2,010 U	2,010 U	2,050 U	1,980 U	1,980 U
Benzo[a]pyrene	137 J	392 U	402 U	402 U	409 U	396 U	396 U
Benzo[b]fluoranthene	221 J	392 U	402 U	402 U	409 U	396 U	396 U
Benzo[g,h,i]perylene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Benzo[k]fluoranthene	92 J	392 U	402 U	402 U	409 U	396 U	396 U
Benzyl alcohol	805 U	785 U	805 U	805 U	818 U	792 U	792 U
Bis(2-chloroethoxy)methane	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Bis(2-chloroethyl)ether	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Bis(2-chloroisopropyl)ether	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Bis(2-ethylhexyl)phthalate	402 U	392 U	402 U	402 U	409 U	396 U	396 U
4-Bromophenyl phenyl ether	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Butyl benzyl phthalate	402 U	392 U	402 U	402 U	409 U	396 U	396 U
4-Chloro-3-methylphenol	805 U	785 U	805 U	805 U	818 U	792 U	792 U
4-Chloroaniline	805 U	785 U	805 U	805 U	818 U	792 U	792 U
2-Chloronaphthalene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
2-Chlorophenol	402 U	392 U	402 U	402 U	409 U	396 U	396 U
4-Chlorophenyl phenyl ether	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Chrysene	335 J	392 U	402 U	402 U	409 U	396 U	396 U
Di-n-butylphthalate	402 U	392 U	402 U	402 U	409 U	77 J	396 U
Di-n-octylphthalate	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Dibenz[a,h]anthracene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Dibenzofuran	402 U	392 U	402 U	402 U	409 U	396 U	396 U

TABLE C.14a (Cont.)

Borehole Concentrations (µg/kg) at Various Depths							
Compound	JBP1-E-2' (2 ft)	JBP1-E-2'Dup (2 ft)	JBP1-E-4' (4 ft)	JBP1-W-2' (2 ft)	JBP1-W-4' (4 ft)	JBP2-E-2' (2 ft)	JBP2-E-4' (4 ft)
1,2-Dichlorobenzene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
1,3-Dichlorobenzene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
1,4-Dichlorobenzene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
3,3'-Dichlorobenzidine	805 U	785 U	805 U	805 U	818 U	792 U	792 U
2,4-Dichlorophenol	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Diethylphthalate	402 U	392 U	402 U	402 U	409 U	396 U	396 U
2,4-Dimethylphenol	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Dimethylphthalate	402 U	392 U	402 U	402 U	409 U	396 U	396 U
4,6-Dinitro-2-methylphenol	2,010 U	1,960 U	2,010 U	2,010 U	2,050 U	1,980 U	1,980 U
2,4-Dinitrophenol	2,010 U	1,960 U	2,010 U	2,010 U	2,050 U	1,980 U	1,980 U
2,4-Dinitrotoluene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
2,6-Dinitrotoluene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Fluoranthene	306 J	392 U	402 U	402 U	409 U	396 U	396 U
Fluorene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Hexachlorobenzene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Hexachlorobutadiene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Hexachlorocyclopentadiene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Hexachloroethane	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Indeno[1,2,3-c,d]pyrene	402 U	392 U	402 U	402 U	490 U	396 U	396 U
Isophorone	402 U	392 U	402 U	402 U	409 U	396 U	396 U
2-Methylnaphthalene	471	392 U	402 U	402 U	409 U	396 U	396 U
2-Methylphenol	402 U	392 U	402 U	402 U	409 U	396 U	396 U
4-Methylphenol	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Naphthalene	107 J	392 U	402 U	402 U	409 U	396 U	396 U
2-Nitroaniline	2,010 U	1,960 U	2,010 U	2,010 U	2,050 U	1,980 U	1,980 U
3-Nitroaniline	2,010 U	1,960 U	2,010 U	2,010 U	2,050 U	1,980 U	1,980 U

TABLE C.14a (Cont.)

Compound	Borehole Concentrations (µg/kg) at Various Depths						
	JBP1-E-2' (2 ft)	JBP1-E-2'Dup (2 ft)	JBP1-E-4' (4 ft)	JBP1-W-2' (2 ft)	JBP1-W-4' (4 ft)	JBP2-E-2' (2 ft)	JBP2-E-4' (4 ft)
4-Nitroaniline	2,010 U	1,960 U	2,010 U	2,010 U	2,050 U	1,980 U	1,980 U
Nitrobenzene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
2-Nitrophenol	402 U	392 U	402 U	402 U	409 U	396 U	396 U
4-Nitrophenol	2,010 U	1,960 U	2,010 U	2,010 U	2,050 U	1,980 U	1,980 U
N-Nitroso-di-n-propylamine	402 U	392 U	402 U	402 U	409 U	396 U	396 U
N-Nitrosodiphenylamine	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Pentachlorophenol	2,010 U	1,960 U	2,010 U	2,010 U	2,050 U	1,980 U	1,980 U
Phenanthrene	376 J	392 U	402 U	402 U	409 U	396 U	396 U
Phenol	402 U	392 U	402 U	402 U	409 U	396 U	396 U
Pyrene	580	392 U	402 U	402 U	409 U	396 U	396 U
1,2,4-Trichlorobenzene	402 U	392 U	402 U	402 U	409 U	396 U	396 U
2,4,5-Trichlorophenol	402 U	392 U	402 U	402 U	409 U	396 U	396 U
2,4,6-Trichlorophenol	402 U	392 U	402 U	402 U	409 U	396 U	396 U
<hr/>							
Compound	Borehole Concentrations (µg/kg) at Various Depths						
	JBP2-E-4'Dup (4 ft)	JBP2-C-2' (2 ft)	JBP2-C-4' (4 ft)	JBP2-W-2' (2 ft)	JBP2-W-4' (4 ft)	JHDP-C-4' (4 ft)	JHDP-C-6' (6 ft)
Acenaphthene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Acenaphthylene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Anthracene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Benz[a]anthracene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Benzo[a]pyrene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Benzo[b]fluoranthene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Benzo[g,h,i]perylene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Benzoic acid	1,960 U	2,280 U	1,960 U	118 J	1,960 U	175 J	74 J

TABLE C.14a (Cont.)

Compound	Borehole Concentrations (µg/kg) at Various Depths						
	JBP2-E-4'Dup (4 ft)	JBP2-C-2' (2 ft)	JBP2-C-4' (4 ft)	JBP2-W-2' (2 ft)	JBP2-W-4' (4 ft)	JHDP-C-4' (4 ft)	JHDP-C-6' (6 ft)
Benzo[k]fluoranthene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Benzyl alcohol	785 U	910 U	785 U	792 U	785 U	792 U	805 U
Bis(2-chloroethoxy)methane	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Bis(2-chloroethyl)ether	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Bis(2-chloroisopropyl)ether	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Bis(2-ethylhexyl)phthalate	392 U	455 U	392 U	396 U	392 U	396 U	402 U
4-Bromophenyl phenyl ether	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Butyl benzyl phthalate	392 U	455 U	392 U	396 U	392 U	396 U	402 U
4-Chloro-3-methylphenol	785 U	910 U	785 U	792 U	785 U	792 U	805 U
4-Chloroaniline	785 U	910 U	785 U	792 U	785 U	792 U	805 U
2-Chloronaphthalene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
2-Chlorophenol	392 U	455 U	392 U	396 U	392 U	396 U	402 U
4-Chlorophenyl phenyl ether	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Chrysene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Di-n-butylphthalate	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Di-n-octylphthalate	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Dibenz[a,h]anthracene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Dibenzofuran	392 U	455 U	392 U	396 U	392 U	396 U	402 U
1,2-Dichlorobenzene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
1,3-Dichlorobenzene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
1,4-Dichlorobenzene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
3,3'-Dichlorobenzidine	785 U	910 U	785 U	792 U	785 U	792 U	805 U
2,4-Dichlorophenol	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Diethylphthalate	392 U	455 U	392 U	396 U	392 U	396 U	402 U
2,4-Dimethylphenol	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Dimethylphthalate	392 U	455 U	392 U	396 U	392 U	396 U	402 U

TABLE C.14a (Cont.)

Compound	Borehole Concentrations (µg/kg) at Various Depths						
	JBP2-E-4'Dup (4 ft)	JBP2-C-2' (2 ft)	JBP2-C-4' (4 ft)	JBP2-W-2' (2 ft)	JBP2-W-4' (4 ft)	JHDP-C-4' (4 ft)	JHDP-C-6' (6 ft)
4,6-Dinitro-2-methylphenol	1,960 U	2,280 U	1,960 U	1,980 U	1,960 U	1,980 U	2,010 U
2,4-Dinitrophenol	1,960 U	2,280 U	1,960 U	1,980 U	1,960 U	1,980 U	2,010 U
2,4-Dinitrotoluene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
2,6-Dinitrotoluene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Fluoranthene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Fluorene	392 U	531	392 U	396 U	392 U	396 U	402 U
Hexachlorobenzene	392 U	455 U	380 J	845	392 U	396 U	402 U
Hexachlorobutadiene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Hexachlorocyclopentadiene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Hexachloroethane	392 U	455 U	392 U	396 U	392 U	396 U	628
Indenof[1,2,3-c,d]pyrene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Isophorone	392 U	455 U	392 U	396 U	392 U	396 U	402 U
2-Methylnaphthalene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
2-Methylphenol	392 U	455 U	392 U	396 U	392 U	396 U	402 U
4-Methylphenol	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Naphthalene	392 U	50 J	392 U	396 U	392 U	396 U	402 U
2-Nitroaniline	1,960 U	2,280 U	1,960 U	1,980 U	1,960 U	1,980 U	2,010 U
3-Nitroaniline	1,960 U	2,280 U	1,960 U	1,980 U	1,960 U	1,980 U	2,010 U
4-Nitroaniline	1,960 U	2,280 U	1,960 U	1,980 U	1,960 U	1,980 U	2,010 U
Nitrobenzene	57 J	455 U	57 J	396 U	392 U	396 U	402 U
2-Nitrophenol	392 U	455 U	392 U	396 U	392 U	396 U	402 U
4-Nitrophenol	1,960 U	2,280 U	1,960 U	1,980 U	1,960 U	1,980 U	2,010 U
N-Nitroso-di-n-propylamine	392 U	455 U	392 U	396 U	392 U	396 U	402 U
N-Nitrosodiphenylamine	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Pentachlorophenol	1,960 U	2,280 U	1,960 U	1,980 U	1,960 U	1,980 U	2,010 U
Phenanthrene	392 U	52 J	43 J	396 U	392 U	396 U	402 U

TABLE C.14a (Cont.)

Compound	Borehole Concentrations (µg/kg) at Various Depths						
	JBP2-E-4'Dup (4 ft)	JBP2-C-2' (2 ft)	JBP2-C-4' (4 ft)	JBP2-W-2' (2 ft)	JBP2-W-4' (4 ft)	JHDP-C-4' (4 ft)	JHDP-C-6' (6 ft)
Phenol	392 U	455 U	392 U	396 U	392 U	396 U	402 U
Pyrene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
1,2,4-Trichlorobenzene	392 U	455 U	392 U	396 U	392 U	396 U	402 U
2,4,5-Trichlorophenol	392 U	455 U	392 U	396 U	392 U	396 U	402 U
2,4,6-Trichlorophenol	392 U	455 U	392 U	396 U	392 U	396 U	402 U
<hr/>							
Compound	Borehole Concentrations (µg/kg) at Various Depths						
	JHDP-C-6'Dup (6 ft)	JVXP-C-4' (4 ft)	JVXP-C-6' (6 ft)	JSDP-C-4' (4 ft)	JSDP-C-6' (6 ft)	JBPM-A-3" (3 in.)	JBPM-A-3"Dup (3 in.)
Acenaphthene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Acenaphthylene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Anthracene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Benz[a]anthracene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Benzo[a]pyrene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Benzo[b]fluoranthene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Benzo[g,h,i]perylene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Benzoic acid	78 J	91 J	2,330 U	2,210 U	432 U	392 U	392 U
Benzo[k]fluoranthene	369 U	435 U	465 U	442 U	2,160 U	1,960 U	1,960 U
Benzyl alcohol	739 U	871 U	930 U	884 U	432 U	392 U	392 U
Bis(2-chloroethoxy)methane	369 U	435 U	465 U	442 U	864 U	785 U	785 U
Bis(2-chloroethyl)ether	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Bis(2-chloroisopropyl)ether	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Bis(2-ethylhexyl)phthalate	369 U	435 U	465 U	442 U	432 U	392 U	392 U
4-Bromophenyl phenyl ether	369 U	435 U	465 U	442 U	432 U	208 J	392 U
Butyl benzyl phthalate	369 U	435 U	465 U	442 U	432 U	392 U	392 U

TABLE C.14a (Cont.)

Compound	Borehole Concentrations (µg/kg) at Various Depths						
	JHDP-C-6'Dup (6 ft)	JVXP-C-4' (4 ft)	JVXP-C-6' (6 ft)	JSDP-C-4' (4 ft)	JSDP-C-6' (6 ft)	JBPM-A-3" (3 in.)	JBPM-A-3"Dup (3 in.)
4-Chloro-3-methylphenol	739 U	871 U	930 U	884 U	864 U	785 U	785 U
4-Chloroaniline	739 U	871 U	930 U	884 U	864 U	785 U	785 U
2-Chloronaphthalene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
2-Chlorophenol	369 U	435 U	465 U	442 U	432 U	392 U	392 U
4-Chlorophenyl phenyl ether	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Chrysene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Di-n-butylphthalate	369 U	435 U	70 J	442 U	432 U	392 U	392 U
Di-n-octylphthalate	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Dibenz[a,h]anthracene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Dibenzofuran	369 U	435 U	465 U	442 U	432 U	392 U	392 U
1,2-Dichlorobenzene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
1,3-Dichlorobenzene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
1,4-Dichlorobenzene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
3,3'-Dichlorobenzidine	739 U	871 U	930 U	884 U	864 U	785 U	785 U
2,4-Dichlorophenol	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Diethylphthalate	369 U	435 U	465 U	442 U	432 U	392 U	392 U
2,4-Dimethylphenol	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Dimethylphthalate	369 U	435 U	465 U	442 U	432 U	392 U	392 U
4,6-Dinitro-2-methylphenol	1,850 U	2,180 U	2,330 U	2,210 U	2,160 U	1,960 U	1,960 U
2,4-Dinitrophenol	1,850 U	2,180 U	2,330 U	2,210 U	2,160 U	1,960 U	1,960 U
2,4-Dinitrotoluene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
2,6-Dinitrotoluene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Fluoranthene	369 U	435 U	465 U	442 U	432 U	77 J	392 U
Fluorene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Hexachlorobenzene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Hexachlorobutadiene	369 U	435 U	465 U	442 U	432 U	392 U	392 U

TABLE C.14a (Cont.)

Compound	Borehole Concentrations (µg/kg) at Various Depths						
	JHDP-C-6'Dup (6 ft)	JVXP-C-4' (4 ft)	JVXP-C-6' (6 ft)	JSDP-C-4' (4 ft)	JSDP-C-6' (6 ft)	JBPM-A-3" (3 in.)	JBPM-A-3"Dup (3 in.)
Hexachlorocyclopentadiene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Hexachloroethane	282 J	435 U	465 U	442 U	432 U	392 U	392 U
Indeno[1,2,3-c,d]pyrene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Isophorone	369 U	435 U	465 U	442 U	432 U	392 U	392 U
2-Methylnaphthalene	369 U	435 U	465 U	442 U	432 U	139 J	392 U
2-Methylphenol	369 U	435 U	465 U	442 U	432 U	392 U	392 U
4-Methylphenol	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Naphthalene	369 U	435 U	465 U	442 U	432 U	48 J	392 U
2-Nitroaniline	1,850 U	2,180 U	2,330 U	2,210 U	2,160 U	1,960 U	1,960 U
3-Nitroaniline	1,850 U	2,180 U	2,330 U	2,210 U	2,160 U	1,960 U	1,960 U
4-Nitroaniline	1,850 U	2,180 U	2,330 U	2,210 U	2,160 U	1,960 U	1,960 U
Nitrobenzene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
2-Nitrophenol	369 U	435 U	465 U	442 U	432 U	392 U	392 U
4-Nitrophenol	1,850 U	2,180 U	2,330 U	2,210 U	2,160 U	1,960 U	1,960 U
N-Nitroso-di-n-propylamine	369 U	435 U	465 U	442 U	432 U	392 U	392 U
N-Nitrosodiphenylamine	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Pentachlorophenol	1,850 U	2,180 U	2,230 U	2,210 U	2,160 U	1,960 U	1,960 U
Phenanthrene	369 U	435 U	465 U	442 U	432 U	311 J	392 U
Phenol	369 U	435 U	465 U	442 U	432 U	392 U	392 U
Pyrene	369 U	435 U	465 U	442 U	432 U	215 J	392 U
1,2,4-Trichlorobenzene	369 U	435 U	465 U	442 U	432 U	392 U	392 U
2,4,5-Trichlorophenol	369 U	435 U	465 U	442 U	432 U	392 U	392 U
2,4,6-Trichlorophenol	369 U	435 U	465 U	442 U	432 U	392 U	392 U

TABLE C.14a (Cont.)

Compound	Borehole Concentrations (µg/kg) at Various Depths						
	JBPM-A-1' (1 ft)	JBPM-B-3" (3 in.)	JBPM-B-1' (1 ft)	JBPM-C-3" (3 in.)	JBPM-C-1' (1 ft)	JBPP-A-3" (3 in.)	JBPP-A-1' (1 ft)
Acenaphthene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Acenaphthylene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Anthracene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Benz[a]anthracene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Benzo[a]pyrene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Benzo[b]fluoranthene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Benzo[g,h,i]perylene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Benzoic acid	1,960 U	1,880 U	1,930 U	2,100 U	1,900 U	1,930 U	1,960 U
Benzo[k]fluoranthene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Benzyl alcohol	785 U	752 U	772 U	838 U	759 U	772 U	785 U
Bis(2-chloroethoxy)methane	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Bis(2-chloroethyl)ether	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Bis(2-chloroisopropyl)ether	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Bis(2-ethylhexyl)phthalate	392 U	190 J	386 U	419 U	379 U	386 U	392 U
4-Bromophenyl phenyl ether	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Butyl benzyl phthalate	392 U	376 U	386 U	419 U	379 U	386 U	392 U
4-Chloro-3-methylphenol	785 U	752 U	772 U	838 U	759 U	772 U	785 U
4-Chloroaniline	785 U	752 U	772 U	838 U	759 U	772 U	785 U
2-Chloronaphthalene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
2-Chlorophenol	392 U	376 U	386 U	419 U	379 U	386 U	392 U
4-Chlorophenyl phenyl ether	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Chrysene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Di-n-butylphthalate	77 J	376 U	386 U	419 U	379 U	386 U	392 U
Di-n-octylphthalate	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Dibenz[a,h]anthracene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Dibenzofuran	392 U	376 U	386 U	419 U	379 U	386 U	392 U

TABLE C.14a (Cont.)

Compound	Borehole Concentrations (µg/kg) at Various Depths						
	JBPM-A-1' (1 ft)	JBPM-B-3" (3 in.)	JBPM-B-1' (1 ft)	JBPM-C-3" (3 in.)	JBPM-C-1' (1 ft)	JBPP-A-3" (3 in.)	JBPP-A-1' (1 ft)
1,2-Dichlorobenzene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
1,3-Dichlorobenzene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
1,4-Dichlorobenzene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
3,3'-Dichlorobenzidine	785 U	752 U	772 U	838 U	759 U	772 U	785 U
2,4-Dichlorophenol	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Diethylphthalate	49 J	376 U	386 U	419 U	379 U	386 U	392 U
2,4-Dimethylphenol	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Dimethylphthalate	392 U	376 U	386 U	419 U	379 U	386 U	392 U
4,6-Dinitro-2-methylphenol	1,960 U	1,880 U	1,930 U	2,100 U	1,900 U	1,930 U	1,960 U
2,4-Dinitrophenol	1,960 U	1,880 U	1,930 U	2,100 U	1,900 U	1,930 U	1,960 U
2,4-Dinitrotoluene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
2,6-Dinitrotoluene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Fluoranthene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Fluorene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Hexachlorobenzene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Hexachlorobutadiene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Hexachlorocyclopentadiene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Hexachloroethane	498	376 U	386 U	419 U	379 U	386 U	392 U
Indeno[1,2,3-c,d]pyrene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Isophorone	392 U	376 U	386 U	419 U	379 U	386 U	392 U
2-Methylnaphthalene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
2-Methylphenol	392 U	376 U	386 U	419 U	379 U	386 U	392 U
4-Methylphenol	392 U	376 U	386 U	419 U	379 U	386 U	392 U
Naphthalene	392 U	376 U	386 U	419 U	379 U	386 U	392 U
2-Nitroaniline	1,960 U	1,880 U	1,930 U	2,100 U	1,900 U	1,930 U	1,960 U
3-Nitroaniline	1,960 U	1,880 U	1,930 U	2,100 U	1,900 U	1,930 U	1,960 U

TABLE C.14a (Cont.)

Compound	Borehole Concentrations (µg/kg) at Various Depths					
	JBPM-A-1' (1 ft)	JBPM-B-3" (3 in.)	JBPM-B-1' (1 ft)	JBPM-C-3" (3 in.)	JBPM-C-1' (1 ft)	JBPP-A-1' (1 ft)
4-Nitroaniline	1,960	U	1,930	U	1,900	U
Nitrobenzene	392	U	386	U	379	U
2-Nitrophenol	392	U	386	U	379	U
4-Nitrophenol	1,960	U	1,930	U	1,900	U
N-Nitroso-di-n-propylamine	392	U	386	U	379	U
N-Nitrosodiphenylamine	392	U	386	U	379	U
Pentachlorophenol	1,960	U	1,930	U	1,900	U
Phenanthrene	392	U	386	U	379	U
Phenol	392	U	386	U	379	U
Pyrene	392	U	386	U	379	U
1,2,4-Trichlorobenzene	392	U	386	U	379	U
2,4,5-Trichlorophenol	392	U	386	U	379	U
2,4,6-Trichlorophenol	392	U	386	U	379	U
<hr/>						
Compound	Borehole Concentrations (µg/kg) at Various Depths					
	JBPP-B-3" (3 in.)	JBPP-B-1' (1 ft)	JBPP-C-3" (3 in.)	JBPP-C-1' (1 ft)		
Acenaphthene	455	U	392	U	392	U
Acenaphthylene	455	U	392	U	392	U
Anthracene	455	U	392	U	392	U
Benz[a]anthracene	455	U	392	U	392	U
Benzo[a]pyrene	455	U	392	U	392	U
Benzo[b]fluoranthene	455	U	392	U	392	U
Benzo[g,h,i]perylene	455	U	392	U	392	U
Benzoic acid	2,280	U	1,950	U	1,960	U

TABLE C.14a (Cont.)

Compound	Borehole Concentrations (µg/kg) at Various Depths			
	JBPP-B-3" (3 in.)	JBPP-B-1' (1 ft)	JBPP-C-3" (3 in.)	JBPP-C-1' (1 ft)
Benzo[k]fluoranthene	455 U	389 U	392 U	392 U
Benzyl alcohol	910 U	778 U	785 U	785 U
Bis(2-chloroethoxy)methane	455 U	389 U	392 U	392 U
Bis(2-chloroethyl)ether	455 U	389 U	392 U	392 U
Bis(2-chloroisopropyl)ether	455 U	389 U	392 U	392 U
Bis(2-ethylhexyl)phthalate	455 U	389 U	392 U	392 U
4-Bromophenyl phenyl ether	455 U	389 U	392 U	392 U
Butyl benzyl phthalate	455 U	389 U	392 U	392 U
4-Chloro-3-methylphenol	910 U	778 U	785 U	785 U
4-Chloroaniline	910 U	778 U	785 U	785 U
2-Chloronaphthalene	455 U	389 U	392 U	392 U
2-Chlorophenol	455 U	389 U	392 U	392 U
4-Chlorophenyl phenyl ether	455 U	389 U	392 U	392 U
Chrysene	455 U	389 U	392 U	392 U
Di-n-butylphthalate	56 J	389 U	392 U	392 U
Di-n-octylphthalate	455 U	389 U	392 U	392 U
Dibenz[a,h]anthracene	455 U	389 U	392 U	392 U
Dibenzofuran	455 U	389 U	392 U	392 U
1,2-Dichlorobenzene	455 U	389 U	392 U	392 U
1,3-Dichlorobenzene	455 U	389 U	392 U	392 U
1,4-Dichlorobenzene	455 U	389 U	392 U	392 U
3,3'-Dichlorobenzidine	910 U	778 U	785 U	785 U
2,4-Dichlorophenol	455 U	389 U	392 U	392 U
Diethylphthalate	455 U	389 U	392 U	392 U
2,4-Dimethylphenol	455 U	389 U	392 U	392 U
Dimethylphthalate	455 U	389 U	392 U	392 U

TABLE C.14a (Cont.)

Compound	Borehole Concentrations (µg/kg) at Various Depths				
	JBPP-B-3" (3 in.)	JBPP-B-1' (1 ft)	JBPP-C-3" (3 in.)	JBPP-C-1' (1 ft)	
4,6-Dinitro-2-methylphenol	2,280 U	1,950 U	1,960 U	1,960 U	U
2,4-Dinitrophenol	2,280 U	1,950 U	1,960 U	1,960 U	U
2,4-Dinitrotoluene	455 U	389 U	392 U	392 U	U
2,6-Dinitrotoluene	455 U	389 U	392 U	392 U	U
Fluoranthene	455 U	389 U	392 U	392 U	U
Fluorene	455 U	389 U	392 U	392 U	U
Hexachlorobenzene	455 U	389 U	392 U	392 U	U
Hexachlorobutadiene	455 U	389 U	392 U	392 U	U
Hexachlorocyclopentadiene	455 U	389 U	392 U	392 U	U
Hexachloroethane	455 U	389 U	392 U	392 U	U
Indeno[1,2,3-c,d]pyrene	455 U	389 U	392 U	392 U	U
Isophorone	455 U	389 U	392 U	392 U	U
2-Methylnaphthalene	161 J	389 U	392 U	392 U	U
2-Methylphenol	455 U	389 U	392 U	392 U	U
4-Methylphenol	455 U	389 U	392 U	392 U	U
Naphthalene	309 J	389 U	392 U	392 U	U
2-Nitroaniline	2,280 U	1,950 U	1,960 U	1,960 U	U
3-Nitroaniline	2,280 U	1,950 U	1,960 U	1,960 U	U
4-Nitroaniline	2,280 U	1,950 U	1,960 U	1,960 U	U
Nitrobenzene	455 U	389 U	392 U	392 U	U
2-Nitrophenol	455 U	389 U	392 U	392 U	U
4-Nitrophenol	2,280 U	1,950 U	1,960 U	1,960 U	U
N-Nitroso-di-n-propylamine	455 U	389 U	392 U	392 U	U
N-Nitrosodiphenylamine	455 U	389 U	392 U	392 U	U
Pentachlorophenol	2,280 U	1,950 U	1,960 U	1,960 U	U
Phenanthrene	73 J	389 U	392 U	392 U	U

TABLE C.14a (Cont.)

Compound	Borehole Concentrations ( $\mu\text{g/kg}$ ) at Various Depths			
	JBPP-B-3" (3 in.)	JBPP-B-1' (1 ft)	JBPP-C-3" (3 in.)	JBPP-C-1' (1 ft)
Phenol	455 U	389 U	392 U	392 U
Pyrene	455 U	389 U	392 U	392 U
1,2,4-Trichlorobenzene	455 U	389 U	392 U	392 U
2,4,5-Trichlorophenol	455 U	389 U	392 U	392 U
2,4,6-Trichlorophenol	455 U	389 U	392 U	392 U

<sup>a</sup> Sampled by Weston, analyzed by GP Environmental Services, CLP/HSL volatile organics; provisional data.

Data qualifiers:

U = analyte was analyzed for but not detected.

J = estimated value.

TABLE C.14b Semivolatile Organics Analyses for Soil Borings, January 1994<sup>a</sup>

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	CLP1 (0-6 in.)	CLP1 (6-24 in.)	CLP1 (24-40 in.)	CLP2 (0-6 in.)	CLP2 (6-24 in.)	
Acenaphthene	500 U	420 U	420 U	420 U	430 U	U
Acenaphthylene	500 U	420 U	420 U	420 U	430 U	U
Anthracene	500 U	420 U	420 U	420 U	430 U	U
Benz[a]anthracene	500 U	420 U	420 U	420 U	430 U	U
Benzo[a]pyrene	500 U	420 U	420 U	420 U	430 U	U
Benzo[b]fluoranthene	500 U	420 U	420 U	420 U	430 U	U
Benzo[g,h,i]perylene	500 U	420 U	420 U	420 U	430 U	U
Benzo[k]fluoranthene	500 U	420 U	420 U	420 U	430 U	U
Bis(2-chloroethoxy)methane	500 U	420 U	420 U	420 U	430 U	U
Bis(2-chloroethyl)ether	500 U	420 U	420 U	420 U	430 U	U
Bis(2-chloroisopropyl)ether	500 U	420 U	420 U	420 U	430 U	U
Bis(2-ethylhexyl)phthalate	500 JB	420 JB	420 JB	420 JB	430 JB	JB
4-Bromophenyl phenyl ether	500 U	420 U	420 U	420 U	430 U	U
Butylbenzylphthalate	500 U	420 U	420 U	420 U	430 U	U
Carbazole	500 U	420 U	420 U	420 U	430 U	U
4-Chloro-3-methylphenol	500 U	420 U	420 U	420 U	430 U	U
4-Chloroaniline	500 U	420 U	420 U	420 U	430 U	U
2-Chloronaphthalene	500 U	420 U	420 U	420 U	430 U	U
2-Chlorophenol	500 U	420 U	420 U	420 U	430 U	U
4-Chlorophenyl phenyl ether	500 U	420 U	420 U	420 U	430 U	U
Chrysene	500 U	420 U	420 U	420 U	430 U	U
Di-n-butylphthalate	500 JB	420 JB	420 JB	420 JB	430 JB	JB
Di-n-octyl phthalate	500 U	420 U	420 U	420 U	430 U	U
Dibenz[a,h]anthracene	500 U	420 U	420 U	420 U	430 U	U
Dibenzofuran	500 U	420 U	420 U	420 U	430 U	U
1,2-Dichlorobenzene	500 U	420 U	420 U	420 U	430 U	U
1,3-Dichlorobenzene	500 U	420 U	420 U	420 U	430 U	U
1,4-Dichlorobenzene	500 U	420 U	420 U	420 U	430 U	U

TABLE C.14b (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	CLP1 (0-6 in.)	CLP1 (6-24 in.)	CLP1 (24-40 in.)	CLP2 (0-6 in.)	CLP2 (6-24 in.)	
3,3'-Dichlorobenzidine	500 U	420 U	420 U	420 U	430 U	
2,4- Dichlorophenol	500 U	420 U	420 U	420 U	430 U	
Diethylphthalate	500 U	420 U	420 J	420 U	430	
2,4-Dimethylphenol	500 U	420 U	420 U	420 J	430 J	
Dimethylphthalate	500 U	420 U	420 U	420 U	430 U	
4,6-Dinitro-2-methylphenol	1,200 U	1,000 U	1,000 U	1,000 U	1,100 U	
2,4-Dinitrophenol	1,200 U	1,000 U	1,000 U	1,000 U	1,100 U	
2,4-Dinitrotoluene	500 U	420 U	420 U	420 U	430 U	
2,6-Dinitrotoluene	500 U	420 U	420 U	420 U	430 U	
Fluoranthene	500 U	420 U	420 U	420 U	430 U	
Fluorene	500 U	420 U	420 U	420 U	430 U	
Hexachlorobenzene	500 J	420 U	420 J	420 J	430 J	
Hexachlorobutadiene	500 U	420 U	420 U	420 U	430 U	
Hexachlorocyclopentadiene	500 U	420 U	420 U	420 U	430 U	
Hexachloroethane	500 U	420 U	420 U	420 U	430 U	
Indeno[1,2,3-c,d]pyrene	500 U	420 U	420 U	420 U	430 U	
Isophorone	500 U	420 U	420 U	420 U	430 U	
2-Methylnaphthalene	500 U	420 U	420 U	420 U	430 U	
2-Methylphenol	500 U	420 U	420 U	420 U	430 J	
4-Methylphenol	500 U	420 U	420 U	420 J	430	
Naphthalene	500 U	420 U	420 U	420	430	
2-Nitroaniline	1,200 U	1,000 U	1,000 U	1,000 U	1,100 J	
3-Nitroaniline	1,200 U	1,000 U	1,000 U	1,000 U	1,100 U	
4-Nitroaniline	1,200 U	1,000 U	1,000 U	1,000 U	1,100 U	
Nitrobenzene	500 U	420 U	420 U	420 U	430 U	
2-Nitrophenol	500 U	420 U	420 U	420 U	430 U	
4-Nitrophenol	1,200 U	1,000 U	1,000 U	1,000 U	1,100 U	
N-Nitroso-di-n-propylamine	500 U	420 U	420 U	420 U	430 U	
N-Nitrosodiphenylamine	500 U	420 U	420 U	420 U	430 J	

TABLE C.14b (Cont.)

Soil Concentrations (µg/kg) at Various Depth Intervals					
Compound	CLP1 (0-6 in.)	CLP1 (6-24 in.)	CLP1 (24-40 in.)	CLP2 (0-6 in.)	CLP2 (6-24 in.)
Pentachlorophenol	1,200 U	1,000 U	1,000 U	1,000 U	1,100 U
Phenanthrene	500 U	420 U	420 U	420 U	430 U
Phenol	500 U	420 U	420 U	420 J	430 J
Pyrene	500 U	420 U	420 U	420 U	430 U
1,2,4-Trichlorobenzene	500 U	420 U	420 U	420 U	430 U
2,4,5-Trichlorophenol	1,200 U	1,000 U	1,000 U	1,000 U	1,100 U
2,4,6-Trichlorophenol	500 U	420 U	420 U	420 U	430 U
-----					
Soil Concentrations (µg/kg) at Various Depth Intervals					
Compound	CLP2 (24-48 in.)	CLP3 (0-6 in.)	CLP3 (6-24 in.)	CLP3-Dup (6-24 in.)	CLP3 (24-48 in.)
Acenaphthene	500 U	590 U	490 U	2,500 U	970 U
Acenaphthylene	500 U	590 U	490 U	2,500 U	970 U
Anthracene	500 U	590 U	490 U	2,500 U	970 U
Benzo[a]anthracene	500 U	590 U	490 U	2,500 U	970 U
Benzo[a]pyrene	500 U	590 U	490 U	2,500 U	970 U
Benzo[b]fluoranthene	500 U	590 U	490 U	2,500 U	970 U
Benzo[g,h,i]perylene	500 U	590 U	490 U	2,500 U	970 U
Benzo[k]fluoranthene	500 U	590 U	490 U	2,500 U	970 U
Bis(2-chloroethoxy)methane	500 U	590 U	490 U	2,500 U	970 U
Bis(2-chloroethyl)ether	500 U	590 U	490 U	2,500 U	970 U
Bis(2-chloroisopropyl)ether	500 U	590 U	490 U	2,500 U	970 U
Bis(2-ethylhexyl)phthalate	500 U	590 JB	260 JB	2,500 U	460 JB
4-Bromophenyl phenyl ether	500 U	590 U	490 U	2,500 U	970 U
Butylbenzylphthalate	500 U	590 U	490 U	2,500 U	970 U
Carbazole	500 U	590 U	490 U	2,500 U	970 U
4-Chloro-3-methylphenol	500 U	590 U	490 U	2,500 U	970 U
4-Chloroaniline	500 U	590 U	490 U	2,500 U	970 U

TABLE C.14b (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	CLP2 (24-48 in.)	CLP3 (0-6 in.)	CLP3 (6-24 in.)	CLP3-Dup (6-24 in.)	CLP3 (24-48 in.)	
2-Chloronaphthalene	500 U	590 U	490 U	2,500 U	970 U	U
2-Chlorophenol	500 U	590 U	490 U	2,500 U	970 U	U
4-Chlorophenyl phenyl ether	500 U	590 U	490 U	2,500 U	970 U	U
Chrysene	500 U	590 J	490 U	2,500 U	970 U	U
Di-n-butylphthalate	500 U	590 JB	220 JB	2,500 U	380 JB	JB
Di-n-octyl phthalate	500 U	590 U	490 U	2,500 U	970 U	U
Dibenz[a,h]anthracene	500 U	590 U	490 U	2,500 U	970 U	U
Dibenzofuran	500 U	590 U	490 U	2,500 U	970 U	U
1,2-Dichlorobenzene	500 U	590 U	490 U	2,500 U	420 J	J
1,3-Dichlorobenzene	500 U	590 U	490 U	2,500 U	210 J	J
1,4-Dichlorobenzene	500 U	590 U	490 U	2,500 U	970 U	U
3,3'-Dichlorobenzidine	500 U	590 U	490 U	2,500 U	970 U	U
2,4-Dichlorophenol	500 U	590 U	490 U	2,500 U	970 U	U
Diethylphthalate	500 U	590 U	2,000	2,500 U	970 U	U
2,4-Dimethylphenol	500 U	590 U	490 U	2,500 U	970 U	U
Dimethylphthalate	500 U	590 U	490 U	2,500 U	970 U	U
4,6-Dinitro-2-methylphenol	1,200 U	1,500 U	1,200 U	6,200 U	2,400 U	U
2,4-Dinitrophenol	1,200 U	1,500 U	1,200 U	6,200 U	2,400 U	U
2,4-Dinitrotoluene	500 U	590 U	490 U	2,500 U	970 U	U
2,6-Dinitrotoluene	500 U	590 U	490 U	2,500 U	970 U	U
Fluoranthene	500 U	590 J	490 U	2,500 U	970 U	U
Fluorene	500 U	590 U	490 U	2,500 U	970 U	U
Hexachlorobenzene	500 U	590	3,100	2,500 U	710 J	J
Hexachlorobutadiene	500 U	590 U	490 U	2,500 U	970 U	U
Hexachlorocyclopentadiene	500 U	590 U	490 U	2,500 U	970 U	U
Hexachloroethane	500 U	590 J	490 U	2,500 U	970 U	U
Indenof[1,2,3-c,d]pyrene	500 U	590 U	490 U	2,500 U	970 U	U
Isophorone	500 U	590 U	490 U	2,500 U	970 U	U
2-Methylnaphthalene	500 U	590 U	200 J	2,500 U	97 J	J

TABLE C.14b (Cont.)

Compound	Soil Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals				
	CLP2 (24-48 in.)	CLP3 (0- 6 in.)	CLP3 (6-24 in.)	CLP3-Dup (6-24 in.)	CLP3 (24-48 in.)
2-Methylphenol	500 U	590 U	130 J	2,500 U	140 J
4-Methylphenol	500 U	590 U	180 J	2,500 U	190 J
Naphthalene	500 U	590 U	90 J	2,500 U	970 U
2-Nitroaniline	1,200 U	1,500 U	1,200 U	6,200 U	2,400 U
3-Nitroaniline	1,200 U	1,500 U	1,200 U	6,200 U	2,400 U
4-Nitroaniline	1,200 U	1,500 U	1,200 U	6,200 U	2,400 U
Nitrobenzene	500 U	590 U	490 U	2,500 U	970 U
2-Nitrophenol	500 U	590 U	490 U	2,500 U	1,400 U
4-Nitrophenol	1,200 U	1,500 U	1,200 U	6,200 U	2,400 U
N-Nitroso-di-n-propylamine	500 U	590 U	490 U	2,500 U	970 U
N-Nitrosodiphenylamine	500 U	590 U	240 J	2,500 U	970 U
Pentachlorophenol	1,200 U	1,500 U	1,200 U	6,200 U	2,400 U
Phenanthrene	500 U	590 U	490 U	2,500 U	970 U
Phenol	500 U	590 U	490 U	2,500 U	970 U
Pyrene	500 U	590 J	53 J	2,500 U	970 U
1,2,4-Trichlorobenzene	500 U	590 U	490 U	2,500 U	970 U
2,4,5-Trichlorophenol	1,200 U	1,500 U	1,200 U	6,200 U	2,400 U
2,4,6-Trichlorophenol	500 U	590 U	490 U	2,500 U	970 U

TABLE C.14b (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals								
	CLP4 (0-6 in.)	CLP4 (6-24 in.)	CLP4 (24-48 in.)	CLP4-RE (24-48 in.)	CLP5 (0-6 in.)	CLP5-RE (0-6 in.)	CLP5 (6-24 in.)	CLP5 (24-48 in.)	CLP5-Dup (24-48 in.)
Acenaphthene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Acenaphthylene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Anthracene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Benz[a]anthracene	69 J	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Benzo[a]pyrene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Benzo[b]fluoranthene	200 J	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Benzo[g,h,i]perylene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Benzo[k]fluoranthene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Bis(2-chloroethoxy)methane	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Bis(2-chloroethyl)ether	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Bis(2-chloroisopropyl)ether	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Bis(2-ethylhexyl)phthalate	170 JB	140 JB	4,300 U	440 JB	870 B	790 B	400 U	130 JB	140 JB
4-Bromophenyl phenyl ether	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Butylbenzylphthalate	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Carbazole	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
4-Chloro-3-methylphenol	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
4-Chloroaniline	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
2-Chloronaphthalene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
2-Chlorophenol	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
4-Chlorophenyl phenyl ether	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Chrysene	110 J	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Di-n-butylphthalate	230 JB	120 JB	4,300 U	4,300 U	180 JB	200 JB	85 JB	100 JB	120 JB
Di-n-octylphthalate	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Dibenz[a,h]anthracene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Dibenzofuran	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
1,2-Dichlorobenzene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
1,3-Dichlorobenzene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
1,4-Dichlorobenzene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
3,3'-Dichlorobenzidine	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
2,4-Dichlorophenol	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U

TABLE C.14b (Cont.)

Soil Concentrations (µg/kg) at Various Depth Intervals									
Compound	CLP4 (0-6 in.)	CLP4 (6-24 in.)	CLP4 (24-48 in.)	CLP4-RE (24-48 in.)	CLP5 (0-6 in.)	CLP5-RE (0-6 in.)	CLP5 (6-24 in.)	CLP5 (24-48 in.)	CLP5-Dup (24-48 in.)
Diethylphthalate	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	49 J	440 U
2,4-Dimethylphenol	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Dimethylphthalate	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
4,6-Dinitro-2-methylphenol	1,200 U	1,100 U	11,000 U	11,000 U	1,100 U	1,100 U	990 U	1,100 U	1,100 U
2,4-Dinitrophenol	1,200 U	1,100 U	11,000 U	11,000 U	1,100 U	1,100 U	990 U	1,100 U	1,100 U
2,4-Dinitrotoluene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
2,6-Dinitrotoluene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Fluoranthene	150 J	62 J	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Fluorene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Hexachlorobenzene	430 J	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Hexachlorobutadiene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Hexachlorocyclopentadiene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Hexachloroethane	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Indeno[1,2,3-c,d]pyrene	470 U	440 U	4,300 U	4,300 U	420 U	100 J	400 U	440 U	440 U
Isophorone	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
2-Methylnaphthalene	470 U	200 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
2-Methylphenol	470 U	110 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
4-Methylphenol	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Naphthalene	470 U	120 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
2-Nitroaniline	1,200 U	1,100 U	11,000 U	11,000 U	1,100 U	1,100 U	990 U	1,100 U	1,100 U
3-Nitroaniline	1,200 U	1,100 U	11,000 U	11,000 U	1,100 U	1,100 U	990 U	1,100 U	1,100 U
4-Nitroaniline	1,200 U	1,100 U	11,000 U	11,000 U	1,100 U	1,100 U	990 U	1,100 U	1,100 U
Nitrobenzene	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
2-Nitrophenol	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
4-Nitrophenol	1,200 U	1,100 U	11,000 U	11,000 U	1,100 U	1,100 U	990 U	1,100 U	1,100 U
N-Nitroso-di-n-propylamine	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
N-Nitrosodiphenylamine	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Pentachlorophenol	1,200 U	1,100 U	11,000 U	11,000 U	1,100 U	1,100 U	990 U	1,100 U	1,100 U
Phenanthrene	59 J	120 J	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U
Phenol	470 U	440 U	4,300 U	4,300 U	420 U	420 U	400 U	440 U	440 U

TABLE C.14b (Cont.)

Soil Concentrations (µg/kg) at Various Depth Intervals									
Compound	CLP4 (0-6 in.)	CLP4 (6-24 in.)	CLP4 (24-48 in.)	CLP4-RE (24-48 in.)	CLP5 (0-6 in.)	CLP5-RE (0-6 in.)	CLP5 (6-24 in.)	CLP5 (24-48 in.)	CLP5-Dup (24-48 in.)
Pyrene	130	J	86	J	4,300	U	420	U	440
1,2,4-Trichlorobenzene	470	U	440	U	4,300	U	420	U	440
2,4,5-Trichlorophenol	1,200	U	1,100	U	11,000	U	1,100	U	1,100
2,4,6-Trichlorophenol	470	U	440	U	4,300	U	420	U	440

Soil Concentrations (µg/kg) at Various Depth Intervals									
Compound	CLP6 (0-6 in.)	CLP6 (6-24 in.)	CLP6-RE (6-24 in.)	CLP7 (0-6 in.)	CLP7 (6-24 in.)	CLP7-RE (6-24 in.)	CLP7 (24-48 in.)	CLP8 (0-6 in.)	CLP9 (0-6 in.)
Acenaphthene	880	U	420	U	510	U	420	U	820
Acenaphthylene	880	U	420	U	510	U	420	U	820
Anthracene	880	U	420	U	510	U	420	U	820
Benz[a]anthracene	880	U	86	J	510	U	420	U	820
Benzo[a]pyrene	880	U	420	U	510	U	420	U	820
Benzo[b]fluoranthene	880	U	420	U	510	U	420	U	820
Benzo[g,h,i]perylene	880	U	420	U	510	U	420	U	820
Benzo[k]fluoranthene	880	U	420	U	510	U	420	U	820
Bis(2-chloroethoxy)methane	880	U	420	U	510	U	420	U	820
Bis(2-chloroethyl)ether	880	U	420	U	510	U	420	U	820
Bis(2-chloroisopropyl)ether	880	U	420	U	510	U	420	U	820
Bis(2-ethylhexyl)phthalate	180	JB	160	JB	170	JB	85	JB	120
4-Bromophenyl phenyl ether	880	U	420	U	510	U	420	U	820
Butylbenzylphthalate	880	U	420	U	510	U	420	U	820
Carbazole	880	U	420	U	510	U	420	U	820
4-Chloro-3-methylphenol	880	U	420	U	510	U	420	U	820
4-Chloroaniline	880	U	420	U	510	U	420	U	820
2-Chloronaphthalene	880	U	420	U	510	U	420	U	820
2-Chlorophenol	880	U	420	U	510	U	420	U	820
4-Chlorophenyl phenyl ether	880	U	420	U	510	U	420	U	820
Chrysene	880	U	97	J	510	U	420	U	820

TABLE C.14b (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals								
	CLP6 (0-6 in.)	CLP6 (6-24 in.)	CLP6-RE (6-24 in.)	CLP7 (0-6 in.)	CLP7 (6-24 in.)	CLP7-RE (6-24 in.)	CLP7 (24-48 in.)	CLP8 (0-6 in.)	CLP9 (0-6 in.)
Di-n-butylphthalate	880 U	160 JB	170 JB	190 JB	94 JB	420 U	100 JB	2,000 U	120 JB
Di-n-octylphthalate	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
Dibenz[a,h]anthracene	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
Dibenzofuran	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
1,2-Dichlorobenzene	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
1,3-Dichlorobenzene	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
1,4-Dichlorobenzene	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
3,3'-Dichlorobenzidine	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
2,4-Dichlorophenol	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
Diethylphthalate	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
2,4-Dimethylphenol	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
Dimethylphthalate	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
4,6-Dinitro-2-methylphenol	2,200 U	1,000 U	1,000 U	1,300 U	1,000 U	1,100 U	1,000 U	5,100 U	2,000 U
2,4-Dinitrophenol	2,200 U	1,000 U	1,000 U	1,300 U	1,000 U	1,100 U	1,000 U	5,100 U	2,000 U
2,4-Dinitrotoluene	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
2,6-Dinitrotoluene	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
Fluoranthene	880 U	140 J	140 J	510 U	420 U	420 U	420 U	2,000 U	820 U
Fluorene	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
Hexachlorobenzene	880 U	65 J	75 J	510 U	420 U	420 U	420 U	490 J	500 U
Hexachlorobutadiene	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
Hexachlorocyclopentadiene	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
Hexachloroethane	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
Indeno[1,2,3-c,d]pyrene	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
Isophorone	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
2-Methylnaphthalene	880 U	120 J	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
2-Methylphenol	880 U	80 J	75 J	510 U	420 U	420 U	420 U	2,000 U	820 U
4-Methylphenol	880 U	92 J	91 U	510 U	420 U	420 U	420 U	2,000 U	820 U
Naphthalene	880 U	67 J	63 J	510 U	420 U	420 U	420 U	2,000 U	820 U
2-Nitroaniline	2,200 U	1,000 U	1,000 U	1,300 U	1,000 U	1,100 U	1,000 U	5,100 U	2,000 U
3-Nitroaniline	2,200 U	1,000 U	1,000 U	1,300 U	1,000 U	1,100 U	1,000 U	5,100 U	2,000 U

TABLE C.14b (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals								
	CLP6 (0-6 in.)	CLP6 (6-24 in.)	CLP6-RE (6-24 in.)	CLP7 (0-6 in.)	CLP7 (6-24 in.)	CLP7-RE (6-24 in.)	CLP7 (24-48 in.)	CLP8 (0-6 in.)	CLP9 (0-6 in.)
4-Nitroaniline	2,200 U	1,000 U	1,000 U	1,300 U	1,000 U	1,100 U	1,000 U	5,100 U	2,000 U
Nitrobenzene	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
2-Nitrophenol	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
4-Nitrophenol	2,200 U	1,000 U	1,000 U	1,300 U	1,000 U	1,100 U	1,000 U	5,100 U	2,000 U
N-Nitroso-di-n-propylamine	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
N-Nitrosodiphenylamine	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
Pentachlorophenol	2,200 U	1,000 U	1,000 U	1,300 U	1,000 U	1,100 U	1,000 U	5,100 U	2,000 U
Phenanthrene	880 U	74 J	71 J	510 U	420 U	420 U	420 U	2,000 U	820 U
Phenol	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U
Pyrene	880 U	180 J	140 J	510 U	420 U	420 U	420 U	2,000 U	820 U
1,2,4-Trichlorobenzene	880 U	46 J	45 J	510 U	420 U	420 U	420 U	2,000 U	44 J
2,4,5-Trichlorophenol	2,200 U	1,000 U	1,000 U	1,300 U	1,000 U	1,100 U	1,000 U	5,100 U	2,000 U
2,4,6-Trichlorophenol	880 U	420 U	420 U	510 U	420 U	420 U	420 U	2,000 U	820 U

<sup>a</sup> Sampled by ANL, analyzed by Weston Gulf Coast, CLP/HSL semivolatile organics.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

J = estimated value.

B = analyte was found in the associated blank.

TABLE C.14c Semivolatile Organics Analyses for Soil Borings, May 1994<sup>a</sup>

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	TBSPBOR1 (0-2 ft)	TBSPBOR1 Dup (0-2 ft)	TBSPBOR1 (2-4 ft)	TBSPBOR1 (4-6 ft)	TBSPBOR1 (6-8 ft)	TBSPBOR1 (8-10 ft)
Acenaphthene	380 U	380 U	410 U	400 U	410 U	410 U
Acenaphthylene	380 U	380 U	410 U	400 U	410 U	410 U
Anthracene	380 U	380 U	410 U	61 J	410 U	410 U
Benz[a]anthracene	42 J	380 U	410 U	400 U	410 U	410 U
Benzo[a]pyrene	380 U	380 U	410 U	400 U	410 U	410 U
Benzo[b]fluoranthene	380 U	380 U	410 U	400 U	410 U	410 U
Benzo[g,h,i]perylene	380 U	380 U	410 U	400 U	410 U	410 U
Benzo[k]fluoranthene	380 U	380 U	410 U	400 U	410 U	410 U
Bis(2-chloroethoxy)methane	380 U	380 U	410 U	400 U	410 U	410 U
Bis(2-chloroethyl)ether	380 U	380 U	410 U	400 U	410 U	410 U
Bis(2-chloroisopropyl)ether	380 U	380 U	410 U	400 U	410 U	410 U
Bis(2-ethylhexyl)phthalate	240 J	380 U	410 U	400 U	54 J	410 U
4-Bromophenyl phenyl ether	380 U	380 U	410 U	400 U	410 U	410 U
Butylbenzylphthalate	380 U	380 U	410 U	400 U	410 U	410 U
Carbazole	380 U	380 U	47 J	88 J	410 U	410 U
4-Chloro-3-methylphenol	380 U	380 U	410 U	400 U	410 U	410 U
4-Chloroaniline	380 U	380 U	410 U	400 U	410 U	410 U
2-Chloronaphthalene	380 U	380 U	410 U	400 U	410 U	410 U
2-Chlorophenol	380 U	380 U	410 U	400 U	410 U	410 U
4-Chlorophenyl phenyl ether	380 U	380 U	410 U	400 U	410 U	410 U
Chrysene	43 J	380 U	410 U	400 U	410 U	410 U
Di-n-butylphthalate	390 B	290 JB	310 JB	290 JB	320 JB	110 JB
Di-n-octyl phthalate	380 U	380 U	410 U	400 U	410 U	410 U
Dibenz[a,h]anthracene	380 U	380 U	410 U	400 U	410 U	410 U

TABLE C.14c (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals							
	TBSPBOR I (0-2 ft)	TBSPBOR I Dup (0-2 ft)	TBSPBOR I (2-4 ft)	TBSPBOR I (4-6 ft)	TBSPBOR I (6-8 ft)	TBSPBOR I (8-10 ft)		
Dibenzofuran	380	U	38	J	410	U	410	U
1,2-Dichlorobenzene	380	U	380	U	410	U	410	U
1,3-Dichlorobenzene	380	U	380	U	410	U	410	U
1,4-Dichlorobenzene	380	U	380	U	410	U	410	U
3,3'-Dichlorobenzidine	380	U	380	U	410	U	410	U
2,4-Dichlorophenol	380	U	380	U	410	U	410	U
Diethylphthalate	190	J	99	J	410	U	410	U
2,4-Dimethylphenol	380	U	380	U	410	U	410	U
Dimethylphthalate	380	U	380	U	410	U	410	U
4,6-Dinitro-2-methylphenol	960	U	940	U	1,000	U	1,000	U
2,4-Dinitrophenol	960	U	940	U	1,000	U	1,000	U
2,4-Dinitrotoluene	380	U	380	U	410	U	410	U
2,6-Dinitrotoluene	380	U	380	U	410	U	410	U
Fluoranthene	73	J	63	J	410	U	410	U
Fluorene	380	U	380	U	410	U	410	U
Hexachlorobenzene	200	J	210	J	410	U	410	U
Hexachlorobutadiene	380	U	380	U	410	U	410	U
Hexachlorocyclopentadiene	380	U	380	U	410	U	410	U
Hexachloroethane	580		350	J	410	U	410	U
Indeno[1,2,3-c,d]pyrene	380	U	380	U	410	U	410	U
Isophorone	380	U	380	U	410	U	410	U
2-Methylnaphthalene	110	J	230	J	410	U	410	U
2-Methylphenol	380	U	380	U	410	U	410	U

TABLE C.14c (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals						
	TBSPBOR I (0-2 ft)	TBSPBOR I Dup (0-2 ft)	TBSPBOR I (2-4 ft)	TBSPBOR I (4-6 ft)	TBSPBOR I (6-8 ft)	TBSPBOR I (8-10 ft)	
4-Methylphenol	380 U	380 U	410 U	400 U	410 U	410 U	
Naphthalene	380 U	61 J	410 U	400 U	410 U	410 U	
2-Nitroaniline	960 U	940 U	1,000 U	1,000 U	1,000 U	1,000 U	
3-Nitroaniline	960 U	940 U	1,000 U	1,000 U	1,000 U	1,000 U	
4-Nitroaniline	960 U	940 U	1,000 U	1,000 U	1,000 U	1,000 U	
Nitrobenzene	380 U	380 U	410 U	400 U	410 U	410 U	
2-Nitrophenol	380 U	380 U	410 U	400 U	410 U	410 U	
4-Nitrophenol	960 U	940 U	1,000 U	1,000 U	1,000 U	1,000 U	
N-Nitroso-di-n-propylamine	380 U	380 U	410 U	400 U	410 U	410 U	
N-Nitrosodiphenylamine	650	950	64 J	120 J	44 J	410 U	
Pentachlorophenol	960 U	940 U	1,000 U	1,000 U	1,000 U	1,000 U	
Phenanthrene	99 J	130 J	53 J	62 J	410 U	410 U	
Phenol	380 U	380 U	410 U	400 U	410 U	410 U	
Pyrene	63 J	74 J	42 J	400 U	410 U	410 U	
1,2,4-Trichlorobenzene	130 J	340 J	410 U	400 U	410 U	410 U	
2,4,5-Trichlorophenol	960 U	940 U	1,000 U	1,000 U	1,000 U	1,000 U	
2,4,6-Trichlorophenol	380 U	380 U	410 U	400 U	410 U	410 U	



TABLE C.14c (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals						
	TBSPBOR1 (10-12 ft)	TBSPBOR2 (0-2 ft)	TBSPBOR2 Dup (0-2 ft)	TBSPBOR2 (2-4 ft)	TBSPBOR2 (4-6 ft)	TBSPBOR2 (6-8 ft)	TBSPBOR2 (8-10 ft)
Dibenz[a,h]anthracene	390 U	390 U	390 U	390 U	390 U	400 U	400 U
Dibenzofuran	390 U	390 U	390 U	390 U	390 U	400 U	400 U
1,2-Dichlorobenzene	390 U	170 J	390 U	390 U	390 U	400 U	400 U
1,3-Dichlorobenzene	390 U	390 U	390 U	390 U	390 U	400 U	400 U
1,4-Dichlorobenzene	390 UN	390 U	390 U	390 U	390 U	400 U	400 U
3,3'-Dichlorobenzidine	390 U	390 U	390 U	390 U	390 U	400 U	400 U
2,4- Dichlorophenol	390 U	390 U	390 U	390 U	390 U	400 U	400 U
Diethylphthalate	390 U	390 U	390 U	390 U	390 U	400 U	400 U
2,4-Dimethylphenol	390 U	390 U	390 U	390 U	390 U	400 U	400 U
Dimethylphthalate	390 U	390 U	390 U	390 U	390 U	400 U	400 U
4,6-Dinitro-2-methylphenol	980 U	970 U	960 U	980 U	980 U	990 U	1,000 U
2,4-Dinitrophenol	980 U	970 U	960 U	980 U	980 U	990 U	1,000 U
2,4-Dinitrotoluene	390 U	390 U	390 U	390 U	390 U	400 U	400 U
2,6-Dinitrotoluene	390 U	390 U	390 U	390 U	390 U	400 U	400 U
Fluoranthene	390 U	390 U	390 U	390 U	390 U	400 U	400 U
Fluorene	390 U	390 U	390 U	390 U	390 U	400 U	400 U
Hexachlorobenzene	390 U	390 U	390 U	390 U	390 U	400 U	400 U
Hexachlorobutadiene	390 U	390 U	390 U	390 U	390 U	400 U	400 U
Hexachlorocyclopentadiene	390 U	390 U	390 U	390 U	390 U	400 U	400 U
Hexachloroethane	390 U	390 U	390 U	390 U	390 U	400 U	58 J
Indeno[1,2,3-c,d]pyrene	390 U	390 U	390 U	390 U	390 U	400 U	400 U
Isophorone	390 U	390 U	390 U	390 U	390 U	400 U	400 U
2-Methylnaphthalene	390 U	390 U	71 J	390 U	390 U	400 U	400 U



TABLE C.14c (Cont.)

Soil Concentrations (µg/kg) at Various Depth Intervals						
Compound	HBOR1 (0-2 ft)	HBOR1 (2-4 ft)	HBOR1 (4-6 ft)	HBOR1 (6-8 ft)	HBOR1 (8-10 ft)	HBOR2 (0-2 ft)
Acenaphthene	430 U	400 U	400 U	390 U	380 U	390 U
Acenaphthylene	430 U	400 U	400 U	390 U	380 U	390 U
Anthracene	430 U	400 U	400 U	390 U	380 U	390 U
Benz[a]anthracene	310 J	400 U	400 U	390 U	380 U	390 U
Benzo[a]pyrene	400 J	400 U	400 U	390 U	380 U	390 U
Benzo[b]fluoranthene	660	400 U	400 U	390 U	380 U	50 J
Benzo[g,h,i]perylene	110 J	400 U	400 U	390 U	380 U	390 U
Benzo[k]fluoranthene	120 J	400 U	400 U	390 U	380 U	390 U
Bis(2-chloroethoxy)methane	430 U	400 U	400 U	390 U	380 U	390 U
Bis(2-chloroethyl)ether	430 U	400 U	400 U	390 U	380 U	390 U
Bis(2-chloroisopropyl)ether	430 U	400 U	400 U	390 U	380 U	390 U
Bis(2-ethylhexyl)phthalate	430 U	400 U	42 J	950	42 J	39 J
4-Bromophenyl phenyl ether	430 U	400 U	400 U	390 U	380 U	390 U
Butylbenzylphthalate	430 U	49 J	46 J	54 J	46 J	390 U
Carbazole	430 U	400 U	400 U	390 U	380 U	390 U
4-Chloro-3-methylphenol	430 U	400 U	400 U	390 U	380 U	390 U
4-Chloroaniline	430 U	400 U	400 U	390 U	380 U	390 U
2-Chloronaphthalene	430 U	400 U	400 U	390 U	380 U	390 U
2-Chlorophenol	430 U	400 U	400 U	390 U	380 U	390 U
4-Chlorophenyl phenyl ether	430 U	400 U	400 U	390 U	380 U	390 U
Chrysene	390 J	400 U	400 U	390 U	380 U	390 U
Di-n-butylphthalate	290 JB	260 JB	270 JB	210 JB	210 JB	210 JB
Di-n-octylphthalate	430 U	400 U	400 U	190 J	380 U	390 U
Dibenz[a,h]anthracene	55 J	400 U	400 U	390 U	380 U	390 U

TABLE C.14c (Cont.)

Soil Concentrations (µg/kg) at Various Depth Intervals							
Compound	HBOR1 (0-2 ft)	HBOR1 (2-4 ft)	HBOR1 (4-6 ft)	HBOR1 (6-8 ft)	HBOR1 (8-10 ft)	HBOR2 (0-2 ft)	
Dibenzofuran	430 U	400 U	400 U	390 U	380 U	390 U	
1,2-Dichlorobenzene	430 U	400 U	400 U	390 U	380 U	390 U	
1,3-Dichlorobenzene	430 U	400 U	400 U	390 U	380 U	390 U	
1,4-Dichlorobenzene	430 U	400 U	400 U	390 U	380 U	390 U	
3,3'-Dichlorobenzidine	430 U	400 U	400 U	390 U	380 U	390 U	
2,4-Dichlorophenol	430 U	400 U	400 U	390 U	380 U	390 U	
Diethylphthalate	430 U	400 U	400 U	390 U	380 U	390 U	
2,4-Dimethylphenol	430 U	400 U	400 U	390 U	380 U	390 U	
Dimethylphthalate	430 U	400 U	400 U	390 U	380 U	390 U	
4,6-Dinitro-2-methylphenol	1,100 U	990 U	1,000 U	960 U	950 U	980 U	
2,4-Dinitrophenol	1,100 U	990 U	1,000 U	960 U	950 U	980 U	
2,4-Dinitrotoluene	430 U	400 U	400 U	390 U	380 U	390 U	
2,6-Dinitrotoluene	430 U	400 U	400 U	390 U	380 U	390 U	
Fluoranthene	260 J	400 U	400 U	390 U	380 U	62 J	
Fluorene	430 U	400 U	400 U	390 U	380 U	390 U	
Hexachlorobenzene	430 U	400 U	400 U	390 U	380 U	390 U	
Hexachlorobutadiene	430 U	58 J	400 U	390 U	380 U	390 U	
Hexachlorocyclopentadiene	430 U	400 U	400 U	390 U	380 U	390 U	
Hexachloroethane	430 U	400 U	400 U	390 U	380 U	390 U	
Indeno[1,2,3-c,d]pyrene	120 J	400 U	400 U	390 U	380 U	390 U	
Isophorone	430 U	400 U	400 U	390 U	380 U	390 U	
2-Methylnaphthalene	430 U	400 U	400 U	390 U	380 U	390 U	
2-Methylphenol	430 U	400 U	400 U	390 U	380 U	390 U	
4-Methylphenol	430 U	400 U	400 U	390 U	380 U	390 U	

TABLE C.14c (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	HBOR1 (0-2 ft)	HBOR1 (2-4 ft)	HBOR1 (4-6 ft)	HBOR1 (6-8 ft)	HBOR1 (8-10 ft)	HBOR2 (0-2 ft)
Naphthalene	430 U	400 U	400 U	390 U	380 U	390 U
2-Nitroaniline	1,100 U	990 U	1,000 U	960 U	950 U	980 U
3-Nitroaniline	1,100 U	990 U	1,000 U	960 U	950 U	980 U
4-Nitroaniline	1,100 U	990 U	1,000 U	960 U	950 U	980 U
Nitrobenzene	430 U	400 U	400 U	390 U	380 U	390 U
2-Nitrophenol	430 U	400 U	400 U	390 U	380 U	390 U
4-Nitrophenol	1,100 U	990 U	1,000 U	960 U	950 U	980 U
N-Nitroso-di-n-propylamine	430 U	400 U	400 U	390 U	380 U	390 U
N-Nitrosodiphenylamine	430 U	400 U	400 U	390 U	380 U	390 U
Pentachlorophenol	1,100 U	990 U	1,000 U	960 U	950 U	980 U
Phenanthrene	73 J	400 U	400 U	390 U	380 U	390 U
Phenol	430 U	400 U	400 U	390 U	380 U	390 U
Pyrene	200 J	400 U	400 U	390 U	380 U	55 J
1,2,4-Trichlorobenzene	430 U	400 U	400 U	390 U	380 U	390 U
2,4,5-Trichlorophenol	1,100 U	990 U	1,000 U	960 U	950 U	980 U
2,4,6-Trichlorophenol	430 U	400 U	400 U	390 U	380 U	390 U

TABLE C.14c (Cont.)

Compound	Soil Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals				
	HBOR2 (2-4 ft)	HBOR2 (4-6 ft)	HBOR2 (6-8 ft)	HBOR2 (8-10 ft)	
Acenaphthene	390 U	390 U	400 U	420 U	U
Acenaphthylene	390 U	390 U	400 U	420 U	U
Anthracene	390 U	390 U	400 U	420 U	U
Benz[a]anthracene	390 U	390 U	400 U	420 U	U
Benzo[a]pyrene	390 U*	390 U	400 U	420 U	U
Benzo[b]fluoranthene	390 U*	390 U	400 U	420 U	U
Benzo[g,h,i]perylene	390 U*	390 U	400 U	420 U	U
Benzo[k]fluoranthene	390 U*	390 U	400 U	420 U	U
Bis(2-chloroethoxy)methane	390 U	390 U	400 U	420 U	U
Bis(2-chloroethyl)ether	390 U	390 U	400 U	420 U	U
Bis(2-chloroisopropyl)ether	390 U	390 U	400 U	420 U	U
Bis(2-ethylhexyl)phthalate	200 J	41 J	400 U	420 U	U
4-Bromophenyl phenyl ether	390 U	390 U	400 U	420 U	U
Butylbenzylphthalate	390 U	390 U	400 U	420 U	U
Carbazole	390 U	390 U	400 U	420 U	U
4-Chloro-3-methylphenol	390 U	390 U	400 U	420 U	U
4-Chloroaniline	390 U	390 U	400 U	420 U	U
2-Chloronaphthalene	390 U	390 U	400 U	420 U	U
2-Chlorophenol	390 U	390 U	400 U	420 U	U
4-Chlorophenyl phenyl ether	390 U	390 U	400 U	420 U	U
Chrysene	390 U	390 U	400 U	420 U	U
Di-n-butylphthalate	270 JB	190 JB	180 JB	190 J	J
Di-n-octylphthalate	390 U*	390 U	400 U	420 U	U
Dibenz[a,h]anthracene	390 U*	390 U	400 U	420 U	U

TABLE C.14c (Cont.)

Compound	Soil Concentrations ( $\mu\text{g}/\text{kg}$ ) at Various Depth Intervals				
	HBOR2 (2-4 ft)	HBOR2 (4-6 ft)	HBOR2 (6-8 ft)	HBOR2 (8-10 ft)	
Dibenzofuran	390 U	390 U	400 U	420 U	U
1,2-Dichlorobenzene	390 U	390 U	400 U	420 U	U
1,3-Dichlorobenzene	390 U	390 U	400 U	420 U	U
1,4-Dichlorobenzene	390 U	390 U	400 U	420 U	U
3,3'-Dichlorobenzidine	390 U	390 U	400 U	420 U	U
2,4-Dichlorophenol	390 U	390 U	400 U	420 U	U
Diethylphthalate	390 U	390 U	400 U	420 U	U
2,4-Dimethylphenol	390 U	390 U	400 U	420 U	U
Dimethylphthalate	390 U	390 U	400 U	420 U	U
4,6-Dinitro-2-methylphenol	970 U	960 U	1,000 U	1,000 U	U
2,4-Dinitrophenol	970 U	960 U	1,000 U	1,000 U	U
2,4-Dinitrotoluene	390 U	390 U	400 U	420 U	U
2,6-Dinitrotoluene	390 U	390 U	400 U	420 U	U
Fluoranthene	390 U	390 U	400 U	420 U	U
Fluorene	390 U	390 U	400 U	420 U	U
Hexachlorobenzene	390 U	390 U	400 U	420 U	U
Hexachlorobutadiene	390 U	390 U	400 U	420 U	U
Hexachlorocyclopentadiene	390 U	390 U	400 U	420 U	U
Hexachloroethane	390 U	390 U	400 U	420 U	U
Indenol 1,2,3-c,d]pyrene	390 U*	390 U	400 U	420 U	U
Isophorone	390 U	390 U	400 U	420 U	U
2-Methylnaphthalene	390 U	390 U	400 U	420 U	U
2-Methylphenol	390 U	390 U	400 U	420 U	U
4-Methylphenol	390 U	390 U	400 U	420 U	U

TABLE C.14c (Cont.)

Compound	Soil Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals				
	HBOR2 (2-4 ft)	HBOR2 (4-6 ft)	HBOR2 (6-8 ft)	HBOR2 (8-10 ft)	
Naphthalene	390 U	390 U	400 U	420 U	U
2-Nitroaniline	970 U	960 U	1,000 U	1,000 U	U
3-Nitroaniline	970 U	960 U	1,000 U	1,000 U	U
4-Nitroaniline	970 U	960 U	1,000 U	1,000 U	U
Nitrobenzene	390 U	390 U	400 U	420 U	U
2-Nitrophenol	390 U	390 U	400 U	420 U	U
4-Nitrophenol	970 U	960 U	1,000 U	1,000 U	U
N-Nitroso-di-n-propylamine	390 U	390 U	400 U	420 U	U
N-Nitrosodiphenylamine	390 U	390 U	400 U	420 U	U
Pentachlorophenol	970 U	960 U	1,000 U	1,000 U	U
Phenanthrene	390 U	390 U	400 U	420 U	U
Phenol	390 U	390 U	400 U	420 U	U
Pyrene	75 J	390 U	400 U	420 U	U
1,2,4-Trichlorobenzene	390 U	390 U	400 U	420 U	U
2,4,5-Trichlorophenol	970 U	960 U	1,000 U	1,000 U	U
2,4,6-Trichlorophenol	390 U	390 U	400 U	420 U	U

TABLE C.14c (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	TBNPBORI (0-2 ft)	TBNPBORI (2-4 ft)	TBNPBORI (4-6 ft)	TBNPBORI (6-8 ft)	TBNPBORI (8-10 ft)	
Acenaphthene	410 U	410 U	410 U	410 U	400 U	U
Acenaphthylene	410 U	410 U	410 U	410 U	400 U	U
Anthracene	410 U	410 U	410 U	410 U	400 U	U
Benz[a]anthracene	410 U	410 U	410 U	410 U	400 U	U
Benzo[a]pyrene	410 U*	410 U	410 U	410 U	400 U	U
Benzo[b]fluoranthene	410 U*	410 U	410 U	410 U	400 U	U
Benzo[g,h,i]perylene	410 U*	410 U	410 U	410 U	400 U	U
Benzo[k]fluoranthene	410 U*	410 U	410 U	410 U	400 U	U
Bis(2-chloroethoxy)methane	410 U	410 U	410 U	410 U	400 U	U
Bis(2-chloroethyl)ether	410 U	410 U	410 U	410 U	400 U	U
Bis(2-chloroisopropyl)ether	410 U	410 U	410 U	410 U	400 U	U
Bis(2-ethylhexyl)phthalate	210 J	100 J	93 J	45 J	160 J	J
4-Bromophenyl phenyl ether	410 U	410 U	410 U	410 U	400 U	U
Butylbenzylphthalate	410 U	410 U	410 U	410 U	400 U	U
Carbazole	410 U	410 U	410 U	410 U	400 U	U
4-Chloro-3-methylphenol	410 U	410 U	410 U	410 U	400 U	U
4-Chloroaniline	410 U	410 U	410 U	410 U	400 U	U
2-Chloronaphthalene	410 U	410 U	410 U	410 U	400 U	U
2-Chlorophenol	410 U	410 U	410 U	410 U	400 U	U
4-Chlorophenyl phenyl ether	410 U	410 U	410 U	410 U	400 U	U
Chrysene	410 U	410 U	410 U	410 U	400 U	U
Di-n-butylphthalate	310 JB	290 JB	190 JB	200 JB	210 JB	JB
Di-n-octylphthalate	410 U*	410 U	410 U	410 U	400 U	U
Dibenz[a,h]anthracene	410 U*	410 U	410 U	410 U	400 U	U

TABLE C.14c (Cont.)

Compound	Soil Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals					
	TBNPBOR I (0-2 ft)	TBNPBOR I (2-4 ft)	TBNPBOR I (4-6 ft)	TBNPBOR I (6-8 ft)	TBNPBOR I (8-10 ft)	
Dibenzofuran	410 U	410 U	410 U	410 U	400 U	
1,2-Dichlorobenzene	410 U	410 U	410 U	410 U	400 U	
1,3-Dichlorobenzene	410 U	410 U	410 U	410 U	400 U	
1,4-Dichlorobenzene	410 U	410 U	410 U	410 U	400 U	
3,3'-Dichlorobenzidine	410 U	410 U	410 U	410 U	400 U	
2,4-Dichlorophenol	410 U	410 U	410 U	410 U	400 U	
Diethylphthalate	410 U	410 U	410 U	410 U	400 U	
2,4-Dimethylphenol	410 U	410 U	410 U	410 U	400 U	
Dimethylphthalate	410 U	410 U	410 U	410 U	400 U	
4,6-Dinitro-2-methylphenol	1,000 U	1,000 U	1,000 U	1,000 U	1,000 U	
2,4-Dinitrophenol	1,000 U	1,000 U	1,000 U	1,000 U	1,000 U	
2,4-Dinitrotoluene	410 U	410 U	410 U	410 U	400 U	
2,6-Dinitrotoluene	410 U	410 U	410 U	410 U	400 U	
Fluoranthene	410 U	410 U	410 U	410 U	400 U	
Fluorene	410 U	410 U	410 U	410 U	400 U	
Hexachlorobenzene	410 U	920	180 J	97 J	400 U	
Hexachlorobutadiene	410 U	410 U	410 U	410 U	400 U	
Hexachlorocyclopentadiene	410 U	410 U	410 U	410 U	400 U	
Hexachloroethane	410 U	410 U	410 U	410 U	400 U	
Indeno[1,2,3-c,d]pyrene	410 U*	410 U	410 U	410 U	400 U	
Isophorone	410 U	410 U	410 U	410 U	400 U	
2-Methylnaphthalene	230 J	42 J	410 U	410 U	400 U	

TABLE C.14c (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	TBNPBORI (0-2 ft)	TBNPBORI (2-4 ft)	TBNPBORI (4-6 ft)	TBNPBORI (6-8 ft)	TBNPBORI (8-10 ft)	
2-Methylphenol	410 U	410 U	410 U	410 U	400 U	
4-Methylphenol	410 U	410 U	410 U	410 U	400 U	
Naphthalene	89 J	42 J	410 U	410 U	400 U	
2-Nitroaniline	1,000 U	1,000 U	1,000 U	1,000 U	1,000 U	
3-Nitroaniline	1,000 U	1,000 U	1,000 U	1,000 U	1,000 U	
4-Nitroaniline	1,000 U	1,000 U	1,000 U	1,000 U	1,000 U	
Nitrobenzene	55 J	410 U	410 U	410 U	400 U	
2-Nitrophenol	410 U	410 U	410 U	410 U	400 U	
4-Nitrophenol	1,000 U	1,000 U	1,000 U	1,000 U	1,000 U	
N-Nitroso-di-n-propylamine	410 U	410 U	410 U	410 U	400 U	
N-Nitrosodiphenylamine	410 U	160 J	410 U	410 U	400 U	
Pentachlorophenol	1,000 U	1,000 U	1,000 U	1,000 U	1,000 U	
Phenanthrene	250 J	410 U	410 U	410 U	400 U	
Phenol	410 U	410 U	410 U	410 U	400 U	
Pyrene	79 J	410 U	410 U	410 U	400 U	
1,2,4-Trichlorobenzene	410 U	410 U	410 U	410 U	400 U	
2,4,5-Trichlorophenol	1,000 U	1,000 U	1,000 U	1,000 U	1,000 U	
2,4,6-Trichlorophenol	43 J	410 U	410 U	410 U	400 U	

See next page for footnotes.

TABLE C.14c (Cont.)

<sup>a</sup> Sampled by ANL, analyzed by Weston Gulf Coast or ANL/ACL, CLP/HSL semivolatile organics.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

J = estimated value.

B = analyte was found in the associated blank.

N = spike and spike duplicate recovery or percent RPD were outside the control limits.

\* = internal standard area counts were outside QC limits.

TABLE C.14d Semivolatile Organics Analyses for Soil Borings, May 1995<sup>a</sup>

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	VXBOR1 (0-2 ft)	VXBOR1 (2-4 ft)	VXBOR1 (6-8 ft)	VXBOR1 (8-10 ft)	VXBOR2 (0-2 ft)	VXBOR2 (2-4 ft)
Acenaphthene	380 U	410 U	460 U	390 U	410 U	380 U
Acenaphthylene	380 U	410 U	460 U	390 U	410 U	380 U
Anthracene	380 U	410 U	460 U	1,400 U	410 U	380 U
Benz[a]anthracene	380 U	410 U	460 U	390 U	410 U	380 U
Benzo[a]pyrene	380 U	410 U	460 U	390 U	410 U	380 U
Benzo[b]fluoranthene	380 U	410 U	460 U	390 U	410 U	380 U
Benzo[g,h,i]perylene	380 U	410 U	460 U	390 U	410 U	380 U
Benzo[k]fluoranthene	380 U	410 U	460 U	390 U	410 U	380 U
Bis(2-chloroethoxy)methane	380 U	410 U	460 U	390 U	410 U	380 U
Bis(2-chloroethyl)ether	380 U	410 U	460 U	390 U	410 U	380 U
Bis(2-ethylhexyl)phthalate	1,600 B	1,400 B	2,500 B	1,100 B	1,300 B	960 B
4-Bromophenyl phenyl ether	380 U	410 U	460 U	390 U	410 U	380 U
Butylbenzylphthalate	750 B	260 JB	460 U	390 U	410 U	380 U
Carbazole	380 U	410 U	460 U	390 U	410 U	380 U
4-Chloro-3-methylphenol	380 U	410 U	460 U	390 U	410 U	380 U
4-Chloroaniline	380 U	410 U	460 U	390 U	410 U	380 U
2-Chloronaphthalene	380 U	410 U	460 U	390 U	410 U	380 U
2-Chlorophenol	380 U	410 U	460 U	390 U	410 U	380 U
4-Chlorophenyl phenyl ether	380 U	410 U	460 U	390 U	410 U	380 U
Chrysene	380 U	410 U	460 U	390 U	410 U	380 U
Di-n-butylphthalate	200 JB	1,200 B	350 JB	460 B	160 JB	380 U
Di-n-octylphthalate	380 U	410 U	460 U	390 U	410 U	380 U
Dibenz[a,h]anthracene	380 U	410 U	460 U	390 U	410 U	380 U
Dibenzofuran	380 U	410 U	460 U	390 U	410 U	380 U

TABLE C.14d (Cont.)

Compound	Soil Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals					
	VXBOR1 (0-2 ft)	VXBOR1 (2-4 ft)	VXBOR1 (6-8 ft)	VXBOR1 (8-10 ft)	VXBOR2 (0-2 ft)	VXBOR2 (2-4 ft)
1,2-Dichlorobenzene	380 U	410 U	460 U	390 U	410 U	380 U
1,3-Dichlorobenzene	380 U	410 U	460 U	390 U	410 U	380 U
1,4-Dichlorobenzene	380 U	410 U	460 U	390 U	410 U	380 U
3,3'-Dichlorobenzidine	380 U	410 U	460 U	390 U	410 U	380 U
2,4-Dichlorophenol	380 U	410 U	460 U	390 U	410 U	380 U
Diethylphthalate	380 U	410 U	460 U	390 U	410 U	380 U
2,4-Dimethylphenol	380 U	410 U	460 U	390 U	410 U	380 U
Dimethylphthalate	380 U	410 U	460 U	390 U	410 U	380 U
4,6-Dinitro-2-methylphenol	950 U	1,000 U	1,200 U	990 U	1,000 U	950 U
2,4-Dinitrophenol	950 U	1,000 U	1,200 U	990 U	1,000 U	950 U
2,4-Dinitrotoluene	380 U	410 U	460 U	390 U	410 U	380 U
2,6-Dinitrotoluene	380 U	410 U	460 U	390 U	410 U	380 U
Fluoranthene	380 U	410 U	460 U	390 U	410 U	380 U
Fluorene	380 U	410 U	980 U	390 U	410 U	380 U
Hexachlorobenzene	380 U	410 U	460 U	390 U	410 U	380 U
Hexachlorobutadiene	380 U	410 U	460 U	390 U	410 U	380 U
Hexachlorocyclopentadiene	380 U	410 U	460 U	390 U	410 U	380 U
Hexachloroethane	380 U	410 U	460 U	390 U	410 U	380 U
Indeno[1,2,3-c,d]pyrene	380 U	410 U	460 U	390 U	410 U	380 U
Isophorone	380 U	410 U	460 U	390 U	410 U	380 U
2-Methylnaphthalene	380 U	410 U	460 U	390 U	410 U	380 U
2-Methylphenol	380 U	410 U	460 U	390 U	410 U	380 U
4-Methylphenol	380 U	410 U	460 U	390 U	410 U	380 U

TABLE C.14d (Cont.)

Compound	Soil Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals					
	VXBOR1 (0-2 ft)	VXBOR1 (2-4 ft)	VXBOR1 (6-8 ft)	VXBOR1 (8-10 ft)	VXBOR2 (0-2 ft)	VXBOR2 (2-4 ft)
Naphthalene	380 U	410 U	460 U	390 U	410 U	380 U
2-Nitroaniline	950 U	1,000 U	1,200 U	990 U	1,000 U	950 U
3-Nitroaniline	950 U	1,000 U	1,200 U	990 U	1,000 U	950 U
4-Nitroaniline	950 U	1,000 U	1,200 U	990 U	1,000 U	950 U
Nitrobenzene	380 U	410 U	460 U	390 U	410 U	380 U
2-Nitrophenol	380 U	410 U	460 U	390 U	410 U	380 U
4-Nitrophenol	950 U	1,000 U	1,200 U	990 U	1,000 U	950 U
N-Nitroso-di-n-propylamine	380 U	410 U	460 U	390 U	410 U	380 U
N-Nitrosodiphenylamine	380 U	410 U	460 U	390 U	410 U	380 U
2,2'-Oxybis-(1-chloropropane)	380 U	410 U	460 U	390 U	410 U	380 U
Pentachlorophenol	950 U	1,000 U	1,200 U	990 U	1,000 U	950 U
Phenanthrene	380 U	3,500 U	2,000 U	1,200 U	410 U	380 U
Phenol	380 U	410 U	460 U	390 U	410 U	380 U
Pyrene	380 U	280 J	460 U	160 J	410 U	380 U
1,2,4-Trichlorobenzene	380 U	410 U	460 U	390 U	410 U	380 U
2,4,5-Trichlorophenol	950 U	1,000 U	1,200 U	990 U	1,000 U	950 U
2,4,6-Trichlorophenol	380 U	410 U	460 U	390 U	410 U	380 U

TABLE C.14d (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	VXBOR2 (4-6 ft)	VXBOR2 (6-8 ft)	VXBOR2 (8-10 ft)	VXBOR2 (10-12 ft)	FTBOR1 (0-2 ft)	FTBOR1 Dup (0-2 ft)
Acenaphthene	390 U	410 U	420 U	390 U	390 U	390 U
Acenaphthylene	390 U	410 U	420 U	390 U	390 U	390 U
Anthracene	390 U	410 U	420 U	390 U	390 U	390 U
Benz[a]anthracene	390 U	410 U	420 U	390 U	390 U	390 U
Benzo[a]pyrene	390 U	410 U	420 U	390 U	390 U	390 U
Benzo[b]fluoranthene	390 U	410 U	420 U	390 U	390 U	390 U
Benzo[g,h,i]perylene	390 U	410 U	420 U	390 U	390 U	390 U
Benzo[k]fluoranthene	390 U	410 U	420 U	390 U	390 U	390 U
Bis(2-chloroethoxy)methane	390 U	410 U	420 U	390 U	390 U	390 U
Bis(2-chloroethyl)ether	390 U	410 U	420 U	390 U	390 U	390 U
Bis(2-ethylhexyl)phthalate	1,500	2,000	4,300 B	4,100 B	1,700 B	4,600 B
4-Bromophenyl phenyl ether	390 U	410 U	420 U	390 U	390 U	390 U
Butylbenzylphthalate	390 U	410 U	420 U	390 U	390 U	390 U
Carbazole	390 U	410 U	420 U	390 U	390 U	390 U
4-Chloro-3-methylphenol	390 U	410 U	420 U	390 U	390 U	390 U
4-Chloroaniline	390 U	410 U	420 U	390 U	390 U	390 U
2-Chloronaphthalene	390 U	410 U	420 U	390 U	390 U	390 U
2-Chlorophenol	390 U	410 U	420 U	390 U	390 U	390 U
4-Chlorophenyl phenyl ether	390 U	410 U	420 U	390 U	390 U	390 U
Chrysene	390 U	410 U	420 U	390 U	390 U	390 U
Di-n-butylphthalate	140 JB	410 U	100 J	210 J	110 J	170 J
Di-n-octylphthalate	390 U	410 U	420 U	390 U	390 U	390 U
Dibenz[a,h]anthracene	390 U	410 U	420 U	390 U	390 U	390 U
Dibenzofuran	390 U	410 U	420 U	390 U	390 U	390 U

TABLE C.14d (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	VXBOR2 (4-6 ft)	VXBOR2 (6-8 ft)	VXBOR2 (8-10 ft)	VXBOR2 (10-12 ft)	FTBOR1 (0-2 ft)	FTBOR1 Dup (0-2 ft)
1,2-Dichlorobenzene	390 U	410 U	420 U	390 U	390 U	390 U
1,3-Dichlorobenzene	390 U	410 U	420 U	390 U	390 U	390 U
1,4-Dichlorobenzene	390 U	410 U	420 U	390 U	390 U	390 U
3,3'-Dichlorobenzidine	390 U	410 U	420 U	390 U	390 U	390 U
2,4-Dichlorophenol	390 U	410 U	420 U	390 U	390 U	390 U
Diethylphthalate	390 U	410 U	420 U	390 - U	390 U	390 U
2,4-Dimethylphenol	390 U	410 U	420 U	390 U	390 U	390 U
Dimethylphthalate	390 U	410 U	420 U	390 U	390 U	390 U
4,6-Dinitro-2-methylphenol	990 U	1,000 U	1,100 U	980 U	980 U	990 U
2,4-Dinitrophenol	990 U	1,000 U	1,100 U	980 U	980 U	990 U
2,4-Dinitrotoluene	390 U	410 U	420 U	390 U	390 U	390 U
2,6-Dinitrotoluene	390 U	410 U	420 U	390 U	390 U	390 U
Fluoranthene	390 U	410 U	420 U	390 U	390 U	390 U
Fluorene	390 U	410 U	420 U	390 U	390 U	390 U
Hexachlorobenzene	390 U	410 U	420 U	390 U	390 U	390 U
Hexachlorobutadiene	390 U	410 U	420 U	390 U	390 U	390 U
Hexachlorocyclopentadiene	390 U	410 U	420 U	390 U	390 U	390 U
Hexachloroethane	390 U	410 U	420 U	390 U	390 U	390 U
Indeno[1,2,3-c,d]pyrene	390 U	410 U	420 U	390 U	390 U	390 U
Isophorone	390 U	410 U	420 U	390 U	390 U	390 U
2-Methylnaphthalene	390 U	410 U	420 U	390 U	390 U	390 U
4-Methylphenol	390 U	410 U	420 U	390 U	390 U	390 U
2-Methylphenol	390 U	410 U	420 U	390 U	390 U	390 U
Naphthalene	390 U	410 U	420 U	390 U	390 U	390 U

TABLE C.14d (Cont.)

Compound	Soil Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals					
	VXBOR2 (4-6 ft)	VXBOR2 (6-8 ft)	VXBOR2 (8-10 ft)	VXBOR2 (10-12 ft)	FTBOR1 (0-2 ft)	FTBOR1 Dup (0-2 ft)
2-Nitroaniline	990 U	1,000 U	1,100 U	980 U	980 U	990 U
3-Nitroaniline	990 U	1,000 U	1,100 U	980 U	980 U	990 U
4-Nitroaniline	990 U	1,000 U	1,100 U	980 U	980 U	990 U
Nitrobenzene	390 U	410 U	420 U	390 U	390 U	390 U
2-Nitrophenol	390 U	410 U	420 U	390 U	390 U	390 U
4-Nitrophenol	990 U	1,000 U	1,100 U	980 U	980 U	990 U
N-Nitroso-di-n-propylamine	390 U	410 U	420 U	390 U	390 U	390 U
N-Nitrosodiphenylamine	390 U	410 U	420 U	390 U	390 U	390 U
2,2'-Oxybis-(1-chloropropane)	390 U	410 U	420 U	390 U	390 U	390 U
Pentachlorophenol	990 U	1,000 U	1,100 U	980 U	980 U	990 U
Phenanthrene	390 U	410 U	420 U	390 U	390 U	390 U
Phenol	390 U	410 U	420 U	390 U	390 U	390 U
Pyrene	390 U	410 U	420 U	390 U	390 U	390 U
1,2,4-Trichlorobenzene	390 U	410 U	420 U	390 U	390 U	390 U
2,4,5-Trichlorophenol	990 U	1,000 U	1,100 U	980 U	980 U	990 U
2,4,6-Trichlorophenol	390 U	410 U	420 U	390 U	390 U	390 U

TABLE C.14d (Cont.)

Soil Concentrations (µg/kg) at Various Depth Intervals						
Compound	FTBOR1 (2-4 ft)	FTBOR1 Dup (2-4 ft)	FTBOR1 (4-6 ft)	FTBOR1 (6-8 ft)	FTBOR1 (8-10 ft)	FTBOR1 (10-12 ft)
Acenaphthene	380 U	380 U	390 U	400 U	460 U+	410 U
Acenaphthylene	380 U	380 U	390 U	400 U	460 U+	410 U
Anthracene	380 U	380 U	390 U	400 U	460 U+	410 U
Benz[a]anthracene	380 U	380 U	390 U	400 U	460 U+	410 U
Benzo[a]pyrene	380 U	380 U	390 U	400 U	460 U+	410 U
Benzo[b]fluoranthene	380 U	380 U	390 U	400 U	460 U+	410 U
Benzo[g,h,i]perylene	380 U	380 U	390 U	400 U	460 U+	410 U
Benzo[k]fluoranthene	380 U	380 U	390 U	400 U	460 U+	410 U
Bis(2-chloroethoxy)methane	380 U	380 U	390 U	400 U	460 U+	410 U
Bis(2-chloroethyl)ether	380 U	380 U	390 U	400 U	460 U+	410 U
Bis(2-ethylhexyl)phthalate	4,300 B	4,100 B	4,500 B	3,200 B	460 U+	3,200 B
4-Bromophenyl phenyl ether	380 U	380 U	390 U	400 U	460 U+	410 U
Butylbenzylphthalate	380 U	380 U	390 U	400 U	460 U+	410 U
Carbazole	380 U	380 U	390 U	400 U	460 U+	410 U
4-Chloro-3-methylphenol	380 U	380 U	390 U	400 U	460 U+	410 U
4-Chloroaniline	380 U	380 U	390 U	400 U	460 U+	410 U
2-Chloronaphthalene	380 U	380 U	390 U	400 U	460 U+	410 U
2-Chlorophenol	380 U	380 U	390 U	400 U	460 U+	410 U
4-Chlorophenyl phenyl ether	380 U	380 U	390 U	400 U	460 U+	410 U
Chrysene	380 U	380 U	390 U	400 U	460 U+	410 U
Di-n-butylphthalate	380 U	140 J	130 J	120 J	200 JB+	410 U
Di-n-octylphthalate	380 U	380 U	390 U	400 U	460 U+	410 U
Dibenz[a,h]anthracene	380 U	380 U	390 U	400 U	460 U+	410 U
Dibenzofuran	380 U	380 U	390 U	400 U	460 U+	410 U

TABLE C.14d (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	FTBORI (2-4 ft)	FTBORI Dup (2-4 ft)	FTBORI (4-6 ft)	FTBORI (6-8 ft)	FTBORI (8-10 ft)	FTBORI (10-12 ft)
1,2-Dichlorobenzene	380 U	380 U	390 U	400 U	460 U+	410 U
1,3-Dichlorobenzene	380 U	380 U	390 U	400 U	460 U+	410 U
1,4-Dichlorobenzene	380 U	380 U	390 U	400 U	460 U+	410 U
3,3'-Dichlorobenzidine	380 U	380 U	390 U	400 U	460 U+	410 U
2,4-Dichlorophenol	380 U	380 U	390 U	400 U	460 U+	410 U
Diethylphthalate	380 U	380 U	390 U	400 U	460 U+	410 U
2,4-Dimethylphenol	380 U	380 U	390 U	400 U	460 U+	410 U
Dimethylphthalate	380 U	380 U	390 U	400 U	460 U+	410 U
4,6-Dinitro-2-methylphenol	960 U	950 U	980 U	1,000 U	1,100 U+	1,000 U
2,4-Dinitrophenol	960 U	950 U	980 U	1,000 U	1,100 U+	1,000 U
2,4-Dinitrotoluene	380 U	380 U	390 U	400 U	460 U+	410 U
2,6-Dinitrotoluene	380 U	380 U	390 U	400 U	460 U+	410 U
Fluoranthene	380 U	380 U	390 U	400 U	460 U+	410 U
Fluorene	380 U	380 U	390 U	400 U	460 U+	410 U
Hexachlorobenzene	380 U	380 U	390 U	400 U	460 U+	410 U
Hexachlorobutadiene	380 U	380 U	390 U	400 U	460 U+	410 U
Hexachlorocyclopentadiene	380 U	380 U	390 U	400 U	460 U+	410 U
Hexachloroethane	380 U	380 U	390 U	400 U	460 U+	410 U
Indeno[1,2,3-c,d]pyrene	380 U	380 U	390 U	400 U	460 U+	410 U
Isophorone	380 U	380 U	390 U	400 U	460 U+	410 U
2-Methylnaphthalene	380 U	380 U	390 U	400 U	460 U+	410 U
2-Methylphenol	380 U	380 U	390 U	400 U	460 U+	410 U
4-Methylphenol	380 U	380 U	390 U	400 U	460 U+	410 U
Naphthalene	380 U	380 U	390 U	400 U	460 U+	410 U

TABLE C.14d (Cont.)

Soil Concentrations (µg/kg) at Various Depth Intervals						
Compound	FTBOR1 (2-4 ft)	FTBOR1 Dup (2-4 ft)	FTBOR1 (4-6 ft)	FTBOR1 (6-8 ft)	FTBOR1 (8-10 ft)	FTBOR1 (10-12 ft)
2-Nitroaniline	960 U	950 U	980 U	1,000 U	1,100 U+	1,000 U
3-Nitroaniline	960 U	950 U	980 U	1,000 U	1,100 U+	1,000 U
4-Nitroaniline	960 U	950 U	980 U	1,000 U	1,100 U+	1,000 U
Nitrobenzene	380 U	380 U	390 U	400 U	460 U+	410 U
2-Nitrophenol	380 U	380 U	390 U	400 U	460 U+	410 U
4-Nitrophenol	960 U	950 U	980 U	1,000 U	1,100 U+	1,000 U
N-Nitroso-di-n-propylamine	380 U	380 U	390 U	400 U	460 U+	410 U
N-Nitrosodiphenylamine	380 U	380 U	390 U	400 U	460 U+	410 U
2,2'-Oxybis-(1-chloropropane)	380 U	380 U	390 U	400 U	460 U+	410 U
Pentachlorophenol	960 U	950 U	980 U	1,000 U	1,100 U+	1,000 U
Phenanthrene	380 U	380 U	390 U	400 U	460 U+	410 U
Phenol	380 U	380 U	390 U	400 U	460 U+	410 U
Pyrene	380 U	380 U	390 U	400 U	460 U+	410 U
1,2,4-Trichlorobenzene	380 U	380 U	390 U	400 U	460 U+	410 U
2,4,5-Trichlorophenol	960 U	950 U	980 U	1,000 U	1,100 U+	1,000 U
2,4,6-Trichlorophenol	380 U	380 U	390 U	400 U	460 U+	410 U

TABLE C.14d (Cont.)

Soil Concentrations (µg/kg) at Various Depth Intervals						
Compound	TBNPBOR3 (0-2 ft)	TBNPBOR (2-4 ft)	TBNPBOR3 (4-6 ft)	TBNPBOR3 (6-8 ft)	TBNPBOR (8-10 ft)	TBNPBOR3 (10-12 ft)
Acenaphthene	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Acenaphthylene	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Anthracene	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Benz[a]anthracene	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Benzo[a]pyrene	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Benzo[b]fluoranthene	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Benzo[g,h,i]perylene	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Benzo[k]fluoranthene	51 J	446 UJ	465 U	393 U	412 U	406 U*J
Bis(2-chloroethoxy)methane	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Bis(2-chloroethyl)ether	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Bis(2-ethylhexyl)phthalate	65 J	446 UJ	1,300	1,900	210 J	1,800 *J
4-Bromophenyl phenyl ether	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Butylbenzylphthalate	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Carbazole	393 U	446 UJ	465 U	393 U	412 U	406 U*J
4-Chloro-3-methylphenol	393 U	446 UJ	465 U	393 U	412 U	406 U*J
4-Chloroaniline	393 U	446 UJ	465 U	393 U	412 U	406 U*J
2-Chloronaphthalene	393 U	446 UJ	465 U	393 U	412 U	406 U*J
2-Chlorophenol	393 U	446 UJ	465 U	393 U	412 U	406 U*J
4-Chlorophenyl phenyl ether	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Chrysene	393 U	446 UJ	465 U	393 U	412 U	406 U*J
di-n-Butylphthalate	393 U	446 UJ	465 U	393 U	63 J	406 U*J
di-n-Octylphthalate	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Dibenz[a,h]anthracene	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Dibenzofuran	393 U	446 UJ	465 U	393 U	412 U	406 U*J

TABLE C.14d (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals						
	TBNPBOR3 (0-2 ft)	TBNPBOR (2-4 ft)	TBNPBOR3 (4-6 ft)	TBNPBOR3 (6-8 ft)	TBNPBOR (8-10 ft)	TBNPBOR3 (10-12 ft)	
1,2-Dichlorobenzene	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
1,3-Dichlorobenzene	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
1,4-Dichlorobenzene	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
3,3'-Dichlorobenzidine	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
2,4-Dichlorophenol	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
Diethylphthalate	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
2,4-Dimethylphenol	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
Dimethylphthalate	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
4,6-Dinitro-2-methylphenol	988 U	1,120 UJ	1,170 U	988 U	1,040 U	1,020 U*J	
2,4-Dinitrophenol	988 U	1,120 UJ	1,170 U	988 U	1,040 U	1,020 U*J	
2,4-Dinitrotoluene	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
2,6-Dinitrotoluene	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
Fluoranthene	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
Fluorene	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
Hexachlorobenzene	170 J	446 UJ	465 U	393 U	412 U	406 U*J	
Hexachlorobutadiene	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
Hexachlorocyclopentadiene	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
Hexachloroethane	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
Indeno[1,2,3-cd]pyrene	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
Isophorone	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
2-Methylnaphthalene	120 J	446 UJ	580	2,100	412 U	1,700 *J	
2-Methylphenol	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
4-Methylphenol	393 U	446 UJ	465 U	393 U	412 U	406 U*J	
Naphthalene	393 U	446 UJ	710	1,800	412 U	1,600 *J	

TABLE C.14d (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals					
	TBNPBOR3 (0-2 ft)	TBNPBOR (2-4 ft)	TBNPBOR3 (4-6 ft)	TBNPBOR3 (6-8 ft)	TBNPBOR (8-10 ft)	TBNPBOR3 (10-12 ft)
2-Nitroaniline	988 U	1,120 UJ	1,170 U	988 U	1,040 U	1,020 U*J
3-Nitroaniline	988 U	1,120 UJ	1,170 U	988 U	1,040 U	1,020 U*J
4-Nitroaniline	988 U	1,120 UJ	1,170 U	988 U	1,040 U	1,020 U*J
Nitrobenzene	393 U	446 UJ	465 U	393 U	412 U	406 U*J
2-Nitrophenol	393 U	446 UJ	465 U	393 U	412 U	406 U*J
4-Nitrophenol	988 U	1,120 UJ	1,170 U	988 U	1,040 U	1,020 U*J
N-Nitroso-di-n-propylamine	393 U	446 UJ	465 U	393 U	412 U	406 U*J
N-Nitrosodiphenylamine	393 U	446 UJ	465 U	393 U	412 U	406 U*J
2,2'-Oxybis-(1-chloropropane)	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Pentachlorophenol	988 U	1,120 UJ	1,170 U	988 U	1,040 U	1,020 U*J
Phenanthrene	93 J	446 UJ	465 U	880	412 U	406 U*J
Phenol	393 U	446 UJ	465 U	393 U	412 U	406 U*J
Pyrene	62 J	446 UJ	465 U	393 U	412 U	406 U*J
1,2,4-Trichlorobenzene	393 U	446 UJ	465 U	393 U	412 U	406 U*J
2,4,5-Trichlorophenol	988 U	1,120 UJ	1,170 U	988 U	1,040 U	1,020 U*J
2,4,6-Trichlorophenol	393 U	446 UJ	465 U	393 U	412 U	406 U*J

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals			
	VXBOR3 (2-4 ft)	VXBOR4 (2-4 ft)	VXBOR4 (4-6 ft)	VXBOR5 (8-10 ft)
Acenaphthene	7,920 U	8,350 UJ	8,050 U	428 U
Acenaphthylene	7,920 U	8,350 UJ	8,050 U	428 U
Anthracene	810 J	8,350 UJ	8,050 U	428 U

TABLE C.14d (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals				
	VXBOR3 (2-4 ft)	VXBOR4 (2-4 ft)	VXBOR4 (4-6 ft)	VXBOR5 (4-6 ft)	VXBOR5 (8-10 ft)
Benz[a]anthracene	7,920 U	1,200 UJ	8,050 U	428 U	407 U
Benzo[a]pyrene	7,920 U	1,300 J	8,050 U	428 U	407 U
Benzo[b]fluoranthene	7,920 U	1,200 J	1,020 J	428 U	407 U
Benzo[g,h,i]perylene	890 J	2,400 J	1,600 J	428 U	407 U
Benzo[k]fluoranthene	7,920 U	8,350 UJ	3,100 J	428 U	407 U
Bis(2-chloroethoxy)methane	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Bis(2-chloroethyl)ether	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Bis(2-ethylhexyl)phthalate	7,920 U	8,350 UJ	8,050 U	428 U	407 U
4-Bromophenyl phenyl ether	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Butylbenzylphthalate	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Carbazole	7,920 U	8,350 UJ	8,050 U	428 U	407 U
4-Chloro-3-methylphenol	7,920 U	8,350 UJ	8,050 U	428 U	407 U
4-Chloroaniline	7,920 U	8,350 UJ	8,050 U	428 U	407 U
2-Chloronaphthalene	7,920 U	8,350 UJ	8,050 U	428 U	407 U
2-Chlorophenol	7,920 U	8,350 UJ	8,050 U	428 U	407 U
4-Chlorophenyl phenyl ether	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Chrysene	1,500 J	2,100 J	1,100 J	428 U	407 U
di-n-Butylphthalate	7,920 U	47,000 BJ	27,000 B	428 U	73 JB
di-n-Octylphthalate	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Dibenz[a,h]anthracene	7,920 U	1,700 J	8,050 U	428 U	407 U
Dibenzofuran	7,920 U	8,350 UJ	8,050 U	428 U	407 U
1,2-Dichlorobenzene	7,920 U	8,350 UJ	8,050 U	428 U	407 U
1,3-Dichlorobenzene	7,920 U	8,350 UJ	8,050 U	428 U	407 U
1,4-Dichlorobenzene	7,920 U	8,350 UJ	8,050 U	428 U	407 U

TABLE C.14d (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals				
	VXBOR3 (2-4 ft)	VXBOR4 (2-4 ft)	VXBOR4 (4-6 ft)	VXBOR5 (4-6 ft)	VXBOR5 (8-10 ft)
3,3'-Dichlorobenzidine	7,920 U	8,350 UJ	8,050 U	428 U	407 U
2,4-Dichlorophenol	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Diethylphthalate	7,920 U	8,350 UJ	8,050 U	428 U	407 U
2,4-Dimethylphenol	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Dimethylphthalate	7,920 U	8,350 UJ	8,050 U	428 U	407 U
4,6-Dinitro-2-methylphenol	19,900 U	21,000 UJ	20,200 U	1080 U	1020 U
2,4-Dinitrophenol	19,900 U	21,000 UJ	20,200 U	1080 U	1020 U
2,4-Dinitrotoluene	7,920 U	8,350 UJ	8,050 U	428 U	407 U
2,6-Dinitrotoluene	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Fluoranthene	7,920 U	2,600 J	1,900 J	150 J	407 U
Fluorene	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Hexachlorobenzene	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Hexachlorobutadiene	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Hexachlorocyclopentadiene	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Hexachloroethane	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Indeno[1,2,3-cd]pyrene	7,920 U	2,000 J	8,050 U	428 U	407 U
Isophorone	7,920 U	8,350 UJ	8,050 U	428 U	407 U
2-Methylnaphthalene	980 J	53,000 J	12,000	8100 *	407 U
2-Methylphenol	7,920 U	8,350 UJ	8,050 U	428 U	407 U
4-Methylphenol	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Naphthalene	7,920 U	8,350 UJ	8,050 U	420 J	407 U
2-Nitroaniline	19,900 U	21,000 UJ	20,200 U	1080 U	1020 U
3-Nitroaniline	19,900 U	21,000 UJ	20,200 U	1080 U	1020 U
4-Nitroaniline	19,900 U	21,000 UJ	20,200 U	1080 U	1020 U

TABLE C.14d (Cont.)

Compound	Soil Concentrations (µg/kg) at Various Depth Intervals				
	VXBOR3 (2-4 ft)	VXBOR4 (2-4 ft)	VXBOR4 (4-6 ft)	VXBOR5 (4-6 ft)	VXBOR5 (8-10 ft)
Nitrobenzene	7,920 U	8,350 UJ	8,050 U	428 U	407 U
2-Nitrophenol	7,920 U	8,350 UJ	8,050 U	428 U	407 U
4-Nitrophenol	19,900 U	21,000 UJ	20,200 U	1080 U	1020 U
N-Nitroso-di-n-propylamine	7,920 U	8,350 UJ	8,050 U	428 U	407 U
N-Nitrosodiphenylamine	7,920 U	8,350 UJ	8,050 U	428 U	407 U
2,2'-Oxybis-(1-chloropropane)	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Pentachlorophenol	19,900 U	21,000 UJ	20,200 U	1080 U	1020 U
Phenanthrene	1,500 J	32,000 J	27,000	3100	407 U
Phenol	7,920 U	8,350 UJ	8,050 U	428 U	407 U
Pyrene	3,300 J	8,350 UJ	8,050 U	170 J	407 U
1,2,4-Trichlorobenzene	7,920 U	8,350 UJ	8,050 U	428 U	407 U
2,4,5-Trichlorophenol	19,900 U	21,000 UJ	20,200 U	1080 U	1020 U
2,4,6-Trichlorophenol	7,920 U	8,350 UJ	8,050 U	428 U	407 U

Compound	Soil Concentrations (µg/kg) at 0-6 in.		
	SQPS-1	SQPS-5	SQPS-8
Acenaphthene	412 U	407 U	686 U
Acenaphthylene	412 U	407 U	686 U
Anthracene	412 U	407 U	686 U
Benz[a]anthracene	412 U	407 U	686 U
Benzol[a]pyrene	412 U	407 U	686 U
Benzol[b]fluoranthene	412 U	407 U	686 U
Benzol[g,h,i]perylene	412 U	407 U	686 U

TABLE C.14d (Cont.)

Compound	Soil Concentrations (µg/kg) at 0-6 in.			
	SQPS-1	SQPS-5	SQPS-8	
Benzo[k]fluoranthene	412	42	686	U
Bis(2-chloroethoxy)methane	412	407	686	U
Bis(2-chloroethyl)ether	412	407	686	U
Bis(2-ethylhexyl)phthalate	412	407	686	U
4-Bromophenyl phenyl ether	412	407	686	U
Butylbenzylphthalate	412	407	686	U
Carbazole	412	407	686	U
4-Chloro-3-methylphenol	412	407	686	U
4-Chloroaniline	412	407	686	U
2-Chloronaphthalene	412	407	686	U
2-Chlorophenol	412	407	686	U
4-Chlorophenyl phenyl ether	412	407	686	U
Chrysene	412	407	686	U
di-n-Butylphthalate	412	407	686	U
di-n-Octylphthalate	412	407	686	U
Dibenz[a,h]anthracene	412	407	686	U
Dibenzofuran	412	407	686	U
1,2-Dichlorobenzene	412	407	686	U
1,3-Dichlorobenzene	412	407	686	U
1,4-Dichlorobenzene	412	407	686	U
3,3'-Dichlorobenzidine	412	407	686	U
2,4-Dichlorophenol	412	407	686	U
Diethylphthalate	412	407	686	U

TABLE C.14d (Cont.)

Compound	Soil Concentrations ( $\mu\text{g/kg}$ ) at 0-6 in.			
	SQPS-1	SQPS-5	SQPS-8	
2,4-Dimethylphenol	412 U	407 U	686 U	
Dimethylphthalate	412 U	407 U	686 U	
4,6-Dinitro-2-methylphenol	1,040 U	1,020 U	1,730 U	
2,4-Dinitrophenol	1,040 U	1,020 U	1,730 U	
2,4-Dinitrotoluene	412 U	407 U	686 U	
2,6-Dinitrotoluene	412 U	407 U	686 U	
Fluoranthene	412 U	407 U	686 U	
Fluorene	412 U	407 U	686 U	
Hexachlorobenzene	412 U	407 U	686 U	
Hexachlorobutadiene	412 U	407 U	686 U	
Hexachlorocyclopentadiene	412 U	407 U	686 UJ	
Hexachloroethane	412 U	407 U	686 U	
Indeno[1,2,3-cd]pyrene	412 U	407 U	686 U	
Isophorone	412 U	407 U	686 U	
2-Methylnaphthalene	412 U	407 U	686 U	
2-Methylphenol	412 U	407 U	686 U	
4-Methylphenol	412 U	407 U	686 U	
Naphthalene	412 U	407 U	686 U	
2-Nitroaniline	1,040 U	1,020 U	1,730 U	
3-Nitroaniline	1,040 U	1,020 U	1,730 U	
4-Nitroaniline	1,040 U	1,020 U	1,730 U	
Nitrobenzene	412 U	407 U	686 U	
2-Nitrophenol	412 U	407 U	686 U	
4-Nitrophenol	1,040 U	1,020 U	1,730 U	

TABLE C.14d (Cont.)

Compound	Soil Concentrations (µg/kg) at 0-6 in.			
	SQPS-1	SQPS-5	SQPS-8	
N-Nitroso-di-n-propylamine	412 U	407 U	686 U	
N-Nitrosodiphenylamine	412 U	407 U	686 U	
2,2'-Oxybis-(1-chloropropane)	412 U	407 U	686 U	
Pentachlorophenol	1,040 U	1,020 U	1,730 U	
Phenanthrene	412 U	407 U	686 U	
Phenol	412 U	407 U	686 U	
Pyrene	412 U	407 U	686 U	
1,2,4-Trichlorobenzene	412 U	407 U	686 U	
2,4,5-Trichlorophenol	1,040 U	1,020 U	1,730 U	
2,4,6-Trichlorophenol	412 U	407 U	686 U	

<sup>a</sup> Sampled by ANL and analyzed by GP Environmental Services.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

J = estimated value.

\* = internal standard area counts were outside QC limits.

B = analyte was found in the associated blank.

TABLE C.15a Inorganic Analysis for Soil Borings, January 1993<sup>a</sup>

Analyte	Soil Concentrations (mg/kg) at Various Depths							
	JBP1-E-2' (2 ft)	JBP1-E-2'Dup (2 ft)	JBP1-E-4' (4 ft)	JBP1-W-2' (2 ft)	JBP1-W-4' (4 ft)	JBP2-E-2' (2 ft)	JBP2-E-4' (4 ft)	JBP2-E-4'Dup (4 ft)
Aluminum	11,300	6,870	12,600	14,000	12,800	10,900	3,810	6,480
Antimony	5.08	4.57	U	4.68	U	4.6	U	4.57
Arsenic	5.02	3.22	4.18	3.58	2.01	3.5	1.32	2.33
Barium	125	45.3	34.1	47.5	22.4	32.7	21.5	29.5
Beryllium	0.31	0.19	U	0.33	0.28	0.23	U	0.38
Cadmium	3.21	0.57	U	0.59	U	0.58	U	0.57
Calcium	1,530	5,670	787	529	828	987	618	3,640
Chromium	36.6	11.6	18.2	16.5	16.5	14.2	6.51	12.7
Cobalt	5.64	5.43	U	5.56	U	5.47	U	5.43
Copper	248	34.1	10.1	19.9	10.9	6.85	9.73	10.1
Iron	35,800	11,400	23,100	13,300	20,400	14,100	4,900	21,100
Lead	340	36.4	10.5	13.2	9.31	15.9	23.6	96.3
Magnesium	2,340	1,200	1,940	2,490	1,610	1,560	572	704
Manganese	197	118	72.6	98.6	47	64.6	21.5	108
Mercury	0.12	0.12	U	0.12	U	0.12	U	0.12
Nickel	20.4	9.34	13.8	15.4	10	8.19	6.91	6.88
Potassium	916	530	1,220	1,460	1,460	971	338	482
Selenium	1.05	1.02	1.05	1.05	1.07	1.03	1.03	1.02
Silver	1.63	0.17	U	0.56	0.17	0.17	U	0.17
Sodium	46.5	45.2	U	46.3	U	333	45.4	86.5
Thallium	0.56	0.54	U	0.56	U	0.55	U	0.55
Vanadium	19.8	12.8	23.4	22.1	25.1	19.2	7.57	18.9
Zinc	1,220	182	123	303	52.1	94.4	76.5	72



TABLE C.15a (Cont.)

Soil Concentrations (mg/kg) at Various Depths								
Analyte	JVXP-C-6' (6 ft)	JSDP-C-4' (4 ft)	JSDP-C-6' (6 ft)	JBPM-A-3" (3 in.)	JBPM-A-3"Dup (3 in.)	JBPM-A-1' (1 ft)	JBPM-B-3" (3 in.)	JBPM-B-1' (1 ft)
Aluminum	2,230	4,700	4,120	8,480	7,860	8,320	8,680	11,900
Antimony	5.41 U	5.12 U	5.03 U	4.58 U	4.55 U	4.57 U	13.7	4.49 U
Arsenic	1.04 U	1.38	0.97 U	3.95	4.8	22.5	7.49	3.58
Barium	8.1	15.5	12.7	403	158	216	336	42.8
Beryllium	0.23 U	2.14 U	0.21 U	0.43	0.30	0.26	0.34	0.40
Cadmium	0.68 U	0.64 U	0.63 U	2.95	2.37	6.05	5.94	0.56 U
Calcium	178	240	269	1,170	1,150	1,930	1,710	228
Chromium	3.15	4.09	5.54	37.8	34.9	67.9	53.4	15.6
Cobalt	6.42	6.09 U	5.98 U	5.44 U	5.41 U	5.42 U	6.41	5.33 U
Copper	4.84 U	4.59 U	4.51 U	305	209	392	521	4.77
Iron	3,170	5,970	5,090	13,400	12,600	21,000	28,300	20,500
Lead	2.6	3.37	8.22	145	129	542	79,800	11.2
Magnesium	551	1,010	944	1,470	1,170	1,350	4,460	1,550
Manganese	25.6	48.1	38.4	142	138	163	209	86.6
Mercury	0.1 U	0.1 U	0.1 U	0.13	0.22	0.95	0.22	0.1 U
Nickel	8.14 U	7.72 U	7.58 U	8.19	6.86 U	12.5	24.2	7.26
Potassium	405	383	376	431	384	429	243	508
Selenium	1.21 U	1.15 U	1.13 U	1.03 U	1.02 U	1.02 U	1.98	1.01 U
Silver	0.20 U	0.19 U	0.18 U	2.91	1.87	1.81	1.49	0.16 U
Sodium	53.5	50.7 U	49.8 U	51	91.7	91.9	206	50
Thallium	0.65 U	0.61 U	0.60 U	0.55 U	0.55 U	0.55 U	0.52 U	0.54 U
Vanadium	6 U	6.74	5.58 U	15.1	15.8	13.8	10.4	26.3
Zinc	13.1	13.5	12.8	237	690	678	1,000	46.9

TABLE C.15a (Cont.)

Analyte	Soil Concentrations (mg/kg) at Various Depths							
	JBPM-C-3" (3 in.)	JBPM-C-1' (1 ft)	JBPP-A-3" (3 in.)	JBPP-A-1' (1 ft)	JBPP-B-3" (3 in.)	JBPP-B-1' (1 ft)	JBPP-C-3" (3 in.)	JBPP-C-1' (1 ft)
Aluminum	10,400	5,100	5,670	7,320	6,720	5,860	5,910	10,500
Antimony	4.88 U	4.4 U	4.5 U	4.55 U	67.3	44.2	4.57 U	4.57 U
Arsenic	12.3	2.32	1.76	2.32	16.7	109	2.56	1.88
Barium	2,400	150	107	31.5	534	300	53.2	32.4
Beryllium	0.20 U	0.30	0.21	0.19 U	0.22 U	0.19 U	0.21	0.26
Cadmium	2.43	0.55 U	0.56 U	0.57 U	11.4	9.57	0.99	0.57 U
Calcium	1,240	155	445	526	27,900	1,390	420	701
Chromium	89.6	7.47	17	10.3	223	103	11.3	14.3
Cobalt	5.79 U	5.22 U	5.34 U	5.41 U	11.1	108	5.43 U	5.43 U
Copper	365	21	60.5	4.08 U	908	662	33.2	8.39
Iron	18,600	7,470	11,300	11,900	24,900	47,100	9,790	17,400
Lead	290	6.05	105	8.37	1,180	1,110	28	9
Magnesium	22,400	3,020	874	999	13,500	2,220	984	1,380
Manganese	229	73.3	75.6	61.7	270	240	85.8	83
Mercury	0.1 U	0.1 U	0.12 U	0.12 U	0.42	3.6	0.12 U	0.12 U
Nickel	20.9	6.62 U	6.77 U	6.86 U	103	43.3	7	7.53
Potassium	271	329	331	384	668	381	337	554
Selenium	1.09 U	0.99 U	1.01 U	1.02 U	1.18 U	7.12	1.02 U	1.0 U
Silver	0.45	0.16 U	0.26	0.17 U	8.53	5.84	0.19	0.17 U
Sodium	54.3	43.5 U	44.5 U	45 U	176	44.8 U	45.2 U	45.2 U
Thallium	0.58 U	0.53 U	0.54 U	0.55 U	0.63 U	0.54 U	0.55 U	0.55 U

TABLE C.15a (Cont.)

Analyte	Soil Concentrations (mg/kg) at Various Depths							
	JBPM-C-3" (3 in.)	JBPM-C-1' (1 ft)	JBPP-A-3" (3 in.)	JBPP-A-1' (1 ft)	JBPP-B-3" (3 in.)	JBPP-B-1' (1 ft)	JBPP-C-3" (3 in.)	JBPP-C-1' (1 ft)
Vanadium	11.3	10.6	12.6	15	25.2	12.3	12	23.4
Zinc	252	27	84.1	20.2	1,640	5,820	82.8	20.5

<sup>a</sup> Sampled by Weston, analyzed by GP Environmental Services; provisional data.

Data qualifier:

U = analyte was analyzed for but not detected; detection limit given.

TABLE C.15b Inorganic Analyses for Soil Borings, January 1994<sup>a</sup>

Parameter	Soil Concentrations (mg/kg) at Various Depth Intervals							
	CLP1 (0-6 in.)	CLP1 (6-24 in.)	CLP1 (24-40 in.)	CLP2 (0-6 in.)	CLP2 (6-24 in.)	CLP2 (24-48 in.)	CLP3 (0-6 in.)	CLP3 (6-24 in.)
<b>Metals</b>								
Aluminum	8,480	8,480	9,510	11,500	8,640	7,530	17,500	10,800
Antimony	360	54.4	5.1	119	198	134	16.6	47.7
Arsenic	18.3	46.9	18.9	37.3	31.6	39.8	24	15.4
Barium	873	1,470	1,340	837	1,180	1,230	843	1,580
Beryllium	0.44	0.31	0.56	0.34	0.23	0.42	0.95	0.59
Cadmium	6.5	9.1	3.4	6.4	8.9	8.1	1.6	7.0
Calcium	9,730	2,320	1,510	1,500	1,640	1,650	2,330	3,880
Chromium	171	293	85.9	338	878	312	59.6	130
Cobalt	6.1	6.7	5.1	7.7	10.3	8.4	8.5	7.3
Copper	616	2,170	301	1,840	4,320	1,380	530	1,070
Iron	21,200	46,200	20,600	68,800	104,000	69,400	29,000	49,000
Lead	41,000	6,460	1,060	16,500	24,200	18,900	3,190	15,500
Magnesium	2,870	3,400	3,030	2,160	2,590	2,500	3,390	3,230
Manganese	209	333	142	374	499	289	146	293
Mercury	0.5	0.46	0.38	0.27	0.18	0.21	1.5	1.4
Nickel	23.1	34.8	19.5	41.5	59.6	42.4	28.3	40.6
Potassium	613	408	489	443	419	283	1,190	791
Selenium	0.52	0.63	0.69	0.39	0.43	1.7	0.54	0.40
Silver	41.9	14.3	2.2	23.4	40.3	20.4	2.9	10.7
Sodium	144	156	219	141	161	292	263	437
Thallium	0.36	0.32	0.3	1.5	1.6	1.8	0.45	0.39
Vanadium	17.8	14.1	15.1	14.3	14.5	12.7	32.4	18.4
Zinc	2,760	5,760	1,530	5,330	5,730	5,950	2,490	4,780

TABLE C.15b (Cont.)

Soil Concentrations (mg/kg) at Various Depth Intervals							
Parameter	CLP1 (0-6 in.)	CLP1 (6-24 in.)	CLP1 (24-40 in.)	CLP2 (0-6 in.)	CLP2 (6-24 in.)	CLP2 (24-48 in.)	CLP3 (6-24 in.)
Other Parameters							
Cyanide (total)	1.0	13	16	1.0	3.0	4.0	11
Solids (%)	66.4	77.7	79.6	78.6	77	66	66.2
Soil Concentrations (mg/kg) at Various Depth Intervals							
Parameter	CLP3-Dup (6-24 in.)	CLP3 (24-48 in.)	CLP4 (0-6 in.)	CLP4 (6-24 in.)	CLP4 (24-48 in.)	CLP5 (0-6 in.)	CLP5 (24-48 in.)
Metals							
Aluminum	10,900	9,280	9,310	13,900	10,300	8,070	10,800
Antimony	76.8	14.6	29.8	24.8	13.4	5.3	U
Arsenic	20.5	21.1	18.3	16	4.6	12.5	U
Barium	1,450	503	820	803	143	294	267
Beryllium	0.44	0.78	0.56	0.58	1.3	0.39	81.8
Cadmium	9.5	5.8	5.5	5.0	2.2	2.4	0.57
Calcium	5,340	4,530	2,050	3,430	4,430	2,720	0.71
Chromium	146	47.9	59.6	73.5	18.6	73.5	2,820
Cobalt	9.0	5.3	5.3	4.7	6.1	4.2	17
Copper	1,120	320	608	552	72.8	760	6.4
Iron	83,900	24,200	22,100	27,200	15,800	14,600	22.6
Lead	11,100	2,800	4,580	5,040	371	791	13,900
Magnesium	3,290	3,980	2,530	3,010	2,430	1,440	21.3
Manganese	593	151	186	201	107	168	1,690
Mercury	1.1	0.69	1.2	1.5	0.24	0.48	191
							0.23

TABLE C.15b (Cont.)

Soil Concentrations (mg/kg) at Various Depth Intervals								
Parameter	CLP3-Dup (6-24 in.)	CLP3 (24-48 in.)	CLP4 (0-6 in.)	CLP4 (6-24 in.)	CLP4 (24-48 in.)	CLP5 (0-6 in.)	CLP5 (6-24 in.)	CLP5 (24-48 in.)
Nickel	45	18.8	23.8	26.2	13.3	12.2	13	10.2
Potassium	675	1,190	617	662	952	506	339	557
Selenium	0.36	0.73	U	0.33	U	0.42	0.38	0.5
Silver	12.5	3.1	4.6	3.5	3.1	3.7	1.3	0.66
Sodium	521	1,400	189	284	537	88.7	158	125
Thallium	1.9	0.85	2.0	1.9	0.76	0.31	U	0.33
Vanadium	15.7	13.6	14.8	15	15.2	13.8	13.6	18.1
Zinc	6,690	2,960	2,880	2,940	1,400	732	845	114
Other Parameter								
Cyanide (mg/kg)	120	16	0.8	U	1.0	0.8	U	0.8
Solids (%)	34.4	67.3	68.8	74.8	38.3	78.6	83.8	74.3
Soil Concentrations (mg/kg) at Various Depth Intervals								
Parameter	CLP5-Dup (24-48 in.)	CLP6 (0-6 in.)	CLP6 (6-24 in.)	CLP7 (0-6 in.)	CLP7 (6-24 in.)	CLP7 (24-48 in.)	CLP8 (0-6 in.)	CLP9 (0-6 in.)
Metals								
Aluminum	8,820	7,990	8,640	17,000	7,030	8,930	5,080	6,780
Antimony	5.0	U	38.6	6.3	U	5.2	U	19.5
Arsenic	2.2	39.8	22.9	12.3	4.5	6.2	41	17.1
Barium	62.1	756	828	157	87.7	245	1,560	498
Beryllium	0.62	0.54	0.42	0.98	0.55	0.52	0.45	0.31
Cadmium	0.78	2.5	6.2	1.4	0.9	0.67	U	4.5

TABLE C.15b (Cont.)

Parameter	Soil Concentrations (mg/kg) at Various Depth Intervals								
	CLP5-Dup (24-48 in.)	CLP6 (0-6 in.)	CLP6 (6-24 in.)	CLP7 (0-6 in.)	CLP7 (6-24 in.)	CLP7 (24-48 in.)	CLP8 (0-6 in.)	CLP9 (0-6 in.)	
Calcium	2,140	3,520	2,800	3,950	4,080	11,100	386	1,090	
Chromium	10.8	65.2	79.3	28.6	11.8	14.4	118	82.5	
Cobalt	6.6	6.1	9.0	9.1	4.2	4.8	5.6	3.8	
Copper	15.3	439	559	61.5	28.6	26.4	1,040	449	
Iron	9,830	28,600	60,900	22,700	8,370	11,100	90,800	16,500	
Lead	23.1	2,440	5,340	163	135	107	94,200	2,050	
Magnesium	1,500	2,170	2,350	2,560	1,090	1,400	765	3,880	
Manganese	99.7	316	393	340	172	216	134	156	
Mercury	0.13	0.79	0.46	0.2	0.11	U	0.6	0.22	
Nickel	9.4	20.4	38.2	17.2	8.4	9.5	24.8	17.9	
Potassium	417	507	606	870	384	505	1,130	308	
Selenium	0.44	0.43	0.62	0.42	0.43	0.36	2.8	0.5	
Silver	0.6	5.1	6.7	0.75	U	0.62	U	2.0	
Sodium	102	156	250	101	81.9	133	504	78.3	
Thallium	0.33	U	0.32	U	0.31	U	3.8	U	U
Vanadium	13.3	16.9	20.1	32.7	12.2	16.5	20.2	11.7	
Zinc	87.9	3,720	4,450	176	92.2	103	1,420	1,250	
Other Parameters									
Cyanide (total)	0.8	U	0.8	U	0.8	U	5.0	0.7	U
Solids (%)	75.3	75.3	78.5	64.2	78.1	0.8	32.5	81.1	

<sup>a</sup> Sampled by ANL, analyzed by Weston Gulf Coast, CLP TAL metals and other inorganic parameters.

Data qualifier:

U = analyte was analyzed for but not detected; detection limit given.

TABLE C.15c Inorganic Analyses for Soil Borings, 1994-1995<sup>a</sup>

Soil Concentrations (mg/kg) at Various Depth Intervals							
Parameter	TBSPBOR1 (0-2 ft)	TBSPBOR1 Dup (0-2 ft)	TBSPBOR1 (2-4 ft)	TBSPBOR1 (4-6 ft)	TBSPBOR1 (6-8 ft)	TBSPBOR1 (8-10 ft)	TBSPBOR1 (10-12 ft)
Metals							
Aluminum	10,900	9,940	13,300	13,300	13,100	11,400	8,520
Antimony	6.2 N	6.0	2.9 UN	4.6 N	2.8 UN	2.9 UN	2.8 UN
Arsenic	28.2	20.2	9.7	8.9	6.5	6.8	3.0
Barium	212	283	124	147	143	53.5	42.3
Beryllium	0.43	0.38	0.54	0.5	0.52	0.4	0.32
Cadmium	2.1	3.0	3.2	1.0	1.5	0.79	0.57
Calcium	2,130	3,900	1,580	2,250	1,790	2,000	1,650
Chromium	34.3	53.8	24.2	25	20.8	19.2	14.3
Cobalt	7.0	5.6	6.3	6.0	6.0	5.8	5.9
Copper	277	366	151	71.1	36.3	24.8	10.3
Iron	52,000	26,500	20,300	20,400	21,800	17,200	15,300
Lead	650 @	831	204 @	116 @	38.8 @	58.8 @	10 @
Magnesium	1,580	1,720	1,700	2,010	1,960	1,550	1,490
Manganese	219	172	88.6	116	91.3	78.2	64
Mercury	1.3	1.8	0.38	0.1 U	0.13 U	0.1 U	0.1 U
Nickel	24.4	19	14.2	13	12.1	11.8	12.3
Potassium	531	473	530	603	630	716	596
Selenium	1.7	1.4	1.1	0.23 W	0.24 W	0.26 W	0.16 UW
Silver	1.6	2.5	1.0	0.42	2.4	0.65	0.37 U
Sodium	179	186	136	91.9	76	55.4	35.8
Thallium	0.26 UW	0.25 U	0.27 UW	0.26 UW	0.27 UW	0.27 UW	0.25 UW

TABLE C.15c (Cont.)

Parameter	Soil Concentrations (mg/kg) at Various Depth Intervals						
	TBSPBOR1 (0-2 ft)	TBSPBOR1 Dup (0-2 ft)	TBSPBOR1 (2-4 ft)	TBSPBOR1 (4-6 ft)	TBSPBOR1 (6-8 ft)	TBSPBOR1 (8-10 ft)	TBSPBOR1 (10-12 ft)
Metals (Cont.)							
Vanadium	17.8	17.6	20.6	25.5	26.2	21.7	14.5
Zinc	757 E	1,240	450 E	192 E	79.6 E	61.3 E	38.1 E
Other parameter							
Cyanide (total)	1.9 U	1.9 U	2.0 U	1.7 U	1.9 U	1.7 U	1.8 U
Parameter	Soil Concentrations (mg/kg) at Various Depth Intervals						
	TBSPBOR2 (0-2 ft)	TBSPBOR2 Dup (0-2 ft)	TBSPBOR2 (2-4 ft)	TBSPBOR2 (4-6 ft)	TBSPBOR2 (6-8 ft)	TBSPBOR2 (8-10 ft)	
Metals							
Aluminum	11,300	9,160	9,900	5,270	6,380	9,720	
Antimony	2.8 UN	2.7 U	2.9 UN	2.8 UN	2.8 UN	2.8 UN	
Arsenic	5.4	4.5	4.9	1.4	1.9	1.5 W	
Barium	53.1	40.5	39.3	24.6	36.5	59.3	
Beryllium	0.27	0.28	0.49	0.23	3.0	0.37	
Cadmium	0.95	0.7	0.51 U	0.49 U	0.5 U	0.5 U	
Calcium	934	937	887	716	876	1290	
Chromium	19.4	16.5	16.4	8.9	11.2	14.5	
Cobalt	6.0	5.2	5.2	2.6	4.6	6.4	
Copper	72.4	55.7	19.4	6.8	7.2	11	
Iron	16,200	15,200	19,700	7,870	13,400	11,900	
Lead	28.2 @	22.5	9.6 @	11 @	11.8 @	16.2 @	

TABLE C.15c (Cont.)

Soil Concentrations (mg/kg) at Various Depth Intervals						
Parameter	TBSPBOR2 (0-2 ft)	TBSPBOR2 Dup (0-2 ft)	TBSPBOR2 (2-4 ft)	TBSPBOR2 (4-6 ft)	TBSPBOR2 (6-8 ft)	TBSPBOR2 (8-10 ft)
Metals (Cont.)						
Magnesium	2,130	1,870	1,660	778	1,100	1,810
Manganese	99.3	90.1	66.9	27	57.2	73.3
Mercury	0.09 U	0.1 U	0.1 U	0.11 U	0.1 U	0.11 U
Nickel	13	10.8	10.6	5.2	7.9	12.6
Potassium	748	561	606	524	550	801
Selenium	0.22 W	0.24	0.16 UW	0.16 U	0.2 W	0.33 W
Silver	0.38 U	0.36 U	0.39 U	0.38 U	0.38 U	0.38 U
Sodium	141	123	303	174	96.3	69.1
Thallium	0.25 UW	0.26 U	0.26 UW	0.26 UW	0.25 UW	0.27 UW
Vanadium	21	19.5	20.8	12.3	10.8	11.9
Zinc	97 E	77.4	48.7 E	17.8 E	23 E	44.5 E
Other parameter						
Cyanide (total)	2.0 U	1.9 U	1.8 U	2.1 U	1.8 U	2.1 U
Soil Concentrations (mg/kg) at Various Depth Intervals						
Parameter	HBOR1 (0-2 ft)	HBOR1 (2-4 ft)	HBOR1 (4-6 ft)	HBOR1 (6-8 ft)	HBOR1 (8-10 ft)	HBOR2 (0-2 ft)
Metals						
Aluminum	11,600	8,470	6,920	4,880	3,530	9,120
Antimony	21.5 @N	5.7 U@N	5.7 U@N	4.5 U@N	5.3 U@N	5.5 U@N
Arsenic	15.7	4.6	2.7	1.8	1.7	8.3
						12
						8,440
						5.5 U@N
						12



TABLE C.15c (Cont.)

Parameter	Soil Concentrations (mg/kg) at Various Depth Intervals									
	HBOR2 (4-6 ft)	HBOR2 (6-8 ft)	HBOR2 (8-10 ft)	FTBOR1 (8-10 ft)	HBOR3 (0-2 ft)	HBOR3 (2-4 ft)	HBOR4 (0-2 ft)			
Metals										
Aluminum	8,220	6,970	2,980	4,780	8,440	7,640	9,210	E		
Antimony	5.5	5.2	6.0	6.0	U@N	5.3	0.20	UNWJ		
Arsenic	5.4	1.8	2.0	1.8	8.1	10.0	3.48			
Barium	41.3	27.5	13.7	20	@	137	55.1	@		
Beryllium	0.52	0.37	0.45	0.54	0.76	0.79	0.30			
Cadmium	0.52	0.49	U	0.56	U	0.94	0.46	U		
Calcium	3,000	1,290	532	488	3,400	2,340	3,540			
Chromium	15	12.8	6.4	8.1	@E	22.2	12.7	@E		
Cobalt	3.5	3.1	1.5	2.3	4.2	4.3	50.4			
Copper	17.2	8.1	3.7	5.1	69.2	90	10.9	U@		
Iron	12,300	9,280	4,880	7,080	14,500	14,000	13,600			
Lead	43	12.4	6.5	5.4	@	419	131	@J		
Magnesium	1,300	1,380	596	917	1,580	1,460	1,310			
Manganese	106	50.1	28.9	57.7	152	142	93.2			
Mercury	0.08	0.1	0.1	0.13	U	0.21	0.07			
Nickel	8.4	8.2	2.8	4.3	9.2	8.7	7.5			
Potassium	629	495	295	468	503	444	392			
Selenium	0.19	0.16	0.19	0.2	U	0.37	0.18	UNJ		
Silver	0.57	0.49	0.57	0.56	U	1.3	0.08	U		
Sodium	68.3	50.9	36.2	42.6	63.7	65.1	48.6			
Thallium	0.24	0.25	0.32	0.33	U	0.26	0.32	U		
Vanadium	16.2	11.4	5.1	8.0	19.0	14.6	17.4			
Zinc	57.5	29.2	15.6	25.3	@	224	49.8			

TABLE C.15c (Cont.)

Soil Concentrations (mg/kg) at Various Depth Intervals								
Parameter	HBOR2 (4-6 ft)	HBOR2 (6-8 ft)	HBOR2 (8-10 ft)	FTBOR1 (8-10 ft)	HBOR3 (0-2 ft)	HBOR3 (2-4 ft)	HBOR4 (0-2 ft)	
Other parameter								
Cyanide (total)	1.4 U@	1.4 U@	1.3 U@	1.5 U@	1.3 U@	1.4 U@	1.15 U	
Soil Concentrations (mg/kg) at Various Depth Intervals								
Parameter	TBNPBOR1 (0-2 ft)	TBNPBOR1 (2-4 ft)	TBNPBOR1 (4-6 ft)	TBNPBOR1 (6-8 ft)	TBNPBOR1 (8-10 ft)			
Metals								
Aluminum	22,600	10,300	5,990	4,280	4,710			
Antimony	19.4 @N	15.2 @N	5.4 U@N	4.9 U@N	5.6 U@N			
Arsenic	1,440	2,290	247	199	16.7			
Barium	649 @	1,140 @	414 @	305 @	104 @			
Beryllium	0.76	0.78	0.59	0.39	0.44			
Cadmium	35.5	12.9	44.1	77.4	2.8			
Calcium	4,890	1,550	440	293	247			
Chromium	240 @E	81.7 @E	18.4 @E	18.2 @E	9.7 @E			
Cobalt	10.8	6.4	2.6	2.9	1.8			
Copper	2,240	7,120	1,120	544	90.7			
Iron	61,900	66,500	26,500	21,200	8,940			
Lead	1,910 @	1,630 @	117 @	90.3 @	48.4 @			
Magnesium	2,890	1,980	759	800	952			
Manganese	633	253	70.3	81.9	40.1			
Mercury	2.2	5.2	0.85	0.34	0.09 U			
Nickel	76.4	51.6	19.1	17.8	7.7			

TABLE C.15c (Cont.)

Parameter	Soil Concentrations (mg/kg) at Various Depth Intervals				
	TBNPBOR I (0-2 ft)	TBNPBOR I (2-4 ft)	TBNPBOR I (4-6 ft)	TBNPBOR I (6-8 ft)	TBNPBOR I (8-10 ft)
Metals (Cont.)					
Potassium	802	1,050	685	478	508
Selenium	0.61	0.17 U	0.31	0.2 U	0.18 U
Silver	24.8	14.8	4.4	2.9	0.53 U
Sodium	254	153	46.2	41.3	32.3
Thallium	7.9	3.4	1.6 U	0.32 U	0.3 U
Vanadium	16.6	6.0	6.9	3.1	5.8
Zinc	9,840 @	6,530 @	4,360 @	3,650 @	1,150 @
Other parameter					
Cyanide (total)	1.4 U@	1.4 U@	1.5 U@	1.4 U@	1.3 U@

<sup>a</sup> Sampled by ANL, analyzed by Weston Gulf Coast or ANL/ACL, TCL TAL metals and other inorganic parameters.

Data qualifiers:

N = spike and spike duplicate recovery of percent RPD were outside the control limits.

@ = percent RPD of sample duplicate was outside the control limits.

U = analyte was analyzed for but not detected; detection limit given.

W = postdigestion spike for furnace AAS analysis was outside the control limits.

E = serial dilution percent difference was outside the QC limit.

TABLE C.15d Inorganic Analysis for Soil Borings, May 1995<sup>a</sup>

Parameter	Soil Concentrations (mg/kg) at Various Depth Intervals				
	TBNPBOR2 (0-2 ft)	TBNPBOR2 (2-6 ft)	TBNPBOR2 (6-8 ft)	TBNPBOR2 (10-12 ft)	
Metals					
Aluminum	12,100	6,420	6,340	2630	
Antimony	72.5 NJ	0.28	0.208 U	0.209 U	
Arsenic	14.4	2.74	2.11	1.5	
Barium	464 @J	22.8	24.8	10.9	
Beryllium	0.272	0.241	0.181	0.135 U	
Cadmium	15.8 @J	0.35 U	0.514	0.385	
Calcium	3,060 E@	595	580	143	
Chromium	106 @J	8.02	9.11	2.43	
Cobalt	10	3.96	4.73	3.07	
Copper	1,030 @J	7.64	7.41	2.83 U	
Iron	29,200 E	11,700	12,700	3760	
Lead	4,790 @J	8.09	8.32	3.71	
Magnesium	2,950	937	1,290	731	
Manganese	232 @J	39.2	43.6	24.5	
Mercury	1.53	0.043 U	0.061 U	0.03	
Nickel	49.2	5.23	8.44	4.51	
Potassium	653	583	454	361	
Selenium	0.792	0.186 U	0.196 U	0.197 U	
Silver	9.84	0.082 U	0.086 U	0.086 U	
Sodium	154	67.2	84.8	20.9 U	
Thallium	19.3	0.326 U	0.343 U	0.345 U	

TABLE C.15d (Cont.)

Soil Concentrations (mg/kg) at Various Depth Intervals					
Parameter	TBNPBOR2 (0-2 ft)	TBNPBOR2 (2-6 ft)	TBNPBOR2 (6-8 ft)	TBNPBOR2 (10-12 ft)	
Metals (Cont.)					
Vanadium	16.3	12	8.69	4.33	
Zinc	2,690	EN@	149	198	
Other Parameters					
Cyanide (total)	1.21	UNJ	1.16	U	1.23 U
pH	7.46		5.66	7.21	
Solids (%)	82.6	85.8	81.7	81.2	

Soil Concentrations (mg/kg) at Various Depth Intervals						
Parameter	TBNPBOR3 (0-2 ft)	TBNPBOR3 (2-4 ft)	TBNPBOR3 (4-6 ft)	TBNPBOR3 (6-8 ft)	TBNPBOR3 (8-10 ft)	TBNPBOR3 (10-12 ft)
Metals						
Aluminum	4,430	4,190 J	5,420	6,710	5,160	2,570
Antimony	20.4	23.7 NJ	3.44 NJ	0.202 U	0.212 U	0.209 UNJ
Arsenic	278	63.5	316 @J	7.63	6.44	10.5 @J
Barium	237	246 @J	1,240	61.8	30.6	38.2
Beryllium	0.132 U	0.149 U	0.204 J	0.169	0.253	0.14 J
Cadmium	5.13	3.55 @J	5.71 N@J	0.583	0.698	0.709 N@J
Calcium	2,080	946 @E	811 E	193	164	168 E

TABLE C.15d (Cont.)

Soil Concentrations (mg/kg) at Various Depth Intervals						
Parameter	TBNPBOR3 (0-2 ft)	TBNPBOR3 (2-4 ft)	TBNPBOR3 (4-6 ft)	TBNPBOR3 (6-8 ft)	TBNPBOR3 (8-10 ft)	TBNPBOR3 (10-12 ft)
Metals (Cont.)						
Chromium	72.1	37.2 @J	23.6 N@J	9.23	8.79	5.24 N@J
Cobalt	12.7	9.48	7.33	3.98	2.99	2.75 J
Copper	814	916 @J	191	15.3	7.98	11.9
Iron	154,000	120,000 E	55,400 @J	9,840	13,100	4,660 @J
Lead	3,230	459 @J	92.7	18.6	6.69	22.7
Magnesium	1,090	720	1,850 E	1,470	1180	636 E
Manganese	470	480 @J	186 EN@	43.3	51	32.3 EN@
Mercury	0.931	0.074 J	0.069 J	0.044	0.062 U	0.053 U
Nickel	84.5	51.9	68.8 N@J	8.03	7.12	6.13 N@J
Potassium	366	711	667 J	781	650	288 J
Selenium	1.64	1.77	0.424 WJ	0.19 U	0.2 U	0.197 U
Silver	4.54	0.147	0.099 U	0.083 U	0.087 U	0.086 U
Sodium	83	125	113 J	40.9	48.6	47.9 J
Thallium	0.335 U	0.378 U	0.395 U	0.333 U	0.35 U	0.344 U
Vanadium	4.29	6.68	8.09	8.23	10.2	3.25 J
Zinc	13,900	13,800 @NE	3,880	283	113	205
Other Parameters						
Cyanide (total)	1.2 U	40.8	11.1	1.19 U	1.25 U	1.23 U
pH	6.81	6.22	6.22	7.05	7.09	6.5
Solids (%)	83.5	74	70.9	84	79.9	81.3

TABLE C.15d (Cont.)

Soil Concentrations (mg/kg) at Various Depth Intervals							
Parameter	VXBOR1 (0-2 ft)	VXBOR1 (4-6 ft)	VXBOR1 (6-8 ft)	VXBOR2 (0-2 ft)	VXBOR2 (2-4 ft)	VXBOR2 (4-6 ft)	VXBOR2 (6-8 ft)
Metals							
Aluminum	NA	NA	NA	NA	NA	NA	NA
Antimony	NA	NA	NA	NA	NA	NA	NA
Arsenic	13 U	10 U	10 U	15	10 U	10 U	10 U
Barium	224	62	30	166	51	39	37
Beryllium	NA	NA	NA	NA	NA	NA	NA
Cadmium	10 U	10 U	10 U	10 U	10 U	10 U	10 U
Calcium	NA	NA	NA	NA	NA	NA	NA
Chromium	37	42	13	41	25	17	13
Cobalt	NA	NA	NA	NA	NA	NA	NA
Copper	170	192	10 U	124	10 U	40	10 U
Iron	NA	NA	NA	NA	NA	NA	NA
Lead	210	49	10 U	161	11	10 U	10 U
Magnesium	NA	NA	NA	NA	NA	NA	NA
Manganese	NA	NA	NA	NA	NA	NA	NA
Mercury	10 U	10 U	10 U	10 U	10 U	10 U	10 U
Nickel	11	11	10 U	23	13	10 U	10 U
Potassium	NA	NA	NA	NA	NA	NA	NA
Selenium	10 U	10 U	10 U	10 U	10 U	10 U	10 U
Silver	10 U	10 U	10 U	10 U	10 U	10 U	10 U
Sodium	NA	NA	NA	NA	NA	NA	NA
Thallium	NA	NA	NA	NA	NA	NA	NA
Vanadium	24	27	29	39	41	26	35
Zinc	432	71	19	361	17	31	32

TABLE C.15d (Cont.)

Soil Concentrations (mg/kg) at Various Depth Intervals							
Parameter	VXBOR1 (0-2 ft)	VXBOR1 (4-6 ft)	VXBOR1 (6-8 ft)	VXBOR2 (0-2 ft)	VXBOR2 (2-4 ft)	VXBOR2 (4-6 ft)	VXBOR2 (6-8 ft)
Other Parameters							
Cyanide (total)	NA	NA	NA	NA	NA	NA	NA
pH	NA	NA	NA	NA	NA	NA	NA
Solids (%)	NA	NA	NA	NA	NA	NA	NA
Soil Concentrations (mg/kg) at Various Depth Intervals							
Parameter	VXBOR2 (8-10 ft)	VXBOR2 (10-12 ft)	VXBOR2-Dup (10-12 ft)				
Metals							
Aluminum	NA	NA	NA				
Antimony	NA	NA	NA				
Arsenic	10 U	10 U	10 U				
Barium	38	45	42				
Beryllium	NA	NA	NA				
Cadmium	10 U	10 U	10 U				
Calcium	NA	NA	NA				
Chromium	10 U	17	13				
Cobalt	NA	NA	NA				
Copper	10 U	10 U	10 U				
Iron	NA	NA	NA				
Lead	10 U	10 U	10 U				
Magnesium	NA	NA	NA				
Manganese	NA	NA	NA				

TABLE C.15d (Cont.)

Soil Concentrations (mg/kg) at Various Depth Intervals						
Parameter	VXBOR2 (8-10 ft)	VXBOR2 (10-12 ft)	VXBOR2-Dup (10-12 ft)			
Metals (Cont.)						
Mercury	10 U	10 U	10 U	U		
Nickel	10 U	10 U	10 U	U		
Potassium	NA	NA	NA			
Selenium	10 U	10 U	10 U	U		
Silver	10 U	10 U	10 U	U		
Sodium	NA	NA	NA			
Thallium	NA	NA	NA			
Vanadium	21	25	19			
Zinc	42	63	55			
Other Parameters						
Cyanide (total)	NA	NA	NA			
pH	NA	NA	NA			
Solids (%)	NA	NA	NA			
Soil Concentrations (mg/kg) at Various Depth Intervals						
Parameter	VXBOR4 (2-4 ft)	VXBOR4 (4-6 ft)	VXBOR5 (0-2 ft)	VXBOR5 (4-6 ft)	VXBOR5 (6-8 ft)	VXBOR5 (8-10 ft)
Metals						
Aluminum	22,200 E	3,360	6,890	6,950	1,810	4,420
Antimony	112 NJ	0.691	0.206 UNJ	0.485	0.209 U	0.211 UNJ
Arsenic	18.9	0.905	6.09	4.54	0.568	1.94

TABLE C.15d (Cont.)

Parameter	Soil Concentrations (mg/kg) at Various Depth Intervals					
	VXBOR4 (2-4 ft)	VXBOR4 (4-6 ft)	VXBOR5 (0-2 ft)	VXBOR5 (4-6 ft)	VXBOR5 (6-8 ft)	VXBOR5 (8-10 ft)
Metals (Cont.)						
Barium	2.93 U	17	235 @J	1,410	7.75	17.6 @J
Beryllium	0.14 U	0.135 U	0.195	0.143 U	0.135 U	0.217
Cadmium	2.65	0.49 U	1.72 @J	3.33	0.368 U	0.372 U@J
Calcium	14,800	377	648 E@	1,680	175	373 E@
Chromium	37.9	6.28	15.3 @J	43.3	1.76	9.22 @J
Cobalt	3.99	2.17	5.2	5.32	3.01	3.86
Copper	1,110	33.7	51.4 @J	218	2.82 U	3.78 @J
Iron	16,900 E	4,930	9,600 E	13,800	3,040	10,200 E
Lead	1,690 @J	13.7	27.5 @J	26.3	2.17	2.77 @J
Magnesium	2,460	838	2,480	11,100	504	925
Manganese	223	36.1	61.4 @J	146	21.5	37.6 @J
Mercury	0.426	0.021 U	0.34	0.263	0.052 U	0.054 U
Nickel	55.2	3.89	6.13	16	3.23	4.3
Potassium	611	332	385	372	152	476
Selenium	0.34 NJ	0.196 U	0.29	0.208 U	0.196 U	0.198 U
Silver	2.51	1.02	0.085 UWJ	0.11	0.086 U	0.087 U
Sodium	102	20.8 U	41.6	55	28	42.7
Thallium	0.356 U	0.343 U	0.338 U	0.364 U	0.344 U	0.347 U
Vanadium	28.8	5.02	9.74	8.83	3.56 U	7.61
Zinc	2,320	37.8	223 EN@	342	11.9	17.3 EN@

TABLE C.15d (Cont.)

Parameter	Soil Concentrations (mg/kg) at Various Depth Intervals					
	VXBOR4 (2-4 ft)	VXBOR4 (4-6 ft)	VXBOR5 (0-2 ft)	VXBOR5 (4-6 ft)	VXBOR5 (6-8 ft)	VXBOR5 (8-10 ft)
Other Parameters						
Cyanide (total)	2.63	1.22 U	1.21 UNJ	1.3 U	1.23 U	1.24 UNJ
pH	7.35	7.54	7.39	8.99	7.74	7.62
Solids (%)	78.6	81.7	82.7	76.8	81.4	80.6
Soil Concentrations (mg/kg) at 0-6 in.						
Parameter	SQPS 1	SQPS 2	SQPS 3	SQPS 4	SQPS 5	SQPS 6
Metals						
Aluminum	4,240	8,600	13,300	13,000	7,890	11,000
Antimony	0.212 U	0.559	1.04	0.598	0.94	0.445
Arsenic	0.224 U	2.96	4.96	3.59	2.71	3.02
Barium	94.9	183	323	148	124	166
Beryllium	1.38	0.419	0.539	0.411	0.298	0.517
Cadmium	1.8	1.43	1.99	2.06	1.23	1.41
Calcium	6,320	1,210	974	1,250	385	847
Chromium	34.4	67.4	85	70.5	92	38.9
Cobalt	11.1	4.45	4.78	4.86	2.19	4.9
Copper	98.3	216	267	215	355	120
Iron	11,200	13,600	21,400	17,000	12,300	12,300
Lead	229	65.8	91.6	95.1	69.8	70.4
Magnesium	2,740	1,540	1,710	1,700	912	1,480
Manganese	81.6	170	262	158	99.9	234

TABLE C.15d (Cont.)

Soil Concentrations (mg/kg) at 0-6 in.						
Parameter	SQPS 1	SQPS 2	SQPS 3	SQPS 4	SQPS 5	SQPS 6
Metals (Cont.)						
Mercury	0.086	0.123	0.163	0.166	0.244	0.104
Nickel	3.96	8.77	13.4	8.3	6.05	8.87
Potassium	1,100	396	360	393	298	432
Selenium	0.2 U	0.73	0.438	0.227 U	0.263	0.46
Silver	2.18	3.97	3.15	3.32	4.17	1.92
Sodium	47	71.8	73.5	84	60.1	59.5
Thallium	0.349 U	0.339 U	0.347 U	0.397 U	0.347 U	0.344 U
Vanadium	4.98	14	18.5	22.1	14	18.1
Zinc	78.6	233	603	542	148	353
Other Parameters						
Cyanide (total)	1.25 U	NA	NA	NA	NA	NA
pH	5.39	NA	NA	NA	5.12	NA
Solids (%)	80.2	82.6	80.6	70.6	81.6	81.5

Soil Concentrations (mg/kg) at 0-6 in.			
Parameter	SQPS 7	SQPS 8	SQPS 9
Metals			
Aluminum	9,620	6,610	13100
Antimony	0.239	2.72	2.7
Arsenic	3.77	21.2	60.5
Barium	142	261	286

TABLE C.15d (Cont.)

Parameter	Soil Concentrations (mg/kg) at 0-6 in.		
	SQPS 7	SQPS-8	SQPS 9
Metals (Cont.)			
Beryllium	0.527	0.298	0.309
Cadmium	1.75	20.7	19.2
Calcium	1,330	4,610	1,360
Chromium	25.6	42.2	42.8
Cobalt	4.69	3.82	4.12
Copper	65.2	561	758
Iron	14,700	31,800	32,700
Lead	63.5	165	289
Magnesium	1,140	1,580	2,120
Manganese	270	254	372
Mercury	0.09	0.242	0.25
Nickel	7.8	14	18.1
Potassium	361	547	316
Selenium	0.474	0.714	0.484
Silver	1.84	5.56	15.1
Sodium	77.1	80.8	53
Thallium	0.364	U	0.386
Vanadium	15.9	12.3	10.8
Zinc	420	7,970	5,340
Other Parameters			
Cyanide (total)	NA	2.1	U
pH	NA	4.69	NA
Solids (%)	76.9	45.0	72.5

TABLE C.15d (Cont.)

Parameter	Soil Concentrations (mg/kg) at 0-6 in.					
	TPDGS 1	TPDGS 2	TPDGS 3	TPDGS 4	TPDGS 5	TPDGS 6
<b>Metals</b>						
Aluminum	8,650	11,600	8,490	13,900	11,400	15,700
Antimony	0.921	0.512	0.212	U	0.207	U
Arsenic	3.36	4.02	3.17	3.63	3.34	4.18
Barium	82.3	120	71.4	90.9	75.9	77.4
Beryllium	0.524	0.539	0.61	0.546	0.51	0.494
Cadmium	1.1	0.918	0.682	0.926	0.898	1.07
Calcium	25,300	22,200	4,300	2,410	36,000	2,590
Chromium	12	17.5	9.11	13.5	13.4	15.1
Cobalt	3.2	3.54	3.78	4.35	5.05	6.05
Copper	32.9	128	11.7	18	15	10.7
Iron	11,600	9,130	10,400	20,800	17,300	21,100
Lead	57.1	53.3	25.2	23.5	11.7	17.6
Magnesium	1,080	1150	944	1,220	1,880	1,600
Manganese	253	202	222	201	189	209
Mercury	0.06	0.055	0.06	0.052	0.06	U
Nickel	7.2	16.2	6.46	8.38	7	9.53
Potassium	367	307	300	394	459	569
Selenium	0.244	0.185	0.292	0.293	0.206	0.341
Silver	0.085	0.081	0.118	0.088	U	U
Sodium	151	169	101	101	204	72.8
Thallium	0.34	0.324	0.35	0.35	U	U
Vanadium	13.9	12.2	11.8	18.5	19.4	21.9
Zinc	94.4	79.3	45.5	68	44.4	49.8

TABLE C.15d (Cont.)

Parameter	Soil Concentrations (mg/kg) at 0-6 in.					
	TPDGS 1	TPDGS 2	TPDGS 3	TPDGS 4	TPDGS 5	TPDGS 6
Cyanide (total)	1.21	U	1.16	U	NA	NA
pH	NA	NA	NA	NA	NA	NA
Solids (%)	82.4	86.3	80	79.9	82	81.4

<sup>a</sup> Sampled by ANL and analyzed by GP Environmental Services.

Data qualifiers:

N = spike and spike duplicate recovery of percent RPD were outside the control limits.

J = estimated value.

@ = percent RPD of sample duplicate was outside the control limits.

E = serial dilution percent difference was outside the QC limit.

U = analyte was analyzed for but not detected; detection limit given.

NA = not analyzed.

TABLE C.16a Pesticide and PCB Analyses for Soil Borings, January 1993<sup>a</sup>

Compound	Borehole Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals									
	JBP1-E-2'	JBP1-E-2'Dup	JBP1-E-4'	JBP1-W-2'	JBP1-W-4'	JBP2-E-2'	JBP2-E-4'	JBP2-E-4'Dup		
Aldrin	819	U	80	U	2	U	2	U	2	U
alpha-BHC	617	U	60	U	1	U	1	U	1	U
Aroclor 1016	10,200	U	996	U	20	U	20	U	20	U
Aroclor 1221	10,200	U	996	U	20	U	20	U	20	U
Aroclor 1232	10,200	U	996	U	20	U	20	U	20	U
Aroclor 1242	13,300	U	1,300	U	27	U	26	U	26	U
Aroclor 1248	143,000		14,900		41	U	40	U	40	U
Aroclor 1254	20,500	U	1,990	U	41	U	224		40	U
Aroclor 1260	20,500	U	1,990	U	41	U	40	U	40	U
beta-BHC	1,230	U	119	U	2	U	2	U	2	U
Chlordane	2,870	U	279	U	6	U	6	U	6	U
4,4'-DDD	2,260	U	219	U	5	U	4	U	4	U
4,4'-DDE	819	U	80	U	2	U	2	U	2	U
4,4'-DDT	2,460	U	239	U	5	U	5	U	5	U
delta-BHC	1,840	U	179	U	4	U	4	U	4	U
Dieldrin	409	U	40	U	0.8	U	0.8	U	0.8	U
Endosulfan I	2,870	U	279	U	6	U	6	U	6	U
Endosulfan II	819	U	80	U	2	U	2	U	2	U
Endosulfan sulfate	13,500	U	1,320	U	27	U	26	U	27	U
Endrin	1,230	U	119	U	2	U	2	U	2	U
Endrin aldehyde	4,710	U	458	U	9	U	9	U	9	U
gamma-BHC (Lindane)	819	U	80	U	2	U	2	U	2	U
Heptachlor	617	U	60	U	1	U	1	U	1	U
Heptachlor epoxide	17,000	U	1,660	U	34	U	33	U	33	U
Methoxychlor	36,000	U	3,510	U	72	U	70	U	71	U
Toxaphene	49,100	U	4,780	U	98	U	96	U	97	U

TABLE C.16a (Cont.)

Compound	Borehole Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals									
	JBP2-C-2'	JBP2-C-4'	JBP2-W-2'	JBP2-W-4'	JHDP-C-4'	JHDP-C-6'	JHDP-C-6'Dup	JVXP-C-4'		
Aldrin	2 U	2 U	2 U	2 U	2 U	2 U	2 U	2 U	2	U
alpha-BHC	1 U	1 U	1 U	1 U	1 U	1 U	1 U	1 U	1	U
Aroclor 1016	23 U	20 U	20 U	20 U	20 U	20 U	19 U	22 U	22	U
Aroclor 1221	23 U	20 U	20 U	20 U	20 U	20 U	19 U	22 U	22	U
Aroclor 1232	23 U	20 U	20 U	20 U	20 U	20 U	19 U	22 U	22	U
Aroclor 1242	30 U	26 U	26 U	26 U	26 U	27 U	24 U	29 U	29	U
Aroclor 1248	46 U	40 U	40 U	40 U	40 U	77	178	44 U	44	U
Aroclor 1254	46 U	40 U	40 U	40 U	40 U	41 U	38	44 U	44	U
Aroclor 1260	46 U	40 U	40 U	40 U	40 U	41 U	38	44 U	44	U
beta-BHC	3 U	2 U	2 U	2 U	2 U	2 U	2 U	3 U	3	U
Chlordane	6 U	6 U	6 U	6 U	6 U	6 U	5 U	6 U	6	U
4,4'-DDD	5 U	4 U	4 U	4 U	4 U	7	4 U	5 U	5	U
4,4'-DDE	2 U	2 U	2 U	2 U	2 U	3	3	2 U	2	U
4,4'-DDT	6 U	5 U	5 U	5 U	8	179	6	5 U	5	U
delta-BHC	4 U	4 U	4 U	4 U	4 U	4 U	3	4 U	4	U
Dieldrin	0.9 U	0.8 U	0.8 U	0.8 U	0.8 U	0.8 U	0.8 U	0.9 U	0.9	U
Endosulfan I	6 U	6 U	6 U	6 U	6 U	6 U	5 U	6 U	6	U
Endosulfan II	2 U	2 U	2 U	2 U	2 U	2 U	2 U	2 U	2	U
Endosulfan sulfate	31 U	26 U	27 U	26 U	27 U	27 U	25 U	29 U	29	U
Endrin	3 U	2 U	2 U	2 U	2 U	2 U	2 U	3 U	3	U
Endrin aldehyde	11 U	9 U	9 U	9 U	9 U	9 U	9 U	10 U	10	U
gamma-BHC (Lindane)	2 U	2 U	2 U	2 U	2 U	2 U	2 U	2 U	2	U
Heptachlor	1 U	1 U	1 U	1 U	1 U	1 U	1 U	1 U	1	U
Heptachlor epoxide	38 U	33 U	33 U	33 U	33 U	34 U	31 U	37 U	37	U
Methoxychlor	81 U	70 U	71 U	70 U	71 U	72 U	66 U	78 U	78	U
Toxaphene	110 U	96 U	97 U	96 U	97 U	98 U	90 U	106 U	106	U

TABLE C.16a (Cont.)

Compound	Borehole Concentrations (µg/kg) at Various Depth Intervals									
	JVXP-C-6'	JSDP-C-4'	JSDP-C-6'	JBPM-A-3"	JBPM-A-3"Dup	JBPM-A-1'	JBPM-B-3"	JBPM-B-1'		
Aldrin	2 U	2 U	2 U	2 U	2 U	2 U	2 U	2 U		
alpha-BHC	1 U	1 U	1 U	1 U	1 U	1 U	1 U	1 U		
Aroclor 1016	24 U	22 U	22 U	20 U	20 U	20 U	19 U	20 U		
Aroclor 1221	24 U	22 U	22 U	20 U	20 U	20 U	19 U	20 U		
Aroclor 1232	24 U	22 U	22 U	20 U	20 U	20 U	19 U	20 U		
Aroclor 1242	31 U	29 U	29 U	26 U	26 U	26 U	25 U	26 U		
Aroclor 1248	47 U	45 U	44 U	40 U	40 U	40 U	38 U	39 U		
Aroclor 1254	47 U	45 U	44 U	1,700	1,230	3,160	38 U	39 U		
Aroclor 1260	47 U	45 U	44 U	40 U	40 U	40 U	38 U	39 U		
beta-BHC	3 U	3 U	3 U	2 U	2 U	2 U	2 U	2 U		
Chlordane	7 U	6 U	6 U	6 U	6 U	6 U	5 U	5 U		
4,4'-DDD	5 U	5 U	5 U	4 U	4 U	4 U	4 U	4 U		
4,4'-DDE	2 U	2 U	2 U	2 U	2 U	56	6	2 U		
4,4'-DDT	6 U	5 U	5 U	5 U	5 U	144	7	5 U		
delta-BHC	4 U	4 U	4 U	4 U	4 U	4 U	4	4 U		
Dieldrin	0.9 U	0.9 U	0.9 U	0.8 U	0.8 U	0.8 U	0.8 U	0.8 U		
Endosulfan I	7 U	6 U	6 U	6 U	6 U	6 U	5 U	5 U		
Endosulfan II	2 U	2 U	2 U	2 U	2 U	2 U	2 U	2 U		
Endosulfan sulfate	31 U	30 U	29 U	26 U	26 U	26 U	25 U	26 U		
Endrin	3 U	3 U	3 U	2 U	2 U	2 U	2 U	2 U		
Endrin aldehyde	11 U	10 U	10 U	9 U	9 U	9 U	9 U	9 U		
gamma-BHC (Lindane)	2 U	2 U	2 U	2 U	2 U	2 U	2 U	2 U		
Heptachlor	1 U	1 U	1 U	1 U	1 U	1 U	1 U	1 U		
Heptachlor epoxide	39 U	37 U	36 U	33 U	33 U	33 U	32 U	32 U		
Methoxychlor	83 U	79 U	77 U	70 U	70 U	70 U	67 U	69 U		
Toxaphene	113 U	107 U	105 U	96 U	96 U	96 U	92 U	94 U		

TABLE C.16a (Cont.)

Compound	Borehole Concentrations (µg/kg) at Various Depth Intervals							
	JBPM-C-3"	JBPM-C-1'	JBPP-A-3"	JBPP-A-1'	JBPP-B-3"	JBPP-B-1'	JBPP-C-3"	JBPP-C-1'
Aldrin	2 U	2 U	2 U	2 U	19 U	2 U	2 U	2 U
alpha-BHC	1 U	1 U	1 U	1 U	14 U	1 U	1 U	1 U
Aroclor 1016	21 U	19 U	20 U	20 U	231 U	20 U	20 U	20 U
Aroclor 1221	21 U	19 U	20 U	20 U	231 U	20 U	20 U	20 U
Aroclor 1232	21 U	19 U	20 U	20 U	231 U	20 U	20 U	20 U
Aroclor 1242	28 U	25 U	26 U	26 U	300 U	26 U	26 U	26 U
Aroclor 1248	43 U	39 U	39 U	40 U	3,820	40 U	40 U	40 U
Aroclor 1254	43 U	39 U	39 U	40 U	462 U	40 U	40 U	40 U
Aroclor 1260	43 U	39 U	39 U	40 U	462 U	40 U	40 U	40 U
beta-BHC	3 U	2 U	2 U	2 U	28 U	2 U	2 U	2 U
Chlordane	6 U	5 U	5 U	6 U	65 U	6 U	6 U	6 U
4,4'-DDD	5 U	4 U	4 U	4 U	51 U	4 U	4 U	4 U
4,4'-DDE	12	2 U	2 U	2 U	19 U	42	2 U	2 U
4,4'-DDT	5 U	5 U	5 U	5 U	56 U	5 U	5 U	5 U
delta-BHC	28	3 U	4 U	4 U	42 U	4 U	4 U	4 U
Dieldrin	0.9 U	0.8 U	0.8 U	0.8 U	9 U	0.8 U	0.8 U	0.8 U
Endosulfan I	6 U	5 U	5 U	6 U	65 U	6 U	6 U	6 U
Endosulfan II	2 U	2 U	2 U	2 U	19 U	2 U	2 U	2 U
Endosulfan sulfate	28 U	25 U	26 U	26 U	305 U	26 U	26 U	26 U
Endrin	3 U	2 U	2 U	2 U	28 U	3	2 U	2 U
Endrin aldehyde	10 U	9 U	9 U	9 U	106 U	9 U	9 U	9 U
gamma-BHC (Lindane)	2 U	2 U	2 U	2 U	19 U	2 U	2 U	2 U
Heptachlor	1 U	1 U	1 U	1 U	14 U	20	4	1 U
Heptachlor epoxide	35 U	32 U	33 U	33 U	383 U	33 U	33 U	33 U
Methoxychlor	75 U	68 U	69 U	70 U	813 U	70 U	70 U	70 U
Toxaphene	102 U	93 U	94 U	96 U	1,110 U	95 U	96 U	96 U

See next page for footnotes.

TABLE C.16a (Cont.)

---

<sup>a</sup> Sampled by Weston, analyzed by GP Environmental Services, TCL pesticides and PCBs-SW846 8080; provisional data.

Data qualifier:

U = analyte was analyzed for but not detected.

TABLE C.16b Pesticide and PCB Analyses for Soil Borings, May 1995<sup>a</sup>

Compound	Borehole Concentrations (µg/kg) at Various Depth Intervals											
	TBNPBOR2 (0-2ft)		TBNPBOR2 (2-6 ft)		TBNPBOR3 (0-2 ft)		TBNPBOR3 (2-4 ft)		TBNPBOR3 (4-6 ft)		VXBOR3 (2-4 ft)	
Aldrin	2.06	U	1.99	U	2.04	U	2.3	U	2.4	U	40.6	U
alpha-BHC	2.06	UJ(+)	1.99	U	2.04	U	2.3	U	2.4	UJ	40.6	U
alpha-Chlordane	2.06	UJ(+)	1.99	U	2.04	U	2.3	U	2.4	UJ	40.6	U
Aroclor 1016	39.9	UJ(+)	38.6	U	39.5	U	44.6	U	46.5	UJ	789	U
Aroclor 1221	81.1	UJ(+)	78.4	U	80.3	U	90.5	U	94.5	UJ	1,600	U
Aroclor 1232	39.9	UJ(+)	38.6	U	39.5	U	44.6	U	46.5	UJ	789	U
Aroclor 1242	39.9	UJ(+)	38.6	U	39.5	U	44.6	U	46.5	UJ	789	U
Aroclor 1248	570	J(+)	38.6	U	39.5	U	44.6	U	46.5	UJ	789	U
Aroclor 1254	39.9	UJ(+)	38.6	U	39.5	U	44.6	U	46.5	UJ	789	U
Aroclor 1260	39.9	UJ(+)	38.6	U	39.5	U	44.6	U	46.5	UJ	789	U
beta-BHC	2.06	UJ(+)	1.99	U	2.04	U	2.3	U	2.4	UJ	40.6	U
4,4'-DDD	3.99	UJ(+)	3.86	U	3.95	U	4.46	U	4.65	UJ	78.8	JB
4,4'-DDE	3.99	UJ(+)	3.86	U	1.9	JP	4.46	U	4.65	UJ	18.2	JB
4,4'-DDT	3.99	UJ(+)	3.86	U	3.95	U	4.46	U	4.65	UJ	78.9	U
delta-BHC	2.06	UJ(+)	1.99	U	2.04	U	2.3	U	2.4	UJ	40.6	U
Dieldrin	3.99	UJ(+)	3.86	U	3.95	U	4.46	U	4.65	UJ	78.9	U
Endosulfan I	2.06	UJ(+)	1.99	U	2.04	U	2.3	U	2.4	UJ	40.6	U
Endosulfan II	3.99	UJ(+)	3.86	U	3.95	U	4.46	U	4.65	UJ	78.9	U
Endosulfan sulfate	3.99	UJ(+)	3.86	U	3.95	U	19	P	4.65	UJ	78.9	U
Endrin	3.99	UJ(+)	3.86	U	3.95	U	4.46	U	4.65	UJ	78.9	U
Endrin aldehyde	3.99	UJ(+)	3.86	U	3.95	U	4.46	U	4.65	UJ	78.9	U
Endrin ketone	3.99	UJ(+)	3.86	U	3.95	U	4.9	P	4.65	UJ	78.9	U
gamma-Chlordane	2.06	UJ(+)	1.99	U	2.04	U	2.3	U	2.4	UJ	40.6	U
Heptachlor	2.06	UJ(+)	1.99	U	2.04	U	2.3	U	2.4	UJ	40.6	U
Heptachlor epoxide	2.06	UJ(+)	1.99	U	2.04	U	12.2		2.4	UJ	40.6	U
Lindane (gamma-BHC)	2.06	UJ(+)	1.99	U	2.04	U	2.3	U	2.4	UJ	40.6	U
Methoxychlor	20.6	UJ(+)	19.9	U	20.4	U	23	U	24	UJ	406	U
Toxaphene	206	UJ(+)	199	U	204	U	230	U	240	UJ	4,060	U

TABLE C.16b (Cont.)

Compound	Borehole Concentrations ( $\mu\text{g/kg}$ ) at Various Depth Intervals							
	VXBOR4 (2-4 ft)		VXBOR4 (4-6 ft)		VXBOR5 (4-6 ft)		VXBOR5 (8-10 ft)	
Aldrin	43.2	U	20.8	U	2.21	U	2.11	U
alpha-BHC	43.2	U	20.8	U	1.3	JP	2.11	U
alpha-Chlordane	43.2	U	20.8	U	2.21	U	2.11	U
Aroclor 1016	838	U	404	U	43	U	40.9	U
Aroclor 1221	1700	U	820	U	87.2	U	83.1	U
Aroclor 1232	838	U	404	U	43	U	40.9	U
Aroclor 1242	838	U	404	U	43	U	40.9	U
Aroclor 1248	838	U	404	U	43	U	40.9	U
Aroclor 1254	838	U	404	U	43	U	40.9	U
Aroclor 1260	838	U	404	U	43	U	40.9	U
beta-BHC	43.2	U	20.8	U	2.21	U	2.11	U
4,4'-DDD	83.8	U	40.4	U	4.6		1.5	JB
4,4'-DDE	83.8	U	40.4	U	4.3	U	0.97	JB
4,4'-DDT	83.8	U	40.4	U	4.3	U	4.09	U
delta-BHC	43.2	U	20.8	U	2.21	U	2.11	U
Dieldrin	83.8	U	40.4	U	4.3	U	4.09	U
Endosulfan I	43.2	U	20.8	U	2.21	U	2.11	U
Endosulfan II	83.8	U	40.4	U	4.3	U	4.09	U
Endosulfan sulfate	83.8	U	40.4	U	4.3	U	4.09	U
Endrin	83.8	U	40.4	U	4.3	U	4.09	U
Endrin aldehyde	83.8	U	40.4	U	4.3	U	4.09	U
Endrin ketone	83.8	U	40.4	U	2.9	JP	4.09	U
gamma-Chlordane	43.2	U	20.8	U	2.21	U	2.11	U
Heptachlor	43.2	U	20.8	U	2.21	U	2.11	U
Heptachlor epoxide	43.2	U	20.8	U	2.21	U	2.11	U
Lindane (gamma-BHC)	43.2	U	20.8	U	2.21	U	2.11	U
Methoxychlor	432	U	208	U	22.1	U	21.1	U
Toxaphene	4,320	U	2,080	U	221	U	211	U

<sup>a</sup> Sampled by ANL and analyzed by GP Environmental Services.

Data qualifiers:

U = analyte was analyzed for but not detected.

J = estimated value.

(+) = value obtained from a 1:10 dilution.

B = compound was found in the associated blank.

P = percent difference between the results from two GTC columns is greater than 25%, and the lower of the two values is reported.

TABLE C.17 On-Site Analytical Suite Results for Soil Borings, December 1993–May 1994<sup>a</sup>

Sample No. (Depth Interval)	Collection Date	Average Depth (ft)	Borehole Concentrations (mg/kg)			
			PAH	TPH	PCB	TNT
Sediment						
BOR1-1 (6-8 ft)	04/18/94	7	1 U	10 U	1 U	0.7 U
BOR2-1 (3-5 ft)	04/19/94	4	1 U	100 U10	1 U	0.7 U
BOR3-1 (6-8 ft)	04/19/94	7	1 U	100 G	1 U	0.7 G
BOR4-1 (5-8 ft)	04/19/94	7	1 U	100 U10	1 U	0.7 U
BOR5-1 (2-4 ft)	04/20/94	3	1 U	100 U10	1 U	0.7 U
BOR6-1 (2-4 ft)	04/20/94	3	1 U		1 U	0.7 G
BOR7-1 (2-4 ft)	04/20/94	3		100 U10	1 U	0.7 U
BOR8-1 (0-2 ft)	04/21/94	1	1 U	10 U	1 U	0.7 U
Soil						
TBSPBOR1 (0-2 ft)	05/23/94	1	10 U1	100 U10	10 U1	0.7 U
TBSPBOR1 (2-4 ft)	05/23/94	3	1 U	100 U10	1 U	0.7 U
TBSPBOR1 (4-6 ft)	05/23/94	5	10 U1	100 U10	1 U	0.7 U
TBSPBOR1 (6-8 ft)	05/23/94	7	1 U	10 U	1 U	0.7 U
TBSPBOR1 (8-10 ft)	05/23/94	9	1 U	100 U10	1 U	0.7 U
TBSPBOR1 (10-12 ft)	05/23/94	11	1 U	100 U10	1 U	0.7 U
TBSPBOR2 (0-2 ft)	05/23/94	1	1 U	100 U10	10 G	0.7 U
TBSPBOR2 (2-4 ft)	05/23/94	3	1 U	100 U10	10 U1	0.7 U
TBSPBOR2 (4-6 ft)	05/23/94	5	1 U	10 U	1 U	0.7 U
TBSPBOR2 (6-8 ft)	05/23/94	7	1 U	100 G	1 U	0.7 U
TBSPBOR2 (8-10 ft)	05/23/94	9	1 U	100 G	1 U	0.7 U
TBNPBOR1 (0-2 ft)	05/24/94	1	1 U	100 U10	10 U1	NA
TBNPBOR1 (2-4 ft)	05/24/94	3	1 U	100 G	10 U1	NA
TBNPBOR1 (4-6 ft)	05/24/94	5	1 U	100 U10	10 U1	NA
TBNPBOR1 (6-8 ft)	05/24/94	7	1 U	10 U	NA	NA
HBOR1 (0-2 ft)	05/24/94	1	1 U	100 U10	10 U1	NA
HBOR1 (2-4 ft)	05/24/94	3	1 U	10 U	1 U	NA
HBOR1 (4-6 ft)	05/24/94	5	1 U	10 U	10 U1	NA
HBOR1 (6-8 ft)	05/24/94	7	1 U	10 U	NA	NA
HBOR1 (8-10 ft)	05/24/94	9	NA	100 U10	NA	NA
HBOR2 (0-2 ft)	05/25/94	1	1 U	10 U	1 U	NA
HBOR2 (4-6 ft)	05/25/94	3	1 U	10 U	1 U	NA
VXBOR1 (0-2 ft)	05/16/94	1	1 U	100 G	1 U	0.7 U
VXBOR1 (4-6 ft)	05/16/94	5	10 G	100 G	1 U	0.7 U
VXBOR1 (6-8 ft)	05/16/94	7	10 G	100 G	1 U	0.7 U
VXBOR1 (8-10 ft)	05/16/94	9	10 G	100 G	1 U	0.7 U
VXBOR2 (0-2 ft)	05/16/94	1	1 U	100 G	1 U	0.7 U
VXBOR2 (2-4 ft)	05/16/94	3	1 U	100 G	1 U	0.7 U
VXBOR2 (4-6 ft)	05/16/94	5	1 U	100 G	1 U	0.7 U
VXBOR2 (6-8 ft)	05/16/94	7	1 U	100 G	1 U	0.7 U

TABLE C.17 (Cont.)

Sample No. (Depth Interval)	Collection Date	Average Depth (ft)	Borehole Concentrations (mg/kg)			
			PAH	TPH	PCB	TNT
Soil (Cont.)						
VXBOR2 (8-10 ft)	05/16/94	9	1 U	100 U10	1 U	0.7 U
VXBOR2 (10-12 ft)	05/16/94	11	1 U	100 G	1 U	0.7 U
CLP1 (0-6 in.)	01/24/94	0.25	1 U	10 U	10 U1	0.7 U
CLP1 (6-24 in.)	01/24/94	1.25	1 U	10 U	1 U	0.96
CLP2 (0-6 in.)	01/24/94	0.25	1 U	10 U	1 U	0.7 U
CLP2 (6-24 in.)	01/24/94	1.25	1 U	10 U	1 U	0.7 U
CLP2 (24-48 in.)	01/24/94	3	10 U1	100 U10	1 U	0.7 U
CLP3 (0-6 in.)	01/25/94	0.25	10 U1	100 U10	10 U1	0.7 U
CLP3 (6-24 in.)	01/25/94	1.25	10 U1	10 U	1 U	0.7 U
CLP3 (6-24 in.) Dup	01/25/94	1.25	1 U	10 U	1 U	0.7 U
CLP3 (24-48 in.)	01/25/94	3	1 U	10 U	1 U	0.7 U
CLP4 (0-6 in.)	01/25/94	0.25	1 U	10 U	1 U	0.7 U
CLP4 (6-24 in.)	01/25/94	1.25	1 U	100 U10	1 U	0.7 U
CLP4 (24-48 in.)	01/25/94	3	1 U	100 U10	1 U	0.7 U
CLP5 (0-6 in.)	01/25/94	0.25	1 U	10 U	1 U	0.7 U
CLP5 (6-24 in.)	01/25/94	1.25	1 U	100 U10	1 U	1.95
CLP5 (24-48 in.)	01/25/94	3	1 U	100 G	1 U	1.67
CLP5 (24-48 in.) Dup	01/25/94	3	1 U	100 G	1 U	0.99
CLP6 (0-6 in.)	01/25/94	0.25	1 U	10 U	1 U	0.7 U
CLP6 (6-24 in.)	01/25/94	1.25	10 U1	100 U10	1 U	0.7 U
CLP7 (0-6 in.)	01/25/94	0.25	1 U	10 U	1 U	0.7 U
CLP7 (6-24 in.)	01/25/94	1.25	1 U	10 U	1 U	0.7 U
CLP7 (24-48 in.)	01/25/94	3	1 U	10 U	1 U	0.7 U
CLP8 (0-6 in.)	01/26/94	0.25	1 U	10 U	1 U	0.7 U
CLP9 (0-6 in.)	01/26/94	0.25	1 U	10 U	1 U	0.7 U
OT4A (0-6 in.)	11/09/93	0.25	10 U	10 U	1 U	0.7 U
OT6A (0-6 in.)	11/09/93	0.25	10 U	10 U	1 U	0.7 U
OT8A (0-6 in.)	10/13/93	0.25	NA	NA	NA	0.7 U
OT9A (0-6 in.)	10/13/93	0.25	NA	NA	NA	0.7 U
OT15B (6-12 in.)	11/08/93	0.75	100 U10	100 U10	1 U	NA
OT16B (6-12 in.)	11/08/93	0.75	10 U	10 U	1 U	NA
OT18A (0-6 in.)	11/08/93	0.25	NA	NA	1 U	NA
OT18B (6-12 in.)	11/08/93	0.75	1 U	10 U	NA	NA
OT19A (0-6 in.)	11/08/93	0.25	NA	NA	1 U	NA
OT19B (6-12 in.)	11/08/93	0.75	1 U	NA	NA	NA
OT29A (0-6 in.)	10/27/93	0.25	1 U	100 U10	10 U1	NA
OT29B (6-12 in.)	10/27/93	0.75	NA	10 U	1 U	NA
OT30A (0-6 in.)	10/27/93	0.25	NA	NA	10 U1	NA
OT31A (0-6 in.)	10/13/93	0.25	NA	NA	1 U	NA
OT32A (0-6 in.)	10/13/93	0.25	NA	NA	1 U	NA

See next page for footnotes.

**TABLE C.17 (Cont.)**

---

<sup>a</sup> Sampled and analyzed on-site by ANL.

Data qualifiers:

U = < value given.

10 U1 = <10 mg/kg but >1 mg/kg.

100 U10 = <100 mg/kg but >10 mg/kg.

G = > value given.

NA = not analyzed.

**TABLE C.18 Explosive Compounds Analyses for Soil Samples, May 1995<sup>a</sup>**

Soil Concentrations (µg/kg) at Various Depth Intervals						
Compound	TBNPBR2 (0-2 ft)	VXBOR4 (2-4 ft)	VXBOR4 (4-6 ft)	VXBOR5 (0-2 ft)	VXBOR5 (4-6 ft)	VXBOR5 (8-10 ft)
2-Amino-4,6-dinitrotoluene	46.7	U	46.7	U	46.7	U
4-Amino-2,6-dinitrotoluene	40.8	U	40.8	U	40.8	U
1,3-Dinitrobenzene	37.2	U	37.2	U	37.2	U
2,4-Dinitrotoluene	51.6	U	51.6	U	51.6	U
2,6-Dinitrotoluene	47.6	U	47.6	U	47.6	U
HMX	70.5	U	70.5	U	70.5	U
Nitrobenzene	35.2	U	35.2	U	35.2	U
Nitroglycerin	10,000	U	50,000 *U	10,000	50,000	*U
2-Nitrotoluene	81.4	U	81.4	U	81.4	U
3-Nitrotoluene	81.7	U	81.7	U	81.7	U
4-Nitrotoluene	87.2	U	87.2	U	87.2	U
Pentaerythritol tetranitrate	250	U	1,250 *U	250	250	U
RDX	50.9	U	50.9	U	50.9	U
Tetryl	163	U	163	U	163	U
1,3,5-Trinitrobenzene	40.2	U	40.2	U	40.2	U
2,4,6-Trinitrotoluene	35.6	U	35.6	U	35.6	U

Soil Concentrations (µg/kg) at 0-6 in.							
Compound	SQPS 4	SQPS 5	SQPS 8	SQPS 9	TPDGS 3	TPDGS 4	TPDGS 5
2-Amino-4,6-dinitrotoluene	46.7	U	46.7	U	46.7	U	46.7
4-Amino-2,6-dinitrotoluene	40.8	U	40.8	U	40.8	U	40.8
1,3-Dinitrobenzene	37.2	U	37.2	U	37.2	U	37.2

TABLE C.18 (Cont.)

Compound	Soil Concentrations (µg/kg) at 0-6 in.						
	SQPS 4	SQPS 5	SQPS 8	SQPS 9	TPDGS 3	TPDGS 4	TPDGS 5
2,4-Dinitrotoluene	51.6 U	51.6 U	51.6 U	51.6 U	51.6 U	51.6 U	51.6 U
2,6-Dinitrotoluene	47.6 U	47.6 U	47.6 U	47.6 U	47.6 U	47.6 U	47.6 U
HMX	70.5 U	70.5 U	70.5 U	70.5 U	70.5 U	70.5 U	70.5 U
Nitrobenzene	35.2 U	35.2 U	35.2 U	35.2 U	35.2 U	35.2 U	35.2 U
Nitroglycerin	10,000 U	10,000 U	20,000 U	10,000 U	10,000 U	15,300	10,000 U
2-Nitrotoluene	81.4 U	81.4 U	81.4 U	81.4 U	81.4 U	81.4 U	81.4 U
3-Nitrotoluene	81.7 U	81.7 U	81.7 U	81.7 U	81.7 U	81.7 U	81.7 U
4-Nitrotoluene	87.2 U	87.2 U	87.2 U	87.2 U	87.2 U	87.2 U	87.2 U
Pentaerythritol tetranitrate	250 U	250 U	500 U	500 U	250 U	250 U	250 U
RDX	50.9 U	50.9 U	50.9 U	50.9 U	50.9 U	50.9 U	50.9 U
Tetryl	163 U	163 U	163 U	163 U	163 U	163 U	163 U
1,3,5-Trinitrobenzene	40.2 U	40.2 U	40.2 U	40.2 U	40.2 U	40.2 U	40.2 U
2,4,6-Trinitrotoluene	35.6 U	35.6 U	35.6 U	35.6 U	35.6 U	35.6 U	35.6 U

<sup>a</sup> Sampled by ANL and analyzed by GP Environmental Services.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

\* = internal standard area counts were outside the QC limits.

TABLE C.19 CWA Degradation Products and Organosulfur Compound Analyses for Soil, May 1995

Compound	Soil Concentrations (mg/kg) at Various Depth Intervals					
	HBOR4 (6-8 ft)	HBOR4 (8-10 ft)	HBOR4 (10-12 ft)	HBOR4 (14-16 ft)	TBNPBOR2 (0-2 ft)	TBNPBOR2 (2-6 ft)
CWA degradation products						
Diisopropyl methylphosphonate (DIMP)	0.09	J	0.01	J	0.03	U
Dimethyl methylphosphate (DMMP)	0.157	U	0.152	U	0.16	U
Isopropyl methylphosphonic acid (IMPA)	0.978	U	1.14	U	1.18	U
Methyl phosphonic acid	0.978	U	1.14	U	1.18	U
Thiodiglycol (TDGCL)	4.65	U	4.49	U	4.73	U
Organosulfur compounds						
Benzothiozole (BTZ)	6.35	U	2.45	U	2.59	U
p-Chlorophenylmethyl sulfide (CPMS)	6.35	U	2.45	U	2.59	U
p-Chlorophenylmethyl sulfone (CPMSO2)	13.9	U	5.38	U	5.69	U
p-Chlorophenylmethyl sulfoxide (CPMSO)	13.2	U	5.11	U	5.4	U
Dimethyl disulfide (DMDS)	4.07	U	1.57	U	1.66	U
1,4-Dithiane	2.65	J	1.94	U	1.03	J
1,4-Oxathiane	5.03	U	0.59	J	2.05	U
CWA degradation products						
Diisopropyl methylphosphonate (DIMP)	1.39	U	0.137	U	0.725	U
Dimethyl methylphosphate (DMMP)	0.162	U	0.16	U	0.846	U
Isopropyl methylphosphonic acid (IMPA)	1.43	U	1.1	U	1.36	U
Methyl phosphonic acid	1.43	U	1.1	U	1.36	U
Thiodiglycol (TDGCL)	4.81	U	4.85	U	5	U

Soil Concentrations (mg/kg) at Various Depth Intervals

Compound	Soil Concentrations (mg/kg) at Various Depth Intervals					
	TBNPBOR2 (6-8 ft)	TBNPBOR2 (10-12 ft)	VXBOR4 (2-4 ft)	VXBOR4 (4-6 ft)	VXBOR5 (0-2 ft)	VXBOR5 (4-6 ft)
CWA degradation products						
Diisopropyl methylphosphonate (DIMP)	1.39	U	0.137	U	0.725	U
Dimethyl methylphosphate (DMMP)	0.162	U	0.16	U	0.846	U
Isopropyl methylphosphonic acid (IMPA)	1.43	U	1.1	U	1.36	U
Methyl phosphonic acid	1.43	U	1.1	U	1.36	U
Thiodiglycol (TDGCL)	4.81	U	4.85	U	5	U

TABLE C.19 (Cont.)

Compound	Soil Concentrations (mg/kg) at Various Depth Intervals					
	TBNPBOR2 (6-8 ft)	TBNPBOR2 (10-12 ft)	VXBOR4 (2-4 ft)	VXBOR4 (4-6 ft)	VXBOR5 (0-2 ft)	VXBOR5 (4-6 ft)
Organosulfur compounds						
Benzothiozole (BTZ)	1.32 U	1.33 U	68.7 UJ	26.4 U	1.31 U	1.4 U
p-Chlorophenylmethyl sulfide (CPMS)	1.32 U	1.33 U	68.7 UJ	26.4 U	1.31 U	1.4 U
p-Chlorophenylmethyl sulfone (CPMSO2)	2.89 U	2.92 U	151 U	58 U	2.87 U	3.08 U
p-Chlorophenylmethyl sulfoxide (CPMSO)	2.74 U	0.851 U	143 U	55.1 U	2.72 U	2.92 U
Dimethyl disulfide (DMDS)	0.844 U	U	44 UJ	16.9 U	0.837 U	0.9 U
1,4-Dithiane	1.79 U	1.81 U	93.5 UJ	36 U	0.46 J	1.91 U
1,4-Oxathiane	1.04 U	1.05 U	54.4 UJ	21 U	1.04 U	1.11 U
CWA degradation products						
Diisopropyl methylphosphonate (DIMP)	0.141 U	0.14 U	0.142 U	0.141 U	U	U
Dimethyl methylphosphate (DMMP)	0.165 U	0.17 U	0.166 U	0.165 U	U	U
Isopropyl methylphosphonic acid (IMPA)	1.26 U	1.16 U	1.36 U	1.14 U	U	U
Methyl phosphonic acid	1.26 U	1.16 U	1.36 U	1.14 U	U	U
Thiodiglycol (TDGCL)	4.88 U	4.92 U	4.92 U	4.88 U	U	U
Organosulfur compounds						
Benzothiozole (BTZ)	1.34 U	1.35 U	1.35 U	1.34 U	U	U
p-Chlorophenylmethyl sulfide (CPMS)	1.34 U	1.35 U	1.35 U	1.34 U	U	U
p-Chlorophenylmethyl sulfone (CPMSO2)	2.94 U	2.96 U	2.96 U	2.94 U	U	U
p-Chlorophenylmethyl sulfoxide (CPMSO)	2.79 U	2.81 U	2.81 U	2.79 U	U	U
Dimethyl disulfide (DMDS)	0.858 U	0.87 U	0.865 U	0.858 U	U	U
1,4-Dithiane	1.82 U	1.84 U	0.23 J	1.82 U	U	U
1,4-Oxathiane	1.06 U	1.07 U	1.07 U	1.06 U	U	U

<sup>a</sup> Sampled by ANL, analyzed by GP Environmental Services.

Data qualifiers: J = estimated value. U = analyte was analyzed for but not detected; detection limit given.

**TABLE C.20 Dioxin and Total Petroleum Hydrocarbons Analyses for Soil Samples, May 1995<sup>a</sup>**

Analyte	Soil Concentrations (µg/kg) at Various Depth Intervals							
	TBNPBOR3 (4-6 ft)	VXBOR4 (2-4 ft)	VXBOR4 (4-6 ft)	VXBOR5 (4-6 ft)	VXBOR5 (8-10 ft)			
Heptachlorodibenzo-p-dioxins	2.9	0.16 U	0.15 U	0.11 U	0.03 U			
Heptachlorodibenzo-p-furans	2.9	0.07	0.02 U	0.02 U	0.01 U			
Hexachlorodibenzo-p-dioxins	1.6	0.06 U	0.06 U	0.05 U	0.04 U			
Hexachlorodibenzo-p-furans	3.1	0.03	0.03 U	0.01 U	0.01 U			
Octachlorodibenzo-p-dioxin	4.3	0.32	0.28	0.1	0.03 U			
Octachlorodibenzo-p-furan	1.7	0.04 U	0.04 U	0.04 U	0.02 U			
Pentachlorodibenzo-p-dioxins	0.26	0.03 U	0.03 U	0.04 U	0.03 U			
Pentachlorodibenzo-p-furans	3.4	0.14 U	0.09 U	0.05 U	0.02 U			
2,3,7,8-TCDD	0.18	0.01 U	0.02 U	0.04 U	0.02 U			
2,3,7,8-TCDF	0.49	0.04	0.04	0.02 U	0.01 U			
Tetrachlorodibenzo-p-dioxins	0.07	0.01 U	0.02 U	0.04 U	0.02 U			
Tetrachlorodibenzo-p-furans	1.5	0.04	0.04	0.02 U	0.01 U			
Total petroleum hydrocarbons (mg/kg)	19,000 J	35,400 J(+)	18,200	666	31 UJ(+)			

<sup>a</sup> Sampled by ANL and analyzed by GP Environmental Services.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

J = estimated value.

+ = value obtained from a 1:10 dilution.

**TABLE C.21a Volatile Organics Analyses for Groundwater, May 1994<sup>a</sup>**

[illegible]

TABLE C.21a (Cont.)

Compound	Concentrations (µg/L) in Groundwater						
	TH-4	P-1	P-2	P-3	P-4	P-9	JF-43
1,1,2,2-Tetrachloroethane	10 U	10 U	10 U	4 J	3,500 D	10 U	10 U*
Tetrachloroethene	10 U	10 U	10 U	2,400 D	19	10 U	10 U*
Toluene	10 U	10 U	10 U	6 J	10 U	10 U	10 U*
1,1,1-Trichloroethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U*
1,1,2-Trichloroethane	10 U	10 U	10 U	10 U	68	10 U	10 U*
Trichloroethene	10 U	10 U	10 U	390 D	1,800 D	10 U	10 U*
Vinyl chloride	10 U	10 U	10 U	570 D	74	10 U	10 U*
Xylenes (total)	10 U	10 U	10 U	3 J	10 U	10 U	10 U*

Compound	Concentrations (µg/L) in Groundwater					
	JF-53	JF-63	JF-73	JF-83	JF-173	JF-183
Acetone	10 U	10 U	10 U	10 U	10 U	10 U
Benzene	10 U	10 U	10 U	10 U	10 U	3 J
Bromodichloromethane	10 U	10 U	10 U	10 U	10 U	10 U
Bromoform	10 U	10 U	10 U	10 U	10 U	10 U
Bromomethane	10 U	10 U	10 U	10 U	10 U	10 U
2-Butanone	10 U	10 U	10 U	10 U	10 U	10 U
Carbon disulfide	10 U	10 U	10 U	10 U	10 U	10 U
Carbon tetrachloride	10 U	10 U	10 U	10 U	10 U	3 J
Chlorobenzene	10 U	10 U	10 U	10 U	10 U	10 U
Chloroethane	10 U	10 U	10 U	10 U	10 U	10 U
Chloroform	10 U	9 J	10 U	44	10 U	12
Chloromethane	10 U	10 U	10 U	10 U	10 U	10 U

**TABLE C.21a (Cont.)**

[illegible]

TABLE C.21a (Cont.)

Compound	Concentrations ( $\mu\text{g/L}$ ) in Groundwater									
	JF-62	JF-72	JF-82	JF-51	JF-61	JF-71	JF-81			
Acetone	10	U	10	U	10	U	10	U		U
Benzene	10	U	10	U	10	U	10	U		U
Bromodichloromethane	10	U	10	U	10	U	10	U		U
Bromoform	10	U	10	U	10	U	10	U		U
Bromomethane	10	U	10	U	10	U	10	U		U
2-Butanone	10	U	10	U	10	U	10	U		U
Carbon disulfide	10	U	10	U	10	U	10	U		U
Carbon tetrachloride	10	U	10	U	10	U	10	U		U
Chlorobenzene	10	U	10	U	10	U	10	U		U
Chloroethane	10	U	10	U	10	U	10	U		U
Chloroform	10	U	10	U	10	U	10	U		U
Chloromethane	10	U	10	U	10	U	10	U		U
Dibromochloromethane	10	U	10	U	10	U	10	U		U
1,1-Dichloroethane	10	U	10	U	10	U	10	U		U
1,2-Dichloroethane	10	U	10	U	10	U	10	U		U
1,1-Dichloroethene	10	U	11	6	10	U	10	U	28	
1,2-Dichloroethene (total)	10	U	170	650	10	U	10	U	190	
1,2-Dichloropropane	10	U	10	10	10	U	10	U	10	U
cis-1,3-Dichloropropene	10	U	10	10	10	U	10	U	10	U
trans-1,3-Dichloropropene	10	U	10	10	10	U	10	U	10	U
Ethylbenzene	10	U	10	10	10	U	10	U	10	U
2-Hexanone	10	U	10	10	10	U	10	U	10	U
4-Methyl-2-pentanone	10	U	10	10	10	U	10	U	10	U
Methylene chloride	6	BJ	10	10	10	U	10	U	10	U
Styrene	10	U	10	10	10	U	10	U	10	U

TABLE C.21a (Cont.)

Compound	Concentrations (µg/L) in Groundwater							
	JF-62	JF-72	JF-82	JF-51	JF-61	JF-71	JF-81	
1,1,2,2-Tetrachloroethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	
Tetrachloroethene	10 U	10 U	17	10 U	10 U	10 U	34	
Toluene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	
1,1,1-Trichloroethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	
1,1,2-Trichloroethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	
Trichloroethene	10 U	10 U	1,500 D	850 D	6 J	10 U	1,600 D	
Vinyl chloride	10 U	10 U	23	10 U	10 U	10 U	10 U	
Xylenes (total)	10 U	10 U	10 U	10 U	10 U	10 U	10 U	

<sup>a</sup> Sampled by ANL, analyzed by EA Laboratories, CLP/HSL volatile organics. Wells JF-173 and JF-183 sampled in June and December 1994, respectively.

Data qualifiers:

U = analyte was analyzed for but not detected; detection limit given.

J = estimated value.

D = analyte was identified at given concentration with a secondary dilution factor.

\* = internal standard area counts were outside QC limits.

+ = surrogate recoveries were outside QC limits.

E = analyte concentration exceeded calibration range of instrument; concentration estimated.

**TABLE C.21b Volatile Organics Analyses for Groundwater in Piezometer Located in Marsh, September 1994<sup>a</sup>**

Compound	Concentrations (µg/L) in Groundwater									
	JBPM-1A <sup>b</sup>		JBPM-1B <sup>c</sup>		JBPM-2A		JBPM-2B		JBPM-3A	
Acetone	10	U	10	U	10	U	10	U	10	U
Benzene	2	J	10	U	10	U	10	U	10	U
Bromodichloromethane	10	U	10	U	10	U	10	U	10	U
Bromoform	10	U	10	U	10	U	10	U	10	U
Bromomethane	10	U	10	U	10	U	10	U	10	U
2-Butanone	10	U	10	U	10	U	10	U	10	U
Carbon disulfide	10	U	10	U	10	U	10	U	10	U
Carbon tetrachloride	10	U	10	U	10	U	10	U	10	U
Chlorobenzene	10	U	10	U	10	U	10	U	10	U
Chloroethane	10	U	10	U	10	U	10	U	10	U
Chloroform	13		10	U	10	U	10	U	10	U
Chloromethane	10	U	10	U	10	U	10	U	10	U
Dibromochloromethane	10	U	10	U	10	U	10	U	10	U
1,1-Dichloroethane	10	U	10	U	10	U	10	U	10	U
1,2-Dichloroethane	13		4	J	27		10	U	12	
1,1-Dichloroethene	24		2	J	5	J	10	U	6	J
1,2-Dichloroethene (total)	37,000	D	7,900	D	1,900	D	6	J	1,400	D
1,2-Dichloropropane	10	U	10	U	10	U	10	U	10	U
cis-1,3-Dichloropropene	10	U	10	U	10	U	10	U	10	U
trans-1,3-Dichloropropene	10	U	10	U	10	U	10	U	10	U
Ethylbenzene	10	U	10	U	10	U	10	U	10	U
2-Hexanone	10	U	10	U	10	U	10	U	10	U
4-Methyl-2-pentanone	10	U	10	U	10	U	10	U	10	U
Methylene chloride	10	U	10	U	10	U	10	U	10	U
Styrene	10	U	10	U	10	U	10	U	10	U
1,1,2,2-Tetrachloroethane	8,600	D	50		720	D	10	U	240	DJ
Tetrachloroethene	29		10	U	29		10	U	26	
Toluene	10	U	10	U	10	U	10	U	10	U
1,1,1-Trichloroethane	10	U	10	U	10	U	10	U	10	U
1,1,2-Trichloroethane	440	DJ	10		210	DJ	10	U	170	
Trichloroethene	1,200	DJ	18		4,300	D	10	U	7,300	D
Vinyl chloride	3,200	D	1,300	D	32		5	J	25	
Xylenes (total)	10	U	10	U	10	U	10	U	10	U